Priority	Project	County Location	Implementing Agency	Bridge Number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (sq ft)	Total Particip Cost	Unit Cost	Federal Share	Running Federal Share	Local Share	Running Local Share
1	H Street Rehabilitation Project	Sacramento	City of Sacramento	24C-0076	24C-0076	H Street	American River		58	FO	Bridge deck treatment, joint seal installation, approach slab installation and repair, and concrete spall patching	21894	$491,055	0.04	$434,731	$434,731	$56,324	$56,324
2	I, J, and Jiboom Street Viaducts Repair	Sacramento	City of Sacramento	24C-0006	24C-0006	Jiboom Street	I and J Street Viaducts	N from I Street Viaduct	54.2	SD	Joint seal installation, repair hinge plates	27200	$36,290	0.75	$32,128	$466,859	$4,162	$60,486
2	I, J, and Jiboom Street Viaducts Repair	Sacramento	City of Sacramento	24C-0364L	24C-0364L	I Street	J Street Viaducts	Btwn I-5 & Sac River	67.9	SD	Repair hinge plates, patch concrete spalling on underside of deck	29000	$36,290	0.80	$32,128	$498,986	$4,162	$4,162
2	I, J, and Jiboom Street Viaducts Repair	Sacramento	City of Sacramento	24C-0364R	24C-0364R	J Street	I and Jiboom Street Viaducts	Btwn I-5 & Sac River	77.9		Clean and install joint seal	18945	$72,345	0.26	$64,047	$563,033	$8,298	$12,460
5	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0382L	24C-0382L	Arena Blvd	East Drain Canal	0.9 mi s/o Del Paso Rd	97.7		Clean and install joint seal	3714	$20,956	0.18	$18,552	$581,585	$2,404	$2,404
5	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0382R	24C-0382R	Arena Blvd	East Drain Canal	0.9 mi s/o Del Paso Rd	94.6		Clean and install joint seal	3714	$20,956	0.18	$18,552	$600,138	$2,404	$4,807
5	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0378	24C-0378	Holiday Garage Rd	K Street	e/o 3rd St	78.9		Clean and install joint seal	3768	$16,901	0.22	$14,962	$615,100	$1,939	$1,939
5	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0112	24C-0112	Marconi	Auburn Blvd	0.2 mil w/o Rte 51	94		Clean and install joint seal	28654	$26,290	1.09	$23,275	$638,375	$3,015	$4,954
5	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0133	24C-0133	W Silver Eagle	NEMDC	btwn Northgate & Norwood	96.4		Clean and install joint seal	38000	$32,690	1.16	$28,940	$667,315	$3,750	$3,750
6	Power Inn Rehabilitation Project	Sacramento	City of Sacramento	24C-0025	24C-0025	Power Inn	Morrison Creek	0.1 mi s/o Lemon Hill	93.2		Bridge deck treatment	6100	$12,200	0.50	$10,801	$678,116	$1,399	$5,149
7	La Mancha Way Rehabilitation Project	Sacramento	City of Sacramento	24C-0093	24C-0093	La Mancha	Elder Creek	0.3 mi n/o Mack	75.7	FO	Bridge deck treatment	2500	$9,600	0.26	$8,499	$686,615	$1,101	$1,101
8	Franklin Laguna Creek Rehabilitation Project	Sacramento	City of Sacramento	24C-0116	24C-0116	Franklin	Laguna Creek	0.1 mi s/o Calvine	66.4	SD	Bridge deck treatment	21800	$13,400	1.63	$11,863	$698,478	$1,537	$2,638
9	Florin Perkins Rehabilitation Project	Sacramento	City of Sacramento	24C-0118	24C-0118	Florin Perkins	Morrison Creek	0.5 mi n/o Elder Creek	91.2		Bridge deck treatment	7500	$18,800	0.40	$16,644	$715,121	$2,156	$2,156
10	Franklin Elder Creek Rehabiltation Project	Sacramento	City of Sacramento	24C-0165	24C-0165	Franklin Blvd	S Fork Elder Creek		88.6		Bridge deck treatment	8200	$16,400	0.50	$14,519	$729,640	$1,881	$4,037
11	Elder Creek Rd Rehabiltation Project	Sacramento	City of Sacramento	24C-0204L	24C-0204L	Elder Creek	Morrison Creek		94.6		Bridge deck treatment	3200	$6,400	0.50	$5,666	$735,306	$734	$734
11	Elder Creek Rd Rehabiltation Project	Sacramento	City of Sacramento	24C-0204R	24C-0204R	Elder Creek	Morrison Creek		93.3		Bridge deck treatment	3100	$6,200	0.50	$5,489	$740,795	$711	$1,445
11	Elder Creek Rd Rehabiltation Project	Sacramento	City of Sacramento	24C-0245	24C-0245	Elder Creek	Morrison Creek		93.6		Bridge deck treatment	63500	$34,200	1.86	$30,277	$771,072	$3,923	$3,923
11	Elder Creek Rd Rehabiltation Project	Sacramento	City of Sacramento	24C-0252	24C-0252	Elder Creek	Morrison Creek		92.6	SD	Bridge deck treatment	32000	$21,000	1.52	$18,591	$789,664	$2,409	$6,331
12	Howe Ave Embankment Control	Sacramento	City of Sacramento	24C-0142L	24C-0142L	Howe Ave	La Riviera	0.25 mi n/o SR50	52		Rock slope paving, slope protection	8720	$74,600	0.12	$66,043	$855,707	$8,557	$8,557
12	Howe Ave Embankment Control	Sacramento	City of Sacramento	24C-0142R	24C-0142R	Howe Ave	La Riviera	0.25 mi n/o SR51	54		Rock slope paving, slope protection	8720	$74,600	0.12	$66,043	$921,750	$8,557	$17,113
12	Howe Ave Embankment Control	Sacramento	City of Sacramento	24C-0143L	24C-0143L	Howe Ave	La Riviera	0.25 mi n/o SR52	17		Rock slope paving, slope protection	4520	$74,600	0.06	$66,043	$987,794	$8,557	$8,557
12	Howe Ave Embankment Control	Sacramento	City of Sacramento	24C-0143R	24C-0143R	Howe Ave	La Riviera	0.25 mi n/o SR53	18		Rock slope paving, slope protection	4520	$74,600	0.06	$66,043	$1,053,837	$8,557	$17,113
13	Northgate over NEMDC	Sacramento	City of Sacramento	24C-0099	24C-0099	Northgate Blvd	Natomas East Main Drain Canal	0.1 mi s/o Garden Hwy	89.7		Scour countermeasure	22637	$67,500	0.34	$59,758	$1,113,595	$7,742	$7,742
14	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0359	24C-0359	El Camino Ave	UPRR	0.4 mi w/o Rte 51	89.3		Clean and install joint seal	42109	$18,690	2.25	$16,546	$1,130,141	$2,144	$9,886

14	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0353	24C-0353	Arden Way	UPRR	0.3 mi w/o Rte 61	94.4	Clean and install joint seal	25597	$41,534	0.62	$36,770	$1,166,911	$4,764	$4,764
14	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0122	24C-0122	Pocket Rd	Douglas Drain	2.1 mi w/o Rte 5	85.6	Clean and install joint seal	11625	$32,283	0.36	$28,580	$1,195,491	$3,703	$8,467
14	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0107R	24C-0107R	Howe Ave	American River	0.4 mi n/o SR 50	58.4	Clean and install joint seal	43077	$28,000	1.54	$24,788	$1,220,280	$3,212	$11,678
14	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0107L	24C-0107L	Howe Ave	American River	0.4 mi n/o SR 50	57.6	Clean and install joint seal	43077	$28,000	1.54	$24,788	$1,245,068	$3,212	$14,890
14	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0128	24C-0128	Rio Linda	Arcade Creek	0.1 mi n/o Arcade	88.1	Replace Joint Seal, Deck Seal Treatment	15371	$48,427	0.32	$42,872	$1,287,941	$5,555	$20,445
												$1,454,807		**$1,287,941**	**$23,789,446**	**$166,866**	**$308,014**