

Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft ²)	Total Particip. Cost	Unit Cost (\$/ft ²)	Federal Share	Running Fed Summary	Local Share	Running Local Share
1	Merced	City of Merced	Develop next year's BPMP								1.00	10,000	10,000	8,853	8,853	1,147	1,147
2	Merced	City of Merced	39C0028		M Street	Bear Creek	In Merced	80.3	-	Deck restoration including AC removal and polyester concrete overlay; approach slab installation; bridge strengthening including planter removal and sidewalk replacement; replacement of planters with bridge railing; embankment erosion control and the rehabilitation of the existing scour countermeasure.	6,700.00	1,361,000	203	#####	1,213,746	156,107	157,254
3	Merced	City of Merced	39C0041		G Street	Bear Creek	1.08 MI NE from Route 99	80.5	SD	Deck restoration including removal and replacement of unsound concrete; methacrylate deck treatment; replace unsound approach sidewalk concrete; spot paint bridge railing; embankment erosion control and the rehabilitation of the existing scour countermeasure.	12,400.00	604,000	49	534,721	1,748,468	69,279	226,533

Notes: Total Participating Cost includes:
 PE - Preliminary Engineering including City Management
 CON - Estimated Construction including 10% Mob, 25% Cont, Construction Engineering.