

Federal Fiscal Year 2012/2013 Bridge Preventive Maintenance Program for the Town of Fairfax

Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft <sup>2</sup> )	Total Particip. Cost PE + CON	Unit Cost (\$/ft <sup>2</sup> )	Federal Share	Running Fed Summary	Local Share	Running Local Share
1	MRN	Town of Fairfax (FRFX)	Develop next year's BPMP	-	-	-	-	-	-	Develop next year's BPMP	1	\$8,000	\$8,000	\$7,082	\$7,082	\$918	\$918
2	MRN	Town of Fairfax (FRFX)	27C-0143		Marin Road	Fairfax Creek	0.03 mi southwest of Sir Francis Drake Blvd.	68		1. Replace toppled downstream wingwall at Abutment 2 (left looking downstream). Restore riprap. 2. Repair damaged wingwall upstream at abutment 1 3. Repair 2 spalls at the 2 abutments	1,090	\$266,123	\$244.15	\$235,599	\$242,681	\$30,524	\$31,442
3	MRN	Town of Fairfax (FRFX)	27C-0141		Spruce Road	Fairfax Creek	.15 mi southwest of Sir Francis Drake Blvd. & Azalea Ave	63.9		1. Coldplane AC on deck, apply methacrylate and overlay deck with polyester concrete 2. Replace joint seals (2)	808	\$262,923	\$325	\$232,766	\$475,447	\$30,157	\$61,599
4	MRN	Town of Fairfax (FRFX)	27C-0146		Canyon Road	San Anselmo Cr.	.05 mi southwest of intersection with Cascade Drive	72.8	FO	1. Replace concrete sack wingwall @ abutment 1 (left side looking downstream) with integral R/C wingwall. Repair the downstream wingwall on same side. 2. Strengthen eroded concret at face of abutment 1 3. Clean deck and apply methacrylate to seal the cracks 4. Repair joint seals (2) 5. Repair superstructure concrete spall at northeast rail post	470	\$412,974	\$879	\$365,606	\$841,053	\$47,368	\$108,967