

COUNTY of YUBA  
2015 / 2016 Bridge Preventative Maintenance Program

Priority (Lowest number is Top Priority)	County Location	Bridge No.	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD / FO Status	Work Description	Deck Area (sq ft)	Total Participation Cost	Unit Cost (\$ / sq ft)	Federal Share	Running Federal Summary	Local Share	Running Local Summary
1	YUBA	16C0001	Simpson Lane	Yuba River	0.5 Mi SE of 10th Street	87.1	SD	Repair potholes in AC overlay @ joint locations @ abutment 1 piers 2,4,5 & 6. Remove dirt & debris from around bearing areas, install Type A pourable joint seals @ all joint locations. Joint width measure (see report).	16682	\$194,720.00	\$11.67	\$172,385.62	\$172,385.62	\$22,334.38	\$22,334.38
2	YUBA	16C0050	Ridge Road	Oregon Creek	0.1 Mi E of S.R. 49	92.9	SD	Remove debris that were impacted in joints & reinstall type A joint seals @ both abutments to allow a proper structural expansion. Repair damaged section of railing near abutment 1 left & right. Treat the deck w/methacrylate to seal deck cracks from futher water penetration.	4958	\$56,100.00	\$11.32	\$49,665.33	\$222,050.95	\$6,434.67	\$28,769.05
3	YUBA	16C0031	Woodruff Lane	Jack Slough	0.5 Mi East Jack Slough Rd	88.7		Level approach AC on the abutment 1 end. Deck cracking treatment w/methacrylate to seal cracks from further water penetration.	2837	\$41,100.00	\$14.49	\$36,385.83	\$258,436.78	\$4,714.17	\$33,483.22
4	YUBA	16C0051	Peoria Road	Dry Creek	1.7 Mi North of S.R. 20	96.8		Clean & treat deck w/methcrylate to seal cracks.	4852	\$35,500.00	\$7.32	\$31,428.15	\$289,864.93	\$4,071.85	\$37,555.07
5	YUBA	Develop next years BPMP						Develop next years BPMP	1	\$5,000.00	\$5,000.00	\$4,426.50	\$294,291.43	\$573.50	\$38,128.57
<b>TOTAL</b>										<b>\$332,420.00</b>					