

Federal Fiscal Year 2015/2016 Bridge Preventive Maintenance Program for the Town of San Anselmo - BPMP 5159(022)

PM00090

Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft ²)	Total Particip. Cost	Unit Cost (\$/ft ²)	Federal Share	Running Fed Summary	Local Share	Running Local Share	
1	MRN	Town of San Anselmo (SLMO)	27C-0040		Sir Francis Drake Blvd.	San Anselmo Cr.	.13 mi south of intersection of SFDB and Center Blvd.	66.8		1. Coldplane deck AC on NB lane 2. Apply methacrylate and overlay entire deck with polyester concrete 3. Repair cracks & spalls with epoxy grout 4. Repair joint seals	4,000	\$400,128	\$100	\$354,234	\$354,234	\$45,895	\$45,895	
2	MRN	Town of San Anselmo (SLMO)	27C-0073		Barber Ave.	San Anselmo Cr.	.04 mi east of intersection with SFDB	52.3		1. Coldplane deck AC 2. Clean the deck, apply methacrylate and overlay the deck with polyester concrete 3. Repair cracks & spalls with epoxy grout 4. Repair joint seals	4,100	\$413,325	\$101	\$365,917	\$720,151	\$47,408	\$93,303	
3	MRN	Town of San Anselmo (SLMO)	27C-0101		Center Blvd. (@ Lansdale Ave.)	San Anselmo Cr.	At the intersection of Center Blvd. & Lansdale Ave	54.5	FO	1. Excavate the fill on top of the bridge 2. Clean the deck, place Fiberwrap and backfill 3. Repair joint seals	6,000	\$440,179	\$73	\$389,690	\$1,109,841	\$50,489	\$143,792	
4	MRN	Town of San Anselmo (SLMO)	27C-0100		Bridge Avenue	San Anselmo Cr.	At the intersection of Center Blvd. & Lansdale Ave	58.4		1. Coldplane existing deck AC 2. Clean the deck, apply methacrylate and overlay the deck with polyester concrete 3. Repair barrier rail cracks & spalls 4. Repair the failed joint seals	5,130	\$475,728	\$93	\$421,162	\$1,531,003	\$54,566	\$198,358	
											Total PE + CON		\$ 1,729,360					
											Total PE dollars requested		\$464,736					