STATE OF CALIFORNIA
BUSINESS, TRANSPORTATION AND HOUSING AGENCY
DEPARTMENT OF TRANSPORTATION

2011
CONTRACT COST DATA

A SUMMARY OF COST BY ITEMS FOR HIGHWAY CONSTRUCTION PROJECTS

© 2011 California Department of Transportation
All Rights Reserved

2011
CONTRACT COST DATA

The *Contract Cost Data* book is published annually by the Department of Transportation, Division of Engineering Services - Office Engineer, Office of Contract Awards and Services. This book includes standard contract items for major highway contracts for which bids were *awarded in 2011.* Some of the units of measure for these items were in U.S. Customary Units (English) and were converted to International System of Units (SI) for this publication. The conversion factors used for this purpose are listed in *Appendix A*. For those who wish to convert back to English units, the appropriate conversion factors are listed in *Appendix B*.

Advertised item quantities have been used as source information. Item quantities may vary from the final quantities incorporated into the completed contract. Prices shown in this tabulation are the mechanically weighted average of the awarded bidders' prices and are affected by location, time, quantity in the job and size of the item (relative to the size of the job). In this book, a six-digit item code has been assigned to each standard contract item and the items are listed numerically.

For assistance, contact Division of Engineering Services - Office Engineer, Office of Contract Awards and Services by e-mail at this address: DES-OE_Contract_Service @dot.ca.gov. The Web site address to download this book is http://www.dot.ca.gov/hq/esc/oe/awards.

TABLE OF CONTENTS

INDEX OF ITEM DESCRIPTION ……..A1

CONTRACT ITEM COST DATA……1

APPENDIX A……347
(CONVERSION FACTORS FROM ENGLISH UNITS TO SI UNITS)

APPENDIX B……347
(CONVERSION FACTORS FROM SI UNITS TO ENGLISH UNITS)

Index of Item Description

ITEM DESCRIPTION	ITEM CODE
0 - 9	
1 1/2" BACKFLOW PREVENTER ASSEMBLY	208425
1 1/2" ELECTRIC REMOTE CONTROL VALVE	206604
1 1/2" GATE VALVE	208574
1 1/2" MANUAL CONTROL VALVE	208620
1 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208265
1 1/2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208597
1 1/2" QUICK COUPLING VALVE	208646
1 1/2" WYE STRAINER	208628
1 1/4" ELECTRIC REMOTE CONTROL VALVE	206603
1 1/4" GALVANIZED STEEL PIPE (SUPPLY LINE)	208004
1 1/4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208264
1 1/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208596
1" BACKFLOW PREVENTER ASSEMBLY	208423
1" ELECTRIC REMOTE CONTROL VALVE	206602
1" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208263
1" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208595
1" WYE STRAINER	208626
1.2 M CAST-IN-DRILLED-HOLE CONCRETE PILING	490661
1.2 M CHAIN LINK GATE (TYPE CL-1.8)	802585
1.5 M CAST-IN-DRILLED-HOLE CONCRETE PILING	490663
1.8 M CHAIN LINK GATE (TYPE CL-1.8)	802590
1/2" PLASTIC PIPE (IRRIGATION LINE)	208211
10' CHAIN LINK GATE (TYPE CL-6)	802560
10" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208739
10" CORRUGATED STEEL PIPE (.079" THICK)	665009
10" WELDED STEEL PIPE CONDUIT (.250" THICK)	208809
100 MM THERMOPLASTIC TRAFFIC STRIPE	840561
0 - 9	
100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 1.83 M - 0.30 M)	840567
100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M)	840570
100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 5.18 M - 2.14 M)	840571
1050 MM REINFORCED CONCRETE PIPE	650081
1050 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650131
1050 MM TEMPORARY CULVERT	073032
108" CAST-IN-DRILLED-HOLE CONCRETE PILING	490620
12' CHAIN LINK GATE (TYPE CL-4)	802180
12' CHAIN LINK GATE (TYPE CL-6)	802580
12 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	206751
12" ALTERNATIVE FLARED END SECTION	705307
12" ALTERNATIVE PIPE CULVERT	620060
12" ALTERNATIVE PIPE CULVERT (TYPE A)	620061
12" ALTERNATIVE PIPE DOWNDRAIN	698060
12" ANCHOR ASSEMBLY	692305
12" BITUMINOUS COATED CORRUGATED STEEL PIPE (.064" THICK)	665111
12" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	665112
12" BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (.079" THICK)	703311
12" CONCRETE FLARED END SECTION	705201
12" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208740
12" CORRUGATED STEEL PIPE	665010
12" CORRUGATED STEEL PIPE (.064" THICK)	665011
12" CORRUGATED STEEL PIPE (.079" THICK)	665012
12" CORRUGATED STEEL PIPE CONDUIT (.064" THICK)	208762
12" CORRUGATED STEEL PIPE DOWNDRAIN	690110
12" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690112

ITEM DESCRIPTION	ITEM CODE
0 - 9	
12" CORRUGATED STEEL PIPE RISER (.064" THICK)	703210
12" CORRUGATED STEEL PIPE RISER (.079" THICK)	703211
12" DOWNDRAIN SLIP JOINT	692205
12" ENTRANCE TAPER	692005
12" PLASTIC PIPE	641101
12" REINFORCED CONCRETE PIPE	650010
12" SLOTTED CORRUGATED STEEL PIPE (.109" THICK)	665713
12" STEEL FLARED END SECTION	705007
12" WELDED STEEL PIPE (.250" THICK)	703533
12" WELDED STEEL PIPE CONDUIT (.250" THICK)	208812
120" CAST-IN-DRILLED-HOLE CONCRETE PILING	490622
1200 MM ALTERNATIVE FLARED END SECTION	705341
1200 MM CONCRETE FLARED END SECTION	705229
1200 MM CORRUGATED STEEL PIPE RISER (2.77 MM THICK)	703288
1200 MM REINFORCED CONCRETE PIPE	650084
1200 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650132
1350 MM CONCRETE FLARED END SECTION	705230
1350 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	664047
1350 MM REINFORCED CONCRETE PIPE	650086
1372 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561013
15" ALTERNATIVE FLARED END SECTION	705309
15" ALTERNATIVE PIPE CULVERT	620080
15" CONCRETE FLARED END SECTION	705202
15" CORRUGATED STEEL PIPE (.079" THICK)	665014
15" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690114
15" ENTRANCE TAPER	692006
15" PLASTIC PIPE	641104
15" REINFORCED CONCRETE PIPE	650012

ITEM DESCRIPTION	ITEM CODE
0 - 9	
15" STEEL FLARED END SECTION	705009
150 MM PERFORATED PLASTIC PIPE UNDERDRAIN	680931
150 MM SEWER PIPE (LATERAL)	717074
150 MM THERMOPLASTIC TRAFFIC STRIPE	840562
1500 MM REINFORCED CONCRETE PIPE	650089
1500 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650134
1500 MM WELDED STEEL PIPE (9.53 MM THICK)	703699
1524 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561015
156" CAST-IN-DRILLED-HOLE CONCRETE PILING	490623
16' CHAIN LINK GATE (TYPE CL-6)	802620
16' METAL GATE	801364
16 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	206756
16' WIRE MESH GATE	801230
16" CAST-IN-DRILLED-HOLE CONCRETE PILING	490601
16" CAST-IN-DRILLED-HOLE CONCRETE PILING (BARRIER)	498009
16" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	498016
17" X 13" CORRUGATED STEEL PIPE ARCH (.079" THICK)	667001
18" ALTERNATIVE FLARED END SECTION	705311
18" ALTERNATIVE PIPE CULVERT	620100
18" ALTERNATIVE PIPE CULVERT (TYPE A)	620101
18" ALTERNATIVE PIPE CULVERT (TYPE B)	620102
18" ALTERNATIVE PIPE DOWNDRAIN	698100
18" ALTERNATIVE PIPELINER	155115
18" ALTERNATIVE SLOTTED PIPE	620715
18" ANCHOR ASSEMBLY	692307
18" AUTOMATIC DRAINAGE GATE	705517
18" BITUMINOUS COATED CORRUGATED STEEL PIPE (.064" THICK)	665116
18" BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690217

ITEM DESCRIPTION	ITEM CODE
0 - 9	
18" BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (.079" THICK)	703317
18" BITUMINOUS COATED ENTRANCE TAPER	692037
18" BITUMINOUS COATED SLOTTED CORRUGATED STEEL PIPE (.168" THICK)	665828
18" BITUMINOUS COATED STEEL FLARED END SECTION	705061
18" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	498018
18" CONCRETE FLARED END SECTION	705204
18" CORRUGATED STEEL PIPE (.064" THICK)	665016
18" CORRUGATED STEEL PIPE (.109" THICK)	665018
18" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	690116
18" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690117
18" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	690118
18" CORRUGATED STEEL PIPE RISER (.168" THICK)	703220
18" CURED-IN-PLACE PIPELINER	155314
18" ENTRANCE TAPER	692007
18" PLASTIC PIPE	641107
18" PLASTIC PIPE DOWNDRAIN	690964
18" REINFORCED CONCRETE PIPE	650014
18" REINFORCED CONCRETE PIPE (CLASS II)	650211
18" REINFORCED CONCRETE PIPE (CLASS III)	650311
18" REINFORCED CONCRETE PIPE (CLASS V)	650511
18" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650105
18" SLOTTED CORRUGATED STEEL PIPE (.064" THICK)	665716
18" SLOTTED CORRUGATED STEEL PIPE (.079" THICK)	665717
18" STEEL FLARED END SECTION	705011
18" TAPERED INLET	692107
18" TEMPORARY CULVERT	073006
18" WELDED STEEL PIPE (.250" THICK)	703555

ITEM DESCRIPTION	ITEM CODE
0 - 9	
1800 MM PRECAST CONCRETE PIPE MANHOLE	707252
1800 MM REINFORCED CONCRETE PIPE	650092
2 1/2" GALVANIZED STEEL PIPE (SUPPLY LINE)	208007
2 1/2" GATE VALVE	208576
2 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208267
2 1/2" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208277
2 1/2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208599
2" BACKFLOW PREVENTER ASSEMBLY	208426
2" CONDUIT	860785
2" ELECTRIC REMOTE CONTROL VALVE	206605
2" GALVANIZED STEEL PIPE (SUPPLY LINE)	208006
2" GATE VALVE	208575
2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208266
2" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208276
2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208598
2" WYE STRAINER	208630
2.1 M CAST-IN-DRILLED-HOLE CONCRETE PILING	490669
2.4 M CAST-IN-DRILLED-HOLE CONCRETE PILING	490671
2.4 M CHAIN LINK GATE (TYPE CL-1.8)	802592
20' CHAIN LINK GATE (TYPE CL-6)	802660
200 MM ALTERNATIVE PIPE CULVERT	620902
200 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208731
200 MM CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK)	690155
200 MM THERMOPLASTIC TRAFFIC STRIPE	840563
200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M)	840564
200 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	208798
21" X 15" CORRUGATED STEEL PIPE ARCH (.109" THICK)	667006
24' CHAIN LINK GATE (TYPE CL-6)	802670
24 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	206753

ITEM DESCRIPTION	ITEM CODE
0 - 9	
24" ALTERNATIVE FLARED END SECTION	705315
24" ALTERNATIVE PIPE CULVERT	620140
24" ALTERNATIVE PIPE CULVERT (TYPE A)	620141
24" ALTERNATIVE PIPE CULVERT (TYPE B)	620142
24" ALTERNATIVE PIPE DOWNDRAIN	698140
24" ALTERNATIVE PIPELINER	155121
24" ANCHOR ASSEMBLY	692309
24" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	665123
24" BITUMINOUS COATED CORRUGATED STEEL PIPE (.109" THICK)	665124
24" CAST-IN-DRILLED-HOLE CONCRETE PILING	490603
24" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	498022
24" CONCRETE FLARED END SECTION	705206
24" CORRUGATED STEEL PIPE (.064" THICK)	665022
24" CORRUGATED STEEL PIPE (.079" THICK)	665023
24" CORRUGATED STEEL PIPE (.109" THICK)	665024
24" CORRUGATED STEEL PIPE (.138" THICK)	665025
24" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690123
24" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	690124
24" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	690125
24" CURED-IN-PLACE PIPELINER	155316
24" DOWNDRAIN SLIP JOINT	692209
24" PLASTIC PIPE	641113
24" PRECAST CONCRETE PIPE MANHOLE	707210
24" REINFORCED CONCRETE PIPE	650018
24" REINFORCED CONCRETE PIPE (CLASS II, RUBBER GASKET JOINT)	652215
24" REINFORCED CONCRETE PIPE (CLASS III)	650316
24" REINFORCED CONCRETE PIPE (CLASS V)	650516
24" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650107

ITEM DESCRIPTION	ITEM CODE
0 - 9	
24" STEEL FLARED END SECTION	705015
24" TO 18" CORRUGATED STEEL ECCENTRIC REDUCER (.079" THICK)	702123
24" WELDED STEEL PIPE (.250" THICK)	703575
24" WELDED STEEL PIPE CASING (BRIDGE)	703460
25 MM PLASTIC PIPE (PR 315) (SUPPLY LINE)	208285
250 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208732
27" ALTERNATIVE PIPE CULVERT	620160
3" BACKFLOW PREVENTER ASSEMBLY	208428
3" ELECTRIC REMOTE CONTROL VALVE	206607
3" GALVANIZED STEEL PIPE (SUPPLY LINE ON BRIDGE)	208044
3" GALVANIZED STEEL PIPE (SUPPLY LINE)	208008
3" GATE VALVE	208588
3" PLASTIC PIPE	680207
3" PLASTIC PIPE (EDGE DRAIN OUTLET)	681107
3" PLASTIC PIPE (EDGE DRAIN)	681103
3" PLASTIC PIPE (OUTLET)	680240
3" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208268
3" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208278
3" SUPPLY LINE (BRIDGE)	208028
3.0 M CHAIN LINK GATE (TYPE CL-1.8)	802595
3.7 M CHAIN LINK GATE (TYPE CL-1.8)	802596
3/4" ELECTRIC REMOTE CONTROL VALVE	206601
3/4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208262
3/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208594
3/4" QUICK COUPLING VALVE	208645
30" ALTERNATIVE FLARED END SECTION	705319
30" ALTERNATIVE PIPE CULVERT	620180
30" ALTERNATIVE PIPE CULVERT (TYPE A)	620181
30" ALTERNATIVE PIPE CULVERT (TYPE B)	620182
30" ALTERNATIVE PIPELINER	155127
30" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561004

ITEM DESCRIPTION	ITEM CODE
0 - 9	
30" CAST-IN-DRILLED-HOLE CONCRETE PILING	490604
30" CORRUGATED STEEL PIPE (.079" THICK)	665031
30" CORRUGATED STEEL PIPE (.109" THICK)	665032
30" CORRUGATED STEEL PIPE (.138" THICK)	665033
30" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690131
30" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	690132
30" CURED-IN-PLACE PIPELINER	155318
30" DOWNDRAIN SLIP JOINT	692211
30" PLASTIC PIPE	641119
30" REINFORCED CONCRETE PIPE	650022
30" STEEL FLARED END SECTION	705019
30" WELDED STEEL PIPE (.250" THICK)	703598
300 MM ALTERNATIVE PIPE CULVERT	620904
300 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208733
300 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	664009
300 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	664010
300 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	690160
300 MM ENTRANCE TAPER	692088
300 MM PLASTIC PIPE	641132
300 MM REINFORCED CONCRETE PIPE	650067
300 MM STEEL FLARED END SECTION	705042
36" ALTERNATIVE FLARED END SECTION	705321
36" ALTERNATIVE PIPE CULVERT	620220
36" ALTERNATIVE PIPE CULVERT (TYPE A)	620221
36" ALTERNATIVE PIPE CULVERT (TYPE B)	620222
36" ALTERNATIVE PIPELINER	155130
36" ANCHOR ASSEMBLY	692313
36" AUTOMATIC DRAINAGE GATE	705527
36" BITUMINOUS COATED CORRUGATED STEEL PIPE (.064" THICK)	665135

ITEM DESCRIPTION	ITEM CODE
0 - 9	
36" BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (.138" THICK)	703340
36" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561005
36" CAST-IN-DRILLED-HOLE CONCRETE PILING	490605
36" CORRUGATED STEEL PIPE (.109" THICK)	665037
36" CORRUGATED STEEL PIPE (.168" THICK)	665039
36" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	690137
36" CORRUGATED STEEL PIPE ENERGY DISSIPATOR	702634
36" CORRUGATED STEEL PIPE INLET (.079" THICK)	700638
36" CORRUGATED STEEL PIPE INLET (.109" THICK)	700639
36" CORRUGATED STEEL PIPE INLET (.138" THICK)	700640
36" CORRUGATED STEEL PIPE INLET (.168" THICK)	700641
36" CORRUGATED STEEL PIPE RISER (.064" THICK)	703237
36" CURED-IN-PLACE PIPELINER	155319
36" PLASTIC PIPE	641125
36" PRECAST CONCRETE PIPE INLET	707117
36" PRECAST CONCRETE PIPE MANHOLE	707217
36" PRECAST CONCRETE PIPE MANHOLE (EXTRA STRENGTH)	707218
36" PRECAST CONCRETE PIPE RISER	707417
36" REINFORCED CONCRETE PIPE	650026
36" REINFORCED CONCRETE PIPE (CLASS IV, RUBBER GASKET JOINT)	652424
36" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650109
36" REINFORCED CONCRETE PIPE RISER	707467
36" STEEL FLARED END SECTION	705023
36" WELDED STEEL PIPE (.250" THICK)	703618
365 MM X 575 MM OVAL SHAPED REINFORCED CONCRETE PIPE (CLASS III)	657342
4' CHAIN LINK GATE (TYPE CL-6)	802501
4" ALTERNATIVE CONDUIT	208716
4" CONDUIT	208706

ITEM DESCRIPTION	ITEM CODE
0 - 9	
4" GALVANIZED STEEL PIPE (SUPPLY LINE)	208009
4" GATE VALVE	208589
4" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208279
4" SUPPLY LINE (BRIDGE)	208029
4" THERMOPLASTIC TRAFFIC STRIPE	840504
4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	840523
4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 17-7)	840526
4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	840525
4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 6-1)	840521
4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED)	840581
4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED) (BROKEN 17-7)	840580
4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED, 36-12)	840539
4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED, BROKEN 36-12)	840545
4" TWO-COMPONENT PAINT TRAFFIC STRIPE	840582
4" TWO-COMPONENT PAINT TRAFFIC STRIPE (BROKEN 17-7)	840608
4" WELDED STEEL PIPE CONDUIT (.237" THICK)	208801
4.3 M CHAIN LINK GATE (TYPE CL-1.8)	802671
4.3 M WIRE MESH GATE	801272
4.6 M WIRE MESH GATE	801273
4.9 M CHAIN LINK GATE (TYPE CL-1.8)	802672
4.9 M WIRE MESH GATE	801274
400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	490655
400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	498027
42" ALTERNATIVE FLARED END SECTION	705323
42" ALTERNATIVE PIPE CULVERT	620260
42" ALTERNATIVE PIPE CULVERT (TYPE B)	620262
42" AUTOMATIC DRAINAGE GATE	705529
42" CAST-IN-DRILLED-HOLE CONCRETE PILING	490606

ITEM DESCRIPTION	ITEM CODE
0 - 9	
42" CORRUGATED STEEL PIPE (.109" THICK)	665042
42" CORRUGATED STEEL PIPE (.138" THICK)	665043
42" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	690142
42" CURED-IN-PLACE PIPELINER	155320
42" REINFORCED CONCRETE PIPE	650030
42" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650111
42" X 29" CORRUGATED STEEL PIPE ARCH (.109" THICK)	667024
450 MM ALTERNATIVE FLARED END SECTION	705336
450 MM ALTERNATIVE PIPE CULVERT	620909
450 MM ALTERNATIVE PIPE DOWNDRAIN	698162
450 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	490656
450 MM CONCRETE FLARED END SECTION	705222
450 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	664015
450 MM REINFORCED CONCRETE PIPE	650069
450 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650127
450 MM SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK)	665733
450 MM STEEL FLARED END SECTION	705044
450 MM TEMPORARY CULVERT	073028
48" ALTERNATIVE FLARED END SECTION	705325
48" ALTERNATIVE PIPE CULVERT	620300
48" BITUMINOUS COATED STEEL FLARED END SECTION	705081
48" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561011
48" CAST-IN-DRILLED-HOLE CONCRETE PILING	490607
48" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	490684
48" CORRUGATED STEEL PIPE (.079" THICK)	665046
48" CORRUGATED STEEL PIPE (.109" THICK)	665047
48" CORRUGATED STEEL PIPE (.138" THICK)	665048

ITEM DESCRIPTION	ITEM CODE
0 - 9	
48" CORRUGATED STEEL PIPE (.168" THICK)	665049
48" CORRUGATED STEEL PIPE INLET (.138" THICK)	700656
48" DEBRIS RACK CAGE (H=4')	706607
48" PLASTIC PIPE	641131
48" PRECAST CONCRETE PIPE MANHOLE	707225
48" REINFORCED CONCRETE PIPE	650034
48" TEMPORARY CULVERT	073013
48" WELDED STEEL PIPE (.375" THICK)	703656
5' CHAIN LINK GATE (TYPE CL-6)	802510
5' WIRE MESH GATE	801120
51" REINFORCED CONCRETE PIPE	650036
525 MM REINFORCED CONCRETE PIPE	650072
54" ALTERNATIVE PIPE CULVERT	620340
54" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561014
54" CURED-IN-PLACE PIPELINER	155322
54" REINFORCED CONCRETE PIPE	650038
57" X 38" CORRUGATED STEEL PIPE ARCH (.138" THICK)	667035
6' CHAIN LINK GATE (TYPE CL-6)	802520
6' WIRE MESH GATE	801130
6" ALTERNATIVE PIPE CULVERT	620002
6" CORRUGATED STEEL PIPE CONDUIT (.064" THICK)	208756
6" NON-PERFORATED PLASTIC PIPE UNDERDRAIN	680903
6" PERFORATED PLASTIC PIPE UNDERDRAIN	680902
6" PLASTIC PIPE	681023
6" PLASTIC PIPE (EDGE DRAIN OUTLET)	681113
6" PLASTIC PIPE (EDGE DRAIN)	681108
6" THERMOPLASTIC TRAFFIC STRIPE	840505
6" TWO-COMPONENT PAINT TRAFFIC STRIPE	840583
6" WELDED STEEL PIPE (.105" THICK)	703508
6.4 M WIRE MESH GATE	801277

ITEM DESCRIPTION	ITEM CODE
0 - 9	
60" ALTERNATIVE FLARED END SECTION	705329
60" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561016
60" CAST-IN-DRILLED-HOLE CONCRETE PILING	490609
60" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	490685
60" CORRUGATED STEEL PIPE (.138" THICK)	665056
60" PERMANENT STEEL CASING	490591
60" REINFORCED CONCRETE PIPE	650042
600 MM ALTERNATIVE FLARED END SECTION	705337
600 MM ALTERNATIVE PIPE CULVERT	620913
600 MM ALTERNATIVE PIPE DOWNDRAIN	698169
600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK)	664097
600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	490657
600 MM CONCRETE FLARED END SECTION	705224
600 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK)	690171
600 MM REINFORCED CONCRETE PIPE	650075
600 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650128
600 MM STEEL FLARED END SECTION	705045
600 MM TEMPORARY CULVERT	073029
600 MM WELDED STEEL PIPE CASING (BRIDGE)	703481
66" REINFORCED CONCRETE PIPE	650046
7.3 M CHAIN LINK GATE (TYPE CL-1.8)	802676
72" ALTERNATIVE PIPE CULVERT	620460
72" CAST-IN-DRILLED-HOLE CONCRETE PILING	490611
72" PERMANENT STEEL CASING	490592
72" PRECAST CONCRETE PIPE MANHOLE	707241
72" REINFORCED CONCRETE PIPE	650050
72" WELDED STEEL PIPE (.250" THICK)	703715
75 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	208023

ITEM DESCRIPTION	ITEM CODE
0 - 9	
750 MM ALTERNATIVE FLARED END SECTION	705338
750 MM ALTERNATIVE PIPE CULVERT	620919
750 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK)	664105
750 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	490658
750 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	664028
750 MM REINFORCED CONCRETE PIPE	650077
750 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650129
750 MM TEMPORARY CULVERT	073030
78" CAST-IN-DRILLED-HOLE CONCRETE PILING	490614
8' CHAIN LINK GATE (TYPE CL-6)	802540
8" ALTERNATIVE CONDUIT	208718
8" ALTERNATIVE PIPE UNDERDRAIN	685020
8" ANCHOR ASSEMBLY	692303
8" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208738
8" CORRUGATED STEEL FLUME DOWNDRAIN	691003
8" CORRUGATED STEEL PIPE (.064" THICK)	665005
8" CORRUGATED STEEL PIPE (.079" THICK)	665006
8" CORRUGATED STEEL PIPE DOWNDRAIN	690104
8" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	690105
8" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690106
8" DOWNDRAIN SLIP JOINT	692203
8" ENTRANCE TAPER	692003
8" PERFORATED PLASTIC PIPE UNDERDRAIN	680905
8" PERFORATED STEEL PIPE UNDERDRAIN (.064" THICK)	680405
8" PERFORATED STEEL PIPE UNDERDRAIN (.079" THICK)	680406
8" THERMOPLASTIC TRAFFIC STRIPE	840506
8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	840508
8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	840550

ITEM DESCRIPTION	ITEM CODE
0 - 9	
8" TWO-COMPONENT PAINT TRAFFIC STRIPE	840584
8" WELDED STEEL PIPE CONDUIT (.250" THICK)	208808
90" CAST-IN-DRILLED-HOLE CONCRETE PILING	490617
900 MM ALTERNATIVE FLARED END SECTION	705339
900 MM ALTERNATIVE PIPE CULVERT	620924
900 MM ALTERNATIVE PIPE INLET	708058
900 MM AUTOMATIC DRAINAGE GATE	705569
900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK)	664110
900 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	490675
900 MM CONCRETE FLARED END SECTION	705227
900 MM CORRUGATED STEEL PIPE (3.51 MM THICK)	664035
900 MM CORRUGATED STEEL PIPE INLET (2.77 MM THICK)	700659
900 MM PRECAST CONCRETE PIPE INLET	707133
900 MM PRECAST CONCRETE PIPE MANHOLE	707244
900 MM PRECAST CONCRETE PIPE RISER	707471
900 MM REINFORCED CONCRETE PIPE	650079
900 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650130
900 MM TEMPORARY CULVERT	073031
920 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561009
96" CAST-IN-DRILLED-HOLE CONCRETE PILING	490618
A	
ABANDON CULVERT	150206
ABANDON INLET	150221
ABANDON MANHOLE	150224
ABANDON PIPELINE	150227
ABANDON SEWER	150241
ABANDON WATER WELL	150229
ABUTMENT LUMBER BLOCKING	570115

ITEM DESCRIPTION	ITEM CODE
A	
ACCESS GATE (SOUND WALL)	518010
ACCESS OPENING, DECK	153530
ACCESS OPENING, SOFFIT	153531
ADJUST FRAME AND COVER TO GRADE	152438
ADJUST FRAME AND GRATE TO GRADE	152439
ADJUST INLET	152430
ADJUST MANHOLE	152432
ADJUST MANHOLE TO GRADE	152440
ADJUST METAL BEAM GUARD RAILING	152500
ADJUST MONUMENT COVER	152422
ADJUST MONUMENT TO GRADE	152423
ADJUST OVERSIDE DRAIN	152437
ADJUST PULL BOX	869042
ADJUST RISER	152434
ADJUST SLOTTED DRAIN TO GRADE	152555
ADJUST UTILITY COVER TO GRADE	152469
ADJUST VALVE BOX FRAME AND COVER TO GRADE	152441
ADJUST WATER METER BOX TO GRADE	152403
ADJUST WATER VALVE COVER TO GRADE	152402
ADL BURIAL LOCATION REPORT	190111
AGGREGATE BASE (APPROACH SLAB)	260210
ALTERNATIVE FLARED END SECTION	705300
ALTERNATIVE FLARED TERMINAL SYSTEM	839585
ALTERNATIVE IN-LINE TERMINAL SYSTEM	839584
ANCHOR ASSEMBLY	692301
ANCHOR POST	839529
ANTI-GRAFFITI COATING	511047
ARCHITECTURAL SURFACE (BARRIER)	511036
ARCHITECTURAL TREATMENT	511035
ASBESTOS COMPLIANCE PLAN	190113
ASBESTOS COMPLIANCE PLAN (NATURALLY OCCURING ASBESTOS)	190115
ASPHALT MEMBRANE WATERPROOFING	540101

ITEM DESCRIPTION	ITEM CODE
A	
ASPHALT TREATED PERMEABLE BASE	290201
ASPHALTIC EMULSION	373900
ASPHALTIC EMULSION (CURING SEAL)	270065
ASPHALTIC EMULSION (FOG SEAL COAT)	374002
ASPHALTIC EMULSION (PAINT BINDER)	397001
ASPHALTIC EMULSION (POLYMER MODIFIED)	374492
ASPHALTIC EMULSION MEMBRANE (BONDED WEARING COURSE)	390151
ASPHALT-RUBBER BINDER	370120
B	
BACKFLOW PREVENTER ASSEMBLY BLANKETS	208439
BACKFLOW PREVENTER ASSEMBLY ENCLOSURE	208421
BALL VALVE	208683
BAR REINFORCING STEEL	520101
BAR REINFORCING STEEL (BOX CULVERT)	520107
BAR REINFORCING STEEL (BRIDGE)	520102
BAR REINFORCING STEEL (EPOXY COATED)	520106
BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	520110
BAR REINFORCING STEEL (RETAINING WALL)	520103
BAR REINFORCING STEEL (SOUND WALL)	520105
BAR REINFORCING STEEL, RETAINING WALL (SOUND WALL)	520114
BENCH	994425
BLANK WELL CASING	760030
BOOSTER PUMP	209502
BOOSTER PUMP ELECTRICAL SYSTEM	860798
BRIDGE DECK DRAINAGE SYSTEM	750505
BRIDGE REMOVAL	157550
BRIDGE REMOVAL (PORTION)	157560
BRIDGE REMOVAL (PORTION), LOCATION A	157561
BRIDGE REMOVAL (PORTION), LOCATION B	157562

ITEM DESCRIPTION	ITEM CODE
B	
BRIDGE REMOVAL (PORTION), LOCATION C	157563
BRIDGE REMOVAL (PORTION), LOCATION D	157564
BRIDGE REMOVAL (PORTION), LOCATION E	157565
BRIDGE REMOVAL (PORTION), LOCATION F	157566
BRIDGE REMOVAL (PORTION), LOCATION G	157567
BRIDGE REMOVAL (PORTION), LOCATION H	157568
BRIDGE REMOVAL (PORTION), LOCATION I	157569
BRIDGE REMOVAL (PORTION), LOCATION J	157570
BRIDGE REMOVAL (PORTION), LOCATION K	157571
BRIDGE REMOVAL (PORTION), LOCATION M	157573
BRIDGE REMOVAL, LOCATION A	157551
BRIDGE REMOVAL, LOCATION B	157552
BRIDGE REMOVAL, LOCATION C	157553
BRIDGE REMOVAL, LOCATION I	157559
BUILDING WORK	994650
C	
CABLE ANCHORAGE SYSTEM	692409
CABLE RAILING	839521
CALIFORNIA ST-10 BRIDGE RAIL	839740
CAM COUPLER ASSEMBLY	208562
CAP INLET	155003
CAP MANHOLE	155007
CAP RISER	155006
CEMENT TREATED BASE (PLANT-MIXED, CLASS A)	270011
CHAIN LINK FENCE	800300
CHAIN LINK FENCE (TYPE CL-0.9)	800381
CHAIN LINK FENCE (TYPE CL-1.2)	800385
CHAIN LINK FENCE (TYPE CL-1.8)	800391
CHAIN LINK FENCE (TYPE CL-3, VINYL-CLAD)	800302
CHAIN LINK FENCE (TYPE CL-4)	800320

ITEM DESCRIPTION	ITEM CODE
C	
CHAIN LINK FENCE (TYPE CL-4, VINYL-CLAD)	800321
CHAIN LINK FENCE (TYPE CL-6)	800360
CHAIN LINK FENCE (TYPE CL-6, SLATTED)	800365
CHAIN LINK FENCE (TYPE CL-6, VINYL-CLAD)	800361
CHAIN LINK FENCE (TYPE CL-8)	800400
CHAIN LINK GATE	801900
CHAIN LINK RAILING	833020
CHAIN LINK RAILING (TYPE 4)	833024
CHAIN LINK RAILING (TYPE 7 MODIFIED)	833033
CHAIN LINK RAILING (TYPE 7)	833032
CHAIN LINK RAILING (TYPE 7L)	833034
CHANGEABLE MESSAGE SIGN SYSTEM	860530
CHANNELIZER (SURFACE MOUNTED)	120165
CHANNELIZER (SURFACE MOUNTED) (LEFT IN PLACE)	120166
CHECK VALVE	208670
CLASS 1 AGGREGATE SUBBASE	250101
CLASS 1 CONCRETE (BOX CULVERT)	510413
CLASS 1 CONCRETE (MINOR STRUCTURE)	510409
CLASS 1 CONCRETE (STRUCTURE)	510410
CLASS 1 PERMEABLE MATERIAL	682020
CLASS 1 PERMEABLE MATERIAL (BLANKET)	682022
CLASS 2 AGGREGATE BASE	260201
CLASS 2 AGGREGATE SUBBASE	250201
CLASS 2 CONCRETE (HEADWALL)	510135
CLASS 2 CONCRETE (MINOR STRUCTURE)	510126
CLASS 2 CONCRETE (WINGWALLS)	510138
CLASS 3 AGGREGATE BASE	260301
CLASS 3 AGGREGATE SUBBASE	250301
CLASS 3 PERMEABLE MATERIAL	682045
CLASS 3 PERMEABLE MATERIAL (BLANKET)	682049
CLASS 4 AGGREGATE SUBBASE	250401

ITEM DESCRIPTION	ITEM CODE
C	
CLASS 4 CONCRETE (BACKFILL)	510314
CLASS 4 CONCRETE (BACKFILL)	719598
CLEAN AND PAINT STRUCTURAL STEEL	590115
CLEAN AND PAINT STRUCTURAL STEEL (EXISTING BRIDGE)	590116
CLEAN BRIDGE DECK	153235
CLEAN EXPANSION JOINT	511118
CLEAN STRUCTURAL STEEL (EXISTING BRIDGE)	590106
CLEANING, INSPECTING AND PREPARING HOST PIPE	155210
CLEANOUT ASSEMBLY	680254
CLEARING AND GRUBBING	160101
CLOSE ACCESS, DECK	511125
CLOSED CIRCUIT TELEVISION SYSTEM	860990
COBBLESTONE PAVING	722009
COLD FOAM IN-PLACE RECYCLING	397100
COLD PLANE ASPHALT CONCRETE PAVEMENT	153103
COLD PLANE ASPHALT CONCRETE PAVEMENT (.10' MAXIMUM)	153110
COLD PLANE ASPHALT CONCRETE PAVEMENT (.15' MAXIMUM)	153112
COLD PLANE ASPHALT CONCRETE PAVEMENT (.20' MAXIMUM)	153114
COLD PLANE ASPHALT CONCRETE PAVEMENT (.25' MAXIMUM)	153116
COLUMN CASING	550110
COMMERCIAL FERTILIZER	202018
COMMERCIAL FERTILIZER (GRANULAR)	202030
COMMERCIAL FERTILIZER (PACKET)	202033
COMMERCIAL FERTILIZER (SLOW RELEASE)	202031
COMMUNICATION CONDUIT (BRIDGE)	860792
COMPOST (INCORPORATE)	203025
COMPOST SOCK	203023
CONCRETE (CHANNEL LINING)	721430
CONCRETE (CONCRETE APRON)	721431

ITEM DESCRIPTION	ITEM CODE
C	
CONCRETE (CONCRETED-ROCK SLOPE PROTECTION)	721501
CONCRETE (DITCH LINING)	721420
CONCRETE (SLOPE PROTECTION)	721400
CONCRETE BACKFILL	193118
CONCRETE BACKFILL (SOLDIER PILE WALL)	193116
CONCRETE BACKFILL FAST SETTING	193117
CONCRETE BARRIER	839401
CONCRETE BARRIER (TYPE 25 MODIFIED)	833128
CONCRETE BARRIER (TYPE 25)	833125
CONCRETE BARRIER (TYPE 25A MODIFIED)	833129
CONCRETE BARRIER (TYPE 25B)	833127
CONCRETE BARRIER (TYPE 25R MODIFIED)	833136
CONCRETE BARRIER (TYPE 26 MODIFIED)	833142
CONCRETE BARRIER (TYPE 26)	833140
CONCRETE BARRIER (TYPE 26A MODIFIED)	833143
CONCRETE BARRIER (TYPE 26R MODIFIED)	833148
CONCRETE BARRIER (TYPE 27 MODIFIED)	833187
CONCRETE BARRIER (TYPE 27A MODIFIED)	833159
CONCRETE BARRIER (TYPE 28)	833190
CONCRETE BARRIER (TYPE 50A)	839483
CONCRETE BARRIER (TYPE 60)	839701
CONCRETE BARRIER (TYPE 60A)	839702
CONCRETE BARRIER (TYPE 60C)	839703
CONCRETE BARRIER (TYPE 60D)	839704
CONCRETE BARRIER (TYPE 60E)	839705
CONCRETE BARRIER (TYPE 60G)	839706
CONCRETE BARRIER (TYPE 60GC)	839708
CONCRETE BARRIER (TYPE 60GE)	839709
CONCRETE BARRIER (TYPE 60S)	839710
CONCRETE BARRIER (TYPE 60SC)	839712
CONCRETE BARRIER (TYPE 60SE)	839713

ITEM DESCRIPTION	ITEM CODE
C	
CONCRETE BARRIER (TYPE 732 MODIFIED)	839717
CONCRETE BARRIER (TYPE 732)	839720
CONCRETE BARRIER (TYPE 732A)	839721
CONCRETE BARRIER (TYPE 732B)	839723
CONCRETE BARRIER (TYPE 732R)	839718
CONCRETE BARRIER (TYPE 736 MODIFIED)	839727
CONCRETE BARRIER (TYPE 736)	839725
CONCRETE BARRIER (TYPE 736A)	839726
CONCRETE BARRIER (TYPE 736B)	839731
CONCRETE BARRIER (TYPE 736R)	839728
CONCRETE BARRIER (TYPE 736SV)	839734
CONCRETE BARRIER (TYPE 742)	839735
CONCRETE BARRIER (TYPE 742A)	839736
CONCRETE BARRIER (TYPE 742B)	839737
CONCRETE BARRIER (TYPE K)	833080
CONCRETE INVERT PAVING	155230
CONCRETE PAVEMENT	401000
CONCRETE PAVEMENT (RAMP TERMINI)	401066
CONCRETE PAVEMENT (WEIGH-IN-MOTION)	401102
CONCRETE SEWER MANHOLE	719210
CONCRETED-ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	721607
CONCRETED-ROCK SLOPE PROTECTION (LIGHT, METHOD B)	721608
CONDUCTOR CASING	760025
CONSTRUCTION AREA SIGNS	120090
CONSTRUCTION SITE MANAGEMENT	074016
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT	400050
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (EXPANSION JOINT, TYPE AN)	400090
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (EXPANSION JOINT, TYPE WF)	400092
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (PAVEMENT ANCHOR)	400075
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE A)	400061

ITEM DESCRIPTION	ITEM CODE
C	
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE B)	400062
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE C)	400063
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE D)	400064
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE E)	400065
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (WIDE FLANGE BEAM TERMINAL)	400080
CONTOUR GRADING	197003
CONTRACTOR SUPPLIED BIOLOGIST (DAY)	146001
CONTRACTOR SUPPLIED BIOLOGIST (LS)	146002
CONTROL AND NEUTRAL CONDUCTORS	206560
CORE CONCRETE (1 1/2")	515160
CORE CONCRETE (1 1/8")	515157
CORE CONCRETE (10")	515070
CORE CONCRETE (12")	515069
CORE CONCRETE (2")	515061
CORE CONCRETE (6")	515065
CORE CONCRETE (7")	515066
CORE CONCRETE (8")	515067
CORE CONCRETE (9")	515068
CORRUGATED STEEL FLUME DOWNDRAIN	691001
CRACK EXISTING CONCRETE PAVEMENT	415101
CRACK TREATMENT	374207
CRASH CUSHION (ADIEM)	839603
CRASH CUSHION (REACT 9CBB)	839604
CRASH CUSHION (REACT 9SCBS)	839605
CRASH CUSHION (TYPE CAT)	839601
CRASH CUSHION (TYPE CAT) BACKUP	839602
CRASH CUSHION MODULE, SAND FILLED	839631
CRASH CUSHION, SAND FILLED	839591
CULTIVATE	200120
CULVERT CONTACT GROUTING	155220

ITEM DESCRIPTION	ITEM CODE
C	
CURB DRAIN	719530
CURB RAMP DETECTABLE WARNING SURFACE	731656
D	
DATA CORE	394060
DEBRIS RACK CAGE	706584
DECK SEAL	540100
DECOMPOSED GRANITE (MISCELLANEOUS AREAS) (SQFT)	200117
DECOMPOSED GRANITE (MISCELLANEOUS AREAS) (SQYD)	200118
DELINEATOR (CLASS 1)	820107
DELINEATOR (CLASS 2)	820108
DESTROY WELL	150230
DETECTOR LOOP	860811
DEVELOP WATER SUPPLY	170101
DIAPHRAGM BOLSTER	510805
DITCH EXCAVATION	194001
DOUBLE METAL BEAM BARRIER	839201
DOUBLE METAL BEAM GUARD RAILING (WOOD POST)	839220
DOUBLE THRIE BEAM BARRIER	839310
DOUBLE THRIE BEAM BARRIER (STEEL POST)	839312
DOUBLE THRIE BEAM BARRIER (WOOD POST)	839311
DOWEL BAR (DRILL AND BOND)	406050
DOWEL BAR RETROFIT	406100
DRAINAGE INLET	707050
DRAINAGE INLET MARKER	700617
DRAINAGE MANHOLE	707051
DRAINAGE PUMPING EQUIPMENT	740500
DRILL AND BOND DOWEL	511106
DRILL AND BOND DOWEL (CHEMICAL ADHESIVE)	511110
DRILL PILOT HOLE	760021

ITEM DESCRIPTION	ITEM CODE
D	
DRIVE 18" CAST-IN-STEEL SHELL CONCRETE PILE	495107
DRIVE 24" CAST-IN-STEEL SHELL CONCRETE PILE	495116
DRIVE 36" CAST-IN-STEEL SHELL CONCRETE PILE	495134
DRIVE 48" CAST-IN-STEEL SHELL CONCRETE PILE	495150
DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (610 MM)	499031
DRIVE PILE (CLASS 140)	490739
DRIVE PILE (CLASS 140) (ALTERNATIVE W)	490747
DRIVE PILE (CLASS 200) (ALTERNATIVE W)	490783
DRIVE PILE (CLASS 400) (ALTERNATIVE V)	491010
DRIVE PILE (CLASS 400) (ALTERNATIVE W)	491013
DRIVE PILE (CLASS 625) (ALTERNATIVE W)	490773
DRIVE PILE (CLASS 90)	490737
DRIVE PILE (CLASS 90) (ALTERNATIVE V)	490741
DRIVE PILE (CLASS 90) (ALTERNATIVE W)	490743
DRIVE PILE (CLASS 900) (ALTERNATIVE W)	490701
DRIVE PILING (CLASS 200)	490752
DRIVE STEEL PILE (HP 10 X 42)	490504
DRIVE STEEL PILE (HP 10 X 57)	490509
DRIVE STEEL PILE (HP 14 X 117)	490539
DRIVE STEEL PILE (HP 14 X 89)	490529
DRIVE STEEL PILE (HP 250 X 85)	490512
DRIVE STEEL PIPE PILE (610 MM)	490585
DUFF	202007
DUST CONTROL PLAN	190114
DUST CONTROL PLAN (NATURALLY OCCURRING ASBESTOS)	190116
E	
EARTH RETAINING STRUCTURE	197020
EARTH RETAINING STRUCTURE (GUARD RAILING)	197030
EARTH RETAINING STRUCTURE, LOCATION A	197021

ITEM DESCRIPTION	ITEM CODE
E	
EARTH RETAINING STRUCTURE, LOCATION B	197022
EARTH RETAINING STRUCTURE, LOCATION C	197023
EARTH RETAINING STRUCTURE, LOCATION D	197024
EARTH RETAINING STRUCTURE, LOCATION E	197025
ELECTRIC SERVICE (IRRIGATION)	860797
ELECTRICAL WORK	991061
EMBANKMENT	198050
END ANCHOR ASSEMBLY (TYPE CA)	839582
END ANCHOR ASSEMBLY (TYPE SFT)	839581
END CAP	839555
END CAP (TYPE A)	839576
END CAP (TYPE TA)	839577
END CAP (TYPE TC)	839578
END SECTION	839553
ENTRANCE TAPER	692001
EPOXY ADHESIVE (BOND COAT)	511115
ERECT PRECAST CONCRETE GIRDER	512401
ERECT PRECAST PRESTRESSED CONCRETE BOX GIRDER	512502
ERECT PRECAST PRESTRESSED CONCRETE DECK UNIT	512510
ERECT PRECAST PRESTRESSED CONCRETE GIRDER	512500
ERECT STRUCTURAL STEEL (BRIDGE)	550204
EROSION CONTROL (BLANKET)	203001
EROSION CONTROL (BONDED FIBER MATRIX) (ACRE)	203028
EROSION CONTROL (BONDED FIBER MATRIX) (SQFT)	203027
EROSION CONTROL (COMPOST BLANKET)	203002
EROSION CONTROL (DRILL SEED) (ACRE)	203005
EROSION CONTROL (DRY SEED) (ACRE)	203007
EROSION CONTROL (DRY SEED) (SQFT)	203006
EROSION CONTROL (HYDRAULIC MATRIX)	203017
EROSION CONTROL (HYDROSEED) (ACRE)	203032

ITEM DESCRIPTION	ITEM CODE
E	
EROSION CONTROL (HYDROSEED) (SQFT)	203031
EROSION CONTROL (NETTING)	203018
EROSION CONTROL (POLYMER STABILIZED FIBER MATRIX) (ACRE)	203030
EROSION CONTROL (POLYMER STABILIZED FIBER MATRIX) (SQFT)	203029
EROSION CONTROL (PUNCHED STRAW) (SQFT)	203008
EROSION CONTROL (TYPE C)	203011
EROSION CONTROL (TYPE D)	203016
EROSION CONTROL HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	203022
EXPOSED AGGREGATE FINISH	511045
EXTEND 10" CONDUIT	208907
EXTEND 200 MM CONDUIT	208909
EXTEND 250 MM CONDUIT	208910
EXTEND 6" CONDUIT	208905
EXTEND 8" CONDUIT	208906
EXTENDED PLANT ESTABLISHMENT WORK	204101
EXTINGUISHABLE MESSAGE SIGN	860503
EXTINGUISHABLE MESSAGE SIGN SYSTEM	860504
F	
FENCE (TYPE BW, 4-STRAND, METAL POST)	800008
FENCE (TYPE BW, 4-STRAND, WOOD POST)	800010
FENCE (TYPE BW, 5 STRAND, METAL POST)	800007
FENCE (TYPE BW, METAL POST)	800001
FENCE (TYPE WM AND BW)	800060
FENCE (TYPE WM, METAL POST)	800051
FENCE (TYPE WM, WOOD POST)	800052
FIBER ROLLS	203021
FILTER ASSEMBLY UNIT	208560
FILTER FABRIC	681990
FILTER FABRIC	729000
FINISHING ROADWAY	220101

ITEM DESCRIPTION	ITEM CODE
F	
FISH PROTECTION	146004
FLASHING BEACON (PORTABLE)	120200
FLUME ANCHOR ASSEMBLY	692361
FLUME DOWNDRAIN	691900
FOLIAGE PROTECTOR	205051
FRACTURED FIN TEXTURE	511063
FRACTURED RIB TEXTURE	511064
FRAME AND GRATE	750007
FURNISH 18" CAST-IN-STEEL SHELL CONCRETE PILING	495106
FURNISH 24" CAST-IN-STEEL SHELL CONCRETE PILING	495115
FURNISH 36" CAST-IN-STEEL SHELL CONCRETE PILING	495133
FURNISH 48" CAST-IN-STEEL SHELL CONCRETE PILING	495149
FURNISH AND INSTALL DRAIN PIPE (HORIZONTAL DRAIN)	681501
FURNISH BRIDGE DECK TREATMENT MATERIAL	540108
FURNISH BRIDGE DECK TREATMENT MATERIAL (LOW ODOR)	540109
FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (610 MM)	499030
FURNISH FORMED PANEL SIGN (OVERHEAD)	560233
FURNISH LAMINATED PANEL SIGN (1"-TYPE A)	560244
FURNISH LAMINATED PANEL SIGN (1"-TYPE B)	560245
FURNISH LAMINATED PANEL SIGN (2 1/2"-TYPE B)	560246
FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE A)	560234
FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE B)	560235
FURNISH LAMINATED PANEL SIGN (63.5 MM-TYPE B)	560236
FURNISH LAMINATED PANEL SIGN (63.5 MM-TYPE H)	560237
FURNISH PILE (CLASS 200)	490751
FURNISH PILING (CLASS 140)	490738
FURNISH PILING (CLASS 140) (ALTERNATIVE W)	490746

ITEM DESCRIPTION	ITEM CODE
F	
FURNISH PILING (CLASS 200) (ALTERNATIVE W)	490782
FURNISH PILING (CLASS 400) (ALTERNATIVE V)	491009
FURNISH PILING (CLASS 400) (ALTERNATIVE W)	491012
FURNISH PILING (CLASS 625) (ALTERNATIVE W)	490772
FURNISH PILING (CLASS 90)	490736
FURNISH PILING (CLASS 90) (ALTERNATIVE V)	490740
FURNISH PILING (CLASS 90) (ALTERNATIVE W)	490742
FURNISH PILING (CLASS 900) (ALTERNATIVE W)	490700
FURNISH POLYESTER CONCRETE OVERLAY	515041
FURNISH PRECAST PRESTRESSED CONCRETE BOX GIRDER (70'-80')	512224
FURNISH PRECAST PRESTRESSED CONCRETE BOX GIRDER (90'-100')	512226
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (100'-110')	512279
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (110'-120')	512280
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (35 M-40 M)	512256
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (60'-70')	512290
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (80'-90')	512277
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (30'-40')	512202
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (40'-50')	512203
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (60'-70')	512205
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (70'-80')	512206
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (80'-90')	512207
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (90'-100')	512208
FURNISH PRECAST PRESTRESSED CONCRETE SLAB	512350
FURNISH PRECAST PRESTRESSED CONCRETE SLAB (TYPE SII)	512352
FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	560203

ITEM DESCRIPTION	ITEM CODE
F	
FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY)	560223
FURNISH SIGN STRUCTURE (LIGHTWEIGHT)	560213
FURNISH SIGN STRUCTURE (TRUSS)	560218
FURNISH SIGN STRUCTURE (TUBULAR)	560208
FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-FRAMED)	560251
FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	560248
FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED)	560252
FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED)	560249
FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-FRAMED)	560241
FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-UNFRAMED)	560238
FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-FRAMED)	560242
FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-UNFRAMED)	560239
FURNISH STEEL PILING (HP 10 X 42)	490503
FURNISH STEEL PILING (HP 10 X 57)	490508
FURNISH STEEL PILING (HP 14 X 117)	490538
FURNISH STEEL PILING (HP 14 X 89)	490528
FURNISH STEEL PILING (HP 250 X 85)	490511
FURNISH STEEL PIPE PILING (610 MM)	490584
FURNISH STRUCTURAL STEEL (BRIDGE)	550203
G	
GABION	722020
GEOCOMPOSITE DRAIN	681132
GEOSYNTHETIC PAVEMENT INTERLAYER	393003
GEOSYNTHETIC REINFORCEMENT	198250
GRATED LINE DRAIN	703233
GRAVEL (MISCELLANEOUS AREAS) (SQFT)	200115
GRAVEL (MISCELLANEOUS AREAS) (SQYD)	200116
GRIND BRIDGE DECK	515050
GRIND EXISTING CONCRETE PAVEMENT	420201

ITEM DESCRIPTION	ITEM CODE
G	
GROOVE EXISTING CONCRETE PAVEMENT	420102
GUARD POST	869050
GUARD RAILING DELINEATOR	820118
H	
HANDRAILING	839514
HDPE PLASTIC PIPELINER (16" OD SDR 32.5)	155530
HDPE PLASTIC PIPELINER (22" OD SDR 32.5)	155533
HDPE PLASTIC PIPELINER (28" OD SDR 32.5)	155536
HDPE PLASTIC PIPELINER (30" OD SDR 26)	155554
HDPE PLASTIC PIPELINER (42" OD SDR 26)	155559
HEADED BAR REINFORCEMENT	520120
HEADER BOARD	206003
HEALTH AND SAFETY PLAN	074018
HIGHWAY ADVISORY RADIO SYSTEM	860520
HIGHWAY LIGHTING	860403
HIGHWAY PLANTING	200001
HOT MIX ASPHALT	390130
HOT MIX ASPHALT	390131
HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	390141
HOT MIX ASPHALT (LEVELING)	390135
HOT MIX ASPHALT (OPEN GRADED)	390134
HOT MIX ASPHALT (TYPE A)	390132
HOT MIX ASPHALT (TYPE B)	390133
HOT MIX ASPHALT (TYPE C)	390129
HOT MIX ASPHALT DIKE	394070
I	
IMPERMEABLE MEMBRANE	682007
IMPORTED BORROW	198001
IMPORTED BORROW (CY)	198001
IMPORTED BORROW (LIGHTWEIGHT AGGREGATE)	198009

ITEM DESCRIPTION	ITEM CODE
I	
IMPORTED MATERIAL (SHOULDER BACKING)	198007
IMPORTED ROCKY MATERIAL	198021
IMPORTED TOPSOIL	200101
IMPORTED TOPSOIL (CY)	200102
INDIVIDUAL SLAB REPLACEMENT (RSC)	411105
INDUCTIVE LOOP DETECTOR	860810
INJECT CRACK (EPOXY)	511130
INLET FRAME AND GRATE	750030
INLET GRATE (TYPE 36R)	750049
INSTALL DRAINAGE INLET MARKER	700619
INSTALL MEDIAN MILEAGE PANEL	820180
INSTALL ROADSIDE SIGN (LAMINATED WOOD BOX POST)	568023
INSTALL ROADSIDE SIGN PANEL ON EXISTING POST	568017
INSTALL SIGN (MAST-ARM HANGER METHOD)	568015
INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	568001
INSTALL SIGN OVERLAY	568007
INSTALL SIGN PANEL ON EXISTING FRAME	568016
INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	560204
INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY)	560224
INSTALL SIGN STRUCTURE (LIGHTWEIGHT)	560214
INSTALL SIGN STRUCTURE (TRUSS)	560219
INSTALL SIGN STRUCTURE (TUBULAR)	560209
INTERCONNECTION CONDUIT AND CABLE	860703
INTERCONNECTION CONDUIT AND CONDUCTOR	860701
IRON SULFATE	202003
IRRIGATION CONTROLLER (BATTERY)	206929
IRRIGATION CONTROLLER ENCLOSURE CABINET	208301
IRRIGATION SLEEVE	208310
IRRIGATION SYSTEM	208000
ISOLATION CASING	750041

ITEM DESCRIPTION	ITEM CODE
J	
JACKED 1050 MM REINFORCED CONCRETE PIPE (CLASS III)	655370
JACKED 18" REINFORCED CONCRETE PIPE (CLASS III)	655311
JACKED 1800 MM REINFORCED CONCRETE PIPE (CLASS V)	655581
JACKED 24" REINFORCED CONCRETE PIPE (CLASS II)	655212
JACKED 24" REINFORCED CONCRETE PIPE (CLASS IV)	655416
JACKED 24" REINFORCED CONCRETE PIPE (CLASS V)	655516
JACKED 36" REINFORCED CONCRETE PIPE (CLASS III)	655324
JACKED 42" WELDED STEEL PIPE (.375" THICK)	704245
JACKED 450 MM REINFORCED CONCRETE PIPE (CLASS V)	655572
JACKED 48" REINFORCED CONCRETE PIPE (CLASS V)	655532
JACKED 600 MM REINFORCED CONCRETE PIPE (CLASS III)	655367
JACKED 750 MM REINFORCED CONCRETE PIPE (CLASS III)	655368
JACKED 900 MM REINFORCED CONCRETE PIPE (CLASS III)	655369
JACKED 900 MM REINFORCED CONCRETE PIPE (CLASS V)	655576
JOINT SEAL (ASPHALTIC PLUG)	519133
JOINT SEAL (MR 1 1/2")	519091
JOINT SEAL (MR 1")	519088
JOINT SEAL (MR 1/2")	519081
JOINT SEAL (MR 15 MM)	519120
JOINT SEAL (MR 2")	519100
JOINT SEAL (MR 40 MM)	519142
JOINT SEAL (MR 50 MM)	519144
JOINT SEAL (TYPE AL)	519102
JOINT SEAL ASSEMBLY (MR 100 MM)	519128
JOINT SEAL ASSEMBLY (MR 101 MM - 160 MM)	519129
JOINT SEAL ASSEMBLY (MR 161 MM - 240 MM)	519130
JOINT SEAL ASSEMBLY (MR 2 1/2")	519092
JOINT SEAL ASSEMBLY (MR 3 1/2")	519094

ITEM DESCRIPTION	ITEM CODE
J	
JOINT SEAL ASSEMBLY (MR 3")	519093
JOINT SEAL ASSEMBLY (MR 4 1/2")	519096
JOINT SEAL ASSEMBLY (MR 4")	519095
JOINT SEAL ASSEMBLY (MR 5")	519097
JOINT SEAL ASSEMBLY (MR 6")	519099
JOINT SEAL ASSEMBLY (MR 60 MM)	519124
JOINT SEAL ASSEMBLY (MR 7")	519105
JOINT SEAL ASSEMBLY (MR 80 MM)	519126
JOINT SEAL ASSEMBLY (MR 9")	519118
JOINT SEAL ASSEMBLY (MR 90 MM)	519127
JOINTED PLAIN CONCRETE PAVEMENT	401050
L	
LEAD COMPLIANCE PLAN	190110
LEAN CONCRETE BACKFILL	193119
LEAN CONCRETE BASE	280000
LIGHTING	860401
LIGHTING (AREA)	862026
LIGHTING (CITY STREET)	860402
LIGHTING (NAVIGATION)	860430
LIGHTING (PARKING LOT)	860407
LIGHTING (STAGE CONSTRUCTION)	860415
LIGHTING (TEMPORARY)	860400
LIGHTING AND SIGN ILLUMINATION	860460
LIGHTING AND SIGN ILLUMINATION (LOCATION 1)	860551
LIGHTING AND SIGN ILLUMINATION (LOCATION 2)	860552
LIGHTING AND SIGN ILLUMINATION (LOCATION 3)	860553
LIGHTING AND SIGN ILLUMINATION (LOCATION 4)	860554
LIGHTING AND SIGN ILLUMINATION (LOCATION 5)	860555
LIGHTING AND SIGN ILLUMINATION (LOCATION 6)	860556
LIGHTWEIGHT CONCRETE	511001

ITEM DESCRIPTION	ITEM CODE
L	
LIQUID ASPHALT (PRIME COAT)	395000
M	
MAINTAIN EXISTING IRRIGATION FACILITIES	206401
MAINTAIN EXISTING PLANTED AREAS	204096
MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	860090
MAINTENANCE VEHICLE PULLOUT	209801
MANHOLE	719300
MANHOLE (TYPE A)	719305
MANHOLE (TYPE B)	719306
MANHOLE FRAME AND COVER	750010
MANHOLE FRAME AND GRATE	750011
MARKER	820101
MARKER (CULVERT)	820112
METAL (BARRIER MOUNTED SIGN)	562002
METAL (RAIL MOUNTED SIGN)	562004
METAL (ROADSIDE SIGN)	562001
METAL BEAM GUARD RAILING	832001
METAL BEAM GUARD RAILING (7' POST)	832013
METAL BEAM GUARD RAILING (7' WOOD POST)	832012
METAL BEAM GUARD RAILING (8' POST)	832014
METAL BEAM GUARD RAILING (SPECIAL)	832004
METAL BEAM GUARD RAILING (STEEL POST)	832002
METAL BEAM GUARD RAILING (WOOD POST)	832003
METAL TUBE BRIDGE RAILING	833092
MICRO-SURFACING	378000
MICROWAVE VEHICLE DETECTION SYSTEM	860812
MILEPOST MARKER	820110
MINOR CONCRETE	510501
MINOR CONCRETE (BACKFILL)	510526
MINOR CONCRETE (BACKFILL)	719589

ITEM DESCRIPTION	ITEM CODE
M	
MINOR CONCRETE (CHANNEL LINING)	727905
MINOR CONCRETE (CONCRETE MOW STRIP)	731509
MINOR CONCRETE (CURB AND CURB RAMP)	731626
MINOR CONCRETE (CURB AND GUTTER)	731504
MINOR CONCRETE (CURB AND SIDEWALK)	731505
MINOR CONCRETE (CURB RAMP)	731623
MINOR CONCRETE (CURB)	731501
MINOR CONCRETE (CURB, GUTTER, SIDEWALK AND DRIVEWAY)	731510
MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP)	731627
MINOR CONCRETE (DITCH LINING)	727901
MINOR CONCRETE (DRIVEWAY)	731516
MINOR CONCRETE (EXPOSED AGGREGATE CONCRETE)	731508
MINOR CONCRETE (GUTTER DEPRESSION)	731507
MINOR CONCRETE (GUTTER LINING)	727906
MINOR CONCRETE (GUTTER)	731517
MINOR CONCRETE (ISLAND PAVING)	731511
MINOR CONCRETE (MINOR STRUCTURE)	510502
MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	731502
MINOR CONCRETE (PIPE ENCASEMENT)	510504
MINOR CONCRETE (SIDEWALK)	731521
MINOR CONCRETE (SLOPE PROTECTION)	727902
MINOR CONCRETE (SOUND WALL)	510524
MINOR CONCRETE (STAMPED CONCRETE)	731519
MINOR CONCRETE (TEXTURED PAVING)	731530
MINOR CONCRETE (WALL)	510530
MINOR HOT MIX ASPHALT	390136
MISCELLANEOUS ELECTRICAL	869001
MISCELLANEOUS IRON AND STEEL	750001
MISCELLANEOUS METAL	750500
MISCELLANEOUS METAL (BRIDGE)	750501

ITEM DESCRIPTION	ITEM CODE
M	
MISCELLANEOUS METAL (RESTRAINER - BAR TYPE)	750497
MISCELLANEOUS METAL (RESTRAINER - CABLE TYPE)	750498
MISCELLANEOUS METAL (RESTRAINER - PIPE TYPE)	750496
MOBILIZATION	999990
MOBILIZATION, DEMOBILIZATION, AND FINAL CLEANUP	760090
MODIFY CHAIN LINK FENCE	152650
MODIFY FLASHING BEACON	860615
MODIFY INLET	152604
MODIFY INLET TO MANHOLE	152609
MODIFY IRRIGATION SYSTEM	206555
MODIFY LIGHTING	861503
MODIFY LIGHTING AND SIGN ILLUMINATION	861504
MODIFY MANHOLE	152610
MODIFY RAMP METERING SYSTEM	861088
MODIFY SIGN ILLUMINATION	860508
MODIFY SIGN STRUCTURE	152641
MODIFY SIGNAL	861502
MODIFY SIGNAL (LOCATION 1)	861491
MODIFY SIGNAL (LOCATION 2)	861492
MODIFY SIGNAL (LOCATION 3)	861493
MODIFY SIGNAL (LOCATION 4)	861494
MODIFY SIGNAL (LOCATION 5)	861495
MODIFY SIGNAL AND LIGHTING	861501
MODIFY SIGNAL AND LIGHTING (LOCATION 1)	861497
MODIFY SIGNAL AND LIGHTING (LOCATION 2)	861498
MODIFY TRAFFIC MONITORING STATION	860889
MODIFY TRAFFIC MONITORING STATION (COUNT)	860890
MOVE-IN/MOVE-OUT (EROSION CONTROL)	203026
MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL)	074037
MULCH	202011

ITEM DESCRIPTION	ITEM CODE
N	
NATURAL RESOURCE PROTECTION PLAN	146003
NOISE MONITORING	148005
NPS 3 SUPPLY LINE (BRIDGE)	208038
O	
OBJECT MARKER	820130
OBJECT MARKER (TYPE K)	820131
OBJECT MARKER (TYPE K-1)	820141
OBJECT MARKER (TYPE L)	820132
OBJECT MARKER (TYPE L-1)	820151
OBJECT MARKER (TYPE L-2)	820152
OBJECT MARKER (TYPE N)	820133
OBJECT MARKER (TYPE P)	820134
OBJECT MARKER (TYPE R)	820135
OBLITERATE SURFACING	150305
P	
PAINT CONCRETE SURFACES	590280
PAINT CURB (2-COAT)	597401
PAINT PAVEMENT MARKING	840660
PAINT PAVEMENT MARKING (2-COAT)	840666
PAINT STRUCTURAL STEEL (EXISTING BRIDGE)	590111
PAINT TRAFFIC STRIPE	840653
PAINT TRAFFIC STRIPE (1-COAT)	840655
PAINT TRAFFIC STRIPE (2-COAT)	840656
PAINTED TRAFFIC STRIPE	840600
PARKING BUMPER (PRECAST CONCRETE)	842000
PAVEMENT MARKER (NON-REFLECTIVE-RECESSED)	850121
PAVEMENT MARKER (NON-REFLECTIVE)	850101
PAVEMENT MARKER (REFLECTIVE)	850102
PAVEMENT MARKER (REFLECTIVE-RECESSED)	850120
PAVEMENT MARKER (REFLECTIVE-SPECIAL TYPE H)	850104

ITEM DESCRIPTION	ITEM CODE
P	
PAVEMENT MARKER (RETROREFLECTIVE)	850111
PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)	850122
PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE C)	850110
PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE G)	850112
PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE H)	850113
PAVEMENT REINFORCING FABRIC	393001
PAVEMENT TRANSITION TAPER	416101
PAVING ASPHALT (BINDER, GEOSYNTHETIC PAVEMENT INTERLAYER)	391007
PAVING NOTCH EXTENSION	510800
PEDESTRIAN BARRICADE	833077
PERMEABLE MATERIAL	682001
PERMEABLE MATERIAL (BLANKET)	682008
PERMEABLE MATERIAL (STABILIZATION TRENCH)	682003
PERVIOUS BACKFILL MATERIAL	193030
PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	193031
PICNIC TABLE WITH BENCHES	994420
PILASTER, SOUND WALL	510705
PIPE HANDRAILING	833085
PLACE AND COMPACT EMBANKMENT	197010
PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	394002
PLACE ASPHALT CONCRETE DIKE (TYPE A)	394040
PLACE ASPHALT CONCRETE DIKE (TYPE C)	394044
PLACE ASPHALT CONCRETE DIKE (TYPE D)	394046
PLACE ASPHALT CONCRETE DIKE (TYPE E)	394048
PLACE ASPHALT CONCRETE DIKE (TYPE F)	394049
PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	394090
PLACE HOT MIX ASPHALT DIKE	394071
PLACE HOT MIX ASPHALT DIKE (TYPE A)	394073
PLACE HOT MIX ASPHALT DIKE (TYPE C)	394074

ITEM DESCRIPTION	ITEM CODE
P	
PLACE HOT MIX ASPHALT DIKE (TYPE D)	394075
PLACE HOT MIX ASPHALT DIKE (TYPE E)	394076
PLACE HOT MIX ASPHALT DIKE (TYPE F)	394077
PLACE POLYESTER CONCRETE OVERLAY	515042
PLANT (GROUP A)	204035
PLANT (GROUP B)	204036
PLANT (GROUP F)	204006
PLANT (GROUP G)	204007
PLANT (GROUP H)	204008
PLANT (GROUP I)	204009
PLANT (GROUP K)	204011
PLANT (GROUP M)	204013
PLANT (GROUP U)	204038
PLANT (GROUP W)	204017
PLANT (GROUP Z)	204022
PLANT ESTABLISHMENT WORK	204099
PLANTING PLANT (GROUP L)	204012
PLANTING PLANT (GROUP R)	204018
PLASTIC PIPE LINER	152659
PLUG PIPE	155002
PORTABLE CHANGEABLE MESSAGE SIGN	128650
PORTABLE DELINEATOR	120182
PORTLAND CEMENT CONCRETE (PATCH)	511121
PORTLAND CEMENT CONCRETE BASE	405030
PREPARE AND PAINT CONCRETE	597600
PREPARE AND STAIN CONCRETE	597601
PREPARE CONCRETE BRIDGE DECK SURFACE	153225
PREPARE HOLE	200110
PREPARE HOLE (SOIL AMENDMENT)	200108
PREPARE STORM WATER POLLUTION PREVENTION PLAN	074019
PREPARE WATER POLLUTION CONTROL PROGRAM	074017

ITEM DESCRIPTION	ITEM CODE
P	
PRESTRESSING CAST-IN-PLACE CONCRETE	500001
PROGRESS SCHEDULE (CRITICAL PATH METHOD)	070012
PROGRESS SCHEDULE (CRITICAL PATH)	070010
PRUNE EXISTING PLANTS	200052
PTFE BEARING	518050
PTFE SPHERICAL BEARING	518051
PUMPING PLANT ELECTRICAL EQUIPMENT	741001
Q	
QUICK COUPLING VALVE	208649
R	
RAIL TENSIONING ASSEMBLY	839561
RAILROAD TRACK	601001
RAIN EVENT ACTION PLAN	074056
RAMP METERING SYSTEM	861100
RAMP METERING SYSTEM (LOCATION 1)	861101
RAMP METERING SYSTEM (LOCATION 10)	861110
RAMP METERING SYSTEM (LOCATION 2)	861102
RAMP METERING SYSTEM (LOCATION 3)	861103
RAMP METERING SYSTEM (LOCATION 7)	861107
RAMP METERING SYSTEM (LOCATION 8)	861108
RAMP METERING SYSTEM (LOCATION 9)	861109
RAPID SETTING CONCRETE (PATCH)	511124
REAMING WATER WELL	760022
RECONSTRUCT CHAIN LINK FENCE	151540
RECONSTRUCT DOUBLE THRIE BEAM BARRIER	151570
RECONSTRUCT FENCE	151531
RECONSTRUCT FENCE (TYPE BW)	151536
RECONSTRUCT FENCE (TYPE WM)	151537
RECONSTRUCT METAL BEAM GUARD RAILING	151572
RECONSTRUCT METAL BEAM GUARD RAILING (7' POST)	151623

ITEM DESCRIPTION	ITEM CODE
R	
RECONSTRUCT METAL BEAM GUARD RAILING (WOOD POST)	151625
RECONSTRUCT METAL RAILING (BRIDGE)	159010
RECONSTRUCT THRIE BEAM BARRIER	151568
RECONSTRUCT WOOD FENCE	151534
RECYCLED WATER WARNING SIGNS	209202
REFINISH BRIDGE DECK	515020
REINFORCED CONCRETE CRIB WALL (TYPE A)	513601
RELAY ENTRANCE TAPER	152039
RELAY ENTRANCE TAPER AND PIPE DOWNDRAIN	152037
RELOCATE BACKFLOW PREVENTER	152365
RELOCATE CONCRETE BARRIER (TYPE K)	152372
RELOCATE CRASH CUSHION	152388
RELOCATE EXTINGUISHABLE MESSAGE SIGN	861295
RELOCATE FRAMED SIGN PANEL	152399
RELOCATE GATE	152381
RELOCATE MAILBOX	152370
RELOCATE ROADSIDE SIGN	152390
RELOCATE ROADSIDE SIGN (METAL POST)	152391
RELOCATE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD)	152393
RELOCATE ROADSIDE SIGN (WOOD POST)	152392
RELOCATE ROADSIDE SIGN-ONE POST	152386
RELOCATE ROADSIDE SIGN-TWO POST	152387
RELOCATE SIGN STRUCTURE	152394
RELOCATE SIGN STRUCTURE (BRIDGE-MOUNTED)	152398
REMOVE ASPHALT CONCRETE	150769
REMOVE ASPHALT CONCRETE DIKE	150771
REMOVE ASPHALT CONCRETE OVERSIDE DRAIN	150859
REMOVE ASPHALT CONCRETE SURFACING	150857
REMOVE BASE AND SURFACING	150860
REMOVE BOX CULVERT	156535

ITEM DESCRIPTION	ITEM CODE
R	
REMOVE BRIDGE MOUNTED SIGN	150767
REMOVE BRIDGE RAILING	156579
REMOVE CABLE RAILING	150676
REMOVE CHAIN LINK FENCE	150608
REMOVE CHANNELIZERS	150730
REMOVE CHIP SEAL	153237
REMOVE CONCRETE	153210
REMOVE CONCRETE (CHANNEL)	153220
REMOVE CONCRETE (CURB AND GUTTER)	153215
REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK)	153239
REMOVE CONCRETE (MISCELLANEOUS)	153246
REMOVE CONCRETE (STRUCTURE)	153213
REMOVE CONCRETE BARRIER	153221
REMOVE CONCRETE BARRIER (TYPE 50)	153230
REMOVE CONCRETE BARRIER (TYPE 50C)	153231
REMOVE CONCRETE BARRIER (TYPE K)	153229
REMOVE CONCRETE CURB	153214
REMOVE CONCRETE CURB AND SIDEWALK	153216
REMOVE CONCRETE DECK SURFACE	150870
REMOVE CONCRETE ISLAND (PORTIONS)	153222
REMOVE CONCRETE PAVEMENT	150846
REMOVE CONCRETE PAVEMENT AND BASE	150847
REMOVE CONCRETE SIDEWALK	153218
REMOVE CONCRETE SIDEWALK AND DRIVEWAY	153211
REMOVE CONTRAST TREATMENT	150720
REMOVE CRASH CUSHION	156585
REMOVE CRASH CUSHION (SAND FILLED)	156590
REMOVE CULVERT	150805
REMOVE CURB	150772
REMOVE DELINEATOR	151224
REMOVE DOUBLE METAL BEAM BARRIER	150667

ITEM DESCRIPTION	ITEM CODE
R	
REMOVE DOWNDRAIN	150823
REMOVE DRAINAGE FACILITY	150804
REMOVE ENTRANCE TAPER	150615
REMOVE EXISTING SIGNAL SYSTEM	861349
REMOVE FENCE	150605
REMOVE FENCE (TYPE BW)	150606
REMOVE FLARED END SECTION	150668
REMOVE FLASHING BEACON AND LIGHTING	861490
REMOVE GATE	150620
REMOVE HEADWALL	150821
REMOVE INLET	150820
REMOVE IRRIGATION FACILITY	150685
REMOVE JUNCTION BOX	150828
REMOVE MANHOLE	150826
REMOVE MARKER	150630
REMOVE METAL BEAM BARRIER	150666
REMOVE METAL BEAM GUARD RAILING	150662
REMOVE METAL POST	150749
REMOVE METAL RAILING	156576
REMOVE OVERSIDE DRAIN	150801
REMOVE PAINTED PAVEMENT MARKING	150712
REMOVE PAINTED TRAFFIC STRIPE	150711
REMOVE PAVEMENT	150855
REMOVE PAVEMENT MARKER	150722
REMOVE PAVEMENT MARKING	150713
REMOVE PIPE	150806
REMOVE RAILING	156572
REMOVE REINFORCED CONCRETE BOX CULVERT	150825
REMOVE RETAINING WALL	150829
REMOVE RETAINING WALL (PORTION)	150830
REMOVE ROADSIDE SIGN	150742
REMOVE ROADSIDE SIGN (METAL POST)	150745

ITEM DESCRIPTION	ITEM CODE
R	
REMOVE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD)	150747
REMOVE ROADSIDE SIGN (WOOD POST)	150744
REMOVE ROADSIDE SIGN PANEL	150748
REMOVE SEWER MANHOLE	150824
REMOVE SEWER PIPE	150841
REMOVE SIGN	150740
REMOVE SIGN OVERLAY	150764
REMOVE SIGN PANEL	150763
REMOVE SIGN POST	150765
REMOVE SIGN STRUCTURE	150760
REMOVE SIGN STRUCTURE WALKWAY	150759
REMOVE SLOPE PAVING	150844
REMOVE SOUND WALL	153250
REMOVE TERMINAL SECTION	150659
REMOVE THERMOPLASTIC PAVEMENT MARKING	150715
REMOVE THERMOPLASTIC TRAFFIC STRIPE	150714
REMOVE THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING	150718
REMOVE TRAFFIC STRIPE	150710
REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING	150717
REMOVE TREE	160120
REMOVE UNSOUND CONCRETE	153223
REMOVE WOOD FENCE	150604
REMOVE YELLOW PAINTED TRAFFIC STRIPE	150701
REMOVE YELLOW PAINTED TRAFFIC STRIPE (HAZARDOUS WASTE)	141101
REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING	150705
REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING (HAZARDOUS WASTE)	141104
REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	150704
REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	141103

ITEM DESCRIPTION	ITEM CODE
R	
REPAIR SPALLED CONCRETE	150306
REPAIR SPALLED JOINTS	413111
REPAIR SPALLED SURFACE AREA	515028
REPLACE ASPHALT CONCRETE SURFACING	390095
REPLACE BEARING PAD	518040
REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	401108
REPLACE PULL BOX	862065
REPLACE SIGN PANEL	152750
REPLACE VALVE BOX COVER	208565
RESET CRASH CUSHION	152315
RESET GATE	152291
RESET MAILBOX	152255
RESET MARKER	152301
RESET MARKERS AND DELINEATORS	152303
RESET MILEPOST MARKER	152299
RESET OBJECT MARKER	152300
RESET ROADSIDE SIGN	152320
RESET ROADSIDE SIGN (METAL POST)	152324
RESET ROADSIDE SIGN (ONE POST)	152316
RESET ROADSIDE SIGN (TWO POST)	152317
RESET ROADSIDE SIGN (WOOD POST)	152322
RESET TEMPORARY RAILING (TYPE K)	158210
RETAINING WALL (MASONRY WALL)	513553
RETAINING WALL STEM (TYPE 6)	513551
RETURN CAP (TYPE TA)	839572
ROADSIDE CLEARING	200002
ROADSIDE PAVING (MISCELLANEOUS AREAS)	394095
ROADSIDE SIGN - ONE POST	566011
ROADSIDE SIGN - TWO POST	566012
ROADWAY EXCAVATION	190101
ROADWAY EXCAVATION (DETOUR REMOVAL)	190138

ITEM DESCRIPTION	ITEM CODE
R	
ROADWAY EXCAVATION (NATURALLY OCCURRING ASBESTOS)	190109
ROADWAY EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	190107
ROADWAY EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)	190108
ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	190105
ROCK BLANKET	200114
ROCK EXCAVATION (CONTROLLED BLASTING)	190160
ROCK SLOPE PROTECTION (1 TON, METHOD A)	720104
ROCK SLOPE PROTECTION (1/2 TON, METHOD A)	720106
ROCK SLOPE PROTECTION (1/2 TON, METHOD B)	721006
ROCK SLOPE PROTECTION (1/2T, METHOD A)	720120
ROCK SLOPE PROTECTION (1/2T, METHOD B)	721023
ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	721007
ROCK SLOPE PROTECTION (1/4T, METHOD B)	721024
ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B)	721010
ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	721011
ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B)	721012
ROCK SLOPE PROTECTION (DRAINAGE OUTLET)	720002
ROCK SLOPE PROTECTION (FACING, METHOD B)	721009
ROCK SLOPE PROTECTION (LIGHT, METHOD B)	721008
ROCK SLOPE PROTECTION (NO. 1, METHOD B)	721010
ROCK SLOPE PROTECTION (NO. 2, METHOD B)	721011
ROCK SLOPE PROTECTION FABRIC	729010
ROCK SLOPE PROTECTION(GRANULAR MATERIAL)	720107
ROCK STAIN	203070
ROLLED EROSION CONTROL PRODUCT (BLANKET)	203033

ITEM DESCRIPTION	ITEM CODE
R	
ROLLED EROSION CONTROL PRODUCT (JUTE MESH)	203038
ROLLED EROSION CONTROL PRODUCT (NETTING)	203034
ROLLING CHAIN LINK GATE	804201
ROOT BARRIER	205062
ROOT PROTECTOR	205061
RUBBERIZED ASPHALT CONCRETE (TYPE G)	390126
RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	390137
RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	390140
RUBBERIZED HOT MIX ASPHALT (OPEN GRADED HIGH BINDER)	390139
RUBBERIZED HOT MIX ASPHALT (OPEN GRADED)	390138
RUMBLE STRIP	394050
S	
SALVAGE CONCRETE BARRIER (TYPE K)	151274
SALVAGE CRASH CUSHION	158100
SALVAGE DOUBLE THRIE BEAM BARRIER	151266
SALVAGE FLASHING BEACON	862031
SALVAGE GRATE	151226
SALVAGE METAL BEAM BARRIER	151276
SALVAGE METAL BEAM GUARD RAILING	151272
SALVAGE METAL BRIDGE RAILING	151270
SALVAGE SINGLE THRIE BEAM BARRIER	151265
SALVAGE TERMINAL SECTION	158505
SAMPLING AND ANALYSIS PLAN (NATURALLY OCCURRING ASBESTOS)	190117
SAND BACKFILL	193114
SAND BEDDING	192502
SAND COVER	365001
SCREENINGS (HOT-APPLIED)	375030
SCREENINGS (MEDIUM FINE)	375021
SCREENINGS (MEDIUM)	375022

ITEM DESCRIPTION	ITEM CODE
S	
SEAL COURSE CONCRETE	510000
SEAL ISOLATION JOINT	404093
SEAL JOINT (EXISTING CONCRETE PAVEMENT)	413115
SEAL LONGITUDINAL ISOLATION JOINT	404094
SEAL PAVEMENT JOINT	404092
SEISMIC MONITORING SYSTEM	869072
SEWER MANHOLE FRAME AND COVER	719190
SEWER TERMINAL CLEANOUT	719110
SHOTCRETE	530100
SHOULDER BACKING	190185
SHOULDER RUMBLE STRIP (AC, GROUND-IN INDENTATIONS)	394054
SHOULDER RUMBLE STRIP (CONCRETE PAVEMENT, GROUND-IN	401083
SHOULDER RUMBLE STRIP (CONCRETE PAVEMENT, GROUND-IN INDENTATIONS)	401083
SHOULDER RUMBLE STRIP (CONCRETE PAVEMENT, ROLLED-IN	401081
SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS)	394053
SHOULDER RUMBLE STRIP (HMA,ROLLED-IN INDENTATIONS)	394051
SIGN ILLUMINATION	860501
SIGNAL AND LIGHTING	860201
SIGNAL AND LIGHTING	860301
SIGNAL AND LIGHTING (CITY STREET LOCATION 1)	860300
SIGNAL AND LIGHTING (CITY STREET LOCATION 2)	860302
SIGNAL AND LIGHTING (CITY STREET LOCATION 3)	860303
SIGNAL AND LIGHTING (CITY STREET LOCATION 4)	860304
SIGNAL AND LIGHTING (CITY STREET LOCATION 6)	860306
SIGNAL AND LIGHTING (CITY)	860297
SIGNAL AND LIGHTING (LOCATION 1)	860251
SIGNAL AND LIGHTING (LOCATION 2)	860252
SIGNAL AND LIGHTING (LOCATION 3)	860253
SIGNAL AND LIGHTING (LOCATION 4)	860254

ITEM DESCRIPTION	ITEM CODE
S	
SIGNAL AND LIGHTING (LOCATION 5)	860255
SIGNAL AND LIGHTING (LOCATION 6)	860256
SIGNAL AND LIGHTING (LOCATION 7)	860257
SIGNAL AND LIGHTING (LOCATION 8)	860258
SIGNAL AND LIGHTING (STAGE CONSTRUCTION)	860298
SIGNAL AND LIGHTING (TEMPORARY)	860150
SINGLE THRIE BEAM BARRIER	839301
SINGLE THRIE BEAM BARRIER (WOOD POST)	839302
SLOPE PAVING (CONCRETE)	721810
SLOPE PAVING (MASONRY BLOCK)	721811
SLURRY SEAL	377501
SMALL BUSINESS UTILIZATION REPORT	070013
SNOWPLOW DEFLECTOR	519078
SOIL AMENDMENT	202006
SOIL NAIL ASSEMBLY	197060
SOUND WALL (BARRIER) (MASONRY BLOCK)	517961
SOUND WALL (MASONRY BLOCK)	518002
SPECIAL MARKER	820190
SPOT BLAST CLEAN AND PAINT UNDERCOAT	590135
SPRINKLER (TYPE A-1)	208461
SPRINKLER (TYPE A-2)	208462
SPRINKLER (TYPE A-3)	208463
SPRINKLER (TYPE A-4)	208464
SPRINKLER (TYPE A-5)	208465
SPRINKLER (TYPE A-6)	208466
SPRINKLER (TYPE A-7)	208467
SPRINKLER (TYPE A-8)	208468
SPRINKLER (TYPE B-1)	208471
SPRINKLER (TYPE B-2)	208472
SPRINKLER (TYPE B-3)	208473
SPRINKLER (TYPE B-4)	208474

ITEM DESCRIPTION	ITEM CODE
S	
SPRINKLER (TYPE B-5)	208475
SPRINKLER (TYPE B-6)	208476
SPRINKLER (TYPE C-1)	208481
SPRINKLER (TYPE C-2 MOD)	208480
SPRINKLER (TYPE C-2)	208482
SPRINKLER (TYPE C-3)	208483
SPRINKLER (TYPE D-1)	208526
SPRINKLER CONTROL CONDUIT (BRIDGE)	860796
STABILIZING AGENT (CEMENTITIOUS MATERIAL)	397205
STABILIZING AGENT (FOAMED ASPHALT)	397200
STEEL SHEET PILING	490801
STORM WATER ANNUAL REPORT	074057
STORM WATER SAMPLING AND ANALYSIS DAY	074058
STREET SWEEPING	074041
STRIPPING EXCAVATION	190162
STRUCTURAL CONCRETE	510050
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE EQ)	510085
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N MODIFIED)	510088
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	510086
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	510087
STRUCTURAL CONCRETE, BARRIER SLAB	510072
STRUCTURAL CONCRETE, BOX CULVERT	510090
STRUCTURAL CONCRETE, BRIDGE	510053
STRUCTURAL CONCRETE, BRIDGE (CHANNEL)	510067
STRUCTURAL CONCRETE, BRIDGE FOOTING	510051
STRUCTURAL CONCRETE, HEADWALL	510092
STRUCTURAL CONCRETE, RETAINING WALL	510060
STRUCTURAL CONCRETE, SOUND WALL	510061
STRUCTURAL CONCRETE, WALL	510058
STRUCTURAL CONCRETE, WALL FACING	510040

ITEM DESCRIPTION	ITEM CODE
S	
STRUCTURAL STEEL	550101
STRUCTURAL STEEL (BRIDGE)	550102
STRUCTURE BACKFILL	193001
STRUCTURE BACKFILL (BRIDGE)	193003
STRUCTURE BACKFILL (CRIB WALL)	193012
STRUCTURE BACKFILL (CULVERT)	193004
STRUCTURE BACKFILL (RETAINING WALL)	193013
STRUCTURE BACKFILL (SLURRY CEMENT)	193006
STRUCTURE BACKFILL (SOIL NAIL WALL)	193028
STRUCTURE BACKFILL (SOLDIER PILE WALL)	193029
STRUCTURE BACKFILL (SOUND WALL)	193014
STRUCTURE BACKFILL (TIEBACK WALL)	193026
STRUCTURE BACKFILL, RETAINING WALL (SOUND WALL)	193020
STRUCTURE EXCAVATION	192001
STRUCTURE EXCAVATION (BRIDGE)	192003
STRUCTURE EXCAVATION (CRIB WALL)	192036
STRUCTURE EXCAVATION (CULVERT)	192025
STRUCTURE EXCAVATION (RETAINING WALL)	192037
STRUCTURE EXCAVATION (ROCK SLOPE PROTECTION)	192032
STRUCTURE EXCAVATION (SOIL NAIL WALL)	192055
STRUCTURE EXCAVATION (SOLDIER PILE WALL)	192049
STRUCTURE EXCAVATION (TIEBACK WALL)	192050
STRUCTURE EXCAVATION (TYPE A)	192008
STRUCTURE EXCAVATION (TYPE D)	192020
STRUCTURE EXCAVATION (TYPE DH)	192021
STRUCTURE EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	192057
STRUCTURE EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	192053
SUBGRADE ENHANCEMENT FABRIC	198200
SUBGRADE ENHANCEMENT GEOTEXTILE	198205
SURVEY MONUMENT	810110
S	
SURVEY MONUMENT (TYPE A)	810111
SURVEY MONUMENT (TYPE B)	810112
SURVEY MONUMENT (TYPE D)	810116
SYSTEM TESTING AND DOCUMENTATION	869075
T	
TACK COAT	397005
TAPERED INLET	692101
TEMPORARY ACTIVE TREATMENT SYSTEM	074015
TEMPORARY CHECK DAM	074035
TEMPORARY CONCRETE WASHOUT (PORTABLE)	074042
TEMPORARY CONCRETE WASHOUT BIN	074043
TEMPORARY CONCRETE WASHOUT FACILITY	074032
TEMPORARY CONSTRUCTION ENTRANCE	074033
TEMPORARY CONSTRUCTION ROADWAY	074044
TEMPORARY COVER	074034
TEMPORARY CRASH CUSHION	129110
TEMPORARY CRASH CUSHION MODULE	129100
TEMPORARY DELINEATOR (CLASS 2)	128202
TEMPORARY DRAINAGE INLET PROTECTION	074038
TEMPORARY EROSION CONTROL BLANKET	074027
TEMPORARY FENCE	071301
TEMPORARY FENCE (TYPE BW)	071302
TEMPORARY FENCE (TYPE CL-1.8)	071322
TEMPORARY FENCE (TYPE CL-6)	071321
TEMPORARY FENCE (TYPE ESA)	071325
TEMPORARY FENCE (TYPE WM)	071303
TEMPORARY FIBER ROLL	074028
TEMPORARY FLASHING BEACON	128660
TEMPORARY GRAVEL BAG BERM	074031
TEMPORARY HYDRAULIC MULCH	074051

ITEM DESCRIPTION	ITEM CODE
T	
TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	074040
TEMPORARY HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	074039
TEMPORARY HYDROSEED	074053
TEMPORARY LARGE SEDIMENT BARRIER	074045
TEMPORARY MARKER	120154
TEMPORARY METAL BEAM GUARD RAILING	121140
TEMPORARY MULCH	074026
TEMPORARY PAVEMENT MARKER	120300
TEMPORARY PAVEMENT MARKING	120150
TEMPORARY PAVEMENT MARKING (PAINT)	120149
TEMPORARY PAVEMENT MARKING (TAPE)	120152
TEMPORARY RAILING (TYPE K)	129000
TEMPORARY REINFORCED SILT FENCE	071324
TEMPORARY RETAINING WALL	129510
TEMPORARY SIGNAL SYSTEM	128601
TEMPORARY SILT FENCE	074029
TEMPORARY SOIL BINDER	074055
TEMPORARY SOIL STABILIZER	074025
TEMPORARY STRAW BALE BARRIER	074036
TEMPORARY SUPPORT	072006
TEMPORARY TACKED STRAW	074054
TEMPORARY TERMINAL SECTION (TYPE K)	121161
TEMPORARY TRAFFIC SCREEN	129150
TEMPORARY TRAFFIC STRIPE (PAINT)	120159
TEMPORARY TRAFFIC STRIPE (TAPE)	120151
TEMPORARY WETLAND PROTECTION MAT (LS)	146006
TERMINAL ANCHOR ASSEMBLY (TYPE CA)	839569
TERMINAL ANCHOR ASSEMBLY (TYPE SFT)	839568
TERMINAL SECTION (TYPE C)	839552
TERMINAL SYSTEM (TYPE CAT)	839566
TERMINAL SYSTEM (TYPE CAT) BACKUP	839567

ITEM DESCRIPTION	ITEM CODE
T	
TERMINAL SYSTEM (TYPE ET)	839559
TERMINAL SYSTEM (TYPE SRT)	839565
TESTING WELL	760012
THERMOPLASTIC CROSSWALK AND PAVEMENT MARKING	840519
THERMOPLASTIC PAVEMENT MARKING	840515
THERMOPLASTIC TRAFFIC STRIPE	840501
THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	840560
TIE BAR	406001
TIE BAR (DRILL AND BOND)	406003
TIEBACK ANCHOR	500050
TIEDOWN ANCHOR	500060
TIMBER LAGGING	575004
TIME-RELATED OVERHEAD	070018
TRAFFIC CONE	120119
TRAFFIC CONTROL SURVEILLANCE	120102
TRAFFIC CONTROL SYSTEM	120100
TRAFFIC MONITORING STATION	860930
TRAFFIC MONITORING STATION (COUNT)	860925
TRAFFIC MONITORING STATION (LOCATION 1)	860931
TRAFFIC MONITORING STATION (LOCATION 2)	860932
TRAFFIC MONITORING STATION (LOCATION 3)	860933
TRAFFIC MONITORING STATION (LOCATION 4)	860934
TRAFFIC MONITORING STATION (LOCATION 7)	860937
TRAFFIC PLASTIC DRUM	120199
TRAINING	869080
TRANSITION RAILING (TYPE DTB)	839542
TRANSITION RAILING (TYPE STB)	839540
TRANSITION RAILING (TYPE WB)	839541
TRANSPLANT PALM TREE	204031
TRANSPLANT TREE	204030

ITEM DESCRIPTION	ITEM CODE	ITEM DESCRIPTION	ITEM CODE
T			
TRASH RECEPTACLE	994901		
TREAT BRIDGE DECK	540102		
TREATED LUMBER AND TIMBER	570120		
TUBULAR HANDRAILING	833088		
TURF (SOD)	204042		
TWO-COMPONENT PAINT PAVEMENT MARKING	840661		
TYPE II BARRICADE	120116		
TYPE III BARRICADE	120120		
U			
UNDERDRAIN MARKER	820111		
V			
VEGETATION CONTROL (MINOR CONCRETE)	832070		
W			
WATER METER	208304		
WATER SUPPLY SYSTEM	760080		
WEIGH STATION BYPASS SYSTEM	861204		
WEIGH-IN-MOTION SYSTEM	861200		
WELDED STEEL PIPE CASING (BRIDGE)	703450		
WELL DEVELOPMENT	760011		
WELL SCREEN	760035		
WILD FLOWER SEEDING (SQYD)	204055		
WILDLIFE PASSAGE WAY (TYPE M)	833073		
WILDLIFE PASSAGE WAY (TYPE S)	833072		
WOOD FENCE	800701		
WORK AREA MONITORING	590301		

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
070010	PROGRESS SCHEDULE (CRITICAL PATH)	LS	4	1	1.00	$5,000.00	$5,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$5,000.00**	**$5,000.00**
	Item Code 070010 Total No. of Proj.			**1**		**Total Amount**	**$5,000.00**
070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	1	4	4.00	$6,687.50	$26,750.00
		LS	2	8	8.00	$10,312.50	$82,500.00
		LS	3	18	18.00	$4,694.44	$84,500.00
		LS	4	13	13.00	$2,707.69	$35,200.00
		LS	5	3	3.00	$8,000.00	$24,000.00
		LS	6	6	6.00	$3,566.67	$21,400.00
		LS	7	18	18.00	$6,170.85	$111,075.37
		LS	8	10	10.00	$5,816.00	$58,160.00
		LS	10	4	4.00	$4,350.00	$17,400.00
		LS	11	9	9.00	$4,388.89	$39,500.00
		LS	12	7	7.00	$4,957.14	$34,700.00
	Unit Sub Total	**LS**		**100**	**100.00**	**$5,351.85**	**$535,185.37**
	Item Code 070012 Total No. of Proj.			**100**		**Total Amount**	**$535,185.37**
070013	SMALL BUSINESS UTILIZATION REPORT	EA	1	2	7.00	$235.71	$1,650.00
		EA	2	1	1.00	$250.00	$250.00
		EA	3	4	24.00	$250.00	$6,000.00
		EA	4	6	17.00	$314.71	$5,350.00
		EA	5	1	4.00	$250.00	$1,000.00
		EA	6	2	8.00	$250.00	$2,000.00
		EA	7	4	18.00	$250.00	$4,500.00
		EA	8	6	41.00	$250.00	$10,250.00
		EA	10	1	4.00	$250.00	$1,000.00
		EA	12	2	13.00	$83.85	$1,090.00
	Unit Sub Total	**EA**		**29**	**137.00**	**$241.53**	**$33,090.00**
	Item Code 070013 Total No. of Proj.			**29**		**Total Amount**	**$33,090.00**
070018	TIME-RELATED OVERHEAD	LS	3	1	1.00	$212,800.00	$212,800.00
		LS	4	7	7.00	$258,571.43	$1,810,000.00
		LS	7	5	5.00	$557,428.76	$2,787,143.82
		LS	8	2	2.00	$929,650.00	$1,859,300.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
070018	TIME-RELATED OVERHEAD		LS	11	8	8.00	$401,875.00	$3,215,000.00
			LS	12	3	3.00	$861,000.00	$2,583,000.00
		Unit Sub Total	**LS**		**26**	**26.00**	**$479,509.38**	**$12,467,243.82**
070018	TIME-RELATED OVERHEAD		WDAY	1	4	1,040.00	$882.60	$917,900.00
			WDAY	2	6	1,390.00	$1,043.17	$1,450,000.00
			WDAY	3	16	3,525.00	$2,549.36	$8,986,500.00
			WDAY	4	7	2,660.00	$1,586.71	$4,220,650.00
			WDAY	5	3	1,402.00	$3,195.44	$4,480,000.00
			WDAY	6	5	1,520.00	$2,422.37	$3,682,000.00
			WDAY	7	12	5,255.00	$2,762.82	$14,518,620.00
			WDAY	8	7	2,400.00	$744.50	$1,786,800.00
			WDAY	10	4	1,745.00	$2,961.95	$5,168,600.00
			WDAY	12	2	790.00	$1,930.13	$1,524,800.00
		Unit Sub Total	**WDAY**		**66**	**21,727.00**	**$2,151.05**	**$46,735,870.00**
	Item Code 070018	**Total No. of Proj.**			**92**		**Total Amount**	**$59,203,113.82**
071301	TEMPORARY FENCE		LF	11	2	8,616.00	$2.18	$18,783.00
		Unit Sub Total	**LF**		**2**	**8,616.00**	**$2.18**	**$18,783.00**
071301	TEMPORARY FENCE		M	7	1	8,500.00	$28.50	$242,250.00
			M	8	1	440.00	$22.00	$9,680.00
		Unit Sub Total	**M**		**2**	**8,940.00**	**$28.18**	**$251,930.00**
	Item Code 071301	**Total No. of Proj.**			**4**		**Total Amount**	**$270,713.00**
071302	TEMPORARY FENCE (TYPE BW)		LF	1	1	1,040.00	$5.00	$5,200.00
		Unit Sub Total	**LF**		**1**	**1,040.00**	**$5.00**	**$5,200.00**
	Item Code 071302	**Total No. of Proj.**			**1**		**Total Amount**	**$5,200.00**
071303	TEMPORARY FENCE (TYPE WM)		LF	1	1	230.00	$11.50	$2,645.00
			LF	3	1	330.00	$6.00	$1,980.00
		Unit Sub Total	**LF**		**2**	**560.00**	**$8.26**	**$4,625.00**
	Item Code 071303	**Total No. of Proj.**			**2**		**Total Amount**	**$4,625.00**
071321	TEMPORARY FENCE (TYPE CL-6)		LF	4	9	42,330.00	$7.21	$305,142.00
			LF	7	2	1,240.00	$5.42	$6,722.40

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
071321	TEMPORARY FENCE (TYPE CL-6)	LF	8	1	650.00	$8.50	$5,525.00
		LF	11	1	2,780.00	$1.50	$4,170.00
		LF	12	1	1,280.00	$10.00	$12,800.00
	Unit Sub Total	**LF**		**14**	**48,280.00**	**$6.93**	**$334,359.40**
	Item Code 071321 Total No. of Proj.			**14**		**Total Amount**	**$334,359.40**
071322	TEMPORARY FENCE (TYPE CL-1.8)	LF	7	1	410.00	$11.00	$4,510.00
	Unit Sub Total	**LF**		**1**	**410.00**	**$11.00**	**$4,510.00**
071322	TEMPORARY FENCE (TYPE CL-1.8)	M	7	1	4,020.00	$46.00	$184,920.00
		M	11	2	750.00	$22.60	$16,950.00
	Unit Sub Total	**M**		**3**	**4,770.00**	**$42.32**	**$201,870.00**
	Item Code 071322 Total No. of Proj.			**4**		**Total Amount**	**$206,380.00**
071324	TEMPORARY REINFORCED SILT FENCE	LF	1	2	1,150.00	$6.58	$7,562.50
		LF	4	6	15,310.00	$7.16	$109,600.00
		LF	10	3	31,070.00	$4.07	$126,450.00
	Unit Sub Total	**LF**		**11**	**47,530.00**	**$5.13**	**$243,612.50**
	Item Code 071324 Total No. of Proj.			**11**		**Total Amount**	**$243,612.50**
071325	TEMPORARY FENCE (TYPE ESA)	LF	1	18	17,175.00	$4.48	$76,957.50
		LF	2	10	9,580.00	$4.96	$47,520.00
		LF	3	19	259,060.00	$1.46	$378,170.70
		LF	4	21	61,230.00	$2.96	$181,272.00
		LF	5	6	16,130.00	$3.79	$61,213.00
		LF	6	7	14,000.00	$3.96	$55,421.00
		LF	7	1	190.00	$3.00	$570.00
		LF	8	6	15,690.00	$4.77	$74,797.00
		LF	9	4	30,400.00	$2.41	$73,208.00
		LF	10	4	43,200.00	$2.99	$129,020.00
		LF	11	5	3,200.00	$6.01	$19,237.10
		LF	12	2	4,500.00	$3.16	$14,205.00
	Unit Sub Total	**LF**		**103**	**474,355.00**	**$2.34**	**$1,111,591.30**
071325	TEMPORARY FENCE (TYPE ESA)	M	4	1	590.00	$10.00	$5,900.00
		M	5	1	10,800.00	$5.00	$54,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
071325	TEMPORARY FENCE (TYPE ESA)	M	7	1	2,530.00	$10.66	$26,969.80
		M	8	1	130.00	$30.00	$3,900.00
		M	10	1	580.00	$13.00	$7,540.00
		M	11	1	1,860.00	$10.00	$18,600.00
	Unit Sub Total	**M**		**6**	**16,490.00**	**$7.09**	**$116,909.80**
	Item Code 071325 Total No. of Proj.			**109**		**Total Amount**	**$1,228,501.10**
072006	TEMPORARY SUPPORT	LS	1	1	1.00	$90,000.00	$90,000.00
		LS	6	1	1.00	$30,000.00	$30,000.00
		LS	7	2	2.00	$40,000.00	$80,000.00
		LS	8	1	1.00	$140,000.00	$140,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$68,000.00**	**$340,000.00**
	Item Code 072006 Total No. of Proj.			**5**		**Total Amount**	**$340,000.00**
073006	18" TEMPORARY CULVERT	LF	4	3	1,409.00	$54.91	$77,371.75
	Unit Sub Total	**LF**		**3**	**1,409.00**	**$54.91**	**$77,371.75**
	Item Code 073006 Total No. of Proj.			**3**		**Total Amount**	**$77,371.75**
073013	48" TEMPORARY CULVERT	LF	8	1	120.00	$60.00	$7,200.00
	Unit Sub Total	**LF**		**1**	**120.00**	**$60.00**	**$7,200.00**
	Item Code 073013 Total No. of Proj.			**1**		**Total Amount**	**$7,200.00**
073028	450 MM TEMPORARY CULVERT	M	10	1	55.00	$80.00	$4,400.00
	Unit Sub Total	**M**		**1**	**55.00**	**$80.00**	**$4,400.00**
	Item Code 073028 Total No. of Proj.			**1**		**Total Amount**	**$4,400.00**
073029	600 MM TEMPORARY CULVERT	M	5	1	1,320.00	$150.00	$198,000.00
	Unit Sub Total	**M**		**1**	**1,320.00**	**$150.00**	**$198,000.00**
	Item Code 073029 Total No. of Proj.			**1**		**Total Amount**	**$198,000.00**
073030	750 MM TEMPORARY CULVERT	M	5	1	21.00	$250.00	$5,250.00
	Unit Sub Total	**M**		**1**	**21.00**	**$250.00**	**$5,250.00**
	Item Code 073030 Total No. of Proj.			**1**		**Total Amount**	**$5,250.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
073031	900 MM TEMPORARY CULVERT	M	5	1	20.00	$350.00	$7,000.00
	Unit Sub Total	**M**		**1**	**20.00**	**$350.00**	**$7,000.00**
	Item Code 073031 Total No. of Proj.			**1**		**Total Amount**	**$7,000.00**
073032	1050 MM TEMPORARY CULVERT	M	10	1	32.00	$265.00	$8,480.00
	Unit Sub Total	**M**		**1**	**32.00**	**$265.00**	**$8,480.00**
	Item Code 073032 Total No. of Proj.			**1**		**Total Amount**	**$8,480.00**
074015	TEMPORARY ACTIVE TREATMENT SYSTEM	LS	3	1	1.00	$20,000.00	$20,000.00
		LS	4	5	5.00	$19,000.00	$95,000.00
		LS	7	1	1.00	$250,000.00	$250,000.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$52,142.86**	**$365,000.00**
	Item Code 074015 Total No. of Proj.			**7**		**Total Amount**	**$365,000.00**
074016	CONSTRUCTION SITE MANAGEMENT	LS	1	39	39.00	$9,055.10	$353,149.00
		LS	2	40	40.00	$7,212.06	$288,482.33
		LS	3	71	71.00	$8,589.91	$609,883.38
		LS	4	81	81.00	$8,115.30	$657,339.48
		LS	5	40	40.00	$9,184.38	$367,375.00
		LS	6	49	49.00	$7,480.20	$366,530.00
		LS	7	77	77.00	$9,492.32	$730,908.82
		LS	8	54	54.00	$8,870.57	$479,011.00
		LS	9	15	15.00	$4,306.67	$64,600.00
		LS	10	35	35.00	$14,850.86	$519,780.00
		LS	11	37	37.00	$11,151.70	$412,612.98
		LS	12	34	34.00	$7,726.85	$262,713.00
	Unit Sub Total	**LS**		**572**	**572.00**	**$8,937.74**	**$5,112,384.99**
	Item Code 074016 Total No. of Proj.			**572**		**Total Amount**	**$5,112,384.99**
074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	1	28	28.00	$1,618.43	$45,316.00
		LS	2	27	27.00	$1,598.15	$43,150.00
		LS	3	62	62.00	$2,089.41	$129,543.43
		LS	4	67	67.00	$1,292.97	$86,628.87
		LS	5	31	31.00	$1,279.58	$39,667.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	6	38	38.00	$948.55	$36,045.00
		LS	7	62	62.00	$1,329.88	$82,452.72
		LS	8	42	42.00	$1,510.45	$63,439.00
		LS	9	13	13.00	$815.38	$10,600.00
		LS	10	27	27.00	$3,004.07	$81,110.00
		LS	11	23	23.00	$1,500.83	$34,519.19
		LS	12	27	27.00	$1,304.56	$35,223.00
	Unit Sub Total	**LS**		**447**	**447.00**	**$1,538.47**	**$687,694.21**
	Item Code 074017 Total No. of Proj.			**447**		**Total Amount**	**$687,694.21**
074018	HEALTH AND SAFETY PLAN	LS	3	1	1.00	$1,248.00	$1,248.00
		LS	4	2	2.00	$2,350.00	$4,700.00
		LS	7	1	1.00	$500.00	$500.00
		LS	11	1	1.00	$4,000.00	$4,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$2,089.60**	**$10,448.00**
	Item Code 074018 Total No. of Proj.			**5**		**Total Amount**	**$10,448.00**
074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	1	11	11.00	$3,379.55	$37,175.00
		LS	2	13	13.00	$3,907.69	$50,800.00
		LS	3	9	9.00	$2,504.44	$22,540.00
		LS	4	14	14.00	$5,139.29	$71,950.00
		LS	5	9	9.00	$2,322.22	$20,900.00
		LS	6	11	11.00	$1,631.82	$17,950.00
		LS	7	15	15.00	$7,766.67	$116,500.00
		LS	8	12	12.00	$3,401.25	$40,815.00
		LS	9	2	2.00	$5,250.00	$10,500.00
		LS	10	8	8.00	$5,556.25	$44,450.00
		LS	11	14	14.00	$3,682.14	$51,550.00
		LS	12	7	7.00	$3,950.86	$27,656.00
	Unit Sub Total	**LS**		**125**	**125.00**	**$4,102.29**	**$512,786.00**
	Item Code 074019 Total No. of Proj.			**125**		**Total Amount**	**$512,786.00**
074025	TEMPORARY SOIL STABILIZER	M2	7	1	2,560.00	$1.00	$2,560.00
	Unit Sub Total	**M2**		**1**	**2,560.00**	**$1.00**	**$2,560.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 074025	**Total No. of Proj.**			**1**		**Total Amount**	**$2,560.00**
074026	TEMPORARY MULCH		CY	2	1	30.00	$100.00	$3,000.00
		Unit Sub Total	**CY**		**1**	**30.00**	**$100.00**	**$3,000.00**
074026	TEMPORARY MULCH		M2	7	1	5,200.00	$1.00	$5,200.00
		Unit Sub Total	**M2**		**1**	**5,200.00**	**$1.00**	**$5,200.00**
074026	TEMPORARY MULCH		SQYD	1	2	3,050.00	$3.05	$9,300.00
			SQYD	2	4	11,000.00	$1.98	$21,816.00
			SQYD	5	1	6,900.00	$0.25	$1,725.00
			SQYD	10	1	1,200.00	$1.00	$1,200.00
		Unit Sub Total	**SQYD**		**8**	**22,150.00**	**$1.54**	**$34,041.00**
	Item Code 074026	**Total No. of Proj.**			**10**		**Total Amount**	**$42,241.00**
074027	TEMPORARY EROSION CONTROL BLANKET		M2	7	2	5,060.00	$3.55	$17,966.00
		Unit Sub Total	**M2**		**2**	**5,060.00**	**$3.55**	**$17,966.00**
074027	TEMPORARY EROSION CONTROL BLANKET		SQYD	1	1	980.00	$5.00	$4,900.00
			SQYD	3	1	116,100.00	$2.21	$256,581.00
			SQYD	8	1	1,000.00	$2.00	$2,000.00
			SQYD	10	1	6,000.00	$4.00	$24,000.00
		Unit Sub Total	**SQYD**		**4**	**124,080.00**	**$2.32**	**$287,481.00**
	Item Code 074027	**Total No. of Proj.**			**6**		**Total Amount**	**$305,447.00**
074028	TEMPORARY FIBER ROLL		LF	1	16	40,390.00	$4.44	$179,257.50
			LF	2	23	36,410.00	$3.91	$142,387.40
			LF	3	17	123,175.00	$2.57	$317,162.50
			LF	4	21	87,060.00	$3.45	$299,967.20
			LF	5	5	11,020.00	$5.35	$58,930.00
			LF	6	8	139,700.00	$1.90	$265,921.00
			LF	7	6	38,980.00	$2.55	$99,207.50
			LF	8	15	78,270.00	$2.67	$209,332.00
			LF	9	10	44,550.00	$2.12	$94,359.00
			LF	10	5	121,570.00	$3.22	$391,942.50
			LF	11	7	32,490.00	$2.34	$76,059.50
			LF	12	6	145,700.00	$1.59	$231,306.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**139**	**899,315.00**	**$2.63**	**$2,365,832.10**
074028	TEMPORARY FIBER ROLL		M	4	1	1,880.00	$10.00	$18,800.00
			M	5	1	41,500.00	$7.00	$290,500.00
			M	7	5	3,055.00	$10.58	$32,325.00
			M	8	1	1,590.00	$7.20	$11,448.00
			M	10	2	17,550.00	$6.05	$106,250.00
			M	11	2	21,180.00	$6.32	$133,960.00
		Unit Sub Total	**M**		**12**	**86,755.00**	**$6.84**	**$593,283.00**
	Item Code 074028	**Total No. of Proj.**			**151**		**Total Amount**	**$2,959,115.10**
074029	TEMPORARY SILT FENCE		LF	1	14	38,530.00	$4.35	$167,797.00
			LF	2	7	4,010.00	$4.63	$18,586.00
			LF	3	7	80,060.00	$1.98	$158,124.10
			LF	4	15	75,840.00	$2.45	$186,060.00
			LF	5	1	590.00	$9.00	$5,310.00
			LF	6	3	82,600.00	$2.03	$167,884.00
			LF	7	4	26,970.00	$2.76	$74,430.00
			LF	8	1	6,500.00	$2.70	$17,550.00
			LF	9	1	2,920.00	$1.75	$5,110.00
			LF	10	3	47,780.00	$2.78	$132,740.00
			LF	12	4	18,710.00	$1.64	$30,660.00
		Unit Sub Total	**LF**		**60**	**384,510.00**	**$2.51**	**$964,251.10**
074029	TEMPORARY SILT FENCE		M	5	1	7,600.00	$9.00	$68,400.00
			M	7	2	4,910.00	$3.77	$18,520.00
			M	8	1	2,970.00	$5.00	$14,850.00
		Unit Sub Total	**M**		**4**	**15,480.00**	**$6.57**	**$101,770.00**
	Item Code 074029	**Total No. of Proj.**			**64**		**Total Amount**	**$1,066,021.10**
074031	TEMPORARY GRAVEL BAG BERM		LF	1	6	7,274.00	$7.11	$51,718.00
			LF	2	6	7,200.00	$6.99	$50,321.00
			LF	3	6	4,740.00	$7.45	$35,318.20
			LF	4	5	13,340.00	$7.59	$101,192.40
			LF	7	11	63,250.00	$1.90	$120,132.00
			LF	8	4	3,980.00	$2.40	$9,545.00
			LF	9	2	268.00	$14.61	$3,916.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074031	TEMPORARY GRAVEL BAG BERM	LF	12	5	20,200.00	$2.75	$55,502.00
	Unit Sub Total	**LF**		**45**	**120,252.00**	**$3.56**	**$427,644.60**
074031	TEMPORARY GRAVEL BAG BERM	M	7	5	30,890.00	$14.41	$445,025.00
	Unit Sub Total	**M**		**5**	**30,890.00**	**$14.41**	**$445,025.00**
	Item Code 074031 Total No. of Proj.			**50**		**Total Amount**	**$872,669.60**
074032	TEMPORARY CONCRETE WASHOUT FACILITY	EA	1	3	11.00	$1,690.91	$18,600.00
		EA	2	1	1.00	$1,000.00	$1,000.00
		EA	3	5	18.00	$1,705.56	$30,700.00
		EA	4	4	44.00	$1,682.95	$74,050.00
		EA	6	3	36.00	$422.22	$15,200.00
		EA	7	5	53.00	$1,850.38	$98,070.00
		EA	10	2	9.00	$1,638.89	$14,750.00
		EA	11	6	69.00	$1,041.30	$71,850.00
		EA	12	1	4.00	$4,000.00	$16,000.00
	Unit Sub Total	**EA**		**30**	**245.00**	**$1,388.65**	**$340,220.00**
	Item Code 074032 Total No. of Proj.			**30**		**Total Amount**	**$340,220.00**
074033	TEMPORARY CONSTRUCTION ENTRANCE	EA	1	10	29.00	$1,779.31	$51,600.00
		EA	2	7	24.00	$2,031.21	$48,749.00
		EA	3	9	96.00	$1,898.70	$182,275.00
		EA	4	20	171.00	$1,779.39	$304,275.00
		EA	5	7	24.00	$2,675.00	$64,200.00
		EA	6	5	33.00	$2,347.27	$77,460.00
		EA	7	12	64.00	$2,881.91	$184,442.00
		EA	8	5	22.00	$2,300.00	$50,600.00
		EA	9	1	2.00	$1,000.00	$2,000.00
		EA	10	4	51.00	$3,252.94	$165,900.00
		EA	11	19	92.00	$2,130.09	$195,968.00
		EA	12	5	48.00	$2,314.38	$111,090.00
	Unit Sub Total	**EA**		**104**	**656.00**	**$2,192.93**	**$1,438,559.00**
074033	TEMPORARY CONSTRUCTION ENTRANCE	LS	7	1	1.00	$5,275.37	$5,275.37
	Unit Sub Total	**LS**		**1**	**1.00**	**$5,275.37**	**$5,275.37**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 074033	**Total No. of Proj.**			**105**		**Total Amount**	**$1,443,834.37**
074034	TEMPORARY COVER		M2	5	1	51,500.00	$0.70	$36,050.00
			M2	7	3	2,790.00	$3.26	$9,100.00
			M2	8	1	8,320.00	$1.90	$15,808.00
		Unit Sub Total	**M2**		**5**	**62,610.00**	**$0.97**	**$60,958.00**
074034	TEMPORARY COVER		SQYD	1	6	21,080.00	$3.03	$63,770.00
			SQYD	2	7	8,600.00	$2.87	$24,662.10
			SQYD	3	6	66,330.00	$1.68	$111,730.90
			SQYD	4	17	54,940.00	$2.70	$148,451.50
			SQYD	5	1	100.00	$10.00	$1,000.00
			SQYD	6	3	14,200.00	$3.06	$43,400.00
			SQYD	7	8	14,298.00	$21.10	$301,702.00
			SQYD	8	12	17,570.00	$2.57	$45,114.00
			SQYD	10	2	128,230.00	$1.28	$164,325.00
			SQYD	11	2	930.00	$2.54	$2,360.00
			SQYD	12	1	5,320.00	$2.00	$10,640.00
		Unit Sub Total	**SQYD**		**65**	**331,598.00**	**$2.77**	**$917,155.50**
	Item Code 074034	**Total No. of Proj.**			**70**		**Total Amount**	**$978,113.50**
074035	TEMPORARY CHECK DAM		LF	1	11	3,640.00	$5.97	$21,732.50
			LF	2	12	6,013.00	$8.19	$49,270.00
			LF	3	4	1,460.00	$5.47	$7,990.30
			LF	4	13	4,078.00	$7.32	$29,844.80
			LF	5	3	555.00	$8.41	$4,665.00
			LF	7	1	120.00	$5.00	$600.00
			LF	10	2	12,940.00	$2.99	$38,750.00
			LF	11	10	3,800.00	$4.24	$16,121.00
			LF	12	1	1,640.00	$2.00	$3,280.00
		Unit Sub Total	**LF**		**57**	**34,246.00**	**$5.03**	**$172,253.60**
074035	TEMPORARY CHECK DAM		M	5	1	2,250.00	$12.00	$27,000.00
			M	7	1	40.00	$34.00	$1,360.00
			M	8	1	130.00	$6.00	$780.00
			M	10	1	3,490.00	$10.00	$34,900.00
			M	11	2	2,760.00	$7.33	$20,220.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**6**	**8,670.00**	**$9.72**	**$84,260.00**
	Item Code 074035 Total No. of Proj.			**63**		**Total Amount**	**$256,513.60**
074036	TEMPORARY STRAW BALE BARRIER	LF	2	1	73.00	$13.00	$949.00
		LF	4	1	320.00	$15.00	$4,800.00
	Unit Sub Total	**LF**		**2**	**393.00**	**$14.63**	**$5,749.00**
074036	TEMPORARY STRAW BALE BARRIER	M	11	1	990.00	$25.00	$24,750.00
	Unit Sub Total	**M**		**1**	**990.00**	**$25.00**	**$24,750.00**
	Item Code 074036 Total No. of Proj.			**3**		**Total Amount**	**$30,499.00**
074037	MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL)	EA	1	4	14.00	$1,169.64	$16,375.00
		EA	2	8	30.00	$866.67	$26,000.00
		EA	3	5	72.00	$386.88	$27,855.00
		EA	4	7	69.00	$821.74	$56,700.00
		EA	5	2	42.00	$1,100.00	$46,200.00
		EA	6	2	6.00	$640.00	$3,840.00
		EA	7	2	36.00	$500.00	$18,000.00
		EA	8	1	12.00	$375.00	$4,500.00
		EA	10	3	22.00	$642.05	$14,125.00
		EA	11	2	20.00	$800.00	$16,000.00
		EA	12	2	43.00	$332.56	$14,300.00
	Unit Sub Total	**EA**		**38**	**366.00**	**$666.38**	**$243,895.00**
	Item Code 074037 Total No. of Proj.			**38**		**Total Amount**	**$243,895.00**
074038	TEMPORARY DRAINAGE INLET PROTECTION	EA	1	14	112.00	$363.65	$40,729.00
		EA	2	14	336.00	$187.16	$62,885.00
		EA	3	16	567.00	$163.64	$92,785.00
		EA	4	49	2,333.00	$160.26	$373,889.44
		EA	5	14	471.00	$194.34	$91,533.00
		EA	6	15	236.00	$257.54	$60,780.00
		EA	7	28	1,108.00	$165.32	$183,172.06
		EA	8	13	94.00	$218.79	$20,566.00
		EA	9	5	146.00	$163.12	$23,816.00
		EA	10	5	610.00	$189.66	$115,690.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074038	TEMPORARY DRAINAGE INLET PROTECTION	EA	11	15	348.00	$191.97	$66,804.00
		EA	12	15	1,241.00	$100.58	$124,817.00
	Unit Sub Total	**EA**		**203**	**7,602.00**	**$165.41**	**$1,257,466.50**
074038	TEMPORARY DRAINAGE INLET PROTECTION	LS	4	1	1.00	$500.00	$500.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$500.00**	**$500.00**
	Item Code 074038 Total No. of Proj.			**204**		**Total Amount**	**$1,257,966.50**
074039	TEMPORARY HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	M2	11	1	312,000.00	$0.30	$93,600.00
	Unit Sub Total	**M2**		**1**	**312,000.00**	**$0.30**	**$93,600.00**
074039	TEMPORARY HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	SQYD	2	9	294,490.00	$0.65	$192,211.50
		SQYD	11	1	1,610.00	$0.80	$1,288.00
	Unit Sub Total	**SQYD**		**10**	**296,100.00**	**$0.65**	**$193,499.50**
	Item Code 074039 Total No. of Proj.			**11**		**Total Amount**	**$287,099.50**
074040	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	M2	5	1	182,000.00	$0.90	$163,800.00
	Unit Sub Total	**M2**		**1**	**182,000.00**	**$0.90**	**$163,800.00**
074040	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	SQYD	1	2	37,100.00	$0.77	$28,470.00
		SQYD	2	1	11,300.00	$0.81	$9,153.00
		SQYD	3	4	38,980.00	$0.80	$31,144.00
		SQYD	4	9	178,970.00	$0.87	$155,755.00
		SQYD	5	1	12,600.00	$0.50	$6,300.00
		SQYD	6	1	24,200.00	$1.00	$24,200.00
		SQYD	7	2	96,800.00	$0.99	$95,660.00
		SQYD	10	1	50,400.00	$1.25	$63,000.00
		SQYD	12	3	268,700.00	$0.63	$169,890.00
	Unit Sub Total	**SQYD**		**24**	**719,050.00**	**$0.81**	**$583,572.00**
	Item Code 074040 Total No. of Proj.			**25**		**Total Amount**	**$747,372.00**
074041	STREET SWEEPING	LS	1	13	13.00	$14,526.23	$188,841.00
		LS	2	5	5.00	$8,800.00	$44,000.00
		LS	3	14	14.00	$41,667.71	$583,348.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074041	STREET SWEEPING	LS	4	46	46.00	$12,491.45	$574,606.57
		LS	5	7	7.00	$47,026.00	$329,182.00
		LS	6	8	8.00	$19,462.50	$155,700.00
		LS	7	20	20.00	$49,785.04	$995,700.75
		LS	8	12	12.00	$11,775.00	$141,300.00
		LS	9	4	4.00	$4,000.00	$16,000.00
		LS	10	7	7.00	$38,585.71	$270,100.00
		LS	11	20	20.00	$11,098.65	$221,973.00
		LS	12	11	11.00	$22,809.64	$250,906.00
	Unit Sub Total	**LS**		**167**	**167.00**	**$22,584.77**	**$3,771,657.32**
	Item Code 074041 Total No. of Proj.			**167**		**Total Amount**	**$3,771,657.32**
074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	EA	1	1	2.00	$1,100.00	$2,200.00
		EA	3	1	1.00	$1,500.00	$1,500.00
		EA	8	3	14.00	$1,785.71	$25,000.00
		EA	10	1	1.00	$1,350.00	$1,350.00
		EA	12	1	3.00	$600.00	$1,800.00
	Unit Sub Total	**EA**		**7**	**21.00**	**$1,516.67**	**$31,850.00**
074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	1	17	17.00	$1,277.35	$21,715.00
		LS	2	23	23.00	$3,331.64	$76,627.70
		LS	3	44	44.00	$2,809.93	$123,637.08
		LS	4	32	32.00	$2,880.86	$92,187.47
		LS	5	18	18.00	$4,901.61	$88,229.00
		LS	6	29	29.00	$2,034.69	$59,006.00
		LS	7	58	58.00	$9,379.74	$544,024.99
		LS	8	23	23.00	$3,059.13	$70,360.00
		LS	9	6	6.00	$1,008.33	$6,050.00
		LS	10	12	12.00	$5,000.92	$60,011.00
		LS	11	20	20.00	$2,512.27	$50,245.31
		LS	12	21	21.00	$1,126.14	$23,649.00
	Unit Sub Total	**LS**		**303**	**303.00**	**$4,012.35**	**$1,215,742.55**
	Item Code 074042 Total No. of Proj.			**310**		**Total Amount**	**$1,247,592.55**
074043	TEMPORARY CONCRETE WASHOUT BIN	EA	4	8	129.00	$791.36	$102,085.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074043	TEMPORARY CONCRETE WASHOUT BIN	EA	5	1	90.00	$200.00	$18,000.00
		EA	8	4	15.00	$818.33	$12,275.00
		EA	10	1	2.00	$500.00	$1,000.00
		EA	11	2	5.00	$804.00	$4,020.00
		EA	12	2	41.00	$706.34	$28,960.00
	Unit Sub Total	**EA**		**18**	**282.00**	**$589.86**	**$166,340.00**
074043	TEMPORARY CONCRETE WASHOUT BIN	LS	4	1	1.00	$5,000.00	$5,000.00
		LS	12	1	1.00	$20,000.00	$20,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$12,500.00**	**$25,000.00**
	Item Code 074043 Total No. of Proj.			**20**		**Total Amount**	**$191,340.00**
074044	TEMPORARY CONSTRUCTION ROADWAY	CY	1	1	370.00	$150.00	$55,500.00
		CY	2	1	500.00	$55.00	$27,500.00
		CY	10	1	2,220.00	$90.00	$199,800.00
	Unit Sub Total	**CY**		**3**	**3,090.00**	**$91.52**	**$282,800.00**
	Item Code 074044 Total No. of Proj.			**3**		**Total Amount**	**$282,800.00**
074045	TEMPORARY LARGE SEDIMENT BARRIER	LF	11	2	80.00	$36.47	$2,917.20
	Unit Sub Total	**LF**		**2**	**80.00**	**$36.47**	**$2,917.20**
	Item Code 074045 Total No. of Proj.			**2**		**Total Amount**	**$2,917.20**
074051	TEMPORARY HYDRAULIC MULCH	M2	7	1	2,560.00	$1.00	$2,560.00
		M2	11	1	112,000.00	$0.30	$33,600.00
	Unit Sub Total	**M2**		**2**	**114,560.00**	**$0.32**	**$36,160.00**
074051	TEMPORARY HYDRAULIC MULCH	SQYD	1	1	3,300.00	$0.66	$2,178.00
		SQYD	3	1	26,700.00	$0.40	$10,680.00
		SQYD	10	1	125,000.00	$0.25	$31,250.00
		SQYD	11	2	7,740.00	$0.46	$3,526.20
	Unit Sub Total	**SQYD**		**5**	**162,740.00**	**$0.29**	**$47,634.20**
	Item Code 074051 Total No. of Proj.			**7**		**Total Amount**	**$83,794.20**
074053	TEMPORARY HYDROSEED	M2	4	1	3,150.00	$2.00	$6,300.00
	Unit Sub Total	**M2**		**1**	**3,150.00**	**$2.00**	**$6,300.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074053	TEMPORARY HYDROSEED	SQYD	3	1	72,600.00	$0.20	$14,520.00
		SQYD	6	1	114,000.00	$0.46	$52,440.00
		SQYD	7	1	2,300.00	$0.80	$1,840.00
		SQYD	12	2	54,100.00	$0.44	$23,555.00
	Unit Sub Total	**SQYD**		**5**	**243,000.00**	**$0.38**	**$92,355.00**
	Item Code 074053 Total No. of Proj.			**6**		**Total Amount**	**$98,655.00**
074054	TEMPORARY TACKED STRAW	SQYD	1	1	17,200.00	$0.23	$3,956.00
		SQYD	4	1	4,000.00	$0.25	$1,000.00
	Unit Sub Total	**SQYD**		**2**	**21,200.00**	**$0.23**	**$4,956.00**
	Item Code 074054 Total No. of Proj.			**2**		**Total Amount**	**$4,956.00**
074055	TEMPORARY SOIL BINDER	M2	8	1	43,000.00	$0.10	$4,300.00
	Unit Sub Total	**M2**		**1**	**43,000.00**	**$0.10**	**$4,300.00**
074055	TEMPORARY SOIL BINDER	SQYD	2	7	460,050.00	$0.23	$105,735.00
		SQYD	3	1	26,000.00	$0.21	$5,460.00
		SQYD	4	1	300,000.00	$0.14	$42,000.00
		SQYD	5	1	600.00	$2.00	$1,200.00
		SQYD	6	1	466,000.00	$0.20	$93,200.00
		SQYD	8	2	79,200.00	$0.26	$20,680.00
		SQYD	10	1	125,000.00	$0.15	$18,750.00
		SQYD	12	1	7,950.00	$0.40	$3,180.00
	Unit Sub Total	**SQYD**		**15**	**1,464,800.00**	**$0.20**	**$290,205.00**
	Item Code 074055 Total No. of Proj.			**16**		**Total Amount**	**$294,505.00**
074056	RAIN EVENT ACTION PLAN	EA	1	8	353.00	$429.32	$151,550.00
		EA	2	10	564.00	$421.10	$237,500.00
		EA	3	7	513.00	$494.08	$253,465.00
		EA	4	9	655.00	$411.76	$269,700.00
		EA	5	2	134.00	$500.00	$67,000.00
		EA	7	7	323.00	$465.33	$150,300.00
		EA	10	3	206.00	$266.75	$54,950.00
		EA	11	11	354.00	$385.08	$136,320.00
		EA	12	4	173.00	$437.51	$75,690.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**61**	**3,275.00**	**$426.40**	**$1,396,475.00**
	Item Code 074056	**Total No. of Proj.**			**61**		**Total Amount**	**$1,396,475.00**
074057	STORM WATER ANNUAL REPORT		EA	1	10	16.00	$2,000.00	$32,000.00
			EA	2	13	31.00	$1,722.61	$53,401.00
			EA	3	8	20.00	$1,627.50	$32,550.00
			EA	4	13	29.00	$1,882.76	$54,600.00
			EA	5	8	19.00	$1,701.05	$32,320.00
			EA	6	9	17.00	$1,382.35	$23,500.00
			EA	7	13	29.00	$1,834.48	$53,200.00
			EA	8	7	7.00	$1,207.14	$8,450.00
			EA	9	2	2.00	$1,000.50	$2,001.00
			EA	10	7	16.00	$1,487.50	$23,800.00
			EA	11	15	36.00	$5,727.20	$206,179.10
			EA	12	5	9.00	$1,400.00	$12,600.00
		Unit Sub Total	**EA**		**110**	**231.00**	**$2,314.29**	**$534,601.10**
074057	STORM WATER ANNUAL REPORT		LS	3	1	1.00	$1,000.00	$1,000.00
			LS	5	1	1.00	$2,000.00	$2,000.00
			LS	6	1	1.00	$2,000.00	$2,000.00
			LS	8	2	2.00	$2,000.00	$4,000.00
			LS	12	2	2.00	$1,000.00	$2,000.00
		Unit Sub Total	**LS**		**7**	**7.00**	**$1,571.43**	**$11,000.00**
	Item Code 074057	**Total No. of Proj.**			**117**		**Total Amount**	**$545,601.10**
074058	STORM WATER SAMPLING AND ANALYSIS DAY		EA	1	8	121.00	$412.40	$49,900.00
			EA	2	10	227.00	$411.01	$93,300.00
			EA	3	7	445.00	$398.03	$177,125.00
			EA	4	9	321.00	$229.31	$73,609.00
			EA	5	2	49.00	$938.78	$46,000.00
			EA	7	7	176.00	$571.88	$100,650.00
			EA	10	4	167.00	$593.71	$99,150.00
			EA	11	10	99.00	$538.30	$53,292.00
			EA	12	4	68.00	$405.37	$27,565.00
		Unit Sub Total	**EA**		**61**	**1,673.00**	**$430.72**	**$720,591.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 074058	**Total No. of Proj.**			**61**		**Total Amount**	**$720,591.00**
120090	CONSTRUCTION AREA SIGNS		LS	1	36	36.00	$8,089.19	$291,211.00
			LS	2	39	39.00	$13,975.21	$545,033.00
			LS	3	64	64.00	$9,514.28	$608,913.95
			LS	4	80	80.00	$11,395.36	$911,628.70
			LS	5	40	40.00	$8,331.34	$333,253.63
			LS	6	47	47.00	$12,152.97	$571,189.50
			LS	7	76	76.00	$11,258.77	$855,666.41
			LS	8	49	49.00	$10,134.86	$496,608.00
			LS	9	14	14.00	$6,167.14	$86,340.00
			LS	10	35	35.00	$11,541.63	$403,957.00
			LS	11	35	35.00	$12,842.69	$449,494.04
			LS	12	34	34.00	$14,597.29	$496,308.00
		Unit Sub Total	**LS**		**549**	**549.00**	**$11,019.31**	**$6,049,603.23**
	Item Code 120090	**Total No. of Proj.**			**549**		**Total Amount**	**$6,049,603.23**
120100	TRAFFIC CONTROL SYSTEM		LS	1	37	37.00	$80,678.51	$2,985,104.85
			LS	2	39	39.00	$128,377.54	$5,006,724.00
			LS	3	67	67.00	$157,658.46	$10,563,116.78
			LS	4	79	79.00	$67,894.62	$5,363,674.60
			LS	5	40	40.00	$118,102.98	$4,724,119.00
			LS	6	46	46.00	$97,601.65	$4,489,675.94
			LS	7	76	76.00	$159,226.53	$12,101,216.00
			LS	8	51	51.00	$89,934.45	$4,586,657.00
			LS	9	14	14.00	$93,729.97	$1,312,219.55
			LS	10	35	35.00	$105,017.11	$3,675,598.86
			LS	11	35	35.00	$73,840.73	$2,584,425.59
			LS	12	34	34.00	$67,684.00	$2,301,256.00
		Unit Sub Total	**LS**		**553**	**553.00**	**$107,945.37**	**$59,693,788.17**
	Item Code 120100	**Total No. of Proj.**			**553**		**Total Amount**	**$59,693,788.17**
120102	TRAFFIC CONTROL SURVEILLANCE		WDAY	2	1	15.00	$1,000.00	$15,000.00
		Unit Sub Total	**WDAY**		**1**	**15.00**	**$1,000.00**	**$15,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 120102 Total No. of Proj.			**1**		**Total Amount**	**$15,000.00**
120116	TYPE II BARRICADE	EA	1	1	80.00	$30.00	$2,400.00
		EA	5	1	4.00	$50.00	$200.00
		EA	6	1	150.00	$100.00	$15,000.00
		EA	7	2	78.00	$29.10	$2,270.00
		EA	8	2	12.00	$43.33	$520.00
		EA	10	1	16.00	$55.00	$880.00
		EA	12	3	31.00	$59.45	$1,843.00
	Unit Sub Total	**EA**		**11**	**371.00**	**$62.30**	**$23,113.00**
	Item Code 120116 Total No. of Proj.			**11**		**Total Amount**	**$23,113.00**
120119	TRAFFIC CONE	EA	7	1	110.00	$20.00	$2,200.00
	Unit Sub Total	**EA**		**1**	**110.00**	**$20.00**	**$2,200.00**
	Item Code 120119 Total No. of Proj.			**1**		**Total Amount**	**$2,200.00**
120120	TYPE III BARRICADE	EA	1	5	102.00	$98.04	$10,000.00
		EA	2	1	33.00	$87.45	$2,885.85
		EA	3	6	154.00	$120.06	$18,490.00
		EA	4	5	286.00	$70.07	$20,040.80
		EA	5	6	246.00	$65.85	$16,200.00
		EA	6	7	154.00	$68.21	$10,504.00
		EA	7	5	370.00	$104.86	$38,800.00
		EA	8	10	306.00	$68.15	$20,854.00
		EA	9	3	8.00	$145.00	$1,160.00
		EA	10	4	148.00	$62.60	$9,265.00
		EA	11	3	7.00	$119.29	$835.00
		EA	12	3	85.00	$120.59	$10,250.00
	Unit Sub Total	**EA**		**58**	**1,899.00**	**$83.88**	**$159,284.65**
	Item Code 120120 Total No. of Proj.			**58**		**Total Amount**	**$159,284.65**
120149	TEMPORARY PAVEMENT MARKING (PAINT)	M2	4	1	34.00	$25.00	$850.00
		M2	7	4	657.00	$33.04	$21,707.00
		M2	8	1	38.00	$25.00	$950.00
		M2	11	2	229.00	$27.58	$6,315.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M2**		**8**	**958.00**	**$31.13**	**$29,822.00**
120149	TEMPORARY PAVEMENT MARKING (PAINT)		SQFT	1	4	904.00	$10.91	$9,860.00
			SQFT	2	7	5,254.00	$4.18	$21,962.80
			SQFT	3	4	5,560.00	$1.20	$6,693.00
			SQFT	4	6	8,740.00	$2.42	$21,121.00
			SQFT	6	4	2,940.00	$1.65	$4,853.00
			SQFT	7	2	850.00	$6.25	$5,315.00
			SQFT	8	3	2,000.00	$2.76	$5,510.00
			SQFT	9	1	120.00	$10.00	$1,200.00
			SQFT	10	2	93.00	$9.42	$876.30
			SQFT	11	3	800.00	$3.43	$2,745.30
			SQFT	12	2	3,040.00	$2.20	$6,675.00
		Unit Sub Total	**SQFT**		**38**	**30,301.00**	**$2.86**	**$86,811.40**
120149	TEMPORARY PAVEMENT MARKING (PAINT)		SQYD	1	1	5.30	$120.00	$636.00
		Unit Sub Total	**SQYD**		**1**	**5.30**	**$120.00**	**$636.00**
	Item Code 120149	**Total No. of Proj.**			**47**		**Total Amount**	**$117,269.40**
120150	TEMPORARY PAVEMENT MARKING		SQFT	11	1	510.00	$2.00	$1,020.00
		Unit Sub Total	**SQFT**		**1**	**510.00**	**$2.00**	**$1,020.00**
	Item Code 120150	**Total No. of Proj.**			**1**		**Total Amount**	**$1,020.00**
120151	TEMPORARY TRAFFIC STRIPE (TAPE)		LF	1	3	36,150.00	$1.46	$52,950.00
			LF	2	3	123,500.00	$1.27	$156,700.00
			LF	3	3	311,900.00	$1.09	$339,149.00
			LF	4	4	13,780.00	$2.59	$35,720.00
			LF	6	4	211,850.00	$0.52	$109,582.00
			LF	7	1	14,900.00	$1.87	$27,863.00
			LF	9	1	3,710.00	$2.25	$8,347.50
		Unit Sub Total	**LF**		**19**	**715,790.00**	**$1.02**	**$730,311.50**
120151	TEMPORARY TRAFFIC STRIPE (TAPE)		M	10	1	6,770.00	$4.00	$27,080.00
		Unit Sub Total	**M**		**1**	**6,770.00**	**$4.00**	**$27,080.00**
	Item Code 120151	**Total No. of Proj.**			**20**		**Total Amount**	**$757,391.50**
120152	TEMPORARY PAVEMENT MARKING (TAPE)		SQFT	1	2	174.00	$28.61	$4,977.84

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
120152	TEMPORARY PAVEMENT MARKING (TAPE)	SQFT	2	3	3,755.00	$5.81	$21,815.00
		SQFT	3	1	1,410.00	$4.00	$5,640.00
		SQFT	4	4	390.00	$16.40	$6,396.00
		SQFT	6	4	1,540.00	$6.09	$9,385.00
	Unit Sub Total	**SQFT**		**14**	**7,269.00**	**$6.63**	**$48,213.84**
	Item Code 120152 Total No. of Proj.			**14**		**Total Amount**	**$48,213.84**
120154	TEMPORARY MARKER	EA	2	1	27.00	$25.00	$675.00
		EA	4	1	130.00	$25.00	$3,250.00
	Unit Sub Total	**EA**		**2**	**157.00**	**$25.00**	**$3,925.00**
	Item Code 120154 Total No. of Proj.			**2**		**Total Amount**	**$3,925.00**
120159	TEMPORARY TRAFFIC STRIPE (PAINT)	LF	1	7	96,760.00	$0.52	$49,969.50
		LF	2	9	1,936,910.00	$0.20	$386,666.19
		LF	3	7	1,656,770.00	$0.13	$214,612.00
		LF	4	13	1,541,270.00	$0.54	$833,820.50
		LF	5	4	46,400.00	$0.87	$40,260.00
		LF	6	6	786,840.00	$0.18	$142,595.00
		LF	7	4	161,700.00	$0.68	$110,638.00
		LF	8	7	452,290.00	$0.24	$109,491.00
		LF	9	3	286,340.00	$0.05	$13,056.00
		LF	10	2	14,600.00	$1.35	$19,750.00
		LF	11	8	172,970.00	$0.31	$54,287.20
		LF	12	2	760,000.00	$0.12	$93,910.00
	Unit Sub Total	**LF**		**72**	**7,912,850.00**	**$0.26**	**$2,069,055.39**
120159	TEMPORARY TRAFFIC STRIPE (PAINT)	M	4	1	5,090.00	$1.00	$5,090.00
		M	7	5	141,030.00	$1.06	$149,301.00
		M	8	1	17,500.00	$0.70	$12,250.00
		M	11	2	46,700.00	$0.89	$41,700.00
	Unit Sub Total	**M**		**9**	**210,320.00**	**$0.99**	**$208,341.00**
	Item Code 120159 Total No. of Proj.			**81**		**Total Amount**	**$2,277,396.39**
120165	CHANNELIZER (SURFACE MOUNTED)	EA	1	7	437.00	$37.12	$16,219.80
		EA	2	9	4,063.00	$29.93	$121,609.53
		EA	3	14	2,724.00	$32.98	$89,850.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
120165	CHANNELIZER (SURFACE MOUNTED)	EA	4	18	4,170.00	$32.79	$136,752.80
		EA	5	6	2,037.00	$22.88	$46,600.00
		EA	6	9	11,934.00	$17.40	$207,646.00
		EA	7	17	2,574.00	$31.76	$81,759.23
		EA	8	10	3,612.00	$27.43	$99,074.60
		EA	9	1	110.00	$23.50	$2,585.00
		EA	10	6	1,532.00	$38.31	$58,698.50
		EA	11	1	87.00	$32.00	$2,784.00
		EA	12	8	2,246.00	$27.63	$62,068.00
	Unit Sub Total	**EA**		**106**	**35,526.00**	**$26.06**	**$925,647.46**
	Item Code 120165 Total No. of Proj.			**106**		**Total Amount**	**$925,647.46**
120166	CHANNELIZER (SURFACE MOUNTED) (LEFT IN PLACE)	EA	5	3	38.00	$45.26	$1,720.00
		EA	7	2	270.00	$25.07	$6,770.00
		EA	12	1	14.00	$26.00	$364.00
	Unit Sub Total	**EA**		**6**	**322.00**	**$27.50**	**$8,854.00**
	Item Code 120166 Total No. of Proj.			**6**		**Total Amount**	**$8,854.00**
120182	PORTABLE DELINEATOR	EA	4	1	2,210.00	$14.75	$32,597.50
		EA	5	1	110.00	$6.55	$720.50
		EA	10	1	130.00	$6.00	$780.00
	Unit Sub Total	**EA**		**3**	**2,450.00**	**$13.92**	**$34,098.00**
	Item Code 120182 Total No. of Proj.			**3**		**Total Amount**	**$34,098.00**
120199	TRAFFIC PLASTIC DRUM	EA	1	1	60.00	$50.00	$3,000.00
		EA	2	1	10.00	$56.00	$560.00
		EA	3	5	1,462.00	$30.05	$43,935.00
		EA	4	1	20.00	$65.00	$1,300.00
		EA	11	13	701.00	$62.12	$43,545.00
	Unit Sub Total	**EA**		**21**	**2,253.00**	**$40.99**	**$92,340.00**
	Item Code 120199 Total No. of Proj.			**21**		**Total Amount**	**$92,340.00**
120200	FLASHING BEACON (PORTABLE)	EA	3	1	8.00	$845.00	$6,760.00
		EA	8	4	30.00	$1,195.73	$35,872.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
120200	FLASHING BEACON (PORTABLE)	EA	9	1	2.00	$300.00	$600.00
	Unit Sub Total	**EA**		**6**	**40.00**	**$1,080.80**	**$43,232.00**
	Item Code 120200 Total No. of Proj.			**6**		**Total Amount**	**$43,232.00**
120300	TEMPORARY PAVEMENT MARKER	EA	2	2	13,660.00	$3.42	$46,700.00
		EA	3	8	125,882.00	$2.92	$367,025.00
		EA	4	13	54,096.00	$3.39	$183,553.80
		EA	5	2	1,796.00	$6.10	$10,960.00
		EA	6	7	21,571.00	$3.95	$85,300.50
		EA	7	7	24,400.00	$3.90	$95,237.20
		EA	8	5	12,630.00	$3.21	$40,503.20
		EA	10	2	650.00	$3.58	$2,328.00
		EA	11	10	11,617.00	$3.13	$36,407.80
	Unit Sub Total	**EA**		**56**	**266,302.00**	**$3.26**	**$868,015.50**
	Item Code 120300 Total No. of Proj.			**56**		**Total Amount**	**$868,015.50**
121140	TEMPORARY METAL BEAM GUARD RAILING	LF	3	1	25.00	$25.00	$625.00
	Unit Sub Total	**LF**		**1**	**25.00**	**$25.00**	**$625.00**
	Item Code 121140 Total No. of Proj.			**1**		**Total Amount**	**$625.00**
121161	TEMPORARY TERMINAL SECTION (TYPE K)	EA	4	2	9.00	$1,266.67	$11,400.00
		EA	5	1	13.00	$1,500.00	$19,500.00
		EA	7	4	17.00	$1,352.94	$23,000.00
		EA	12	1	2.00	$2,000.00	$4,000.00
	Unit Sub Total	**EA**		**8**	**41.00**	**$1,412.20**	**$57,900.00**
	Item Code 121161 Total No. of Proj.			**8**		**Total Amount**	**$57,900.00**
128202	TEMPORARY DELINEATOR (CLASS 2)	EA	4	1	200.00	$45.00	$9,000.00
	Unit Sub Total	**EA**		**1**	**200.00**	**$45.00**	**$9,000.00**
	Item Code 128202 Total No. of Proj.			**1**		**Total Amount**	**$9,000.00**
128601	TEMPORARY SIGNAL SYSTEM	LS	1	4	4.00	$124,409.25	$497,637.00
		LS	2	1	1.00	$90,000.00	$90,000.00
		LS	4	3	3.00	$56,000.00	$168,000.00
		LS	10	1	1.00	$42,000.00	$42,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LS**		**9**	**9.00**	**$88,626.33**	**$797,637.00**
	Item Code 128601	**Total No. of Proj.**			**9**		**Total Amount**	**$797,637.00**
128650	PORTABLE CHANGEABLE MESSAGE SIGN		EA	1	20	55.00	$2,683.18	$147,575.00
			EA	2	3	7.00	$5,142.86	$36,000.00
			EA	4	6	18.00	$5,066.67	$91,200.00
			EA	7	1	4.00	$9,500.00	$38,000.00
			EA	8	42	136.00	$3,277.85	$445,787.00
			EA	11	33	118.00	$3,949.92	$466,091.08
			EA	12	1	8.00	$3,900.00	$31,200.00
		Unit Sub Total	**EA**		**106**	**346.00**	**$3,629.63**	**$1,255,853.08**
128650	PORTABLE CHANGEABLE MESSAGE SIGN		LS	1	18	18.00	$12,889.00	$232,002.00
			LS	2	35	35.00	$15,006.78	$525,237.40
			LS	3	66	66.00	$14,111.91	$931,385.79
			LS	4	66	66.00	$6,059.42	$399,922.00
			LS	5	40	40.00	$7,949.03	$317,961.00
			LS	6	46	46.00	$9,480.66	$436,110.50
			LS	8	8	8.00	$5,086.75	$40,694.00
			LS	9	13	13.00	$4,726.92	$61,450.00
			LS	10	35	35.00	$12,863.86	$450,235.00
			LS	11	1	1.00	$7,000.00	$7,000.00
			LS	12	28	28.00	$10,090.64	$282,538.00
		Unit Sub Total	**LS**		**356**	**356.00**	**$10,349.82**	**$3,684,535.69**
	Item Code 128650	**Total No. of Proj.**			**462**		**Total Amount**	**$4,940,388.77**
128660	TEMPORARY FLASHING BEACON		EA	1	1	2.00	$4,500.00	$9,000.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$4,500.00**	**$9,000.00**
	Item Code 128660	**Total No. of Proj.**			**1**		**Total Amount**	**$9,000.00**
129000	TEMPORARY RAILING (TYPE K)		LF	1	12	11,050.00	$35.13	$388,214.00
			LF	2	11	397,280.00	$12.26	$4,872,410.80
			LF	3	17	422,850.00	$6.69	$2,829,140.00
			LF	4	25	411,150.00	$6.89	$2,833,255.00
			LF	5	5	37,640.00	$10.20	$383,800.00
			LF	6	6	258,780.00	$5.56	$1,439,402.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
129000	TEMPORARY RAILING (TYPE K)		LF	7	11	163,720.00	$12.98	$2,125,271.90
			LF	8	9	151,000.00	$11.29	$1,705,343.00
			LF	9	1	1,600.00	$5.00	$8,000.00
			LF	10	4	186,840.00	$6.22	$1,161,800.00
			LF	11	12	82,660.00	$9.35	$773,045.00
			LF	12	7	139,810.00	$7.97	$1,114,805.00
		Unit Sub Total	**LF**		**120**	**2,264,380.00**	**$8.67**	**$19,634,487.20**
129000	TEMPORARY RAILING (TYPE K)		M	4	1	2,400.00	$50.00	$120,000.00
			M	5	1	25,100.00	$10.00	$251,000.00
			M	7	4	25,160.00	$29.78	$749,230.00
			M	8	1	11,900.00	$25.00	$297,500.00
			M	11	2	21,690.00	$15.74	$341,460.00
		Unit Sub Total	**M**		**9**	**86,250.00**	**$20.40**	**$1,759,190.00**
	Item Code 129000	**Total No. of Proj.**			**129**		**Total Amount**	**$21,393,677.20**
129100	TEMPORARY CRASH CUSHION MODULE		EA	1	5	262.00	$281.20	$73,674.84
			EA	2	8	823.00	$144.06	$118,561.12
			EA	3	17	2,199.00	$192.48	$423,268.00
			EA	4	20	2,846.00	$154.67	$440,200.50
			EA	5	3	850.00	$168.65	$143,350.00
			EA	6	6	592.00	$199.47	$118,088.00
			EA	7	14	1,750.00	$192.13	$336,227.52
			EA	8	9	1,297.00	$169.38	$219,689.00
			EA	9	1	120.00	$50.00	$6,000.00
			EA	10	4	666.00	$187.12	$124,624.00
			EA	11	9	880.00	$186.53	$164,146.00
			EA	12	7	1,092.00	$215.23	$235,030.00
		Unit Sub Total	**EA**		**103**	**13,377.00**	**$179.63**	**$2,402,858.98**
	Item Code 129100	**Total No. of Proj.**			**103**		**Total Amount**	**$2,402,858.98**
129110	TEMPORARY CRASH CUSHION		EA	4	1	18.00	$2,800.00	$50,400.00
			EA	8	1	170.00	$175.00	$29,750.00
		Unit Sub Total	**EA**		**2**	**188.00**	**$426.33**	**$80,150.00**
	Item Code 129110	**Total No. of Proj.**			**2**		**Total Amount**	**$80,150.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
129150	TEMPORARY TRAFFIC SCREEN	LF	2	1	46,800.00	$2.00	$93,600.00
		LF	3	3	324,300.00	$1.91	$620,250.00
		LF	4	1	35,400.00	$3.00	$106,200.00
		LF	5	1	1,500.00	$7.00	$10,500.00
		LF	8	1	11,400.00	$3.00	$34,200.00
		LF	10	2	3,200.00	$3.25	$10,400.00
		LF	12	7	124,410.00	$2.46	$305,885.00
	Unit Sub Total	**LF**		**16**	**547,010.00**	**$2.16**	**$1,181,035.00**
129150	TEMPORARY TRAFFIC SCREEN	M	8	1	6,280.00	$10.00	$62,800.00
	Unit Sub Total	**M**		**1**	**6,280.00**	**$10.00**	**$62,800.00**
	Item Code 129150 Total No. of Proj.			**17**		**Total Amount**	**$1,243,835.00**
129510	TEMPORARY RETAINING WALL	SQFT	7	1	7,080.00	$16.00	$113,280.00
	Unit Sub Total	**SQFT**		**1**	**7,080.00**	**$16.00**	**$113,280.00**
	Item Code 129510 Total No. of Proj.			**1**		**Total Amount**	**$113,280.00**
141101	REMOVE YELLOW PAINTED TRAFFIC STRIPE (HAZARDOUS WASTE)	LF	2	2	130,810.00	$0.82	$107,240.00
		LF	3	1	1,390.00	$10.00	$13,900.00
		LF	4	2	3,260.00	$1.32	$4,289.00
		LF	6	1	206,000.00	$0.16	$32,960.00
		LF	7	2	28,870.00	$0.92	$26,479.00
		LF	10	2	20,870.00	$0.52	$10,750.00
		LF	11	12	233,940.00	$0.35	$83,047.30
		LF	12	1	1,140.00	$1.45	$1,653.00
	Unit Sub Total	**LF**		**23**	**626,280.00**	**$0.45**	**$280,318.30**
141101	REMOVE YELLOW PAINTED TRAFFIC STRIPE (HAZARDOUS WASTE)	M	7	1	10,200.00	$2.00	$20,400.00
		M	11	1	3,280.00	$1.50	$4,920.00
	Unit Sub Total	**M**		**2**	**13,480.00**	**$1.88**	**$25,320.00**
	Item Code 141101 Total No. of Proj.			**25**		**Total Amount**	**$305,638.30**
141103	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	LF	1	7	220,530.00	$0.54	$118,799.00
		LF	2	5	69,100.00	$1.16	$79,851.20

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
141103	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	LF	3	18	277,510.00	$1.03	$284,666.00
		LF	4	37	1,333,940.00	$0.58	$772,717.60
		LF	5	10	205,510.00	$0.69	$141,394.00
		LF	6	10	164,510.00	$0.53	$87,555.40
		LF	7	36	873,910.00	$0.45	$393,697.90
		LF	8	20	510,150.00	$0.42	$216,157.00
		LF	10	7	93,545.00	$0.55	$51,393.00
		LF	12	19	1,411,280.00	$0.40	$566,178.00
	Unit Sub Total	**LF**		**169**	**5,159,985.00**	**$0.53**	**$2,712,409.10**
141103	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	M	4	1	2,850.00	$4.00	$11,400.00
		M	5	1	15,900.00	$1.40	$22,260.00
		M	7	4	21,630.00	$1.67	$36,227.00
		M	8	1	7,120.00	$3.50	$24,920.00
		M	10	1	810.00	$10.00	$8,100.00
	Unit Sub Total	**M**		**8**	**48,310.00**	**$2.13**	**$102,907.00**
	Item Code 141103 Total No. of Proj.			**177**		**Total Amount**	**$2,815,316.10**
141104	REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING (HAZARDOUS WASTE)	LF	7	1	53,100.00	$0.42	$22,302.00
	Unit Sub Total	**LF**		**1**	**53,100.00**	**$0.42**	**$22,302.00**
141104	REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING (HAZARDOUS WASTE)	SQFT	1	3	780.00	$10.18	$7,943.00
		SQFT	2	1	79.00	$10.49	$829.03
		SQFT	3	3	1,720.00	$9.52	$16,370.00
		SQFT	4	1	1,320.00	$2.50	$3,300.00
		SQFT	5	1	400.00	$5.00	$2,000.00
		SQFT	6	1	3,670.00	$1.68	$6,165.60
		SQFT	7	3	1,550.00	$2.58	$3,994.00
		SQFT	10	4	2,860.00	$5.30	$15,152.00
		SQFT	12	2	1,150.00	$1.83	$2,100.00
	Unit Sub Total	**SQFT**		**19**	**13,529.00**	**$4.28**	**$57,853.63**
	Item Code 141104 Total No. of Proj.			**20**		**Total Amount**	**$80,155.63**
146001	CONTRACTOR SUPPLIED BIOLOGIST (DAY)	DAY	10	1	120.00	$1,000.00	$120,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**DAY**		**1**	**120.00**	**$1,000.00**	**$120,000.00**
146001	CONTRACTOR SUPPLIED BIOLOGIST (DAY)	WDAY	1	1	150.00	$700.00	$105,000.00
	Unit Sub Total	**WDAY**		**1**	**150.00**	**$700.00**	**$105,000.00**
	Item Code 146001 Total No. of Proj.			**2**		**Total Amount**	**$225,000.00**
146002	CONTRACTOR SUPPLIED BIOLOGIST (LS)	LS	1	1	1.00	$60,000.00	$60,000.00
		LS	3	1	1.00	$100,000.00	$100,000.00
		LS	4	2	2.00	$25,500.00	$51,000.00
		LS	5	1	1.00	$45,000.00	$45,000.00
		LS	6	4	4.00	$17,947.50	$71,790.00
		LS	7	2	2.00	$67,150.00	$134,300.00
		LS	8	1	1.00	$27,000.00	$27,000.00
		LS	9	1	1.00	$35,000.00	$35,000.00
	Unit Sub Total	**LS**		**13**	**13.00**	**$40,314.62**	**$524,090.00**
	Item Code 146002 Total No. of Proj.			**13**		**Total Amount**	**$524,090.00**
146003	NATURAL RESOURCE PROTECTION PLAN	LS	1	1	1.00	$6,950.00	$6,950.00
		LS	3	2	2.00	$3,750.00	$7,500.00
		LS	5	1	1.00	$4,000.00	$4,000.00
		LS	6	1	1.00	$4,200.00	$4,200.00
		LS	7	1	1.00	$5,000.00	$5,000.00
		LS	10	1	1.00	$2,000.00	$2,000.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$4,235.71**	**$29,650.00**
	Item Code 146003 Total No. of Proj.			**7**		**Total Amount**	**$29,650.00**
146004	FISH PROTECTION	LS	10	1	1.00	$15,000.00	$15,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$15,000.00**	**$15,000.00**
	Item Code 146004 Total No. of Proj.			**1**		**Total Amount**	**$15,000.00**
146006	TEMPORARY WETLAND PROTECTION MAT (LS)	LS	3	1	1.00	$13,207.00	$13,207.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$13,207.00**	**$13,207.00**
	Item Code 146006 Total No. of Proj.			**1**		**Total Amount**	**$13,207.00**
148005	NOISE MONITORING	LS	4	34	34.00	$1,504.37	$51,148.69

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
148005	NOISE MONITORING		LS	7	2	2.00	$48,100.00	$96,200.00
		Unit Sub Total	**LS**		**36**	**36.00**	**$4,093.02**	**$147,348.69**
	Item Code 148005	**Total No. of Proj.**			**36**		**Total Amount**	**$147,348.69**
150206	ABANDON CULVERT		EA	1	7	15.00	$1,792.67	$26,890.00
			EA	2	2	12.00	$1,533.33	$18,400.00
			EA	3	4	21.00	$1,457.14	$30,600.00
			EA	4	3	17.00	$829.41	$14,100.00
			EA	5	1	1.00	$1,200.00	$1,200.00
			EA	6	2	6.00	$1,433.33	$8,600.00
			EA	8	1	4.00	$1,700.00	$6,800.00
			EA	9	1	1.00	$2,750.00	$2,750.00
			EA	10	1	1.00	$2,500.00	$2,500.00
			EA	11	1	9.00	$200.00	$1,800.00
		Unit Sub Total	**EA**		**23**	**87.00**	**$1,306.21**	**$113,640.00**
150206	ABANDON CULVERT		LF	1	1	270.00	$21.50	$5,805.00
			LF	2	1	400.00	$32.00	$12,800.00
			LF	3	2	660.00	$59.45	$39,240.00
			LF	4	7	3,048.00	$20.99	$63,977.00
			LF	6	1	320.00	$20.00	$6,400.00
			LF	7	1	390.00	$25.00	$9,750.00
			LF	9	1	44.00	$68.00	$2,992.00
			LF	10	2	2,630.00	$14.45	$38,010.00
			LF	11	1	440.00	$9.00	$3,960.00
			LF	12	2	83.00	$70.84	$5,880.00
		Unit Sub Total	**LF**		**19**	**8,285.00**	**$22.79**	**$188,814.00**
150206	ABANDON CULVERT		M	4	1	57.00	$25.00	$1,425.00
			M	5	1	580.00	$8.00	$4,640.00
		Unit Sub Total	**M**		**2**	**637.00**	**$9.52**	**$6,065.00**
	Item Code 150206	**Total No. of Proj.**			**44**		**Total Amount**	**$308,519.00**
150221	ABANDON INLET		EA	2	1	1.00	$1,700.00	$1,700.00
			EA	3	3	13.00	$842.31	$10,950.00
			EA	4	2	8.00	$556.25	$4,450.00
			EA	7	2	23.00	$1,413.04	$32,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150221	ABANDON INLET		EA	10	1	11.00	$600.00	$6,600.00
			EA	11	1	6.00	$200.00	$1,200.00
		Unit Sub Total	**EA**		**10**	**62.00**	**$925.81**	**$57,400.00**
	Item Code 150221	**Total No. of Proj.**			**10**		**Total Amount**	**$57,400.00**
150224	ABANDON MANHOLE		EA	4	2	5.00	$524.00	$2,620.00
			EA	5	1	5.00	$400.00	$2,000.00
			EA	8	1	1.00	$500.00	$500.00
		Unit Sub Total	**EA**		**4**	**11.00**	**$465.45**	**$5,120.00**
	Item Code 150224	**Total No. of Proj.**			**4**		**Total Amount**	**$5,120.00**
150227	ABANDON PIPELINE		EA	3	1	220.00	$200.00	$44,000.00
		Unit Sub Total	**EA**		**1**	**220.00**	**$200.00**	**$44,000.00**
150227	ABANDON PIPELINE		LF	4	2	1,510.00	$3.82	$5,766.00
			LF	7	1	1,570.00	$11.00	$17,270.00
		Unit Sub Total	**LF**		**3**	**3,080.00**	**$7.48**	**$23,036.00**
150227	ABANDON PIPELINE		M	7	2	131.00	$91.69	$12,012.00
		Unit Sub Total	**M**		**2**	**131.00**	**$91.69**	**$12,012.00**
	Item Code 150227	**Total No. of Proj.**			**6**		**Total Amount**	**$79,048.00**
150229	ABANDON WATER WELL		EA	3	1	1.00	$7,000.00	$7,000.00
			EA	5	1	1.00	$7,000.00	$7,000.00
			EA	10	1	1.00	$11,000.00	$11,000.00
		Unit Sub Total	**EA**		**3**	**3.00**	**$8,333.33**	**$25,000.00**
	Item Code 150229	**Total No. of Proj.**			**3**		**Total Amount**	**$25,000.00**
150230	DESTROY WELL		EA	6	1	3.00	$6,300.00	$18,900.00
		Unit Sub Total	**EA**		**1**	**3.00**	**$6,300.00**	**$18,900.00**
	Item Code 150230	**Total No. of Proj.**			**1**		**Total Amount**	**$18,900.00**
150241	ABANDON SEWER		M	7	1	2,650.00	$14.00	$37,100.00
		Unit Sub Total	**M**		**1**	**2,650.00**	**$14.00**	**$37,100.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150241	**Total No. of Proj.**			**1**		**Total Amount**	**$37,100.00**
150305	OBLITERATE SURFACING		M2	7	1	10,100.00	$1.00	$10,100.00
			M2	8	1	690.00	$11.00	$7,590.00
		Unit Sub Total	**M2**		**2**	**10,790.00**	**$1.64**	**$17,690.00**
150305	OBLITERATE SURFACING		SQYD	1	2	165.00	$9.64	$1,590.00
			SQYD	2	1	170.00	$20.00	$3,400.00
			SQYD	3	5	13,990.00	$1.26	$17,630.00
			SQYD	5	1	1,330.00	$2.00	$2,660.00
			SQYD	6	1	2,820.00	$2.50	$7,050.00
			SQYD	8	2	6,850.00	$2.53	$17,304.00
			SQYD	10	1	1,440.00	$4.00	$5,760.00
		Unit Sub Total	**SQYD**		**13**	**26,765.00**	**$2.07**	**$55,394.00**
	Item Code 150305	**Total No. of Proj.**			**15**		**Total Amount**	**$73,084.00**
150306	REPAIR SPALLED CONCRETE		CF	7	1	29.00	$411.00	$11,919.00
		Unit Sub Total	**CF**		**1**	**29.00**	**$411.00**	**$11,919.00**
	Item Code 150306	**Total No. of Proj.**			**1**		**Total Amount**	**$11,919.00**
150604	REMOVE WOOD FENCE		LF	4	1	590.00	$5.00	$2,950.00
		Unit Sub Total	**LF**		**1**	**590.00**	**$5.00**	**$2,950.00**
	Item Code 150604	**Total No. of Proj.**			**1**		**Total Amount**	**$2,950.00**
150605	REMOVE FENCE		LF	1	6	5,060.00	$2.85	$14,440.00
			LF	2	1	300.00	$8.00	$2,400.00
			LF	3	4	25,660.00	$4.37	$112,070.50
			LF	4	6	30,300.00	$3.31	$100,275.00
			LF	6	3	62,363.00	$1.02	$63,682.00
			LF	7	1	2,800.00	$5.00	$14,000.00
			LF	8	1	950.00	$4.00	$3,800.00
			LF	10	2	3,750.00	$2.91	$10,910.00
		Unit Sub Total	**LF**		**24**	**131,183.00**	**$2.45**	**$321,577.50**
150605	REMOVE FENCE		M	4	1	1,170.00	$8.00	$9,360.00
			M	5	1	9,770.00	$9.00	$87,930.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150605	REMOVE FENCE		M	10	1	9,270.00	$3.50	$32,445.00
			M	11	1	290.00	$15.00	$4,350.00
		Unit Sub Total	**M**		**4**	**20,500.00**	**$6.54**	**$134,085.00**
	Item Code 150605	**Total No. of Proj.**			**28**		**Total Amount**	**$455,662.50**
150606	REMOVE FENCE (TYPE BW)		LF	1	1	66.00	$30.00	$1,980.00
			LF	2	1	40.00	$2.50	$100.00
			LF	3	2	1,590.00	$3.84	$6,100.00
			LF	5	1	810.00	$2.00	$1,620.00
			LF	6	1	51,100.00	$1.50	$76,650.00
			LF	8	1	4,440.00	$2.50	$11,100.00
		Unit Sub Total	**LF**		**7**	**58,046.00**	**$1.68**	**$97,550.00**
	Item Code 150606	**Total No. of Proj.**			**7**		**Total Amount**	**$97,550.00**
150608	REMOVE CHAIN LINK FENCE		LF	1	1	730.00	$4.00	$2,920.00
			LF	2	1	380.00	$4.10	$1,558.00
			LF	3	3	990.00	$8.59	$8,502.50
			LF	4	6	30,630.00	$2.50	$76,519.20
			LF	5	4	35,220.00	$3.50	$123,150.00
			LF	6	3	1,018.00	$9.30	$9,469.84
			LF	7	2	6,619.00	$6.78	$44,851.80
			LF	8	2	310.00	$5.06	$1,570.00
			LF	9	1	830.00	$5.00	$4,150.00
			LF	10	1	1,210.00	$6.00	$7,260.00
			LF	11	3	14,220.00	$4.64	$66,000.00
			LF	12	3	2,220.00	$7.20	$15,980.00
		Unit Sub Total	**LF**		**30**	**94,377.00**	**$3.83**	**$361,931.34**
150608	REMOVE CHAIN LINK FENCE		M	7	3	3,758.00	$9.83	$36,956.50
			M	8	1	515.00	$18.00	$9,270.00
		Unit Sub Total	**M**		**4**	**4,273.00**	**$10.82**	**$46,226.50**
	Item Code 150608	**Total No. of Proj.**			**34**		**Total Amount**	**$408,157.84**
150615	REMOVE ENTRANCE TAPER		EA	3	1	3.00	$750.00	$2,250.00
			EA	4	1	3.00	$150.00	$450.00
			EA	6	2	6.00	$206.67	$1,240.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**4**	**12.00**	**$328.33**	**$3,940.00**
	Item Code 150615	**Total No. of Proj.**			**4**		**Total Amount**	**$3,940.00**
150620	REMOVE GATE		EA	1	2	2.00	$250.00	$500.00
			EA	4	2	5.00	$287.00	$1,435.00
			EA	5	3	18.00	$300.00	$5,400.00
			EA	7	1	4.00	$250.00	$1,000.00
			EA	9	1	1.00	$100.00	$100.00
			EA	10	1	16.00	$375.00	$6,000.00
		Unit Sub Total	**EA**		**10**	**46.00**	**$313.80**	**$14,435.00**
	Item Code 150620	**Total No. of Proj.**			**10**		**Total Amount**	**$14,435.00**
150630	REMOVE MARKER		EA	1	3	18.00	$38.33	$690.00
			EA	2	6	297.00	$23.49	$6,978.00
			EA	4	1	43.00	$1.00	$43.00
			EA	5	1	10.00	$1.00	$10.00
			EA	6	1	2.00	$150.00	$300.00
			EA	9	4	149.00	$18.15	$2,705.00
			EA	10	1	18.00	$1.00	$18.00
		Unit Sub Total	**EA**		**17**	**537.00**	**$20.01**	**$10,744.00**
	Item Code 150630	**Total No. of Proj.**			**17**		**Total Amount**	**$10,744.00**
150659	REMOVE TERMINAL SECTION		EA	3	1	15.00	$350.00	$5,250.00
		Unit Sub Total	**EA**		**1**	**15.00**	**$350.00**	**$5,250.00**
	Item Code 150659	**Total No. of Proj.**			**1**		**Total Amount**	**$5,250.00**
150662	REMOVE METAL BEAM GUARD RAILING		LF	1	10	15,090.00	$7.33	$110,565.00
			LF	2	12	6,582.00	$8.62	$56,740.00
			LF	3	22	117,181.00	$5.43	$635,958.20
			LF	4	15	48,800.00	$4.69	$228,949.00
			LF	5	7	3,616.00	$10.22	$36,948.00
			LF	6	6	12,643.00	$6.53	$82,600.00
			LF	7	11	9,606.00	$8.35	$80,163.50
			LF	8	10	98,113.00	$6.38	$625,725.60
			LF	10	4	5,750.00	$8.06	$46,340.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150662	REMOVE METAL BEAM GUARD RAILING	LF	11	7	9,060.00	$8.28	$75,019.80
		LF	12	10	47,725.00	$5.15	$245,554.00
	Unit Sub Total	**LF**		**114**	**374,166.00**	**$5.95**	**$2,224,563.10**
150662	REMOVE METAL BEAM GUARD RAILING	M	4	1	550.00	$15.00	$8,250.00
		M	5	1	340.00	$25.00	$8,500.00
		M	7	4	1,280.00	$21.97	$28,120.00
		M	8	1	43.00	$29.00	$1,247.00
		M	11	2	957.00	$13.37	$12,795.00
	Unit Sub Total	**M**		**9**	**3,170.00**	**$18.58**	**$58,912.00**
	Item Code 150662 Total No. of Proj.			**123**		**Total Amount**	**$2,283,475.10**
150666	REMOVE METAL BEAM BARRIER	LF	11	1	690.00	$37.00	$25,530.00
	Unit Sub Total	**LF**		**1**	**690.00**	**$37.00**	**$25,530.00**
	Item Code 150666 Total No. of Proj.			**1**		**Total Amount**	**$25,530.00**
150667	REMOVE DOUBLE METAL BEAM BARRIER	LF	3	2	3,710.00	$6.25	$23,170.00
		LF	7	4	26,370.00	$6.76	$178,328.00
	Unit Sub Total	**LF**		**6**	**30,080.00**	**$6.70**	**$201,498.00**
150667	REMOVE DOUBLE METAL BEAM BARRIER	M	4	1	110.00	$26.00	$2,860.00
		M	7	1	1,910.00	$35.00	$66,850.00
	Unit Sub Total	**M**		**2**	**2,020.00**	**$34.51**	**$69,710.00**
	Item Code 150667 Total No. of Proj.			**8**		**Total Amount**	**$271,208.00**
150668	REMOVE FLARED END SECTION	EA	1	2	40.00	$396.25	$15,850.00
		EA	2	5	18.00	$445.83	$8,025.00
		EA	3	4	45.00	$151.56	$6,820.00
		EA	4	6	31.00	$167.10	$5,180.00
		EA	6	1	62.00	$200.00	$12,400.00
		EA	7	1	1.00	$350.00	$350.00
		EA	8	1	3.00	$125.00	$375.00
		EA	10	2	19.00	$426.84	$8,110.00
		EA	12	2	6.00	$750.00	$4,500.00
	Unit Sub Total	**EA**		**24**	**225.00**	**$273.82**	**$61,610.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150668 Total No. of Proj.			**24**		**Total Amount**	**$61,610.00**
150676	REMOVE CABLE RAILING	LF	2	1	170.00	$50.00	$8,500.00
	Unit Sub Total	**LF**		**1**	**170.00**	**$50.00**	**$8,500.00**
	Item Code 150676 Total No. of Proj.			**1**		**Total Amount**	**$8,500.00**
150685	REMOVE IRRIGATION FACILITY	LS	8	1	1.00	$3,600.00	$3,600.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$3,600.00**	**$3,600.00**
	Item Code 150685 Total No. of Proj.			**1**		**Total Amount**	**$3,600.00**
150701	REMOVE YELLOW PAINTED TRAFFIC STRIPE	LF	4	1	90.00	$24.00	$2,160.00
		LF	7	1	470.00	$1.50	$705.00
		LF	11	1	860.00	$1.45	$1,247.00
	Unit Sub Total	**LF**		**3**	**1,420.00**	**$2.90**	**$4,112.00**
	Item Code 150701 Total No. of Proj.			**3**		**Total Amount**	**$4,112.00**
150704	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	LF	3	1	240.00	$8.00	$1,920.00
		LF	4	1	2,700.00	$1.00	$2,700.00
		LF	12	1	540.00	$6.60	$3,564.00
	Unit Sub Total	**LF**		**3**	**3,480.00**	**$2.35**	**$8,184.00**
150704	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	M	7	1	1,160.00	$3.20	$3,712.00
		M	10	1	2,150.00	$2.00	$4,300.00
	Unit Sub Total	**M**		**2**	**3,310.00**	**$2.42**	**$8,012.00**
	Item Code 150704 Total No. of Proj.			**5**		**Total Amount**	**$16,196.00**
150705	REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING	SQFT	2	1	1,100.00	$5.00	$5,500.00
	Unit Sub Total	**SQFT**		**1**	**1,100.00**	**$5.00**	**$5,500.00**
	Item Code 150705 Total No. of Proj.			**1**		**Total Amount**	**$5,500.00**
150710	REMOVE TRAFFIC STRIPE	LF	1	1	3,430.00	$1.00	$3,430.00
		LF	2	5	674,510.00	$0.48	$322,426.10
		LF	3	8	902,240.00	$0.34	$309,188.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150710	REMOVE TRAFFIC STRIPE	LF	7	3	67,970.00	$0.67	$45,710.00
	Unit Sub Total	**LF**		**17**	**1,648,150.00**	**$0.41**	**$680,754.60**
150710	REMOVE TRAFFIC STRIPE	M	8	1	18,500.00	$1.50	$27,750.00
		M	11	1	34,100.00	$1.00	$34,100.00
	Unit Sub Total	**M**		**2**	**52,600.00**	**$1.18**	**$61,850.00**
	Item Code 150710 Total No. of Proj.			**19**		**Total Amount**	**$742,604.60**
150711	REMOVE PAINTED TRAFFIC STRIPE	LF	1	1	2,970.00	$0.65	$1,930.50
		LF	2	3	5,930.00	$1.16	$6,905.00
		LF	4	4	76,110.00	$0.69	$52,172.40
		LF	5	7	161,720.00	$0.41	$66,623.40
		LF	6	2	619,000.00	$0.18	$110,030.00
		LF	7	8	196,150.00	$0.42	$82,767.30
		LF	8	1	97,100.00	$0.30	$29,130.00
		LF	9	1	5,200.00	$1.20	$6,240.00
		LF	10	2	551,130.00	$0.35	$194,547.50
		LF	11	18	829,160.00	$0.24	$202,923.30
		LF	12	8	641,900.00	$0.38	$242,696.00
	Unit Sub Total	**LF**		**55**	**3,186,370.00**	**$0.31**	**$995,965.40**
150711	REMOVE PAINTED TRAFFIC STRIPE	M	4	1	3,420.00	$1.50	$5,130.00
		M	5	1	32,000.00	$1.20	$38,400.00
		M	7	4	29,510.00	$1.46	$43,005.20
		M	11	1	29,600.00	$1.20	$35,520.00
	Unit Sub Total	**M**		**7**	**94,530.00**	**$1.29**	**$122,055.20**
	Item Code 150711 Total No. of Proj.			**62**		**Total Amount**	**$1,118,020.60**
150712	REMOVE PAINTED PAVEMENT MARKING	M2	4	1	30.00	$35.00	$1,050.00
		M2	5	1	75.00	$36.00	$2,700.00
		M2	7	2	330.00	$27.82	$9,180.00
		M2	11	1	59.00	$25.00	$1,475.00
	Unit Sub Total	**M2**		**5**	**494.00**	**$29.16**	**$14,405.00**
150712	REMOVE PAINTED PAVEMENT MARKING	SQFT	1	1	84.00	$3.00	$252.00
		SQFT	2	3	700.00	$4.59	$3,210.00
		SQFT	3	2	440.00	$5.45	$2,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150712	REMOVE PAINTED PAVEMENT MARKING	SQFT	6	2	1,070.00	$1.25	$1,339.00
		SQFT	7	2	410.00	$3.46	$1,418.00
		SQFT	9	1	3,230.00	$2.16	$6,976.80
		SQFT	10	1	27.00	$25.00	$675.00
		SQFT	11	4	1,180.00	$1.94	$2,283.50
		SQFT	12	4	3,380.00	$1.33	$4,502.00
	Unit Sub Total	**SQFT**		**20**	**10,521.00**	**$2.19**	**$23,056.30**
	Item Code 150712 Total No. of Proj.			**25**		**Total Amount**	**$37,461.30**
150713	REMOVE PAVEMENT MARKING	LF	7	1	750.00	$2.94	$2,205.00
	Unit Sub Total	**LF**		**1**	**750.00**	**$2.94**	**$2,205.00**
150713	REMOVE PAVEMENT MARKING	M2	7	1	13.00	$15.00	$195.00
		M2	8	1	33.00	$30.00	$990.00
		M2	11	1	150.00	$14.00	$2,100.00
	Unit Sub Total	**M2**		**3**	**196.00**	**$16.76**	**$3,285.00**
150713	REMOVE PAVEMENT MARKING	SQFT	1	1	53.00	$10.00	$530.00
		SQFT	2	2	590.00	$8.94	$5,273.62
		SQFT	3	4	190.00	$6.57	$1,248.25
		SQFT	4	3	3,640.00	$3.03	$11,023.00
		SQFT	6	2	2,100.00	$2.90	$6,093.00
		SQFT	7	1	470.00	$2.20	$1,034.00
		SQFT	10	1	3,280.00	$3.00	$9,840.00
		SQFT	12	1	48.00	$5.00	$240.00
	Unit Sub Total	**SQFT**		**15**	**10,371.00**	**$3.40**	**$35,281.87**
	Item Code 150713 Total No. of Proj.			**19**		**Total Amount**	**$40,771.87**
150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	LF	1	12	248,128.00	$0.44	$110,063.90
		LF	2	9	205,370.00	$0.51	$104,524.00
		LF	3	12	62,410.00	$0.75	$46,778.00
		LF	4	35	1,612,870.00	$0.41	$653,989.50
		LF	5	19	721,240.00	$0.33	$235,107.00
		LF	6	20	1,042,452.00	$0.23	$239,557.10
		LF	7	40	894,600.00	$0.41	$364,564.00
		LF	8	17	178,850.00	$0.57	$102,616.50
		LF	10	21	244,835.00	$0.42	$101,689.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	LF	11	8	17,720.00	$0.95	$16,894.70
		LF	12	21	1,511,240.00	$0.33	$491,310.60
	Unit Sub Total	**LF**		**214**	**6,739,715.00**	**$0.37**	**$2,467,094.30**
150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	M	4	1	2,430.00	$1.80	$4,374.00
		M	5	1	17,900.00	$1.20	$21,480.00
		M	7	5	31,450.00	$1.47	$46,196.20
		M	10	1	480.00	$2.00	$960.00
		M	11	1	1,230.00	$1.20	$1,476.00
	Unit Sub Total	**M**		**9**	**53,490.00**	**$1.39**	**$74,486.20**
	Item Code 150714 Total No. of Proj.			**223**		**Total Amount**	**$2,541,580.50**
150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	M2	4	1	34.00	$45.00	$1,530.00
		M2	5	1	270.00	$36.00	$9,720.00
		M2	7	2	47.00	$43.40	$2,040.00
		M2	10	2	60.00	$20.83	$1,250.00
		M2	11	1	24.00	$25.00	$600.00
	Unit Sub Total	**M2**		**7**	**435.00**	**$34.80**	**$15,140.00**
150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	SQFT	1	13	14,124.00	$4.86	$68,625.50
		SQFT	2	13	16,668.00	$4.46	$74,279.00
		SQFT	3	11	11,675.00	$2.65	$30,967.00
		SQFT	4	22	18,000.00	$2.69	$48,433.80
		SQFT	5	18	40,011.00	$1.57	$62,952.12
		SQFT	6	23	33,600.00	$1.97	$66,306.50
		SQFT	7	28	25,100.00	$2.57	$64,430.00
		SQFT	8	10	5,197.00	$2.83	$14,724.80
		SQFT	9	3	1,120.00	$4.25	$4,759.00
		SQFT	10	20	25,670.00	$2.64	$67,814.60
		SQFT	11	12	13,635.00	$5.18	$70,648.25
		SQFT	12	17	46,633.00	$1.75	$81,425.50
	Unit Sub Total	**SQFT**		**190**	**251,433.00**	**$2.61**	**$655,366.07**
	Item Code 150715 Total No. of Proj.			**197**		**Total Amount**	**$670,506.07**
150717	REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING	M2	11	1	260.00	$25.00	$6,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M2**		**1**	**260.00**	**$25.00**	**$6,500.00**
	Item Code 150717 Total No. of Proj.			**1**		**Total Amount**	**$6,500.00**
150718	REMOVE THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING	SQFT	3	1	2,310.00	$2.60	$6,006.00
	Unit Sub Total	**SQFT**		**1**	**2,310.00**	**$2.60**	**$6,006.00**
	Item Code 150718 Total No. of Proj.			**1**		**Total Amount**	**$6,006.00**
150720	REMOVE CONTRAST TREATMENT	SQFT	2	1	402.00	$4.00	$1,608.00
		SQFT	3	1	3,696.00	$2.00	$7,392.00
		SQFT	5	2	8,845.00	$0.55	$4,876.25
		SQFT	6	1	15,033.00	$0.92	$13,830.36
		SQFT	7	3	29,992.00	$0.77	$23,184.00
	Unit Sub Total	**SQFT**		**8**	**57,968.00**	**$0.88**	**$50,890.61**
	Item Code 150720 Total No. of Proj.			**8**		**Total Amount**	**$50,890.61**
150722	REMOVE PAVEMENT MARKER	EA	1	1	8,500.00	$1.00	$8,500.00
		EA	2	2	460.00	$3.09	$1,420.00
		EA	3	1	130.00	$10.00	$1,300.00
		EA	4	50	154,561.00	$1.13	$174,014.00
		EA	5	5	13,096.00	$1.04	$13,562.00
		EA	6	9	15,280.00	$0.90	$13,733.00
		EA	7	56	556,694.00	$0.81	$450,581.30
		EA	8	27	120,732.00	$0.89	$107,095.90
		EA	10	11	13,983.00	$1.01	$14,112.00
		EA	12	19	302,169.00	$0.54	$163,047.00
	Unit Sub Total	**EA**		**181**	**1,185,605.00**	**$0.80**	**$947,365.20**
150722	REMOVE PAVEMENT MARKER	LF	7	1	780.00	$1.00	$780.00
		LF	12	2	15,070.00	$0.55	$8,228.90
	Unit Sub Total	**LF**		**3**	**15,850.00**	**$0.57**	**$9,008.90**
	Item Code 150722 Total No. of Proj.			**184**		**Total Amount**	**$956,374.10**
150730	REMOVE CHANNELIZERS	EA	4	1	25.00	$10.00	$250.00
		EA	5	2	26.00	$1.69	$44.00
		EA	7	1	10.00	$10.00	$100.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150730	REMOVE CHANNELIZERS	EA	11	1	62.00	$5.00	$310.00
		EA	12	3	1,738.00	$10.68	$18,558.00
	Unit Sub Total	**EA**		**8**	**1,861.00**	**$10.35**	**$19,262.00**
	Item Code 150730 Total No. of Proj.			**8**		**Total Amount**	**$19,262.00**
150740	REMOVE SIGN	LS	11	1	1.00	$50.00	$50.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$50.00**	**$50.00**
	Item Code 150740 Total No. of Proj.			**1**		**Total Amount**	**$50.00**
150742	REMOVE ROADSIDE SIGN	EA	1	7	59.00	$163.56	$9,650.00
		EA	2	6	291.00	$89.78	$26,126.00
		EA	3	14	337.00	$99.88	$33,660.00
		EA	4	12	300.00	$91.75	$27,526.00
		EA	5	5	226.00	$106.31	$24,025.00
		EA	6	11	95.00	$107.55	$10,217.00
		EA	7	8	147.00	$111.84	$16,440.50
		EA	8	3	16.00	$123.13	$1,970.00
		EA	9	3	94.00	$134.37	$12,631.00
		EA	10	8	100.00	$86.79	$8,679.00
		EA	11	9	187.00	$106.89	$19,989.00
		EA	12	11	290.00	$143.76	$41,691.00
	Unit Sub Total	**EA**		**97**	**2,142.00**	**$108.59**	**$232,604.50**
	Item Code 150742 Total No. of Proj.			**97**		**Total Amount**	**$232,604.50**
150744	REMOVE ROADSIDE SIGN (WOOD POST)	EA	4	3	91.00	$116.42	$10,594.00
		EA	7	3	80.00	$126.13	$10,090.16
		EA	8	2	53.00	$32.60	$1,728.00
		EA	12	1	3.00	$95.00	$285.00
	Unit Sub Total	**EA**		**9**	**227.00**	**$99.99**	**$22,697.16**
	Item Code 150744 Total No. of Proj.			**9**		**Total Amount**	**$22,697.16**
150745	REMOVE ROADSIDE SIGN (METAL POST)	EA	4	1	1.00	$204.00	$204.00
		EA	7	4	190.00	$119.08	$22,625.00
	Unit Sub Total	**EA**		**5**	**191.00**	**$119.52**	**$22,829.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150745 Total No. of Proj.			**5**		**Total Amount**	**$22,829.00**
150747	REMOVE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	3	3	31.00	$69.68	$2,160.00
		EA	4	3	28.00	$97.03	$2,716.90
		EA	7	3	51.00	$94.82	$4,835.86
		EA	11	1	2.00	$100.00	$200.00
		EA	12	6	73.00	$78.44	$5,726.00
	Unit Sub Total	**EA**		**16**	**185.00**	**$84.53**	**$15,638.76**
	Item Code 150747 Total No. of Proj.			**16**		**Total Amount**	**$15,638.76**
150748	REMOVE ROADSIDE SIGN PANEL	EA	1	1	12.00	$50.00	$600.00
		EA	3	1	33.00	$150.00	$4,950.00
		EA	4	1	2.00	$50.00	$100.00
		EA	6	1	2.00	$30.00	$60.00
		EA	8	1	3.00	$50.00	$150.00
		EA	11	1	1.00	$36.00	$36.00
		EA	12	1	19.00	$20.00	$380.00
	Unit Sub Total	**EA**		**7**	**72.00**	**$87.17**	**$6,276.00**
	Item Code 150748 Total No. of Proj.			**7**		**Total Amount**	**$6,276.00**
150749	REMOVE METAL POST	EA	3	1	3.00	$350.00	$1,050.00
		EA	6	1	3.00	$450.00	$1,350.00
	Unit Sub Total	**EA**		**2**	**6.00**	**$400.00**	**$2,400.00**
	Item Code 150749 Total No. of Proj.			**2**		**Total Amount**	**$2,400.00**
150759	REMOVE SIGN STRUCTURE WALKWAY	KG	8	1	3,070.00	$0.60	$1,842.00
	Unit Sub Total	**KG**		**1**	**3,070.00**	**$0.60**	**$1,842.00**
	Item Code 150759 Total No. of Proj.			**1**		**Total Amount**	**$1,842.00**
150760	REMOVE SIGN STRUCTURE	EA	1	1	1.00	$3,500.00	$3,500.00
		EA	3	6	22.00	$4,609.09	$101,400.00
		EA	4	8	40.00	$4,198.50	$167,940.00
		EA	6	1	1.00	$1,250.00	$1,250.00
		EA	7	8	21.00	$4,266.67	$89,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150760	REMOVE SIGN STRUCTURE	EA	8	1	1.00	$1,800.00	$1,800.00
		EA	10	3	11.00	$3,818.18	$42,000.00
		EA	11	4	14.00	$2,071.43	$29,000.00
		EA	12	4	36.00	$3,472.22	$125,000.00
	Unit Sub Total	**EA**		**36**	**147.00**	**$3,819.66**	**$561,490.00**
	Item Code 150760 Total No. of Proj.			**36**		**Total Amount**	**$561,490.00**
150763	REMOVE SIGN PANEL	EA	4	2	13.00	$368.54	$4,791.00
		EA	7	1	6.00	$2,200.00	$13,200.00
		EA	12	1	12.00	$150.00	$1,800.00
	Unit Sub Total	**EA**		**4**	**31.00**	**$638.42**	**$19,791.00**
	Item Code 150763 Total No. of Proj.			**4**		**Total Amount**	**$19,791.00**
150764	REMOVE SIGN OVERLAY	EA	8	1	5.00	$225.00	$1,125.00
	Unit Sub Total	**EA**		**1**	**5.00**	**$225.00**	**$1,125.00**
	Item Code 150764 Total No. of Proj.			**1**		**Total Amount**	**$1,125.00**
150765	REMOVE SIGN POST	EA	1	1	6.00	$90.00	$540.00
	Unit Sub Total	**EA**		**1**	**6.00**	**$90.00**	**$540.00**
	Item Code 150765 Total No. of Proj.			**1**		**Total Amount**	**$540.00**
150767	REMOVE BRIDGE MOUNTED SIGN	EA	3	3	23.00	$3,578.26	$82,300.00
		EA	7	1	2.00	$3,500.00	$7,000.00
		EA	12	2	5.00	$1,600.00	$8,000.00
	Unit Sub Total	**EA**		**6**	**30.00**	**$3,243.33**	**$97,300.00**
	Item Code 150767 Total No. of Proj.			**6**		**Total Amount**	**$97,300.00**
150769	REMOVE ASPHALT CONCRETE	CY	2	1	1,830.00	$50.00	$91,500.00
		CY	7	1	26,000.00	$14.85	$386,100.00
		CY	9	1	70.00	$100.00	$7,000.00
	Unit Sub Total	**CY**		**3**	**27,900.00**	**$17.37**	**$484,600.00**
150769	REMOVE ASPHALT CONCRETE	SQFT	5	1	2,510.00	$1.60	$4,016.00
		SQFT	7	1	300.00	$8.00	$2,400.00
		SQFT	12	1	780.00	$1.32	$1,029.60

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**SQFT**		**3**	**3,590.00**	**$2.07**	**$7,445.60**
150769	REMOVE ASPHALT CONCRETE		SQYD	1	1	2.70	$125.00	$337.50
			SQYD	2	2	2,294.00	$16.33	$37,460.00
			SQYD	3	1	30.00	$65.00	$1,950.00
			SQYD	12	2	551.00	$21.23	$11,695.00
		Unit Sub Total	**SQYD**		**6**	**2,877.70**	**$17.88**	**$51,442.50**
	Item Code 150769	**Total No. of Proj.**			**12**		**Total Amount**	**$543,488.10**
150771	REMOVE ASPHALT CONCRETE DIKE		LF	1	8	89,447.00	$2.15	$192,746.00
			LF	2	11	70,613.00	$2.25	$159,145.00
			LF	3	23	153,862.00	$1.37	$210,590.50
			LF	4	20	145,449.00	$0.99	$143,770.50
			LF	5	7	26,300.00	$1.87	$49,246.40
			LF	6	11	111,418.00	$0.55	$61,264.00
			LF	7	10	144,010.00	$1.45	$208,698.80
			LF	8	10	64,389.00	$3.79	$243,782.50
			LF	9	2	17,030.00	$1.02	$17,345.00
			LF	10	7	32,770.00	$1.38	$45,188.50
			LF	11	9	454,350.00	$0.29	$131,645.00
			LF	12	9	88,830.00	$2.96	$262,653.00
		Unit Sub Total	**LF**		**127**	**1,398,468.00**	**$1.23**	**$1,726,075.20**
150771	REMOVE ASPHALT CONCRETE DIKE		M	7	2	314.00	$14.99	$4,708.00
			M	8	1	420.00	$3.00	$1,260.00
		Unit Sub Total	**M**		**3**	**734.00**	**$8.13**	**$5,968.00**
	Item Code 150771	**Total No. of Proj.**			**130**		**Total Amount**	**$1,732,043.20**
150772	REMOVE CURB		LF	7	2	13,958.00	$3.00	$41,874.00
		Unit Sub Total	**LF**		**2**	**13,958.00**	**$3.00**	**$41,874.00**
150772	REMOVE CURB		M	4	1	97.00	$15.00	$1,455.00
		Unit Sub Total	**M**		**1**	**97.00**	**$15.00**	**$1,455.00**
	Item Code 150772	**Total No. of Proj.**			**3**		**Total Amount**	**$43,329.00**
150801	REMOVE OVERSIDE DRAIN		EA	3	1	48.00	$250.00	$12,000.00
			EA	5	1	3.00	$600.00	$1,800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150801	REMOVE OVERSIDE DRAIN		EA	8	1	2.00	$300.00	$600.00
		Unit Sub Total	**EA**		**3**	**53.00**	**$271.70**	**$14,400.00**
	Item Code 150801	**Total No. of Proj.**			**3**		**Total Amount**	**$14,400.00**
150804	REMOVE DRAINAGE FACILITY		CY	8	1	8.00	$220.00	$1,760.00
		Unit Sub Total	**CY**		**1**	**8.00**	**$220.00**	**$1,760.00**
150804	REMOVE DRAINAGE FACILITY		EA	3	1	1.00	$2,000.00	$2,000.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$2,000.00**	**$2,000.00**
150804	REMOVE DRAINAGE FACILITY		LF	3	1	25.00	$10.00	$250.00
		Unit Sub Total	**LF**		**1**	**25.00**	**$10.00**	**$250.00**
	Item Code 150804	**Total No. of Proj.**			**3**		**Total Amount**	**$4,010.00**
150805	REMOVE CULVERT		EA	1	7	81.00	$532.80	$43,157.00
			EA	2	4	23.00	$820.43	$18,870.00
			EA	3	1	2.00	$1,800.00	$3,600.00
			EA	4	1	23.00	$500.00	$11,500.00
			EA	6	1	10.00	$700.00	$7,000.00
			EA	10	2	14.00	$803.57	$11,250.00
		Unit Sub Total	**EA**		**16**	**153.00**	**$623.38**	**$95,377.00**
150805	REMOVE CULVERT		LF	1	3	1,290.00	$26.26	$33,870.00
			LF	2	4	3,241.00	$12.46	$40,370.00
			LF	3	7	9,848.60	$10.21	$100,543.50
			LF	4	12	13,822.00	$16.75	$231,491.40
			LF	5	2	60.00	$142.40	$8,544.00
			LF	6	1	1,430.00	$14.00	$20,020.00
			LF	8	1	140.00	$20.00	$2,800.00
			LF	9	2	1,350.00	$2.68	$3,620.00
			LF	10	4	6,280.00	$18.20	$114,315.00
			LF	11	1	4.00	$60.00	$240.00
		Unit Sub Total	**LF**		**37**	**37,465.60**	**$14.84**	**$555,813.90**
150805	REMOVE CULVERT		M	5	1	1,790.00	$45.00	$80,550.00
			M	11	2	448.00	$51.21	$22,940.00
		Unit Sub Total	**M**		**3**	**2,238.00**	**$46.24**	**$103,490.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150805	**Total No. of Proj.**			**56**		**Total Amount**	**$754,680.90**
150806	REMOVE PIPE		EA	1	2	3.00	$835.00	$2,505.00
		Unit Sub Total	**EA**		**2**	**3.00**	**$835.00**	**$2,505.00**
150806	REMOVE PIPE		LF	1	1	670.00	$2.80	$1,876.00
			LF	3	2	590.00	$9.45	$5,575.00
			LF	4	5	4,678.00	$5.79	$27,090.00
			LF	5	2	340.00	$23.47	$7,980.00
			LF	6	1	7.00	$38.00	$266.00
			LF	7	8	7,589.00	$32.95	$250,037.10
			LF	8	2	600.00	$20.35	$12,210.00
			LF	10	1	4.00	$500.00	$2,000.00
			LF	12	4	4,610.00	$23.43	$107,990.00
		Unit Sub Total	**LF**		**26**	**19,088.00**	**$21.74**	**$415,024.10**
150806	REMOVE PIPE		M	4	1	68.00	$55.00	$3,740.00
			M	7	6	2,269.00	$54.89	$124,553.00
			M	8	1	330.00	$70.00	$23,100.00
		Unit Sub Total	**M**		**8**	**2,667.00**	**$56.77**	**$151,393.00**
	Item Code 150806	**Total No. of Proj.**			**36**		**Total Amount**	**$568,922.10**
150820	REMOVE INLET		EA	1	11	49.00	$821.43	$40,250.00
			EA	2	7	62.00	$687.10	$42,600.00
			EA	3	9	134.00	$526.13	$70,502.00
			EA	4	14	294.00	$689.45	$202,698.51
			EA	5	6	58.00	$620.69	$36,000.00
			EA	6	7	28.00	$942.68	$26,395.00
			EA	7	11	129.00	$931.90	$120,215.00
			EA	8	2	12.00	$462.50	$5,550.00
			EA	10	5	95.00	$461.84	$43,875.00
			EA	11	3	23.00	$560.87	$12,900.00
			EA	12	4	68.00	$769.26	$52,310.00
		Unit Sub Total	**EA**		**79**	**952.00**	**$686.23**	**$653,295.51**
	Item Code 150820	**Total No. of Proj.**			**79**		**Total Amount**	**$653,295.51**
150821	REMOVE HEADWALL		CF	9	1	25.00	$10.00	$250.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**CF**		**1**	**25.00**	**$10.00**	**$250.00**
150821	REMOVE HEADWALL		EA	1	5	19.00	$997.89	$18,960.00
			EA	2	3	63.00	$254.76	$16,050.00
			EA	3	5	12.00	$1,005.00	$12,060.00
			EA	4	11	44.00	$1,220.51	$53,702.50
			EA	5	2	14.00	$571.43	$8,000.00
			EA	6	6	72.00	$560.83	$40,380.00
			EA	7	2	31.00	$887.10	$27,500.00
			EA	8	2	4.00	$755.00	$3,020.00
			EA	10	5	19.00	$843.68	$16,030.00
			EA	11	3	5.00	$980.00	$4,900.00
			EA	12	1	1.00	$1,000.00	$1,000.00
		Unit Sub Total	**EA**		**45**	**284.00**	**$709.87**	**$201,602.50**
	Item Code 150821	**Total No. of Proj.**			**46**		**Total Amount**	**$201,852.50**
150823	REMOVE DOWNDRAIN		EA	1	6	12.00	$1,491.67	$17,900.00
			EA	2	1	2.00	$150.00	$300.00
			EA	3	2	11.00	$527.27	$5,800.00
			EA	4	1	3.00	$600.00	$1,800.00
			EA	6	1	13.00	$100.00	$1,300.00
			EA	8	1	1.00	$200.00	$200.00
			EA	12	1	1.00	$400.00	$400.00
		Unit Sub Total	**EA**		**13**	**43.00**	**$644.19**	**$27,700.00**
150823	REMOVE DOWNDRAIN		LF	2	2	650.00	$13.38	$8,700.00
			LF	3	3	968.00	$24.52	$23,740.00
			LF	4	1	2,030.00	$24.00	$48,720.00
			LF	6	3	970.00	$7.34	$7,124.00
			LF	8	1	830.00	$16.00	$13,280.00
			LF	10	1	140.00	$20.00	$2,800.00
		Unit Sub Total	**LF**		**11**	**5,588.00**	**$18.68**	**$104,364.00**
	Item Code 150823	**Total No. of Proj.**			**24**		**Total Amount**	**$132,064.00**
150824	REMOVE SEWER MANHOLE		EA	4	2	9.00	$838.89	$7,550.00
			EA	7	1	1.00	$3,000.00	$3,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**3**	**10.00**	**$1,055.00**	**$10,550.00**
	Item Code 150824 Total No. of Proj.			**3**		**Total Amount**	**$10,550.00**
150825	REMOVE REINFORCED CONCRETE BOX CULVERT	CY	7	1	220.00	$153.00	$33,660.00
	Unit Sub Total	**CY**		**1**	**220.00**	**$153.00**	**$33,660.00**
150825	REMOVE REINFORCED CONCRETE BOX CULVERT	EA	10	1	1.00	$8,500.00	$8,500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$8,500.00**	**$8,500.00**
	Item Code 150825 Total No. of Proj.			**2**		**Total Amount**	**$42,160.00**
150826	REMOVE MANHOLE	EA	3	1	1.00	$1,500.00	$1,500.00
		EA	4	3	7.00	$1,814.29	$12,700.00
		EA	5	1	9.00	$500.00	$4,500.00
		EA	7	2	12.00	$1,266.67	$15,200.00
		EA	8	1	1.00	$1,160.00	$1,160.00
	Unit Sub Total	**EA**		**8**	**30.00**	**$1,168.67**	**$35,060.00**
	Item Code 150826 Total No. of Proj.			**8**		**Total Amount**	**$35,060.00**
150828	REMOVE JUNCTION BOX	EA	3	1	1.00	$2,500.00	$2,500.00
		EA	6	1	1.00	$500.00	$500.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$1,500.00**	**$3,000.00**
	Item Code 150828 Total No. of Proj.			**2**		**Total Amount**	**$3,000.00**
150829	REMOVE RETAINING WALL	LF	4	2	69.00	$190.00	$13,110.00
		LF	7	2	1,504.00	$22.05	$33,168.80
	Unit Sub Total	**LF**		**4**	**1,573.00**	**$29.42**	**$46,278.80**
150829	REMOVE RETAINING WALL	M	4	1	61.00	$150.00	$9,150.00
		M	7	1	110.00	$105.00	$11,550.00
	Unit Sub Total	**M**		**2**	**171.00**	**$121.05**	**$20,700.00**
150829	REMOVE RETAINING WALL	SQFT	7	1	5,250.00	$12.00	$63,000.00
	Unit Sub Total	**SQFT**		**1**	**5,250.00**	**$12.00**	**$63,000.00**
	Item Code 150829 Total No. of Proj.			**7**		**Total Amount**	**$129,978.80**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150830	REMOVE RETAINING WALL (PORTION)	LF	4	1	1,360.00	$19.25	$26,180.00
	Unit Sub Total	**LF**		**1**	**1,360.00**	**$19.25**	**$26,180.00**
150830	REMOVE RETAINING WALL (PORTION)	LS	11	1	1.00	$6,530.00	$6,530.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$6,530.00**	**$6,530.00**
150830	REMOVE RETAINING WALL (PORTION)	SQFT	2	1	300.00	$150.00	$45,000.00
	Unit Sub Total	**SQFT**		**1**	**300.00**	**$150.00**	**$45,000.00**
	Item Code 150830 Total No. of Proj.			**3**		**Total Amount**	**$77,710.00**
150841	REMOVE SEWER PIPE	LF	4	1	1,190.00	$25.00	$29,750.00
	Unit Sub Total	**LF**		**1**	**1,190.00**	**$25.00**	**$29,750.00**
150841	REMOVE SEWER PIPE	M	4	1	360.00	$60.00	$21,600.00
		M	7	1	130.00	$60.00	$7,800.00
	Unit Sub Total	**M**		**2**	**490.00**	**$60.00**	**$29,400.00**
	Item Code 150841 Total No. of Proj.			**3**		**Total Amount**	**$59,150.00**
150844	REMOVE SLOPE PAVING	CY	2	1	45.00	$125.00	$5,625.00
	Unit Sub Total	**CY**		**1**	**45.00**	**$125.00**	**$5,625.00**
150844	REMOVE SLOPE PAVING	LS	11	1	1.00	$12,000.00	$12,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$12,000.00**	**$12,000.00**
150844	REMOVE SLOPE PAVING	M2	8	1	309.00	$30.00	$9,270.00
	Unit Sub Total	**M2**		**1**	**309.00**	**$30.00**	**$9,270.00**
	Item Code 150844 Total No. of Proj.			**3**		**Total Amount**	**$26,895.00**
150846	REMOVE CONCRETE PAVEMENT	CY	3	1	28,100.00	$40.00	$1,124,000.00
		CY	6	2	16,440.00	$35.52	$583,900.00
		CY	7	1	24.00	$361.63	$8,679.12
	Unit Sub Total	**CY**		**4**	**44,564.00**	**$38.52**	**$1,716,579.12**
150846	REMOVE CONCRETE PAVEMENT	M2	7	2	22,140.00	$2.49	$55,200.00
		M2	10	1	120.00	$33.00	$3,960.00
		M2	11	1	8,010.00	$20.00	$160,200.00
	Unit Sub Total	**M2**		**4**	**30,270.00**	**$7.25**	**$219,360.00**
150846	REMOVE CONCRETE PAVEMENT	SQFT	7	1	261,000.00	$0.35	$91,350.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**SQFT**		**1**	**261,000.00**	**$0.35**	**$91,350.00**
150846	REMOVE CONCRETE PAVEMENT	SQYD	2	1	840.00	$71.00	$59,640.00
		SQYD	7	4	305,977.00	$14.82	$4,534,510.00
		SQYD	10	1	150,000.00	$1.50	$225,000.00
		SQYD	12	1	1,010.00	$9.50	$9,595.00
	Unit Sub Total	**SQYD**		**7**	**457,827.00**	**$10.55**	**$4,828,745.00**
	Item Code 150846 Total No. of Proj.			**16**		**Total Amount**	**$6,856,034.12**
150847	REMOVE CONCRETE PAVEMENT AND BASE	CY	3	1	87,200.00	$13.85	$1,207,720.00
		CY	11	1	9,380.00	$22.00	$206,360.00
	Unit Sub Total	**CY**		**2**	**96,580.00**	**$14.64**	**$1,414,080.00**
	Item Code 150847 Total No. of Proj.			**2**		**Total Amount**	**$1,414,080.00**
150855	REMOVE PAVEMENT	CY	3	1	120.00	$28.15	$3,378.00
	Unit Sub Total	**CY**		**1**	**120.00**	**$28.15**	**$3,378.00**
	Item Code 150855 Total No. of Proj.			**1**		**Total Amount**	**$3,378.00**
150857	REMOVE ASPHALT CONCRETE SURFACING	CY	3	1	24.00	$45.00	$1,080.00
	Unit Sub Total	**CY**		**1**	**24.00**	**$45.00**	**$1,080.00**
150857	REMOVE ASPHALT CONCRETE SURFACING	M2	7	1	7,820.00	$9.00	$70,380.00
		M2	10	1	270.00	$14.00	$3,780.00
		M2	11	1	435.00	$20.00	$8,700.00
	Unit Sub Total	**M2**		**3**	**8,525.00**	**$9.72**	**$82,860.00**
150857	REMOVE ASPHALT CONCRETE SURFACING	SQFT	1	1	25,650.00	$1.50	$38,475.00
		SQFT	2	8	167,907.00	$2.20	$369,078.05
		SQFT	3	12	320,381.00	$0.96	$307,546.28
		SQFT	4	5	103,322.00	$0.72	$74,462.80
		SQFT	6	4	21,414.00	$1.01	$21,654.96
		SQFT	7	2	46,479.00	$0.24	$10,923.90
		SQFT	8	4	77,090.00	$1.02	$78,598.06
		SQFT	10	2	5,328.00	$2.91	$15,498.00
	Unit Sub Total	**SQFT**		**38**	**767,571.00**	**$1.19**	**$916,237.05**
150857	REMOVE ASPHALT CONCRETE SURFACING	SQYD	6	1	5,820.00	$3.00	$17,460.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150857	REMOVE ASPHALT CONCRETE SURFACING	SQYD	7	1	29,600.00	$1.40	$41,440.00
	Unit Sub Total	**SQYD**		**2**	**35,420.00**	**$1.66**	**$58,900.00**
	Item Code 150857 Total No. of Proj.			**44**		**Total Amount**	**$1,059,077.05**
150859	REMOVE ASPHALT CONCRETE OVERSIDE DRAIN	EA	3	3	65.00	$271.38	$17,640.00
		EA	4	2	37.00	$697.30	$25,800.00
		EA	5	1	1.00	$2,000.00	$2,000.00
		EA	6	1	2.00	$50.00	$100.00
	Unit Sub Total	**EA**		**7**	**105.00**	**$433.71**	**$45,540.00**
	Item Code 150859 Total No. of Proj.			**7**		**Total Amount**	**$45,540.00**
150860	REMOVE BASE AND SURFACING	CY	1	2	6,980.00	$16.40	$114,460.00
		CY	3	1	1,450.00	$20.00	$29,000.00
		CY	4	6	7,209.00	$16.47	$118,702.00
		CY	7	1	5,100.00	$5.00	$25,500.00
		CY	8	1	10.00	$200.00	$2,000.00
		CY	10	1	560.00	$12.00	$6,720.00
		CY	11	1	150.00	$80.00	$12,000.00
	Unit Sub Total	**CY**		**13**	**21,459.00**	**$14.37**	**$308,382.00**
150860	REMOVE BASE AND SURFACING	M3	8	1	460.00	$15.00	$6,900.00
	Unit Sub Total	**M3**		**1**	**460.00**	**$15.00**	**$6,900.00**
150860	REMOVE BASE AND SURFACING	SQYD	3	1	500.00	$15.00	$7,500.00
	Unit Sub Total	**SQYD**		**1**	**500.00**	**$15.00**	**$7,500.00**
	Item Code 150860 Total No. of Proj.			**15**		**Total Amount**	**$322,782.00**
150870	REMOVE CONCRETE DECK SURFACE	SQFT	1	1	1,600.00	$7.50	$12,000.00
		SQFT	2	4	33,205.00	$2.90	$96,145.00
		SQFT	3	4	384,301.00	$0.52	$199,380.82
		SQFT	4	3	84,071.00	$1.10	$92,862.00
		SQFT	5	1	6,420.00	$1.90	$12,198.00
		SQFT	6	1	21,140.00	$0.75	$15,855.00
		SQFT	7	4	51,265.00	$1.67	$85,636.00
		SQFT	8	3	220,508.00	$1.03	$227,344.64
		SQFT	10	1	24,615.00	$3.00	$73,845.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150870	REMOVE CONCRETE DECK SURFACE	SQFT	11	1	16,481.00	$16.00	$263,696.00
		SQFT	12	2	11,845.00	$2.19	$25,946.25
	Unit Sub Total	**SQFT**		**25**	**855,451.00**	**$1.29**	**$1,104,908.71**
	Item Code 150870 Total No. of Proj.			**25**		**Total Amount**	**$1,104,908.71**
151224	REMOVE DELINEATOR	EA	1	1	5.00	$56.00	$280.00
		EA	2	5	995.00	$22.36	$22,250.00
		EA	4	1	8.00	$20.00	$160.00
		EA	9	5	526.00	$14.85	$7,810.00
		EA	11	1	210.00	$31.00	$6,510.00
		EA	12	4	146.00	$11.64	$1,700.00
	Unit Sub Total	**EA**		**17**	**1,890.00**	**$20.48**	**$38,710.00**
	Item Code 151224 Total No. of Proj.			**17**		**Total Amount**	**$38,710.00**
151226	SALVAGE GRATE	EA	3	1	24.00	$40.00	$960.00
	Unit Sub Total	**EA**		**1**	**24.00**	**$40.00**	**$960.00**
	Item Code 151226 Total No. of Proj.			**1**		**Total Amount**	**$960.00**
151265	SALVAGE SINGLE THRIE BEAM BARRIER	LF	6	1	12,000.00	$7.00	$84,000.00
		LF	10	1	12,300.00	$6.00	$73,800.00
	Unit Sub Total	**LF**		**2**	**24,300.00**	**$6.49**	**$157,800.00**
	Item Code 151265 Total No. of Proj.			**2**		**Total Amount**	**$157,800.00**
151266	SALVAGE DOUBLE THRIE BEAM BARRIER	LF	10	1	13,000.00	$10.00	$130,000.00
	Unit Sub Total	**LF**		**1**	**13,000.00**	**$10.00**	**$130,000.00**
	Item Code 151266 Total No. of Proj.			**1**		**Total Amount**	**$130,000.00**
151270	SALVAGE METAL BRIDGE RAILING	LF	3	1	1,183.00	$10.00	$11,830.00
		LF	4	2	1,690.00	$8.06	$13,620.00
		LF	6	2	1,787.00	$15.12	$27,012.00
		LF	7	1	4,037.00	$6.66	$26,886.42
		LF	10	1	5,172.00	$13.00	$67,236.00
		LF	12	1	497.00	$10.00	$4,970.00
	Unit Sub Total	**LF**		**8**	**14,366.00**	**$10.55**	**$151,554.42**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 151270 Total No. of Proj.			**8**		**Total Amount**	**$151,554.42**
151272	SALVAGE METAL BEAM GUARD RAILING	LF	2	1	2,330.00	$12.00	$27,960.00
		LF	5	1	180.00	$30.00	$5,400.00
		LF	6	3	540.00	$15.59	$8,420.00
		LF	8	1	475.00	$20.00	$9,500.00
		LF	9	1	1,280.00	$7.00	$8,960.00
	Unit Sub Total	**LF**		**7**	**4,805.00**	**$12.54**	**$60,240.00**
151272	SALVAGE METAL BEAM GUARD RAILING	M	10	1	58.00	$25.00	$1,450.00
	Unit Sub Total	**M**		**1**	**58.00**	**$25.00**	**$1,450.00**
	Item Code 151272 Total No. of Proj.			**8**		**Total Amount**	**$61,690.00**
151274	SALVAGE CONCRETE BARRIER (TYPE K)	LF	1	1	880.00	$35.00	$30,800.00
		LF	7	3	1,600.00	$13.24	$21,178.00
	Unit Sub Total	**LF**		**4**	**2,480.00**	**$20.96**	**$51,978.00**
	Item Code 151274 Total No. of Proj.			**4**		**Total Amount**	**$51,978.00**
151276	SALVAGE METAL BEAM BARRIER	LF	7	1	2,254.00	$7.62	$17,175.48
	Unit Sub Total	**LF**		**1**	**2,254.00**	**$7.62**	**$17,175.48**
	Item Code 151276 Total No. of Proj.			**1**		**Total Amount**	**$17,175.48**
151531	RECONSTRUCT FENCE	EA	3	1	980.00	$40.00	$39,200.00
	Unit Sub Total	**EA**		**1**	**980.00**	**$40.00**	**$39,200.00**
	Item Code 151531 Total No. of Proj.			**1**		**Total Amount**	**$39,200.00**
151534	RECONSTRUCT WOOD FENCE	LS	3	1	1.00	$2,500.00	$2,500.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$2,500.00**	**$2,500.00**
	Item Code 151534 Total No. of Proj.			**1**		**Total Amount**	**$2,500.00**
151536	RECONSTRUCT FENCE (TYPE BW)	LF	6	1	1,000.00	$8.20	$8,200.00
	Unit Sub Total	**LF**		**1**	**1,000.00**	**$8.20**	**$8,200.00**
	Item Code 151536 Total No. of Proj.			**1**		**Total Amount**	**$8,200.00**
151537	RECONSTRUCT FENCE (TYPE WM)	LF	1	2	13,580.00	$5.10	$69,250.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**2**	**13,580.00**	**$5.10**	**$69,250.00**
	Item Code 151537 Total No. of Proj.			**2**		**Total Amount**	**$69,250.00**
151540	RECONSTRUCT CHAIN LINK FENCE	LF	1	1	1,200.00	$8.00	$9,600.00
		LF	4	1	140.00	$38.00	$5,320.00
		LF	5	2	344.00	$19.02	$6,544.00
		LF	10	2	25.00	$83.00	$2,075.00
	Unit Sub Total	**LF**		**6**	**1,709.00**	**$13.77**	**$23,539.00**
151540	RECONSTRUCT CHAIN LINK FENCE	M	7	1	85.00	$60.00	$5,100.00
	Unit Sub Total	**M**		**1**	**85.00**	**$60.00**	**$5,100.00**
	Item Code 151540 Total No. of Proj.			**7**		**Total Amount**	**$28,639.00**
151568	RECONSTRUCT THRIE BEAM BARRIER	LF	2	1	1,800.00	$17.00	$30,600.00
		LF	4	1	160.00	$30.00	$4,800.00
		LF	6	2	31,010.00	$4.65	$144,050.00
	Unit Sub Total	**LF**		**4**	**32,970.00**	**$5.44**	**$179,450.00**
	Item Code 151568 Total No. of Proj.			**4**		**Total Amount**	**$179,450.00**
151570	RECONSTRUCT DOUBLE THRIE BEAM BARRIER	LF	6	1	1,490.00	$30.00	$44,700.00
		LF	10	1	460.00	$45.00	$20,700.00
	Unit Sub Total	**LF**		**2**	**1,950.00**	**$33.54**	**$65,400.00**
	Item Code 151570 Total No. of Proj.			**2**		**Total Amount**	**$65,400.00**
151572	RECONSTRUCT METAL BEAM GUARD RAILING	LF	1	5	10,400.00	$20.24	$210,480.00
		LF	2	11	93,210.00	$17.16	$1,599,720.00
		LF	3	5	11,754.00	$16.35	$192,158.00
		LF	5	4	14,010.00	$13.27	$185,860.00
		LF	6	4	2,280.00	$25.72	$58,650.00
		LF	8	3	44,120.00	$12.86	$567,170.00
		LF	10	1	290.00	$32.00	$9,280.00
	Unit Sub Total	**LF**		**33**	**176,064.00**	**$16.04**	**$2,823,318.00**
151572	RECONSTRUCT METAL BEAM GUARD RAILING	M	8	1	400.00	$100.00	$40,000.00
		M	10	1	240.00	$27.00	$6,480.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**2**	**640.00**	**$72.63**	**$46,480.00**
	Item Code 151572 Total No. of Proj.			**35**		**Total Amount**	**$2,869,798.00**
151623	RECONSTRUCT METAL BEAM GUARD RAILING (7' POST)	LF	1	1	2,000.00	$19.00	$38,000.00
	Unit Sub Total	**LF**		**1**	**2,000.00**	**$19.00**	**$38,000.00**
	Item Code 151623 Total No. of Proj.			**1**		**Total Amount**	**$38,000.00**
151625	RECONSTRUCT METAL BEAM GUARD RAILING (WOOD POST)	LF	1	2	5,085.00	$14.44	$73,445.00
		LF	3	3	16,040.00	$13.28	$212,940.00
		LF	4	1	1,000.00	$19.00	$19,000.00
		LF	12	1	600.00	$20.00	$12,000.00
	Unit Sub Total	**LF**		**7**	**22,725.00**	**$13.97**	**$317,385.00**
151625	RECONSTRUCT METAL BEAM GUARD RAILING (WOOD POST)	M	7	1	20.00	$110.00	$2,200.00
	Unit Sub Total	**M**		**1**	**20.00**	**$110.00**	**$2,200.00**
	Item Code 151625 Total No. of Proj.			**8**		**Total Amount**	**$319,585.00**
152037	RELAY ENTRANCE TAPER AND PIPE DOWNDRAIN	EA	3	1	1.00	$990.00	$990.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$990.00**	**$990.00**
	Item Code 152037 Total No. of Proj.			**1**		**Total Amount**	**$990.00**
152039	RELAY ENTRANCE TAPER	EA	3	1	15.00	$690.00	$10,350.00
	Unit Sub Total	**EA**		**1**	**15.00**	**$690.00**	**$10,350.00**
	Item Code 152039 Total No. of Proj.			**1**		**Total Amount**	**$10,350.00**
152255	RESET MAILBOX	EA	1	1	3.00	$400.00	$1,200.00
		EA	3	1	15.00	$300.00	$4,500.00
		EA	4	1	6.00	$400.00	$2,400.00
		EA	6	1	6.00	$340.00	$2,040.00
		EA	10	2	39.00	$199.36	$7,775.00
	Unit Sub Total	**EA**		**6**	**69.00**	**$259.64**	**$17,915.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 152255 Total No. of Proj.			**6**		**Total Amount**	**$17,915.00**
152291	RESET GATE	EA	3	1	6.00	$1,000.00	$6,000.00
	Unit Sub Total	**EA**		**1**	**6.00**	**$1,000.00**	**$6,000.00**
	Item Code 152291 Total No. of Proj.			**1**		**Total Amount**	**$6,000.00**
152299	RESET MILEPOST MARKER	EA	2	1	1.00	$40.00	$40.00
		EA	6	1	17.00	$60.00	$1,020.00
		EA	8	2	18.00	$37.56	$676.00
		EA	10	2	6.00	$83.33	$500.00
		EA	11	1	1.00	$100.00	$100.00
	Unit Sub Total	**EA**		**7**	**43.00**	**$54.33**	**$2,336.00**
	Item Code 152299 Total No. of Proj.			**7**		**Total Amount**	**$2,336.00**
152300	RESET OBJECT MARKER	EA	5	1	8.00	$21.00	$168.00
		EA	6	1	120.00	$60.00	$7,200.00
		EA	8	2	404.00	$40.59	$16,400.00
	Unit Sub Total	**EA**		**4**	**532.00**	**$44.68**	**$23,768.00**
	Item Code 152300 Total No. of Proj.			**4**		**Total Amount**	**$23,768.00**
152301	RESET MARKER	EA	1	2	23.00	$70.43	$1,620.00
		EA	4	1	1.00	$500.00	$500.00
		EA	5	1	6.00	$25.00	$150.00
	Unit Sub Total	**EA**		**4**	**30.00**	**$75.67**	**$2,270.00**
	Item Code 152301 Total No. of Proj.			**4**		**Total Amount**	**$2,270.00**
152303	RESET MARKERS AND DELINEATORS	EA	8	1	95.00	$290.00	$27,550.00
	Unit Sub Total	**EA**		**1**	**95.00**	**$290.00**	**$27,550.00**
	Item Code 152303 Total No. of Proj.			**1**		**Total Amount**	**$27,550.00**
152315	RESET CRASH CUSHION	EA	4	1	1.00	$1,400.00	$1,400.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,400.00**	**$1,400.00**
	Item Code 152315 Total No. of Proj.			**1**		**Total Amount**	**$1,400.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
152316	RESET ROADSIDE SIGN (ONE POST)	EA	1	4	6.00	$206.67	$1,240.00
		EA	2	3	9.00	$388.84	$3,499.60
		EA	3	1	2.00	$150.00	$300.00
		EA	5	1	2.00	$150.00	$300.00
		EA	6	1	63.00	$225.00	$14,175.00
		EA	8	3	50.00	$104.80	$5,240.00
	Unit Sub Total	**EA**		**13**	**132.00**	**$187.53**	**$24,754.60**
	Item Code 152316 Total No. of Proj.			**13**		**Total Amount**	**$24,754.60**
152317	RESET ROADSIDE SIGN (TWO POST)	EA	1	1	1.00	$500.00	$500.00
		EA	6	1	3.00	$400.00	$1,200.00
		EA	8	1	4.00	$190.00	$760.00
		EA	9	1	1.00	$350.00	$350.00
	Unit Sub Total	**EA**		**4**	**9.00**	**$312.22**	**$2,810.00**
	Item Code 152317 Total No. of Proj.			**4**		**Total Amount**	**$2,810.00**
152320	RESET ROADSIDE SIGN	EA	1	1	12.00	$500.00	$6,000.00
		EA	2	3	53.00	$206.13	$10,925.00
		EA	3	7	30.00	$191.75	$5,752.50
		EA	4	2	6.00	$225.67	$1,354.00
		EA	5	3	21.00	$173.71	$3,648.00
		EA	6	10	91.00	$167.37	$15,231.00
		EA	7	1	21.00	$185.00	$3,885.00
		EA	8	3	62.00	$233.87	$14,500.00
		EA	10	2	46.00	$144.35	$6,640.00
		EA	11	5	10.00	$222.30	$2,223.00
	Unit Sub Total	**EA**		**37**	**352.00**	**$199.31**	**$70,158.50**
	Item Code 152320 Total No. of Proj.			**37**		**Total Amount**	**$70,158.50**
152322	RESET ROADSIDE SIGN (WOOD POST)	EA	3	1	2.00	$250.00	$500.00
		EA	10	1	13.00	$100.00	$1,300.00
	Unit Sub Total	**EA**		**2**	**15.00**	**$120.00**	**$1,800.00**
	Item Code 152322 Total No. of Proj.			**2**		**Total Amount**	**$1,800.00**
152324	RESET ROADSIDE SIGN (METAL POST)	EA	1	1	2.00	$350.00	$700.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**1**	**2.00**	**$350.00**	**$700.00**
	Item Code 152324 Total No. of Proj.			**1**		**Total Amount**	**$700.00**
152365	RELOCATE BACKFLOW PREVENTER	EA	4	1	1.00	$1,177.72	$1,177.72
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,177.72**	**$1,177.72**
	Item Code 152365 Total No. of Proj.			**1**		**Total Amount**	**$1,177.72**
152370	RELOCATE MAILBOX	EA	3	1	4.00	$250.00	$1,000.00
		EA	5	1	44.00	$250.00	$11,000.00
		EA	10	2	14.00	$358.57	$5,020.00
	Unit Sub Total	**EA**		**4**	**62.00**	**$274.52**	**$17,020.00**
	Item Code 152370 Total No. of Proj.			**4**		**Total Amount**	**$17,020.00**
152372	RELOCATE CONCRETE BARRIER (TYPE K)	LF	4	1	20.00	$20.00	$400.00
	Unit Sub Total	**LF**		**1**	**20.00**	**$20.00**	**$400.00**
152372	RELOCATE CONCRETE BARRIER (TYPE K)	M	8	1	1,780.00	$2.60	$4,628.00
	Unit Sub Total	**M**		**1**	**1,780.00**	**$2.60**	**$4,628.00**
	Item Code 152372 Total No. of Proj.			**2**		**Total Amount**	**$5,028.00**
152381	RELOCATE GATE	EA	3	1	1.00	$2,000.00	$2,000.00
		EA	7	1	1.00	$1,200.00	$1,200.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$1,600.00**	**$3,200.00**
	Item Code 152381 Total No. of Proj.			**2**		**Total Amount**	**$3,200.00**
152386	RELOCATE ROADSIDE SIGN-ONE POST	EA	1	2	5.00	$204.00	$1,020.00
		EA	2	1	1.00	$200.00	$200.00
		EA	4	5	21.00	$225.71	$4,740.00
		EA	12	1	1.00	$250.00	$250.00
	Unit Sub Total	**EA**		**9**	**28.00**	**$221.79**	**$6,210.00**
	Item Code 152386 Total No. of Proj.			**9**		**Total Amount**	**$6,210.00**
152387	RELOCATE ROADSIDE SIGN-TWO POST	EA	1	1	1.00	$260.00	$260.00
		EA	4	5	18.00	$470.83	$8,475.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**6**	**19.00**	**$459.74**	**$8,735.00**
	Item Code 152387	**Total No. of Proj.**			**6**		**Total Amount**	**$8,735.00**
152388	RELOCATE CRASH CUSHION		EA	2	1	2.00	$2,000.00	$4,000.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$2,000.00**	**$4,000.00**
	Item Code 152388	**Total No. of Proj.**			**1**		**Total Amount**	**$4,000.00**
152390	RELOCATE ROADSIDE SIGN		EA	1	2	5.00	$290.00	$1,450.00
			EA	2	2	6.00	$237.50	$1,425.00
			EA	3	6	67.00	$187.99	$12,595.00
			EA	4	5	31.00	$183.06	$5,675.00
			EA	5	4	9.00	$274.44	$2,470.00
			EA	6	4	20.00	$163.75	$3,275.00
			EA	7	4	35.00	$310.71	$10,875.00
			EA	8	4	44.00	$278.41	$12,250.00
			EA	9	1	2.00	$178.00	$356.00
			EA	10	6	21.00	$207.10	$4,349.00
			EA	11	2	7.00	$312.86	$2,190.00
			EA	12	2	16.00	$258.13	$4,130.00
		Unit Sub Total	**EA**		**42**	**263.00**	**$232.09**	**$61,040.00**
	Item Code 152390	**Total No. of Proj.**			**42**		**Total Amount**	**$61,040.00**
152391	RELOCATE ROADSIDE SIGN (METAL POST)		EA	3	1	2.00	$559.27	$1,118.54
			EA	4	1	1.00	$200.00	$200.00
		Unit Sub Total	**EA**		**2**	**3.00**	**$439.51**	**$1,318.54**
	Item Code 152391	**Total No. of Proj.**			**2**		**Total Amount**	**$1,318.54**
152392	RELOCATE ROADSIDE SIGN (WOOD POST)		EA	12	1	1.00	$533.00	$533.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$533.00**	**$533.00**
	Item Code 152392	**Total No. of Proj.**			**1**		**Total Amount**	**$533.00**
152393	RELOCATE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD)		EA	4	1	1.00	$200.00	$200.00
			EA	12	2	6.00	$205.00	$1,230.00
		Unit Sub Total	**EA**		**3**	**7.00**	**$204.29**	**$1,430.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 152393 Total No. of Proj.			**3**		**Total Amount**	**$1,430.00**
152394	RELOCATE SIGN STRUCTURE	EA	3	2	2.00	$7,500.00	$15,000.00
		EA	12	1	2.00	$10,800.00	$21,600.00
	Unit Sub Total	**EA**		**3**	**4.00**	**$9,150.00**	**$36,600.00**
152394	RELOCATE SIGN STRUCTURE	LS	4	1	1.00	$10,000.00	$10,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$10,000.00**	**$10,000.00**
	Item Code 152394 Total No. of Proj.			**4**		**Total Amount**	**$46,600.00**
152398	RELOCATE SIGN STRUCTURE (BRIDGE-MOUNTED)	EA	3	1	1.00	$14,674.00	$14,674.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$14,674.00**	**$14,674.00**
	Item Code 152398 Total No. of Proj.			**1**		**Total Amount**	**$14,674.00**
152399	RELOCATE FRAMED SIGN PANEL	EA	8	1	4.00	$500.00	$2,000.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$500.00**	**$2,000.00**
	Item Code 152399 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**
152402	ADJUST WATER VALVE COVER TO GRADE	EA	1	1	11.00	$600.00	$6,600.00
		EA	3	1	71.00	$170.00	$12,070.00
		EA	4	2	4.00	$313.21	$1,252.82
		EA	5	2	39.00	$441.92	$17,235.00
		EA	10	2	58.00	$343.10	$19,900.00
		EA	12	2	226.00	$275.58	$62,282.00
	Unit Sub Total	**EA**		**10**	**409.00**	**$291.78**	**$119,339.82**
	Item Code 152402 Total No. of Proj.			**10**		**Total Amount**	**$119,339.82**
152403	ADJUST WATER METER BOX TO GRADE	EA	3	1	8.00	$180.00	$1,440.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$180.00**	**$1,440.00**
	Item Code 152403 Total No. of Proj.			**1**		**Total Amount**	**$1,440.00**
152422	ADJUST MONUMENT COVER	EA	4	1	1.00	$307.00	$307.00
		EA	5	1	2.00	$450.00	$900.00
		EA	6	1	65.00	$322.00	$20,930.00
		EA	7	1	32.00	$120.00	$3,840.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
152422	ADJUST MONUMENT COVER		EA	12	1	16.00	$285.00	$4,560.00
		Unit Sub Total	**EA**		**5**	**116.00**	**$263.25**	**$30,537.00**
	Item Code 152422	**Total No. of Proj.**			**5**		**Total Amount**	**$30,537.00**
152423	ADJUST MONUMENT TO GRADE		EA	4	1	4.00	$350.00	$1,400.00
		Unit Sub Total	**EA**		**1**	**4.00**	**$350.00**	**$1,400.00**
	Item Code 152423	**Total No. of Proj.**			**1**		**Total Amount**	**$1,400.00**
152430	ADJUST INLET		EA	1	4	23.00	$1,295.65	$29,800.00
			EA	2	3	53.00	$1,098.11	$58,200.00
			EA	3	4	39.00	$2,918.59	$113,825.00
			EA	4	5	145.00	$1,202.96	$174,429.30
			EA	5	2	3.00	$2,333.33	$7,000.00
			EA	7	2	44.00	$1,338.64	$58,900.00
			EA	10	2	10.00	$445.00	$4,450.00
			EA	12	2	10.00	$620.00	$6,200.00
		Unit Sub Total	**EA**		**24**	**327.00**	**$1,384.72**	**$452,804.30**
	Item Code 152430	**Total No. of Proj.**			**24**		**Total Amount**	**$452,804.30**
152432	ADJUST MANHOLE		EA	4	1	3.00	$445.00	$1,335.00
			EA	5	1	6.00	$2,000.00	$12,000.00
			EA	6	1	1.00	$1,200.00	$1,200.00
			EA	7	1	3.00	$3,200.00	$9,600.00
			EA	12	2	6.00	$1,125.00	$6,750.00
		Unit Sub Total	**EA**		**6**	**19.00**	**$1,625.53**	**$30,885.00**
	Item Code 152432	**Total No. of Proj.**			**6**		**Total Amount**	**$30,885.00**
152434	ADJUST RISER		EA	11	1	5.00	$1,000.00	$5,000.00
		Unit Sub Total	**EA**		**1**	**5.00**	**$1,000.00**	**$5,000.00**
	Item Code 152434	**Total No. of Proj.**			**1**		**Total Amount**	**$5,000.00**
152437	ADJUST OVERSIDE DRAIN		EA	3	1	12.00	$500.00	$6,000.00
		Unit Sub Total	**EA**		**1**	**12.00**	**$500.00**	**$6,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 152437 Total No. of Proj.			**1**		**Total Amount**	**$6,000.00**
152438	ADJUST FRAME AND COVER TO GRADE	EA	1	2	16.00	$984.38	$15,750.00
		EA	4	2	32.00	$355.78	$11,385.00
		EA	5	3	62.00	$543.55	$33,700.00
		EA	6	1	3.00	$950.00	$2,850.00
		EA	7	1	60.00	$295.00	$17,700.00
		EA	9	2	25.00	$700.00	$17,500.00
		EA	10	6	57.00	$475.79	$27,120.00
	Unit Sub Total	**EA**		**17**	**255.00**	**$494.14**	**$126,005.00**
	Item Code 152438 Total No. of Proj.			**17**		**Total Amount**	**$126,005.00**
152439	ADJUST FRAME AND GRATE TO GRADE	EA	3	4	38.00	$1,636.84	$62,200.00
		EA	4	1	7.00	$450.00	$3,150.00
		EA	6	1	23.00	$400.00	$9,200.00
		EA	10	2	6.00	$800.00	$4,800.00
		EA	12	2	21.00	$672.86	$14,130.00
	Unit Sub Total	**EA**		**10**	**95.00**	**$984.00**	**$93,480.00**
	Item Code 152439 Total No. of Proj.			**10**		**Total Amount**	**$93,480.00**
152440	ADJUST MANHOLE TO GRADE	EA	4	1	1.00	$1,500.00	$1,500.00
		EA	5	1	13.00	$800.00	$10,400.00
		EA	6	1	4.00	$1,100.00	$4,400.00
		EA	7	4	27.00	$2,218.89	$59,910.00
		EA	8	2	4.00	$750.00	$3,000.00
		EA	10	3	50.00	$489.00	$24,450.00
		EA	12	2	90.00	$316.67	$28,500.00
	Unit Sub Total	**EA**		**14**	**189.00**	**$699.26**	**$132,160.00**
	Item Code 152440 Total No. of Proj.			**14**		**Total Amount**	**$132,160.00**
152441	ADJUST VALVE BOX FRAME AND COVER TO GRADE	EA	3	1	1.00	$500.00	$500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$500.00**	**$500.00**
	Item Code 152441 Total No. of Proj.			**1**		**Total Amount**	**$500.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
152469	ADJUST UTILITY COVER TO GRADE	EA	2	1	39.00	$550.00	$21,450.00
		EA	5	2	21.00	$857.14	$18,000.00
		EA	6	1	5.00	$1,500.00	$7,500.00
	Unit Sub Total	**EA**		**4**	**65.00**	**$722.31**	**$46,950.00**
	Item Code 152469 Total No. of Proj.			**4**		**Total Amount**	**$46,950.00**
152500	ADJUST METAL BEAM GUARD RAILING	LF	1	2	1,088.00	$6.91	$7,520.00
		LF	2	2	6,310.00	$6.01	$37,934.50
		LF	3	3	11,300.00	$5.57	$62,945.00
		LF	4	2	5,410.00	$7.50	$40,575.00
		LF	5	1	590.00	$12.30	$7,257.00
		LF	9	1	15,700.00	$6.00	$94,200.00
	Unit Sub Total	**LF**		**11**	**40,398.00**	**$6.20**	**$250,431.50**
	Item Code 152500 Total No. of Proj.			**11**		**Total Amount**	**$250,431.50**
152555	ADJUST SLOTTED DRAIN TO GRADE	LF	1	1	140.00	$100.00	$14,000.00
		LF	3	1	520.00	$105.00	$54,600.00
	Unit Sub Total	**LF**		**2**	**660.00**	**$103.94**	**$68,600.00**
	Item Code 152555 Total No. of Proj.			**2**		**Total Amount**	**$68,600.00**
152604	MODIFY INLET	EA	2	1	2.00	$1,200.00	$2,400.00
		EA	3	1	3.00	$1,500.00	$4,500.00
		EA	4	3	21.00	$2,611.00	$54,830.90
		EA	5	1	3.00	$2,800.00	$8,400.00
		EA	7	2	8.00	$5,500.00	$44,000.00
		EA	11	2	5.00	$960.00	$4,800.00
	Unit Sub Total	**EA**		**10**	**42.00**	**$2,831.69**	**$118,930.90**
	Item Code 152604 Total No. of Proj.			**10**		**Total Amount**	**$118,930.90**
152609	MODIFY INLET TO MANHOLE	EA	4	5	8.00	$2,416.00	$19,328.00
	Unit Sub Total	**EA**		**5**	**8.00**	**$2,416.00**	**$19,328.00**
	Item Code 152609 Total No. of Proj.			**5**		**Total Amount**	**$19,328.00**
152610	MODIFY MANHOLE	EA	3	2	3.00	$1,400.00	$4,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**2**	**3.00**	**$1,400.00**	**$4,200.00**
	Item Code 152610 Total No. of Proj.			**2**		**Total Amount**	**$4,200.00**
152641	MODIFY SIGN STRUCTURE	EA	11	1	2.00	$4,000.00	$8,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$4,000.00**	**$8,000.00**
	Item Code 152641 Total No. of Proj.			**1**		**Total Amount**	**$8,000.00**
152650	MODIFY CHAIN LINK FENCE	LF	3	1	66.00	$20.00	$1,320.00
	Unit Sub Total	**LF**		**1**	**66.00**	**$20.00**	**$1,320.00**
	Item Code 152650 Total No. of Proj.			**1**		**Total Amount**	**$1,320.00**
152659	PLASTIC PIPE LINER	LF	4	1	140.00	$38.11	$5,335.40
	Unit Sub Total	**LF**		**1**	**140.00**	**$38.11**	**$5,335.40**
	Item Code 152659 Total No. of Proj.			**1**		**Total Amount**	**$5,335.40**
152750	REPLACE SIGN PANEL	EA	4	1	1.00	$1,500.00	$1,500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,500.00**	**$1,500.00**
	Item Code 152750 Total No. of Proj.			**1**		**Total Amount**	**$1,500.00**
153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	M2	4	1	1,330.00	$15.00	$19,950.00
		M2	5	1	44,200.00	$2.50	$110,500.00
		M2	7	4	39,100.00	$2.44	$95,435.00
		M2	8	1	2,200.00	$5.00	$11,000.00
		M2	10	2	7,620.00	$3.62	$27,590.00
		M2	11	2	11,560.00	$4.53	$52,376.00
	Unit Sub Total	**M2**		**11**	**106,010.00**	**$2.99**	**$316,851.00**
153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQFT	3	1	150.00	$5.00	$750.00
		SQFT	11	1	2,900.00	$1.00	$2,900.00
	Unit Sub Total	**SQFT**		**2**	**3,050.00**	**$1.20**	**$3,650.00**
153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	1	26	329,123.00	$2.55	$839,429.60
		SQYD	2	29	1,503,110.00	$2.64	$3,966,216.14
		SQYD	3	44	3,562,650.00	$1.33	$4,730,360.00
		SQYD	4	39	2,700,756.00	$1.98	$5,336,078.50
		SQYD	5	19	1,822,370.00	$1.23	$2,240,731.40

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	6	25	1,666,895.00	$1.41	$2,353,046.75
		SQYD	7	15	4,183,180.00	$1.08	$4,500,378.00
		SQYD	8	16	2,616,330.00	$0.89	$2,324,994.00
		SQYD	9	7	23,200.00	$7.53	$174,703.00
		SQYD	10	23	424,843.00	$2.48	$1,052,293.30
		SQYD	11	12	2,208,000.00	$1.33	$2,932,160.00
		SQYD	12	11	448,940.00	$1.25	$560,702.00
	Unit Sub Total	**SQYD**		**266**	**###########**	**$1.44**	**$31,011,092.69**
	Item Code 153103 Total No. of Proj.			**279**		**Total Amount**	**$31,331,593.69**
153110	COLD PLANE ASPHALT CONCRETE PAVEMENT (.10' MAXIMUM)	SQYD	12	2	89,100.00	$1.06	$94,460.00
	Unit Sub Total	**SQYD**		**2**	**89,100.00**	**$1.06**	**$94,460.00**
	Item Code 153110 Total No. of Proj.			**2**		**Total Amount**	**$94,460.00**
153112	COLD PLANE ASPHALT CONCRETE PAVEMENT (.15' MAXIMUM)	SQYD	3	2	8,820.00	$3.06	$27,000.00
	Unit Sub Total	**SQYD**		**2**	**8,820.00**	**$3.06**	**$27,000.00**
	Item Code 153112 Total No. of Proj.			**2**		**Total Amount**	**$27,000.00**
153114	COLD PLANE ASPHALT CONCRETE PAVEMENT (.20' MAXIMUM)	SQYD	12	1	30,000.00	$1.00	$30,000.00
	Unit Sub Total	**SQYD**		**1**	**30,000.00**	**$1.00**	**$30,000.00**
	Item Code 153114 Total No. of Proj.			**1**		**Total Amount**	**$30,000.00**
153116	COLD PLANE ASPHALT CONCRETE PAVEMENT (.25' MAXIMUM)	SQYD	3	1	12,600.00	$1.75	$22,050.00
	Unit Sub Total	**SQYD**		**1**	**12,600.00**	**$1.75**	**$22,050.00**
	Item Code 153116 Total No. of Proj.			**1**		**Total Amount**	**$22,050.00**
153210	REMOVE CONCRETE	CY	2	4	87.10	$139.16	$12,120.93
		CY	3	8	198.00	$157.76	$31,236.00
		CY	4	10	1,078.30	$78.47	$84,609.38
		CY	5	4	148.70	$360.46	$53,600.00
		CY	6	5	936.00	$211.15	$197,632.00
		CY	7	6	1,546.00	$69.25	$107,065.32

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
153210	REMOVE CONCRETE		CY	8	3	142.00	$103.24	$14,660.00
			CY	9	1	16.00	$100.00	$1,600.00
			CY	10	1	880.00	$25.00	$22,000.00
			CY	11	4	575.00	$54.78	$31,500.00
			CY	12	7	633.00	$108.16	$68,465.00
		Unit Sub Total	**CY**		**53**	**6,240.10**	**$100.08**	**$624,488.63**
153210	REMOVE CONCRETE		LF	6	1	1,120.00	$3.00	$3,360.00
			LF	9	1	30.00	$400.00	$12,000.00
		Unit Sub Total	**LF**		**2**	**1,150.00**	**$13.36**	**$15,360.00**
153210	REMOVE CONCRETE		LS	9	1	1.00	$8,800.00	$8,800.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$8,800.00**	**$8,800.00**
153210	REMOVE CONCRETE		M3	7	4	1,215.30	$72.91	$88,603.00
			M3	8	1	53.00	$200.00	$10,600.00
			M3	11	1	290.00	$100.00	$29,000.00
		Unit Sub Total	**M3**		**6**	**1,558.30**	**$82.27**	**$128,203.00**
153210	REMOVE CONCRETE		SQFT	8	1	1,840.00	$2.70	$4,968.00
		Unit Sub Total	**SQFT**		**1**	**1,840.00**	**$2.70**	**$4,968.00**
	Item Code 153210	**Total No. of Proj.**			**63**		**Total Amount**	**$781,819.63**
153211	REMOVE CONCRETE SIDEWALK AND DRIVEWAY		CY	4	1	0.80	$285.00	$228.00
		Unit Sub Total	**CY**		**1**	**0.80**	**$285.00**	**$228.00**
153211	REMOVE CONCRETE SIDEWALK AND DRIVEWAY		M2	7	1	7,680.00	$3.50	$26,880.00
		Unit Sub Total	**M2**		**1**	**7,680.00**	**$3.50**	**$26,880.00**
153211	REMOVE CONCRETE SIDEWALK AND DRIVEWAY		SQYD	3	1	630.00	$12.00	$7,560.00
		Unit Sub Total	**SQYD**		**1**	**630.00**	**$12.00**	**$7,560.00**
	Item Code 153211	**Total No. of Proj.**			**3**		**Total Amount**	**$34,668.00**
153213	REMOVE CONCRETE (STRUCTURE)		LS	2	1	1.00	$1,000.00	$1,000.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$1,000.00**	**$1,000.00**
153213	REMOVE CONCRETE (STRUCTURE)		M3	7	1	8.00	$250.00	$2,000.00
		Unit Sub Total	**M3**		**1**	**8.00**	**$250.00**	**$2,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 153213	**Total No. of Proj.**			**2**		**Total Amount**	**$3,000.00**
153214	REMOVE CONCRETE CURB		CY	8	1	25.00	$62.00	$1,550.00
			CY	11	1	52.00	$28.00	$1,456.00
		Unit Sub Total	**CY**		**2**	**77.00**	**$39.04**	**$3,006.00**
153214	REMOVE CONCRETE CURB		LF	1	2	460.00	$8.96	$4,120.00
			LF	2	1	1,380.00	$7.00	$9,660.00
			LF	3	4	1,478.00	$9.59	$14,177.00
			LF	4	6	17,470.00	$3.62	$63,280.00
			LF	5	2	460.00	$14.87	$6,840.00
			LF	7	4	45,950.00	$3.67	$168,775.00
			LF	11	1	570.00	$8.00	$4,560.00
			LF	12	4	5,314.00	$4.31	$22,885.00
		Unit Sub Total	**LF**		**24**	**73,082.00**	**$4.03**	**$294,297.00**
153214	REMOVE CONCRETE CURB		M	7	1	390.00	$19.00	$7,410.00
		Unit Sub Total	**M**		**1**	**390.00**	**$19.00**	**$7,410.00**
	Item Code 153214	**Total No. of Proj.**			**27**		**Total Amount**	**$304,713.00**
153215	REMOVE CONCRETE (CURB AND GUTTER)		LF	2	1	1,490.00	$5.00	$7,450.00
			LF	3	4	20,342.00	$3.40	$69,105.00
			LF	4	4	19,720.00	$5.50	$108,490.00
			LF	5	1	580.00	$3.50	$2,030.00
			LF	6	2	660.00	$3.26	$2,150.00
			LF	7	1	3,280.00	$6.00	$19,680.00
			LF	12	1	78.00	$12.00	$936.00
		Unit Sub Total	**LF**		**14**	**46,150.00**	**$4.55**	**$209,841.00**
153215	REMOVE CONCRETE (CURB AND GUTTER)		M	7	1	12,000.00	$4.00	$48,000.00
		Unit Sub Total	**M**		**1**	**12,000.00**	**$4.00**	**$48,000.00**
	Item Code 153215	**Total No. of Proj.**			**15**		**Total Amount**	**$257,841.00**
153216	REMOVE CONCRETE CURB AND SIDEWALK		CY	3	1	10.00	$251.00	$2,510.00
		Unit Sub Total	**CY**		**1**	**10.00**	**$251.00**	**$2,510.00**
	Item Code 153216	**Total No. of Proj.**			**1**		**Total Amount**	**$2,510.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
153218	REMOVE CONCRETE SIDEWALK		CY	2	1	0.60	$3,500.00	$2,100.00
			CY	3	2	121.00	$48.21	$5,834.00
			CY	12	1	30.00	$55.00	$1,650.00
		Unit Sub Total	**CY**		**4**	**151.60**	**$63.22**	**$9,584.00**
153218	REMOVE CONCRETE SIDEWALK		LF	4	1	2,130.00	$9.50	$20,235.00
			LF	5	1	380.00	$6.00	$2,280.00
		Unit Sub Total	**LF**		**2**	**2,510.00**	**$8.97**	**$22,515.00**
153218	REMOVE CONCRETE SIDEWALK		M	4	1	12.00	$50.00	$600.00
		Unit Sub Total	**M**		**1**	**12.00**	**$50.00**	**$600.00**
153218	REMOVE CONCRETE SIDEWALK		SQFT	4	1	32,300.00	$0.50	$16,150.00
			SQFT	7	1	780.00	$1.50	$1,170.00
		Unit Sub Total	**SQFT**		**2**	**33,080.00**	**$0.52**	**$17,320.00**
	Item Code 153218	**Total No. of Proj.**			**9**		**Total Amount**	**$50,019.00**
153220	REMOVE CONCRETE (CHANNEL)		CY	4	2	160.00	$109.38	$17,500.00
			CY	7	1	11.00	$115.00	$1,265.00
			CY	12	2	311.10	$46.61	$14,500.00
		Unit Sub Total	**CY**		**5**	**482.10**	**$69.00**	**$33,265.00**
	Item Code 153220	**Total No. of Proj.**			**5**		**Total Amount**	**$33,265.00**
153221	REMOVE CONCRETE BARRIER		LF	2	1	5,970.00	$15.00	$89,550.00
			LF	3	3	3,440.00	$11.77	$40,478.00
			LF	4	5	23,200.00	$9.73	$225,772.60
			LF	5	1	790.00	$13.00	$10,270.00
			LF	6	1	6.00	$450.00	$2,700.00
			LF	7	3	13,307.00	$44.15	$587,544.00
			LF	8	1	240.00	$20.00	$4,800.00
			LF	11	1	24.00	$100.00	$2,400.00
			LF	12	2	1,650.00	$16.73	$27,610.00
		Unit Sub Total	**LF**		**18**	**48,627.00**	**$20.38**	**$991,124.60**
153221	REMOVE CONCRETE BARRIER		M	5	1	2,980.00	$50.00	$149,000.00
			M	7	2	580.00	$87.17	$50,560.00
			M	8	1	560.00	$40.00	$22,400.00
			M	11	1	230.00	$80.00	$18,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**5**	**4,350.00**	**$55.26**	**$240,360.00**
	Item Code 153221 Total No. of Proj.			**23**		**Total Amount**	**$1,231,484.60**
153222	REMOVE CONCRETE ISLAND (PORTIONS)	CY	4	1	10.00	$200.00	$2,000.00
	Unit Sub Total	**CY**		**1**	**10.00**	**$200.00**	**$2,000.00**
153222	REMOVE CONCRETE ISLAND (PORTIONS)	SQFT	4	1	7,010.00	$1.00	$7,010.00
	Unit Sub Total	**SQFT**		**1**	**7,010.00**	**$1.00**	**$7,010.00**
	Item Code 153222 Total No. of Proj.			**2**		**Total Amount**	**$9,010.00**
153223	REMOVE UNSOUND CONCRETE	CF	1	4	1,277.00	$61.42	$78,428.00
		CF	2	10	3,138.00	$38.72	$121,500.00
		CF	3	12	4,044.00	$18.90	$76,437.00
		CF	4	12	5,629.00	$19.41	$109,241.00
		CF	5	3	1,846.00	$22.79	$42,065.60
		CF	6	6	3,891.00	$9.10	$35,400.00
		CF	7	25	22,618.00	$15.77	$356,737.54
		CF	8	7	6,033.00	$21.21	$127,989.00
		CF	10	3	3,389.00	$30.08	$101,952.00
		CF	11	4	1,644.00	$10.48	$17,223.96
		CF	12	4	2,144.00	$33.21	$71,205.00
	Unit Sub Total	**CF**		**90**	**55,653.00**	**$20.45**	**$1,138,179.10**
	Item Code 153223 Total No. of Proj.			**90**		**Total Amount**	**$1,138,179.10**
153225	PREPARE CONCRETE BRIDGE DECK SURFACE	SQFT	1	3	93,565.00	$0.41	$38,414.15
		SQFT	2	15	545,952.00	$0.32	$177,204.90
		SQFT	3	12	888,876.00	$0.22	$196,364.84
		SQFT	4	9	586,193.00	$0.20	$117,296.05
		SQFT	5	2	6,566.00	$0.97	$6,394.00
		SQFT	6	3	45,625.00	$0.21	$9,572.50
		SQFT	7	7	226,365.00	$0.35	$78,574.83
		SQFT	8	8	575,810.00	$0.28	$158,533.14
		SQFT	10	3	204,538.00	$0.13	$25,832.96
		SQFT	11	1	16,481.00	$0.30	$4,944.30
		SQFT	12	2	29,758.00	$0.36	$10,779.20

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**SQFT**		**65**	**3,219,729.00**	**$0.26**	**$823,910.87**
	Item Code 153225	**Total No. of Proj.**			**65**		**Total Amount**	**$823,910.87**
153229	REMOVE CONCRETE BARRIER (TYPE K)		LF	4	2	800.00	$12.38	$9,904.00
			LF	6	1	950.00	$30.00	$28,500.00
			LF	12	1	3,400.00	$5.00	$17,000.00
		Unit Sub Total	**LF**		**4**	**5,150.00**	**$10.76**	**$55,404.00**
153229	REMOVE CONCRETE BARRIER (TYPE K)		M	8	1	48.00	$25.00	$1,200.00
		Unit Sub Total	**M**		**1**	**48.00**	**$25.00**	**$1,200.00**
	Item Code 153229	**Total No. of Proj.**			**5**		**Total Amount**	**$56,604.00**
153230	REMOVE CONCRETE BARRIER (TYPE 50)		LF	3	1	2,460.00	$11.00	$27,060.00
			LF	4	2	13,865.00	$18.98	$263,175.00
			LF	7	1	280.00	$13.00	$3,640.00
		Unit Sub Total	**LF**		**4**	**16,605.00**	**$17.70**	**$293,875.00**
	Item Code 153230	**Total No. of Proj.**			**4**		**Total Amount**	**$293,875.00**
153231	REMOVE CONCRETE BARRIER (TYPE 50C)		LF	3	1	2,500.00	$11.00	$27,500.00
			LF	4	1	500.00	$21.00	$10,500.00
		Unit Sub Total	**LF**		**2**	**3,000.00**	**$12.67**	**$38,000.00**
	Item Code 153231	**Total No. of Proj.**			**2**		**Total Amount**	**$38,000.00**
153235	CLEAN BRIDGE DECK		SQFT	1	2	90,284.00	$0.27	$23,993.00
			SQFT	2	4	56,839.00	$0.23	$13,139.01
			SQFT	3	13	798,412.00	$0.21	$167,726.49
			SQFT	4	9	940,104.00	$0.17	$159,187.61
			SQFT	5	3	582,146.00	$0.13	$74,721.90
			SQFT	6	7	1,079,015.00	$0.13	$142,412.16
			SQFT	7	20	6,679,941.00	$0.12	$830,238.72
			SQFT	8	6	1,382,211.00	$0.18	$247,555.60
			SQFT	10	2	82,998.00	$0.16	$13,559.96
			SQFT	11	4	809,645.00	$0.07	$57,328.44
			SQFT	12	3	390,325.00	$0.18	$69,358.60
		Unit Sub Total	**SQFT**		**73**	**############**	**$0.14**	**$1,799,221.49**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 153235 Total No. of Proj.			**73**		**Total Amount**	**$1,799,221.49**
153237	REMOVE CHIP SEAL	SQFT	1	1	16,473.00	$2.00	$32,946.00
		SQFT	2	1	6,015.00	$1.60	$9,624.00
		SQFT	3	3	100,194.00	$1.20	$120,682.80
		SQFT	6	2	13,467.00	$0.86	$11,578.35
	Unit Sub Total	**SQFT**		**7**	**136,149.00**	**$1.28**	**$174,831.15**
	Item Code 153237 Total No. of Proj.			**7**		**Total Amount**	**$174,831.15**
153239	REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK)	CY	3	1	10.00	$200.00	$2,000.00
		CY	4	1	152.00	$38.10	$5,791.20
		CY	7	1	25.00	$100.00	$2,500.00
		CY	8	1	15.00	$134.00	$2,010.00
		CY	12	2	62.00	$179.03	$11,100.00
	Unit Sub Total	**CY**		**6**	**264.00**	**$88.64**	**$23,401.20**
153239	REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK)	M3	7	1	130.00	$75.00	$9,750.00
	Unit Sub Total	**M3**		**1**	**130.00**	**$75.00**	**$9,750.00**
	Item Code 153239 Total No. of Proj.			**7**		**Total Amount**	**$33,151.20**
153246	REMOVE CONCRETE (MISCELLANEOUS)	CY	3	1	48.00	$100.00	$4,800.00
		CY	4	2	30.00	$100.00	$3,000.00
		CY	12	2	8.50	$197.06	$1,675.00
	Unit Sub Total	**CY**		**5**	**86.50**	**$109.54**	**$9,475.00**
153246	REMOVE CONCRETE (MISCELLANEOUS)	M3	7	1	4.00	$425.00	$1,700.00
		M3	11	1	17.00	$68.00	$1,156.00
	Unit Sub Total	**M3**		**2**	**21.00**	**$136.00**	**$2,856.00**
153246	REMOVE CONCRETE (MISCELLANEOUS)	SQFT	7	1	3,160.00	$1.40	$4,424.00
	Unit Sub Total	**SQFT**		**1**	**3,160.00**	**$1.40**	**$4,424.00**
	Item Code 153246 Total No. of Proj.			**8**		**Total Amount**	**$16,755.00**
153250	REMOVE SOUND WALL	LF	10	1	470.00	$25.00	$11,750.00
	Unit Sub Total	**LF**		**1**	**470.00**	**$25.00**	**$11,750.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
153250	REMOVE SOUND WALL		M	7	1	440.00	$65.00	$28,600.00
		Unit Sub Total	**M**		**1**	**440.00**	**$65.00**	**$28,600.00**
153250	REMOVE SOUND WALL		M2	7	1	462.00	$26.00	$12,012.00
		Unit Sub Total	**M2**		**1**	**462.00**	**$26.00**	**$12,012.00**
	Item Code 153250	**Total No. of Proj.**			**3**		**Total Amount**	**$52,362.00**
153530	ACCESS OPENING, DECK		EA	4	1	20.00	$3,000.00	$60,000.00
		Unit Sub Total	**EA**		**1**	**20.00**	**$3,000.00**	**$60,000.00**
	Item Code 153530	**Total No. of Proj.**			**1**		**Total Amount**	**$60,000.00**
153531	ACCESS OPENING, SOFFIT		EA	2	1	12.00	$2,000.00	$24,000.00
			EA	3	1	18.00	$1,200.00	$21,600.00
			EA	7	2	10.00	$224.00	$2,240.00
			EA	10	1	56.00	$1,000.00	$56,000.00
			EA	12	1	6.00	$1,375.00	$8,250.00
		Unit Sub Total	**EA**		**6**	**102.00**	**$1,098.92**	**$112,090.00**
	Item Code 153531	**Total No. of Proj.**			**6**		**Total Amount**	**$112,090.00**
155002	PLUG PIPE		EA	7	1	1.00	$2,800.00	$2,800.00
			EA	8	1	8.00	$250.00	$2,000.00
		Unit Sub Total	**EA**		**2**	**9.00**	**$533.33**	**$4,800.00**
	Item Code 155002	**Total No. of Proj.**			**2**		**Total Amount**	**$4,800.00**
155003	CAP INLET		EA	3	2	15.00	$700.00	$10,500.00
			EA	4	8	38.00	$1,111.31	$42,229.70
			EA	5	3	8.00	$1,525.00	$12,200.00
			EA	6	1	2.00	$400.00	$800.00
			EA	7	3	11.00	$952.73	$10,480.00
			EA	10	2	12.00	$958.33	$11,500.00
			EA	12	2	11.00	$945.45	$10,400.00
		Unit Sub Total	**EA**		**21**	**97.00**	**$1,011.44**	**$98,109.70**
	Item Code 155003	**Total No. of Proj.**			**21**		**Total Amount**	**$98,109.70**
155006	CAP RISER		EA	6	1	1.00	$200.00	$200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
155006	CAP RISER	EA	11	2	5.00	$800.00	$4,000.00
	Unit Sub Total	**EA**		**3**	**6.00**	**$700.00**	**$4,200.00**
	Item Code 155006 Total No. of Proj.			**3**		**Total Amount**	**$4,200.00**
155007	CAP MANHOLE	EA	4	1	2.00	$2,213.40	$4,426.80
		EA	7	1	3.00	$850.00	$2,550.00
	Unit Sub Total	**EA**		**2**	**5.00**	**$1,395.36**	**$6,976.80**
	Item Code 155007 Total No. of Proj.			**2**		**Total Amount**	**$6,976.80**
155115	18" ALTERNATIVE PIPELINER	LF	3	1	770.00	$137.00	$105,490.00
		LF	4	1	840.00	$225.00	$189,000.00
	Unit Sub Total	**LF**		**2**	**1,610.00**	**$182.91**	**$294,490.00**
	Item Code 155115 Total No. of Proj.			**2**		**Total Amount**	**$294,490.00**
155121	24" ALTERNATIVE PIPELINER	LF	3	4	3,219.00	$181.74	$585,022.00
		LF	4	1	1,290.00	$275.00	$354,750.00
	Unit Sub Total	**LF**		**5**	**4,509.00**	**$208.42**	**$939,772.00**
	Item Code 155121 Total No. of Proj.			**5**		**Total Amount**	**$939,772.00**
155127	30" ALTERNATIVE PIPELINER	LF	3	1	301.00	$170.00	$51,170.00
		LF	4	1	410.00	$326.00	$133,660.00
	Unit Sub Total	**LF**		**2**	**711.00**	**$259.96**	**$184,830.00**
	Item Code 155127 Total No. of Proj.			**2**		**Total Amount**	**$184,830.00**
155130	36" ALTERNATIVE PIPELINER	LF	4	1	740.00	$448.00	$331,520.00
	Unit Sub Total	**LF**		**1**	**740.00**	**$448.00**	**$331,520.00**
	Item Code 155130 Total No. of Proj.			**1**		**Total Amount**	**$331,520.00**
155210	CLEANING, INSPECTING AND PREPARING HOST PIPE	CY	6	2	4,100.00	$1.04	$4,260.00
	Unit Sub Total	**CY**		**2**	**4,100.00**	**$1.04**	**$4,260.00**
155210	CLEANING, INSPECTING AND PREPARING HOST PIPE	LF	3	1	1,250.00	$24.00	$30,000.00
		LF	7	2	2,430.00	$8.26	$20,060.00
		LF	12	1	2,280.00	$7.00	$15,960.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**4**	**5,960.00**	**$11.08**	**$66,020.00**
	Item Code 155210	**Total No. of Proj.**			**6**		**Total Amount**	**$70,280.00**
155220	CULVERT CONTACT GROUTING		CY	4	1	57.00	$500.00	$28,500.00
		Unit Sub Total	**CY**		**1**	**57.00**	**$500.00**	**$28,500.00**
	Item Code 155220	**Total No. of Proj.**			**1**		**Total Amount**	**$28,500.00**
155230	CONCRETE INVERT PAVING		CY	1	1	4.60	$1,500.00	$6,900.00
			CY	6	1	230.00	$815.00	$187,450.00
			CY	11	1	16.00	$2,000.00	$32,000.00
		Unit Sub Total	**CY**		**3**	**250.60**	**$903.23**	**$226,350.00**
	Item Code 155230	**Total No. of Proj.**			**3**		**Total Amount**	**$226,350.00**
155314	18" CURED-IN-PLACE PIPELINER		LF	3	1	120.00	$527.50	$63,300.00
			LF	6	1	320.00	$225.00	$72,000.00
			LF	7	2	1,830.00	$125.68	$230,000.00
			LF	10	1	260.00	$167.00	$43,420.00
			LF	12	1	190.00	$144.00	$27,360.00
		Unit Sub Total	**LF**		**6**	**2,720.00**	**$160.32**	**$436,080.00**
	Item Code 155314	**Total No. of Proj.**			**6**		**Total Amount**	**$436,080.00**
155316	24" CURED-IN-PLACE PIPELINER		LF	3	3	1,857.00	$181.51	$337,066.00
			LF	6	2	850.00	$250.00	$212,500.00
			LF	7	2	668.00	$148.17	$98,980.00
			LF	12	1	1,250.00	$67.00	$83,750.00
		Unit Sub Total	**LF**		**8**	**4,625.00**	**$158.33**	**$732,296.00**
	Item Code 155316	**Total No. of Proj.**			**8**		**Total Amount**	**$732,296.00**
155318	30" CURED-IN-PLACE PIPELINER		LF	3	2	213.00	$266.66	$56,799.00
			LF	6	1	270.00	$300.00	$81,000.00
		Unit Sub Total	**LF**		**3**	**483.00**	**$285.30**	**$137,799.00**
	Item Code 155318	**Total No. of Proj.**			**3**		**Total Amount**	**$137,799.00**
155319	36" CURED-IN-PLACE PIPELINER		LF	3	1	79.00	$350.00	$27,650.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
155319	36" CURED-IN-PLACE PIPELINER	LF	6	2	360.00	$287.50	$103,500.00
	Unit Sub Total	**LF**		**3**	**439.00**	**$298.75**	**$131,150.00**
	Item Code 155319 Total No. of Proj.			**3**		**Total Amount**	**$131,150.00**
155320	42" CURED-IN-PLACE PIPELINER	LF	6	1	280.00	$286.00	$80,080.00
	Unit Sub Total	**LF**		**1**	**280.00**	**$286.00**	**$80,080.00**
	Item Code 155320 Total No. of Proj.			**1**		**Total Amount**	**$80,080.00**
155322	54" CURED-IN-PLACE PIPELINER	LF	6	1	780.00	$318.00	$248,040.00
	Unit Sub Total	**LF**		**1**	**780.00**	**$318.00**	**$248,040.00**
	Item Code 155322 Total No. of Proj.			**1**		**Total Amount**	**$248,040.00**
155530	HDPE PLASTIC PIPELINER (16" OD SDR 32.5)	LF	1	1	670.00	$225.00	$150,750.00
	Unit Sub Total	**LF**		**1**	**670.00**	**$225.00**	**$150,750.00**
	Item Code 155530 Total No. of Proj.			**1**		**Total Amount**	**$150,750.00**
155533	HDPE PLASTIC PIPELINER (22" OD SDR 32.5)	LF	1	1	830.00	$265.00	$219,950.00
	Unit Sub Total	**LF**		**1**	**830.00**	**$265.00**	**$219,950.00**
	Item Code 155533 Total No. of Proj.			**1**		**Total Amount**	**$219,950.00**
155536	HDPE PLASTIC PIPELINER (28" OD SDR 32.5)	LF	1	1	700.00	$303.00	$212,100.00
	Unit Sub Total	**LF**		**1**	**700.00**	**$303.00**	**$212,100.00**
	Item Code 155536 Total No. of Proj.			**1**		**Total Amount**	**$212,100.00**
155554	HDPE PLASTIC PIPELINER (30" OD SDR 26)	LF	1	1	130.00	$205.00	$26,650.00
	Unit Sub Total	**LF**		**1**	**130.00**	**$205.00**	**$26,650.00**
	Item Code 155554 Total No. of Proj.			**1**		**Total Amount**	**$26,650.00**
155559	HDPE PLASTIC PIPELINER (42" OD SDR 26)	LF	1	1	120.00	$285.00	$34,200.00
	Unit Sub Total	**LF**		**1**	**120.00**	**$285.00**	**$34,200.00**
	Item Code 155559 Total No. of Proj.			**1**		**Total Amount**	**$34,200.00**
156535	REMOVE BOX CULVERT	CY	6	1	50.00	$230.00	$11,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**CY**		**1**	**50.00**	**$230.00**	**$11,500.00**
156535	REMOVE BOX CULVERT		LF	6	1	57.00	$100.00	$5,700.00
		Unit Sub Total	**LF**		**1**	**57.00**	**$100.00**	**$5,700.00**
	Item Code 156535	**Total No. of Proj.**			**2**		**Total Amount**	**$17,200.00**
156572	REMOVE RAILING		LF	4	1	630.00	$5.30	$3,339.00
			LF	8	1	210.00	$15.50	$3,255.00
		Unit Sub Total	**LF**		**2**	**840.00**	**$7.85**	**$6,594.00**
	Item Code 156572	**Total No. of Proj.**			**2**		**Total Amount**	**$6,594.00**
156576	REMOVE METAL RAILING		LF	11	1	200.00	$12.00	$2,400.00
		Unit Sub Total	**LF**		**1**	**200.00**	**$12.00**	**$2,400.00**
	Item Code 156576	**Total No. of Proj.**			**1**		**Total Amount**	**$2,400.00**
156579	REMOVE BRIDGE RAILING		LF	6	1	75.00	$125.00	$9,375.00
		Unit Sub Total	**LF**		**1**	**75.00**	**$125.00**	**$9,375.00**
	Item Code 156579	**Total No. of Proj.**			**1**		**Total Amount**	**$9,375.00**
156585	REMOVE CRASH CUSHION		EA	2	1	4.00	$2,200.00	$8,800.00
			EA	3	2	2.00	$832.50	$1,665.00
			EA	4	3	16.00	$439.38	$7,030.00
			EA	5	1	15.00	$150.00	$2,250.00
			EA	6	1	1.00	$800.00	$800.00
			EA	7	2	4.00	$416.63	$1,666.50
			EA	10	1	4.00	$500.00	$2,000.00
			EA	12	1	2.00	$180.00	$360.00
		Unit Sub Total	**EA**		**12**	**48.00**	**$511.91**	**$24,571.50**
	Item Code 156585	**Total No. of Proj.**			**12**		**Total Amount**	**$24,571.50**
156590	REMOVE CRASH CUSHION (SAND FILLED)		EA	1	1	2.00	$900.00	$1,800.00
			EA	3	1	5.00	$1,000.00	$5,000.00
			EA	4	3	7.00	$493.43	$3,454.00
			EA	5	2	29.00	$165.52	$4,800.00
			EA	7	1	4.00	$350.00	$1,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
156590	REMOVE CRASH CUSHION (SAND FILLED)	EA	8	3	35.00	$246.29	$8,620.00
		EA	10	1	2.00	$100.00	$200.00
		EA	12	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**EA**		**13**	**85.00**	**$309.11**	**$26,274.00**
	Item Code 156590 Total No. of Proj.			**13**		**Total Amount**	**$26,274.00**
157550	BRIDGE REMOVAL	LS	1	1	1.00	$360,000.00	$360,000.00
		LS	2	1	1.00	$50,000.00	$50,000.00
		LS	4	1	1.00	$97,000.00	$97,000.00
		LS	5	1	1.00	$18,000.00	$18,000.00
		LS	6	1	1.00	$70,000.00	$70,000.00
		LS	7	1	1.00	$190,000.00	$190,000.00
		LS	8	1	1.00	$350,000.00	$350,000.00
		LS	10	1	1.00	$212,000.00	$212,000.00
	Unit Sub Total	**LS**		**8**	**8.00**	**$168,375.00**	**$1,347,000.00**
	Item Code 157550 Total No. of Proj.			**8**		**Total Amount**	**$1,347,000.00**
157551	BRIDGE REMOVAL, LOCATION A	LS	2	1	1.00	$25,000.00	$25,000.00
		LS	4	1	1.00	$150,000.00	$150,000.00
		LS	7	1	1.00	$150,000.00	$150,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$108,333.33**	**$325,000.00**
	Item Code 157551 Total No. of Proj.			**3**		**Total Amount**	**$325,000.00**
157552	BRIDGE REMOVAL, LOCATION B	LS	4	1	1.00	$160,000.00	$160,000.00
		LS	7	1	1.00	$120,000.00	$120,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$140,000.00**	**$280,000.00**
	Item Code 157552 Total No. of Proj.			**2**		**Total Amount**	**$280,000.00**
157553	BRIDGE REMOVAL, LOCATION C	LS	4	1	1.00	$6,000.00	$6,000.00
		LS	7	1	1.00	$65,000.00	$65,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$35,500.00**	**$71,000.00**
	Item Code 157553 Total No. of Proj.			**2**		**Total Amount**	**$71,000.00**
157559	BRIDGE REMOVAL, LOCATION I	LS	6	1	1.00	$20,000.00	$20,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LS**		**1**	**1.00**	**$20,000.00**	**$20,000.00**
	Item Code 157559	**Total No. of Proj.**			**1**		**Total Amount**	**$20,000.00**
157560	BRIDGE REMOVAL (PORTION)		LS	2	4	4.00	$57,343.53	$229,374.10
			LS	3	6	6.00	$76,375.00	$458,250.00
			LS	4	7	7.00	$69,142.86	$484,000.00
			LS	5	2	2.00	$437,500.00	$875,000.00
			LS	6	2	2.00	$58,800.00	$117,600.00
			LS	7	7	7.00	$33,268.71	$232,880.98
			LS	8	1	1.00	$20,000.00	$20,000.00
			LS	11	1	1.00	$20,000.00	$20,000.00
			LS	12	2	2.00	$4,950.00	$9,900.00
		Unit Sub Total	**LS**		**32**	**32.00**	**$76,468.91**	**$2,447,005.08**
	Item Code 157560	**Total No. of Proj.**			**32**		**Total Amount**	**$2,447,005.08**
157561	BRIDGE REMOVAL (PORTION), LOCATION A		LS	2	2	2.00	$18,500.00	$37,000.00
			LS	3	5	5.00	$29,360.00	$146,800.00
			LS	4	7	7.00	$36,428.57	$255,000.00
			LS	5	1	1.00	$5,000.00	$5,000.00
			LS	6	4	4.00	$22,850.00	$91,400.00
			LS	7	5	5.00	$177,427.32	$887,136.58
			LS	8	3	3.00	$8,466.67	$25,400.00
			LS	10	3	3.00	$9,833.33	$29,500.00
			LS	11	2	2.00	$46,250.00	$92,500.00
			LS	12	4	4.00	$32,525.60	$130,102.40
		Unit Sub Total	**LS**		**36**	**36.00**	**$47,217.75**	**$1,699,838.98**
	Item Code 157561	**Total No. of Proj.**			**36**		**Total Amount**	**$1,699,838.98**
157562	BRIDGE REMOVAL (PORTION), LOCATION B		LS	2	3	3.00	$25,000.00	$75,000.00
			LS	3	4	4.00	$33,200.00	$132,800.00
			LS	4	7	7.00	$59,571.43	$417,000.00
			LS	5	1	1.00	$8,500.00	$8,500.00
			LS	6	4	4.00	$19,568.75	$78,275.00
			LS	7	5	5.00	$158,412.41	$792,062.06
			LS	8	3	3.00	$33,300.00	$99,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
157562	BRIDGE REMOVAL (PORTION), LOCATION B	LS	10	3	3.00	$120,000.00	$360,000.00
		LS	11	2	2.00	$30,250.00	$60,500.00
		LS	12	4	4.00	$26,366.40	$105,465.60
	Unit Sub Total	**LS**		**36**	**36.00**	**$59,152.85**	**$2,129,502.66**
	Item Code 157562 Total No. of Proj.			**36**		**Total Amount**	**$2,129,502.66**
157563	BRIDGE REMOVAL (PORTION), LOCATION C	LS	2	1	1.00	$35,000.00	$35,000.00
		LS	3	3	3.00	$26,666.67	$80,000.00
		LS	4	5	5.00	$39,800.00	$199,000.00
		LS	6	4	4.00	$11,093.75	$44,375.00
		LS	7	4	4.00	$364,335.00	$1,457,340.00
		LS	8	2	2.00	$33,200.00	$66,400.00
		LS	10	1	1.00	$20,000.00	$20,000.00
		LS	11	1	1.00	$17,600.00	$17,600.00
	Unit Sub Total	**LS**		**21**	**21.00**	**$91,415.00**	**$1,919,715.00**
	Item Code 157563 Total No. of Proj.			**21**		**Total Amount**	**$1,919,715.00**
157564	BRIDGE REMOVAL (PORTION), LOCATION D	LS	2	1	1.00	$100,000.00	$100,000.00
		LS	3	2	2.00	$14,000.00	$28,000.00
		LS	4	1	1.00	$80,000.00	$80,000.00
		LS	6	2	2.00	$18,500.00	$37,000.00
		LS	7	3	3.00	$2,345,780.00	$7,037,340.00
		LS	8	1	1.00	$7,800.00	$7,800.00
		LS	10	1	1.00	$20,000.00	$20,000.00
	Unit Sub Total	**LS**		**11**	**11.00**	**$664,558.18**	**$7,310,140.00**
	Item Code 157564 Total No. of Proj.			**11**		**Total Amount**	**$7,310,140.00**
157565	BRIDGE REMOVAL (PORTION), LOCATION E	LS	3	1	1.00	$60,000.00	$60,000.00
		LS	6	1	1.00	$20,000.00	$20,000.00
		LS	7	1	1.00	$250,000.00	$250,000.00
		LS	8	1	1.00	$6,400.00	$6,400.00
		LS	10	1	1.00	$60,000.00	$60,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$79,280.00**	**$396,400.00**
	Item Code 157565 Total No. of Proj.			**5**		**Total Amount**	**$396,400.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
157566	BRIDGE REMOVAL (PORTION), LOCATION F	LS	6	1	1.00	$20,000.00	$20,000.00
		LS	8	1	1.00	$7,400.00	$7,400.00
		LS	10	1	1.00	$40,000.00	$40,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$22,466.67**	**$67,400.00**
	Item Code 157566 Total No. of Proj.			**3**		**Total Amount**	**$67,400.00**
157567	BRIDGE REMOVAL (PORTION), LOCATION G	LS	6	1	1.00	$20,000.00	$20,000.00
		LS	8	1	1.00	$5,200.00	$5,200.00
		LS	10	1	1.00	$18,000.00	$18,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$14,400.00**	**$43,200.00**
	Item Code 157567 Total No. of Proj.			**3**		**Total Amount**	**$43,200.00**
157568	BRIDGE REMOVAL (PORTION), LOCATION H	LS	6	1	1.00	$20,000.00	$20,000.00
		LS	8	1	1.00	$16,400.00	$16,400.00
		LS	10	1	1.00	$45,000.00	$45,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$27,133.33**	**$81,400.00**
	Item Code 157568 Total No. of Proj.			**3**		**Total Amount**	**$81,400.00**
157569	BRIDGE REMOVAL (PORTION), LOCATION I	LS	8	1	1.00	$7,500.00	$7,500.00
		LS	10	1	1.00	$35,000.00	$35,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$21,250.00**	**$42,500.00**
	Item Code 157569 Total No. of Proj.			**2**		**Total Amount**	**$42,500.00**
157570	BRIDGE REMOVAL (PORTION), LOCATION J	LS	6	1	1.00	$20,000.00	$20,000.00
		LS	8	1	1.00	$3,800.00	$3,800.00
		LS	10	1	1.00	$20,000.00	$20,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$14,600.00**	**$43,800.00**
	Item Code 157570 Total No. of Proj.			**3**		**Total Amount**	**$43,800.00**
157571	BRIDGE REMOVAL (PORTION), LOCATION K	LS	6	1	1.00	$20,000.00	$20,000.00
		LS	10	1	1.00	$12,000.00	$12,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$16,000.00**	**$32,000.00**
	Item Code 157571 Total No. of Proj.			**2**		**Total Amount**	**$32,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
157573	BRIDGE REMOVAL (PORTION), LOCATION M	LS	6	1	1.00	$20,000.00	$20,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$20,000.00**	**$20,000.00**
	Item Code 157573 Total No. of Proj.			**1**		**Total Amount**	**$20,000.00**
158100	SALVAGE CRASH CUSHION	EA	4	1	1.00	$300.00	$300.00
		EA	6	1	1.00	$1,500.00	$1,500.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$900.00**	**$1,800.00**
	Item Code 158100 Total No. of Proj.			**2**		**Total Amount**	**$1,800.00**
158210	RESET TEMPORARY RAILING (TYPE K)	LF	1	1	1,100.00	$11.00	$12,100.00
		LF	2	1	1,040.00	$6.75	$7,020.00
	Unit Sub Total	**LF**		**2**	**2,140.00**	**$8.93**	**$19,120.00**
	Item Code 158210 Total No. of Proj.			**2**		**Total Amount**	**$19,120.00**
158505	SALVAGE TERMINAL SECTION	EA	6	1	4.00	$460.00	$1,840.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$460.00**	**$1,840.00**
	Item Code 158505 Total No. of Proj.			**1**		**Total Amount**	**$1,840.00**
159010	RECONSTRUCT METAL RAILING (BRIDGE)	LF	12	1	62.00	$160.00	$9,920.00
	Unit Sub Total	**LF**		**1**	**62.00**	**$160.00**	**$9,920.00**
	Item Code 159010 Total No. of Proj.			**1**		**Total Amount**	**$9,920.00**
160101	CLEARING AND GRUBBING	ACRE	1	1	3.30	$13,500.00	$44,550.00
		ACRE	2	1	24.00	$10,000.00	$240,000.00
	Unit Sub Total	**ACRE**		**2**	**27.30**	**$10,423.08**	**$284,550.00**
160101	CLEARING AND GRUBBING	HA	5	1	70.00	$5,000.00	$350,000.00
	Unit Sub Total	**HA**		**1**	**70.00**	**$5,000.00**	**$350,000.00**
160101	CLEARING AND GRUBBING	LS	1	14	14.00	$13,142.86	$184,000.00
		LS	2	16	16.00	$12,710.25	$203,364.00
		LS	3	17	17.00	$34,337.61	$583,739.39
		LS	4	31	31.00	$49,402.46	$1,531,476.11
		LS	5	9	9.00	$24,248.89	$218,240.00
		LS	6	13	13.00	$127,244.31	$1,654,176.00
		LS	7	19	19.00	$44,445.05	$844,456.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
160101	CLEARING AND GRUBBING	LS	8	10	10.00	$49,015.00	$490,150.00
		LS	9	2	2.00	$23,250.00	$46,500.00
		LS	10	9	9.00	$108,866.67	$979,800.00
		LS	11	11	11.00	$42,205.07	$464,255.80
		LS	12	13	13.00	$36,576.23	$475,491.00
	Unit Sub Total	**LS**		**164**	**164.00**	**$46,802.73**	**$7,675,648.30**
	Item Code 160101 Total No. of Proj.			**167**		**Total Amount**	**$8,310,198.30**
160120	REMOVE TREE	EA	3	1	97.00	$450.00	$43,650.00
	Unit Sub Total	**EA**		**1**	**97.00**	**$450.00**	**$43,650.00**
160120	REMOVE TREE	LS	3	1	1.00	$95,865.00	$95,865.00
		LS	4	1	1.00	$150,000.00	$150,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$122,932.50**	**$245,865.00**
	Item Code 160120 Total No. of Proj.			**3**		**Total Amount**	**$289,515.00**
170101	DEVELOP WATER SUPPLY	LS	2	13	13.00	$13,576.92	$176,500.00
		LS	3	4	4.00	$4,277.50	$17,110.00
		LS	4	9	9.00	$15,472.22	$139,250.00
		LS	5	2	2.00	$35,000.00	$70,000.00
		LS	6	1	1.00	$40,000.00	$40,000.00
		LS	7	2	2.00	$52,000.00	$104,000.00
		LS	8	6	6.00	$45,750.00	$274,500.00
		LS	10	1	1.00	$5,000.00	$5,000.00
		LS	11	4	4.00	$15,250.00	$61,000.00
		LS	12	2	2.00	$9,000.00	$18,000.00
	Unit Sub Total	**LS**		**44**	**44.00**	**$20,576.36**	**$905,360.00**
	Item Code 170101 Total No. of Proj.			**44**		**Total Amount**	**$905,360.00**
190101	ROADWAY EXCAVATION	CY	1	16	180,684.00	$11.41	$2,061,475.00
		CY	2	15	994,936.00	$8.00	$7,960,986.40
		CY	3	20	531,805.00	$11.92	$6,338,661.20
		CY	4	24	388,207.00	$12.30	$4,773,326.70
		CY	5	8	22,340.40	$28.71	$641,295.00
		CY	6	20	911,549.00	$8.82	$8,036,274.90
		CY	7	22	305,067.00	$21.91	$6,685,390.30

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
190101	ROADWAY EXCAVATION	CY	8	10	283,815.00	$9.85	$2,796,280.00
		CY	9	5	10,054.00	$22.90	$230,200.00
		CY	10	8	312,273.00	$12.63	$3,943,490.00
		CY	11	14	104,178.00	$13.24	$1,379,190.00
		CY	12	11	278,424.00	$9.38	$2,610,742.00
	Unit Sub Total	**CY**		**173**	**4,323,332.40**	**$10.98**	**$47,457,311.50**
190101	ROADWAY EXCAVATION	M3	4	1	9,800.00	$25.00	$245,000.00
		M3	5	1	1,030,000.00	$5.00	$5,150,000.00
		M3	7	5	170,670.00	$21.13	$3,605,620.00
		M3	8	1	49,800.00	$10.00	$498,000.00
		M3	10	2	53,300.00	$15.82	$843,000.00
		M3	11	2	177,300.00	$12.20	$2,163,150.00
	Unit Sub Total	**M3**		**12**	**1,490,870.00**	**$8.39**	**$12,504,770.00**
	Item Code 190101	**Total No. of Proj.**		**185**		**Total Amount**	**$59,962,081.50**
190105	ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	CY	4	6	42,540.00	$75.70	$3,220,180.00
		CY	5	1	930.00	$190.00	$176,700.00
		CY	7	3	3,467.00	$155.19	$538,045.13
		CY	12	1	40.00	$840.00	$33,600.00
	Unit Sub Total	**CY**		**11**	**46,977.00**	**$84.48**	**$3,968,525.13**
190105	ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	M3	4	1	70.00	$240.00	$16,800.00
		M3	7	2	1,415.00	$204.73	$289,695.00
	Unit Sub Total	**M3**		**3**	**1,485.00**	**$206.39**	**$306,495.00**
	Item Code 190105	**Total No. of Proj.**		**14**		**Total Amount**	**$4,275,020.13**
190107	ROADWAY EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	CY	3	3	5,270.00	$36.29	$191,241.00
		CY	4	3	13,520.00	$12.60	$170,400.00
		CY	7	1	11,000.00	$12.00	$132,000.00
		CY	10	1	4,810.00	$16.00	$76,960.00
		CY	12	3	18,517.00	$8.79	$162,850.00
	Unit Sub Total	**CY**		**11**	**53,117.00**	**$13.81**	**$733,451.00**
190107	ROADWAY EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	M3	4	1	210.00	$43.00	$9,030.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
190107	ROADWAY EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	M3	8	1	1,190.00	$8.00	$9,520.00
	Unit Sub Total	**M3**		**2**	**1,400.00**	**$13.25**	**$18,550.00**
	Item Code 190107 Total No. of Proj.			**13**		**Total Amount**	**$752,001.00**
190108	ROADWAY EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)	CY	3	1	140.00	$40.00	$5,600.00
	Unit Sub Total	**CY**		**1**	**140.00**	**$40.00**	**$5,600.00**
190108	ROADWAY EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)	M3	4	1	830.00	$37.00	$30,710.00
		M3	7	1	9,100.00	$11.00	$100,100.00
	Unit Sub Total	**M3**		**2**	**9,930.00**	**$13.17**	**$130,810.00**
	Item Code 190108 Total No. of Proj.			**3**		**Total Amount**	**$136,410.00**
190109	ROADWAY EXCAVATION (NATURALLY OCCURRING ASBESTOS)	CY	2	2	177.00	$122.03	$21,600.00
		CY	3	2	2,550.00	$80.59	$205,500.00
	Unit Sub Total	**CY**		**4**	**2,727.00**	**$83.28**	**$227,100.00**
	Item Code 190109 Total No. of Proj.			**4**		**Total Amount**	**$227,100.00**
190110	LEAD COMPLIANCE PLAN	EA	11	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,000.00**	**$1,000.00**
190110	LEAD COMPLIANCE PLAN	LS	1	36	36.00	$2,428.25	$87,417.00
		LS	2	39	39.00	$2,193.15	$85,532.80
		LS	3	68	68.00	$2,049.95	$139,396.43
		LS	4	59	59.00	$2,401.98	$141,717.00
		LS	5	32	32.00	$1,880.81	$60,186.00
		LS	6	42	42.00	$1,934.00	$81,228.00
		LS	7	69	69.00	$3,082.35	$212,682.31
		LS	8	46	46.00	$2,455.72	$112,963.00
		LS	9	9	9.00	$1,165.56	$10,490.00
		LS	10	33	33.00	$3,083.64	$101,760.00
		LS	11	29	29.00	$3,309.12	$95,964.60
		LS	12	26	26.00	$2,116.00	$55,016.00
	Unit Sub Total	**LS**		**488**	**488.00**	**$2,426.95**	**$1,184,353.14**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 190110 Total No. of Proj.			**489**		**Total Amount**	**$1,185,353.14**
190111	ADL BURIAL LOCATION REPORT	LS	3	3	3.00	$3,816.67	$11,450.00
		LS	4	4	4.00	$2,525.00	$10,100.00
		LS	7	2	2.00	$5,250.00	$10,500.00
		LS	10	1	1.00	$20,000.00	$20,000.00
		LS	12	2	2.00	$6,800.00	$13,600.00
	Unit Sub Total	**LS**		**12**	**12.00**	**$5,470.83**	**$65,650.00**
	Item Code 190111 Total No. of Proj.			**12**		**Total Amount**	**$65,650.00**
190113	ASBESTOS COMPLIANCE PLAN	LS	1	3	3.00	$3,583.33	$10,750.00
		LS	2	1	1.00	$3,000.00	$3,000.00
		LS	3	2	2.00	$3,075.00	$6,150.00
		LS	4	1	1.00	$100.00	$100.00
		LS	6	2	2.00	$3,000.00	$6,000.00
		LS	8	1	1.00	$1,500.00	$1,500.00
		LS	10	1	1.00	$2,000.00	$2,000.00
	Unit Sub Total	**LS**		**11**	**11.00**	**$2,681.82**	**$29,500.00**
	Item Code 190113 Total No. of Proj.			**11**		**Total Amount**	**$29,500.00**
190114	DUST CONTROL PLAN	LS	1	3	3.00	$1,533.33	$4,600.00
		LS	10	1	1.00	$380.00	$380.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$1,245.00**	**$4,980.00**
	Item Code 190114 Total No. of Proj.			**4**		**Total Amount**	**$4,980.00**
190115	ASBESTOS COMPLIANCE PLAN (NATURALLY OCCURING ASBESTOS)	LS	1	2	2.00	$1,505.00	$3,010.00
		LS	2	2	2.00	$2,000.00	$4,000.00
		LS	3	6	6.00	$2,007.50	$12,045.00
		LS	10	2	2.00	$1,025.00	$2,050.00
	Unit Sub Total	**LS**		**12**	**12.00**	**$1,758.75**	**$21,105.00**
	Item Code 190115 Total No. of Proj.			**12**		**Total Amount**	**$21,105.00**
190116	DUST CONTROL PLAN (NATURALLY OCCURRING ASBESTOS)	LS	1	2	2.00	$1,400.00	$2,800.00
		LS	2	2	2.00	$2,000.00	$4,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
190116	DUST CONTROL PLAN (NATURALLY OCCURRING ASBESTOS)	LS	3	7	7.00	$1,336.43	$9,355.00
		LS	10	2	2.00	$975.00	$1,950.00
	Unit Sub Total	**LS**		**13**	**13.00**	**$1,392.69**	**$18,105.00**
	Item Code 190116 Total No. of Proj.			**13**		**Total Amount**	**$18,105.00**
190117	SAMPLING AND ANALYSIS PLAN (NATURALLY OCCURRING ASBESTOS)	LS	3	1	1.00	$1,580.00	$1,580.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$1,580.00**	**$1,580.00**
	Item Code 190117 Total No. of Proj.			**1**		**Total Amount**	**$1,580.00**
190138	ROADWAY EXCAVATION (DETOUR REMOVAL)	M3	8	1	1,270.00	$8.40	$10,668.00
	Unit Sub Total	**M3**		**1**	**1,270.00**	**$8.40**	**$10,668.00**
	Item Code 190138 Total No. of Proj.			**1**		**Total Amount**	**$10,668.00**
190160	ROCK EXCAVATION (CONTROLLED BLASTING)	CY	3	1	8.00	$1,580.00	$12,640.00
		CY	10	1	518,000.00	$8.75	$4,532,500.00
	Unit Sub Total	**CY**		**2**	**518,008.00**	**$8.77**	**$4,545,140.00**
	Item Code 190160 Total No. of Proj.			**2**		**Total Amount**	**$4,545,140.00**
190162	STRIPPING EXCAVATION	CY	1	1	230.00	$95.00	$21,850.00
	Unit Sub Total	**CY**		**1**	**230.00**	**$95.00**	**$21,850.00**
	Item Code 190162 Total No. of Proj.			**1**		**Total Amount**	**$21,850.00**
190185	SHOULDER BACKING	CY	1	1	42.00	$104.00	$4,368.00
	Unit Sub Total	**CY**		**1**	**42.00**	**$104.00**	**$4,368.00**
	Item Code 190185 Total No. of Proj.			**1**		**Total Amount**	**$4,368.00**
192001	STRUCTURE EXCAVATION	CY	4	1	770.00	$40.00	$30,800.00
		CY	8	2	948.00	$56.68	$53,736.00
	Unit Sub Total	**CY**		**3**	**1,718.00**	**$49.21**	**$84,536.00**
	Item Code 192001 Total No. of Proj.			**3**		**Total Amount**	**$84,536.00**
192003	STRUCTURE EXCAVATION (BRIDGE)	CF	3	1	768.00	$6.00	$4,608.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**CF**		**1**	**768.00**	**$6.00**	**$4,608.00**
192003	STRUCTURE EXCAVATION (BRIDGE)		CY	1	1	940.00	$90.00	$84,600.00
			CY	2	5	2,492.00	$142.42	$354,901.74
			CY	3	3	4,945.00	$100.39	$496,416.45
			CY	4	8	6,521.00	$61.49	$400,977.00
			CY	5	2	8,921.00	$28.29	$252,364.00
			CY	6	3	2,382.00	$25.84	$61,560.00
			CY	7	4	5,423.00	$46.90	$254,313.51
			CY	8	5	2,668.00	$80.16	$213,880.00
			CY	10	3	3,520.00	$44.95	$158,235.00
			CY	12	4	1,857.00	$79.54	$147,706.00
		Unit Sub Total	**CY**		**38**	**39,669.00**	**$61.13**	**$2,424,953.70**
192003	STRUCTURE EXCAVATION (BRIDGE)		M3	4	1	745.00	$100.00	$74,500.00
			M3	5	1	4,565.00	$50.00	$228,250.00
			M3	7	2	10,652.00	$36.90	$393,045.00
			M3	8	1	3,290.00	$120.00	$394,800.00
			M3	11	2	4,751.00	$40.76	$193,640.00
		Unit Sub Total	**M3**		**7**	**24,003.00**	**$53.50**	**$1,284,235.00**
	Item Code 192003	**Total No. of Proj.**			**46**		**Total Amount**	**$3,713,796.70**
192008	STRUCTURE EXCAVATION (TYPE A)		CY	3	1	1,070.00	$75.00	$80,250.00
			CY	4	1	350.00	$120.00	$42,000.00
			CY	7	1	7,175.00	$250.00	$1,793,750.00
		Unit Sub Total	**CY**		**3**	**8,595.00**	**$222.92**	**$1,916,000.00**
	Item Code 192008	**Total No. of Proj.**			**3**		**Total Amount**	**$1,916,000.00**
192020	STRUCTURE EXCAVATION (TYPE D)		CY	1	1	1,158.00	$255.00	$295,290.00
			CY	2	3	426.00	$648.98	$276,467.54
			CY	3	2	1,316.00	$273.27	$359,620.00
			CY	10	1	370.00	$50.00	$18,500.00
		Unit Sub Total	**CY**		**7**	**3,270.00**	**$290.48**	**$949,877.54**
192020	STRUCTURE EXCAVATION (TYPE D)		M3	7	1	57.00	$230.00	$13,110.00
			M3	8	1	3,332.00	$80.00	$266,560.00
		Unit Sub Total	**M3**		**2**	**3,389.00**	**$82.52**	**$279,670.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 192020 Total No. of Proj.			**9**		**Total Amount**	**$1,229,547.54**
192021	STRUCTURE EXCAVATION (TYPE DH)	CY	3	1	330.00	$100.00	$33,000.00
	Unit Sub Total	**CY**		**1**	**330.00**	**$100.00**	**$33,000.00**
	Item Code 192021 Total No. of Proj.			**1**		**Total Amount**	**$33,000.00**
192025	STRUCTURE EXCAVATION (CULVERT)	CY	7	1	2,720.00	$35.00	$95,200.00
	Unit Sub Total	**CY**		**1**	**2,720.00**	**$35.00**	**$95,200.00**
192025	STRUCTURE EXCAVATION (CULVERT)	M3	8	1	790.00	$16.00	$12,640.00
	Unit Sub Total	**M3**		**1**	**790.00**	**$16.00**	**$12,640.00**
	Item Code 192025 Total No. of Proj.			**2**		**Total Amount**	**$107,840.00**
192032	STRUCTURE EXCAVATION (ROCK SLOPE PROTECTION)	CY	7	1	280.00	$17.00	$4,760.00
	Unit Sub Total	**CY**		**1**	**280.00**	**$17.00**	**$4,760.00**
	Item Code 192032 Total No. of Proj.			**1**		**Total Amount**	**$4,760.00**
192036	STRUCTURE EXCAVATION (CRIB WALL)	CY	10	1	2,560.00	$15.00	$38,400.00
	Unit Sub Total	**CY**		**1**	**2,560.00**	**$15.00**	**$38,400.00**
192036	STRUCTURE EXCAVATION (CRIB WALL)	M3	11	1	205.00	$30.00	$6,150.00
	Unit Sub Total	**M3**		**1**	**205.00**	**$30.00**	**$6,150.00**
	Item Code 192036 Total No. of Proj.			**2**		**Total Amount**	**$44,550.00**
192037	STRUCTURE EXCAVATION (RETAINING WALL)	CY	1	1	23.00	$80.00	$1,840.00
		CY	2	1	298.00	$50.00	$14,900.00
		CY	3	2	591.00	$52.15	$30,820.00
		CY	4	7	24,625.00	$27.37	$673,949.00
		CY	6	4	1,980.00	$20.66	$40,910.00
		CY	7	2	4,652.00	$21.00	$97,670.00
		CY	8	1	5,617.00	$60.00	$337,020.00
		CY	10	2	57,290.00	$5.66	$324,250.00
		CY	11	2	778.00	$36.14	$28,120.00
		CY	12	4	13,782.00	$23.62	$325,548.00
	Unit Sub Total	**CY**		**26**	**109,636.00**	**$17.10**	**$1,875,027.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
192037	STRUCTURE EXCAVATION (RETAINING WALL)	M3	4	1	410.00	$45.00	$18,450.00
		M3	5	1	1,570.00	$50.00	$78,500.00
		M3	7	3	8,809.00	$24.73	$217,816.00
		M3	8	1	3,764.00	$60.00	$225,840.00
		M3	11	1	4,550.00	$40.00	$182,000.00
	Unit Sub Total	**M3**		**7**	**19,103.00**	**$37.83**	**$722,606.00**
	Item Code 192037 Total No. of Proj.			**33**		**Total Amount**	**$2,597,633.00**
192049	STRUCTURE EXCAVATION (SOLDIER PILE WALL)	CY	1	4	998.00	$80.59	$80,430.00
		CY	4	4	887.00	$41.47	$36,788.00
		CY	5	2	1,593.00	$107.94	$171,950.00
	Unit Sub Total	**CY**		**10**	**3,478.00**	**$83.14**	**$289,168.00**
192049	STRUCTURE EXCAVATION (SOLDIER PILE WALL)	M3	5	1	313.00	$60.00	$18,780.00
		M3	11	1	2,940.00	$13.00	$38,220.00
	Unit Sub Total	**M3**		**2**	**3,253.00**	**$17.52**	**$57,000.00**
	Item Code 192049 Total No. of Proj.			**12**		**Total Amount**	**$346,168.00**
192050	STRUCTURE EXCAVATION (TIEBACK WALL)	CY	3	2	349.00	$45.47	$15,870.00
		CY	8	1	468.00	$60.00	$28,080.00
		CY	12	2	1,090.00	$41.01	$44,700.00
	Unit Sub Total	**CY**		**5**	**1,907.00**	**$46.49**	**$88,650.00**
192050	STRUCTURE EXCAVATION (TIEBACK WALL)	M3	8	1	367.00	$80.00	$29,360.00
	Unit Sub Total	**M3**		**1**	**367.00**	**$80.00**	**$29,360.00**
	Item Code 192050 Total No. of Proj.			**6**		**Total Amount**	**$118,010.00**
192053	STRUCTURE EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	CY	4	1	371.00	$78.00	$28,938.00
		CY	7	2	864.00	$303.70	$262,400.00
	Unit Sub Total	**CY**		**3**	**1,235.00**	**$235.90**	**$291,338.00**
192053	STRUCTURE EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	M3	7	2	1,703.00	$39.45	$67,185.00
	Unit Sub Total	**M3**		**2**	**1,703.00**	**$39.45**	**$67,185.00**
	Item Code 192053 Total No. of Proj.			**5**		**Total Amount**	**$358,523.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
192055	STRUCTURE EXCAVATION (SOIL NAIL WALL)	CY	2	1	242.00	$57.50	$13,915.00
		CY	4	2	1,335.00	$31.19	$41,640.00
	Unit Sub Total	**CY**		**3**	**1,577.00**	**$35.23**	**$55,555.00**
192055	STRUCTURE EXCAVATION (SOIL NAIL WALL)	M3	5	1	475.00	$120.00	$57,000.00
	Unit Sub Total	**M3**		**1**	**475.00**	**$120.00**	**$57,000.00**
	Item Code 192055 Total No. of Proj.			**4**		**Total Amount**	**$112,555.00**
192057	STRUCTURE EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	CY	7	2	7,204.00	$11.49	$82,805.60
		CY	12	1	155.00	$8.50	$1,317.50
	Unit Sub Total	**CY**		**3**	**7,359.00**	**$11.43**	**$84,123.10**
	Item Code 192057 Total No. of Proj.			**3**		**Total Amount**	**$84,123.10**
192502	SAND BEDDING	CY	6	1	1.00	$750.00	$750.00
		CY	7	1	150.00	$50.00	$7,500.00
	Unit Sub Total	**CY**		**2**	**151.00**	**$54.64**	**$8,250.00**
192502	SAND BEDDING	M3	4	1	3.00	$50.00	$150.00
		M3	5	1	37.00	$250.00	$9,250.00
	Unit Sub Total	**M3**		**2**	**40.00**	**$235.00**	**$9,400.00**
	Item Code 192502 Total No. of Proj.			**4**		**Total Amount**	**$17,650.00**
193001	STRUCTURE BACKFILL	CY	4	1	400.00	$60.00	$24,000.00
		CY	6	1	290.00	$115.00	$33,350.00
	Unit Sub Total	**CY**		**2**	**690.00**	**$83.12**	**$57,350.00**
	Item Code 193001 Total No. of Proj.			**2**		**Total Amount**	**$57,350.00**
193003	STRUCTURE BACKFILL (BRIDGE)	CF	3	1	752.00	$6.00	$4,512.00
	Unit Sub Total	**CF**		**1**	**752.00**	**$6.00**	**$4,512.00**
193003	STRUCTURE BACKFILL (BRIDGE)	CY	1	1	700.00	$80.00	$56,000.00
		CY	2	5	1,983.00	$129.06	$255,919.00
		CY	3	3	4,543.00	$44.70	$203,050.00
		CY	4	9	5,114.00	$70.76	$361,875.00
		CY	5	1	4,627.00	$25.00	$115,675.00
		CY	6	3	1,905.00	$50.14	$95,520.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
193003	STRUCTURE BACKFILL (BRIDGE)	CY	7	5	9,590.00	$37.29	$357,599.96
		CY	8	5	1,297.00	$70.81	$91,841.00
		CY	10	3	2,026.00	$75.45	$152,865.00
		CY	12	6	1,624.00	$112.85	$183,264.00
	Unit Sub Total	**CY**		**41**	**33,409.00**	**$56.08**	**$1,873,608.96**
193003	STRUCTURE BACKFILL (BRIDGE)	M3	4	1	670.00	$50.00	$33,500.00
		M3	5	1	2,800.00	$60.00	$168,000.00
		M3	7	2	7,055.00	$78.39	$553,050.00
		M3	8	1	5,115.00	$60.00	$306,900.00
		M3	11	2	4,315.00	$25.46	$109,860.00
	Unit Sub Total	**M3**		**7**	**19,955.00**	**$58.70**	**$1,171,310.00**
	Item Code 193003 Total No. of Proj.			**49**		**Total Amount**	**$3,049,430.96**
193004	STRUCTURE BACKFILL (CULVERT)	CY	7	1	2,150.00	$47.00	$101,050.00
	Unit Sub Total	**CY**		**1**	**2,150.00**	**$47.00**	**$101,050.00**
193004	STRUCTURE BACKFILL (CULVERT)	M3	8	1	350.00	$40.00	$14,000.00
	Unit Sub Total	**M3**		**1**	**350.00**	**$40.00**	**$14,000.00**
	Item Code 193004 Total No. of Proj.			**2**		**Total Amount**	**$115,050.00**
193006	STRUCTURE BACKFILL (SLURRY CEMENT)	CY	1	1	10.00	$200.00	$2,000.00
		CY	4	3	1,941.00	$106.92	$207,525.00
		CY	6	2	23.50	$875.74	$20,580.00
		CY	7	1	228.00	$100.00	$22,800.00
		CY	8	2	26.00	$143.08	$3,720.00
		CY	9	1	35.00	$144.00	$5,040.00
		CY	11	2	178.00	$168.11	$29,923.32
	Unit Sub Total	**CY**		**12**	**2,441.50**	**$119.43**	**$291,588.32**
	Item Code 193006 Total No. of Proj.			**12**		**Total Amount**	**$291,588.32**
193012	STRUCTURE BACKFILL (CRIB WALL)	CY	10	1	2,550.00	$20.00	$51,000.00
	Unit Sub Total	**CY**		**1**	**2,550.00**	**$20.00**	**$51,000.00**
193012	STRUCTURE BACKFILL (CRIB WALL)	M3	11	1	190.00	$30.00	$5,700.00
	Unit Sub Total	**M3**		**1**	**190.00**	**$30.00**	**$5,700.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 193012 Total No. of Proj.			**2**		**Total Amount**	**$56,700.00**
193013	STRUCTURE BACKFILL (RETAINING WALL)	CY	1	1	15.00	$185.00	$2,775.00
		CY	2	1	97.00	$100.00	$9,700.00
		CY	3	2	486.00	$39.94	$19,410.00
		CY	4	8	22,457.00	$35.01	$786,178.00
		CY	6	4	1,360.00	$69.40	$94,380.00
		CY	7	3	22,085.00	$23.00	$507,934.30
		CY	8	2	6,106.00	$25.45	$155,380.00
		CY	10	2	38,205.00	$10.36	$395,625.00
		CY	11	2	659.00	$25.89	$17,064.30
		CY	12	4	13,959.00	$30.58	$426,910.00
	Unit Sub Total	**CY**		**29**	**105,429.00**	**$22.91**	**$2,415,356.60**
193013	STRUCTURE BACKFILL (RETAINING WALL)	M3	4	1	257.00	$70.00	$17,990.00
		M3	5	1	1,303.00	$65.00	$84,695.00
		M3	7	2	10,503.00	$59.51	$625,045.00
		M3	8	1	3,914.00	$50.00	$195,700.00
		M3	11	1	5,465.00	$36.00	$196,740.00
	Unit Sub Total	**M3**		**6**	**21,442.00**	**$52.24**	**$1,120,170.00**
	Item Code 193013 Total No. of Proj.			**35**		**Total Amount**	**$3,535,526.60**
193014	STRUCTURE BACKFILL (SOUND WALL)	M3	7	1	95.00	$80.00	$7,600.00
	Unit Sub Total	**M3**		**1**	**95.00**	**$80.00**	**$7,600.00**
	Item Code 193014 Total No. of Proj.			**1**		**Total Amount**	**$7,600.00**
193020	STRUCTURE BACKFILL, RETAINING WALL (SOUND WALL)	M3	7	1	956.00	$80.00	$76,480.00
	Unit Sub Total	**M3**		**1**	**956.00**	**$80.00**	**$76,480.00**
	Item Code 193020 Total No. of Proj.			**1**		**Total Amount**	**$76,480.00**
193026	STRUCTURE BACKFILL (TIEBACK WALL)	CY	3	2	85.00	$91.47	$7,775.00
		CY	8	1	88.00	$25.00	$2,200.00
		CY	12	1	33.00	$60.00	$1,980.00
	Unit Sub Total	**CY**		**4**	**206.00**	**$58.03**	**$11,955.00**
193026	STRUCTURE BACKFILL (TIEBACK WALL)	M3	8	1	39.00	$150.00	$5,850.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**1**	**39.00**	**$150.00**	**$5,850.00**
	Item Code 193026	**Total No. of Proj.**			**5**		**Total Amount**	**$17,805.00**
193028	STRUCTURE BACKFILL (SOIL NAIL WALL)		CY	2	1	20.00	$120.00	$2,400.00
			CY	4	2	390.00	$15.74	$6,140.00
		Unit Sub Total	**CY**		**3**	**410.00**	**$20.83**	**$8,540.00**
193028	STRUCTURE BACKFILL (SOIL NAIL WALL)		M3	5	1	23.00	$300.00	$6,900.00
		Unit Sub Total	**M3**		**1**	**23.00**	**$300.00**	**$6,900.00**
	Item Code 193028	**Total No. of Proj.**			**4**		**Total Amount**	**$15,440.00**
193029	STRUCTURE BACKFILL (SOLDIER PILE WALL)		CY	1	4	582.00	$118.05	$68,705.00
			CY	4	4	461.00	$100.78	$46,460.00
			CY	5	2	715.00	$105.31	$75,300.00
		Unit Sub Total	**CY**		**10**	**1,758.00**	**$108.34**	**$190,465.00**
193029	STRUCTURE BACKFILL (SOLDIER PILE WALL)		M3	5	1	43.00	$320.00	$13,760.00
			M3	11	1	270.00	$24.00	$6,480.00
		Unit Sub Total	**M3**		**2**	**313.00**	**$64.66**	**$20,240.00**
	Item Code 193029	**Total No. of Proj.**			**12**		**Total Amount**	**$210,705.00**
193030	PERVIOUS BACKFILL MATERIAL		CY	4	1	46.00	$170.00	$7,820.00
			CY	6	1	280.00	$110.00	$30,800.00
		Unit Sub Total	**CY**		**2**	**326.00**	**$118.47**	**$38,620.00**
193030	PERVIOUS BACKFILL MATERIAL		M3	7	1	117.00	$55.00	$6,435.00
		Unit Sub Total	**M3**		**1**	**117.00**	**$55.00**	**$6,435.00**
	Item Code 193030	**Total No. of Proj.**			**3**		**Total Amount**	**$45,055.00**
193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)		CY	4	4	1,284.00	$63.65	$81,722.00
			CY	6	1	9.00	$300.00	$2,700.00
			CY	10	1	2,760.00	$25.00	$69,000.00
			CY	11	2	89.00	$167.64	$14,920.00
			CY	12	2	151.00	$51.52	$7,780.00
		Unit Sub Total	**CY**		**10**	**4,293.00**	**$41.03**	**$176,122.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	M3	7	1	10.00	$200.00	$2,000.00
		M3	8	1	308.00	$80.00	$24,640.00
		M3	11	1	404.00	$20.00	$8,080.00
	Unit Sub Total	**M3**		**3**	**722.00**	**$48.09**	**$34,720.00**
	Item Code 193031 Total No. of Proj.			**13**		**Total Amount**	**$210,842.00**
193114	SAND BACKFILL	CY	1	4	188.00	$128.40	$24,140.00
		CY	2	3	173.00	$253.01	$43,770.00
		CY	3	2	120.00	$100.00	$12,000.00
		CY	4	8	1,387.00	$116.05	$160,960.92
		CY	6	2	55.00	$73.82	$4,060.00
		CY	7	1	110.00	$75.00	$8,250.00
		CY	10	2	350.00	$174.29	$61,000.00
		CY	12	1	12.00	$100.00	$1,200.00
	Unit Sub Total	**CY**		**23**	**2,395.00**	**$131.68**	**$315,380.92**
193114	SAND BACKFILL	M3	4	1	10.00	$200.00	$2,000.00
		M3	5	1	150.00	$230.00	$34,500.00
		M3	7	2	37.00	$101.76	$3,765.00
		M3	8	1	170.00	$60.00	$10,200.00
		M3	10	1	3.00	$400.00	$1,200.00
		M3	11	1	110.00	$20.00	$2,200.00
	Unit Sub Total	**M3**		**7**	**480.00**	**$112.22**	**$53,865.00**
	Item Code 193114 Total No. of Proj.			**30**		**Total Amount**	**$369,245.92**
193116	CONCRETE BACKFILL (SOLDIER PILE WALL)	CY	1	3	167.00	$613.77	$102,500.00
		CY	4	4	1,023.00	$262.29	$268,320.00
		CY	5	1	655.00	$205.00	$134,275.00
	Unit Sub Total	**CY**		**8**	**1,845.00**	**$273.76**	**$505,095.00**
	Item Code 193116 Total No. of Proj.			**8**		**Total Amount**	**$505,095.00**
193117	CONCRETE BACKFILL FAST SETTING	CY	4	2	75.00	$244.45	$18,333.90
	Unit Sub Total	**CY**		**2**	**75.00**	**$244.45**	**$18,333.90**
	Item Code 193117 Total No. of Proj.			**2**		**Total Amount**	**$18,333.90**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
193118	CONCRETE BACKFILL		CY	2	1	14.00	$200.00	$2,800.00
			CY	4	1	49.00	$100.00	$4,900.00
		Unit Sub Total	**CY**		**2**	**63.00**	**$122.22**	**$7,700.00**
193118	CONCRETE BACKFILL		M3	4	1	130.00	$150.00	$19,500.00
		Unit Sub Total	**M3**		**1**	**130.00**	**$150.00**	**$19,500.00**
	Item Code 193118	**Total No. of Proj.**			**3**		**Total Amount**	**$27,200.00**
193119	LEAN CONCRETE BACKFILL		CY	1	4	157.00	$375.48	$58,950.00
			CY	4	3	154.00	$156.04	$24,030.00
			CY	5	2	897.00	$144.48	$129,600.00
			CY	12	1	98.00	$100.00	$9,800.00
		Unit Sub Total	**CY**		**10**	**1,306.00**	**$170.28**	**$222,380.00**
193119	LEAN CONCRETE BACKFILL		M3	5	1	65.00	$200.00	$13,000.00
			M3	7	1	95.00	$200.00	$19,000.00
		Unit Sub Total	**M3**		**2**	**160.00**	**$200.00**	**$32,000.00**
	Item Code 193119	**Total No. of Proj.**			**12**		**Total Amount**	**$254,380.00**
194001	DITCH EXCAVATION		CY	1	4	732.00	$40.88	$29,924.00
			CY	2	6	1,574.00	$29.57	$46,540.00
			CY	3	1	5.00	$380.00	$1,900.00
			CY	4	15	11,332.00	$25.28	$286,515.50
			CY	5	1	170.00	$30.00	$5,100.00
			CY	6	1	16,800.00	$15.00	$252,000.00
			CY	7	4	560.00	$35.04	$19,625.00
			CY	8	1	43.00	$95.00	$4,085.00
			CY	10	2	8,530.00	$10.04	$85,640.00
			CY	11	1	880.00	$30.00	$26,400.00
			CY	12	3	11,760.00	$4.16	$48,940.00
		Unit Sub Total	**CY**		**39**	**52,386.00**	**$15.40**	**$806,669.50**
194001	DITCH EXCAVATION		LF	3	1	24.00	$100.00	$2,400.00
		Unit Sub Total	**LF**		**1**	**24.00**	**$100.00**	**$2,400.00**
194001	DITCH EXCAVATION		M3	5	1	37.00	$50.00	$1,850.00
			M3	7	1	370.00	$28.00	$10,360.00
			M3	8	1	3,460.00	$13.00	$44,980.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
194001	DITCH EXCAVATION	M3	10	1	1,350.00	$11.00	$14,850.00
		M3	11	2	1,080.00	$26.17	$28,260.00
	Unit Sub Total	**M3**		**6**	**6,297.00**	**$15.93**	**$100,300.00**
	Item Code 194001 Total No. of Proj.			**46**		**Total Amount**	**$909,369.50**
197003	CONTOUR GRADING	CY	8	1	150.00	$100.00	$15,000.00
	Unit Sub Total	**CY**		**1**	**150.00**	**$100.00**	**$15,000.00**
197003	CONTOUR GRADING	SQYD	3	1	360.00	$11.00	$3,960.00
	Unit Sub Total	**SQYD**		**1**	**360.00**	**$11.00**	**$3,960.00**
	Item Code 197003 Total No. of Proj.			**2**		**Total Amount**	**$18,960.00**
197010	PLACE AND COMPACT EMBANKMENT	M3	8	1	36,600.00	$5.00	$183,000.00
	Unit Sub Total	**M3**		**1**	**36,600.00**	**$5.00**	**$183,000.00**
	Item Code 197010 Total No. of Proj.			**1**		**Total Amount**	**$183,000.00**
197020	EARTH RETAINING STRUCTURE	M2	4	1	1,350.00	$350.00	$472,500.00
		M2	5	1	1,520.00	$400.00	$608,000.00
	Unit Sub Total	**M2**		**2**	**2,870.00**	**$376.48**	**$1,080,500.00**
197020	EARTH RETAINING STRUCTURE	SQFT	3	1	23,560.00	$45.00	$1,060,200.00
	Unit Sub Total	**SQFT**		**1**	**23,560.00**	**$45.00**	**$1,060,200.00**
	Item Code 197020 Total No. of Proj.			**3**		**Total Amount**	**$2,140,700.00**
197021	EARTH RETAINING STRUCTURE, LOCATION A	SQFT	7	2	3,685.00	$49.41	$182,090.00
	Unit Sub Total	**SQFT**		**2**	**3,685.00**	**$49.41**	**$182,090.00**
	Item Code 197021 Total No. of Proj.			**2**		**Total Amount**	**$182,090.00**
197022	EARTH RETAINING STRUCTURE, LOCATION B	SQFT	7	2	6,071.00	$37.71	$228,949.00
	Unit Sub Total	**SQFT**		**2**	**6,071.00**	**$37.71**	**$228,949.00**
	Item Code 197022 Total No. of Proj.			**2**		**Total Amount**	**$228,949.00**
197023	EARTH RETAINING STRUCTURE, LOCATION C	SQFT	7	2	11,790.00	$35.98	$424,250.00
	Unit Sub Total	**SQFT**		**2**	**11,790.00**	**$35.98**	**$424,250.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 197023 Total No. of Proj.			**2**		**Total Amount**	**$424,250.00**
197024	EARTH RETAINING STRUCTURE, LOCATION D	SQFT	7	2	10,890.00	$36.76	$400,320.00
	Unit Sub Total	**SQFT**		**2**	**10,890.00**	**$36.76**	**$400,320.00**
	Item Code 197024 Total No. of Proj.			**2**		**Total Amount**	**$400,320.00**
197025	EARTH RETAINING STRUCTURE, LOCATION E	SQFT	7	1	6,050.00	$46.00	$278,300.00
	Unit Sub Total	**SQFT**		**1**	**6,050.00**	**$46.00**	**$278,300.00**
	Item Code 197025 Total No. of Proj.			**1**		**Total Amount**	**$278,300.00**
197030	EARTH RETAINING STRUCTURE (GUARD RAILING)	SQFT	1	1	63.00	$85.00	$5,355.00
		SQFT	2	1	100.00	$41.00	$4,100.00
	Unit Sub Total	**SQFT**		**2**	**163.00**	**$58.01**	**$9,455.00**
	Item Code 197030 Total No. of Proj.			**2**		**Total Amount**	**$9,455.00**
197060	SOIL NAIL ASSEMBLY	LF	2	1	2,898.00	$56.00	$162,288.00
		LF	4	3	16,359.00	$28.67	$468,996.00
	Unit Sub Total	**LF**		**4**	**19,257.00**	**$32.78**	**$631,284.00**
197060	SOIL NAIL ASSEMBLY	M	5	1	5,380.00	$54.00	$290,520.00
	Unit Sub Total	**M**		**1**	**5,380.00**	**$54.00**	**$290,520.00**
	Item Code 197060 Total No. of Proj.			**5**		**Total Amount**	**$921,804.00**
198001	IMPORTED BORROW (CY)	CY	1	2	5,200.00	$33.04	$171,800.00
	IMPORTED BORROW	CY	1	1	1,820.00	$40.00	$72,800.00
		CY	2	1	25.00	$72.00	$1,800.00
	IMPORTED BORROW (CY)	CY	2	2	18,960.00	$20.97	$397,600.00
	IMPORTED BORROW	CY	3	3	9,829.00	$25.37	$249,340.00
	IMPORTED BORROW (CY)	CY	3	1	9,910.00	$7.85	$77,793.50
		CY	4	3	3,260.00	$5.60	$18,260.00
	IMPORTED BORROW	CY	4	1	2,000.00	$25.00	$50,000.00
	IMPORTED BORROW (CY)	CY	5	1	1,750.00	$28.00	$49,000.00
	IMPORTED BORROW	CY	5	1	18.00	$90.00	$1,620.00
		CY	6	3	291,460.00	$15.63	$4,554,860.00
	IMPORTED BORROW (CY)	CY	6	1	22,800.00	$0.01	$228.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
198001	IMPORTED BORROW (CY)	CY	7	5	251,329.00	$1.09	$273,050.00
	IMPORTED BORROW	CY	7	2	994.00	$71.83	$71,400.00
		CY	8	5	116,710.00	$5.94	$693,610.00
	IMPORTED BORROW (CY)	CY	8	1	380.00	$95.00	$36,100.00
	IMPORTED BORROW	CY	9	2	333.00	$8.59	$2,860.00
	IMPORTED BORROW (CY)	CY	9	2	1,290.00	$12.23	$15,780.00
		CY	10	1	4,680.00	$1.00	$4,680.00
	IMPORTED BORROW	CY	11	1	1,240.00	$28.00	$34,720.00
	IMPORTED BORROW (CY)	CY	12	2	107,800.00	$2.83	$305,030.00
	Unit Sub Total	**CY**		**41**	**851,788.00**	**$8.31**	**$7,082,331.50**
198001	IMPORTED BORROW	M3	5	1	334,000.00	$9.00	$3,006,000.00
	IMPORTED BORROW (CY)	M3	7	1	10,100.00	$6.00	$60,600.00
	IMPORTED BORROW	M3	8	1	43,200.00	$6.00	$259,200.00
	IMPORTED BORROW (CY)	M3	10	1	2,260.00	$20.00	$45,200.00
	Unit Sub Total	**M3**		**4**	**389,560.00**	**$8.65**	**$3,371,000.00**
198001	IMPORTED BORROW (CY)	TON	11	1	160.00	$45.00	$7,200.00
	Unit Sub Total	**TON**		**1**	**160.00**	**$45.00**	**$7,200.00**
	Item Code 198001 Total No. of Proj.			**46**		**Total Amount**	**$10,460,531.50**
198007	IMPORTED MATERIAL (SHOULDER BACKING)	CY	1	1	18.00	$200.00	$3,600.00
		CY	3	2	14,760.00	$38.21	$564,000.00
		CY	10	1	130.00	$75.00	$9,750.00
	Unit Sub Total	**CY**		**4**	**14,908.00**	**$38.73**	**$577,350.00**
198007	IMPORTED MATERIAL (SHOULDER BACKING)	STA	9	1	1,040.00	$1.00	$1,040.00
	Unit Sub Total	**STA**		**1**	**1,040.00**	**$1.00**	**$1,040.00**
198007	IMPORTED MATERIAL (SHOULDER BACKING)	TON	1	11	38,366.00	$22.39	$859,116.00
		TON	2	24	140,548.00	$19.77	$2,779,220.00
		TON	3	23	100,880.00	$14.39	$1,451,765.00
		TON	4	18	9,627.00	$43.36	$417,464.00
		TON	5	14	15,757.00	$33.34	$525,292.90
		TON	6	15	68,740.00	$20.39	$1,401,770.00
		TON	7	2	2,130.00	$34.11	$72,660.00
		TON	8	3	6,450.00	$20.34	$131,190.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
198007	IMPORTED MATERIAL (SHOULDER BACKING)	TON	9	7	11,520.00	$30.84	$355,330.00
		TON	10	17	43,340.00	$26.33	$1,141,064.10
		TON	11	1	2,860.00	$37.00	$105,820.00
		TON	12	1	4,370.00	$4.00	$17,480.00
	Unit Sub Total	**TON**		**136**	**444,588.00**	**$20.82**	**$9,258,172.00**
198007	IMPORTED MATERIAL (SHOULDER BACKING)	TONN	7	2	9,770.00	$9.18	$89,730.00
		TONN	10	1	41.00	$49.00	$2,009.00
	Unit Sub Total	**TONN**		**3**	**9,811.00**	**$9.35**	**$91,739.00**
	Item Code 198007 **Total No. of Proj.**			**144**		**Total Amount**	**$9,928,301.00**
198009	IMPORTED BORROW (LIGHTWEIGHT AGGREGATE)	M3	4	1	1,220.00	$75.00	$91,500.00
	Unit Sub Total	**M3**		**1**	**1,220.00**	**$75.00**	**$91,500.00**
	Item Code 198009 **Total No. of Proj.**			**1**		**Total Amount**	**$91,500.00**
198021	IMPORTED ROCKY MATERIAL	CY	1	1	940.00	$155.00	$145,700.00
	Unit Sub Total	**CY**		**1**	**940.00**	**$155.00**	**$145,700.00**
	Item Code 198021 **Total No. of Proj.**			**1**		**Total Amount**	**$145,700.00**
198050	EMBANKMENT	CY	12	1	253.00	$10.00	$2,530.00
	Unit Sub Total	**CY**		**1**	**253.00**	**$10.00**	**$2,530.00**
	Item Code 198050 **Total No. of Proj.**			**1**		**Total Amount**	**$2,530.00**
198200	SUBGRADE ENHANCEMENT FABRIC	SQYD	3	1	348,000.00	$0.95	$330,600.00
		SQYD	7	1	27,600.00	$3.10	$85,560.00
	Unit Sub Total	**SQYD**		**2**	**375,600.00**	**$1.11**	**$416,160.00**
	Item Code 198200 **Total No. of Proj.**			**2**		**Total Amount**	**$416,160.00**
198205	SUBGRADE ENHANCEMENT GEOTEXTILE	SQFT	4	1	43,300.00	$0.15	$6,495.00
	Unit Sub Total	**SQFT**		**1**	**43,300.00**	**$0.15**	**$6,495.00**
198205	SUBGRADE ENHANCEMENT GEOTEXTILE	SQYD	2	2	162,300.00	$2.18	$353,450.00
		SQYD	4	3	113,570.00	$2.28	$258,500.00
		SQYD	10	1	342,000.00	$2.25	$769,500.00
	Unit Sub Total	**SQYD**		**6**	**617,870.00**	**$2.24**	**$1,381,450.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 198205	**Total No. of Proj.**			**7**		**Total Amount**	**$1,387,945.00**
198250	GEOSYNTHETIC REINFORCEMENT		SQYD	1	1	330.00	$20.00	$6,600.00
			SQYD	2	1	17,300.00	$2.25	$38,925.00
			SQYD	4	1	230.00	$4.00	$920.00
			SQYD	5	1	470.00	$6.00	$2,820.00
			SQYD	7	1	1,650.00	$7.00	$11,550.00
			SQYD	12	1	46,500.00	$4.90	$227,850.00
		Unit Sub Total	**SQYD**		**6**	**66,480.00**	**$4.34**	**$288,665.00**
	Item Code 198250	**Total No. of Proj.**			**6**		**Total Amount**	**$288,665.00**
200001	HIGHWAY PLANTING		LS	1	1	1.00	$9,500.00	$9,500.00
			LS	3	6	6.00	$65,251.33	$391,508.00
			LS	4	6	6.00	$145,570.00	$873,420.00
			LS	5	6	6.00	$29,054.50	$174,327.00
			LS	6	6	6.00	$88,233.33	$529,400.00
			LS	7	9	9.00	$72,211.11	$649,900.00
			LS	8	2	2.00	$14,500.00	$29,000.00
			LS	10	1	1.00	$50,000.00	$50,000.00
			LS	11	6	6.00	$77,633.33	$465,800.00
			LS	12	5	5.00	$29,396.48	$146,982.39
		Unit Sub Total	**LS**		**48**	**48.00**	**$69,163.28**	**$3,319,837.39**
	Item Code 200001	**Total No. of Proj.**			**48**		**Total Amount**	**$3,319,837.39**
200002	ROADSIDE CLEARING		EA	7	1	1.00	$2,090.00	$2,090.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$2,090.00**	**$2,090.00**
200002	ROADSIDE CLEARING		LS	1	1	1.00	$9,400.00	$9,400.00
			LS	2	1	1.00	$7,010.00	$7,010.00
			LS	3	3	3.00	$117,247.67	$351,743.00
			LS	4	8	8.00	$18,925.00	$151,400.00
			LS	5	3	3.00	$11,666.67	$35,000.00
			LS	6	1	1.00	$8,500.00	$8,500.00
			LS	7	2	2.00	$44,250.00	$88,500.00
			LS	8	7	7.00	$15,556.29	$108,894.00
			LS	10	1	1.00	$25,000.00	$25,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
200002	ROADSIDE CLEARING	LS	11	8	8.00	$33,347.00	$266,776.00
		LS	12	4	4.00	$14,475.00	$57,900.00
	Unit Sub Total	**LS**		**39**	**39.00**	**$28,464.69**	**$1,110,123.00**
	Item Code 200002 Total No. of Proj.			**40**		**Total Amount**	**$1,112,213.00**
200052	PRUNE EXISTING PLANTS	LS	6	1	1.00	$2,900.00	$2,900.00
		LS	7	1	1.00	$1,500.00	$1,500.00
		LS	8	2	2.00	$75,500.00	$151,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$38,850.00**	**$155,400.00**
	Item Code 200052 Total No. of Proj.			**4**		**Total Amount**	**$155,400.00**
200101	IMPORTED TOPSOIL	CY	1	4	2,813.00	$36.91	$103,840.00
		CY	3	1	27.00	$50.00	$1,350.00
		CY	4	5	968.00	$79.22	$76,689.50
		CY	5	1	200.00	$50.00	$10,000.00
		CY	7	1	200.00	$40.00	$8,000.00
		CY	11	2	780.00	$38.65	$30,150.00
	Unit Sub Total	**CY**		**14**	**4,988.00**	**$46.12**	**$230,029.50**
200101	IMPORTED TOPSOIL	M3	11	1	9,880.00	$5.00	$49,400.00
	Unit Sub Total	**M3**		**1**	**9,880.00**	**$5.00**	**$49,400.00**
	Item Code 200101 Total No. of Proj.			**15**		**Total Amount**	**$279,429.50**
200102	IMPORTED TOPSOIL (CY)	CY	4	1	760.00	$66.30	$50,388.00
	Unit Sub Total	**CY**		**1**	**760.00**	**$66.30**	**$50,388.00**
	Item Code 200102 Total No. of Proj.			**1**		**Total Amount**	**$50,388.00**
200108	PREPARE HOLE (SOIL AMENDMENT)	CF	8	1	44.00	$25.00	$1,100.00
	Unit Sub Total	**CF**		**1**	**44.00**	**$25.00**	**$1,100.00**
200108	PREPARE HOLE (SOIL AMENDMENT)	EA	7	1	2,250.00	$0.50	$1,125.00
	Unit Sub Total	**EA**		**1**	**2,250.00**	**$0.50**	**$1,125.00**
	Item Code 200108 Total No. of Proj.			**2**		**Total Amount**	**$2,225.00**
200110	PREPARE HOLE	EA	4	1	510.00	$13.50	$6,885.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**510.00**	**$13.50**	**$6,885.00**
	Item Code 200110	**Total No. of Proj.**			**1**		**Total Amount**	**$6,885.00**
200114	ROCK BLANKET		M2	5	1	200.00	$80.00	$16,000.00
			M2	7	1	11,500.00	$65.00	$747,500.00
			M2	8	1	3,950.00	$85.00	$335,750.00
			M2	11	1	1,080.00	$55.00	$59,400.00
		Unit Sub Total	**M2**		**4**	**16,730.00**	**$69.26**	**$1,158,650.00**
200114	ROCK BLANKET		SQYD	1	1	1,170.00	$102.00	$119,340.00
			SQYD	2	1	6,230.00	$63.00	$392,490.00
			SQYD	3	1	210.00	$10.00	$2,100.00
			SQYD	4	1	5,400.00	$19.91	$107,514.00
			SQYD	5	1	310.00	$117.00	$36,270.00
			SQYD	7	1	2,320.00	$55.00	$127,600.00
			SQYD	8	3	9,670.00	$61.39	$593,600.00
			SQYD	11	4	3,910.00	$69.57	$272,026.00
			SQYD	12	4	8,680.00	$50.71	$440,132.50
		Unit Sub Total	**SQYD**		**17**	**37,900.00**	**$55.17**	**$2,091,072.50**
	Item Code 200114	**Total No. of Proj.**			**21**		**Total Amount**	**$3,249,722.50**
200115	GRAVEL (MISCELLANEOUS AREAS) (SQFT)		SQFT	3	1	500.00	$5.00	$2,500.00
			SQFT	12	1	1,940.00	$2.00	$3,880.00
		Unit Sub Total	**SQFT**		**2**	**2,440.00**	**$2.61**	**$6,380.00**
	Item Code 200115	**Total No. of Proj.**			**2**		**Total Amount**	**$6,380.00**
200116	GRAVEL (MISCELLANEOUS AREAS) (SQYD)		SQYD	1	2	520.00	$17.62	$9,160.00
			SQYD	4	1	140.00	$35.00	$4,900.00
			SQYD	6	1	27.00	$13.00	$351.00
			SQYD	7	1	1,830.00	$25.00	$45,750.00
			SQYD	8	3	33,300.00	$8.66	$288,398.00
			SQYD	12	1	585.00	$11.00	$6,435.00
		Unit Sub Total	**SQYD**		**9**	**36,402.00**	**$9.75**	**$354,994.00**
	Item Code 200116	**Total No. of Proj.**			**9**		**Total Amount**	**$354,994.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
200117	DECOMPOSED GRANITE (MISCELLANEOUS AREAS) (SQFT)	SQFT	3	1	650.00	$5.00	$3,250.00
		SQFT	4	1	2,840.00	$13.80	$39,192.00
	Unit Sub Total	**SQFT**		**2**	**3,490.00**	**$12.16**	**$42,442.00**
	Item Code 200117 Total No. of Proj.			**2**		**Total Amount**	**$42,442.00**
200118	DECOMPOSED GRANITE (MISCELLANEOUS AREAS) (SQYD)	SQYD	4	1	990.00	$38.00	$37,620.00
		SQYD	5	1	410.00	$18.00	$7,380.00
		SQYD	6	1	2,500.00	$36.00	$90,000.00
	Unit Sub Total	**SQYD**		**3**	**3,900.00**	**$34.62**	**$135,000.00**
	Item Code 200118 Total No. of Proj.			**3**		**Total Amount**	**$135,000.00**
200120	CULTIVATE	SQYD	5	1	1,560.00	$1.00	$1,560.00
		SQYD	8	1	7,400.00	$0.32	$2,368.00
	Unit Sub Total	**SQYD**		**2**	**8,960.00**	**$0.44**	**$3,928.00**
	Item Code 200120 Total No. of Proj.			**2**		**Total Amount**	**$3,928.00**
202003	IRON SULFATE	LB	11	6	24,000.00	$0.70	$16,752.00
	Unit Sub Total	**LB**		**6**	**24,000.00**	**$0.70**	**$16,752.00**
	Item Code 202003 Total No. of Proj.			**6**		**Total Amount**	**$16,752.00**
202006	SOIL AMENDMENT	CY	2	1	110.00	$15.00	$1,650.00
		CY	4	3	270.00	$54.37	$14,681.00
		CY	7	1	47.00	$30.00	$1,410.00
		CY	8	1	67.00	$24.00	$1,608.00
		CY	10	1	29.00	$45.00	$1,305.00
		CY	11	1	85.00	$24.00	$2,040.00
	Unit Sub Total	**CY**		**8**	**608.00**	**$37.33**	**$22,694.00**
	Item Code 202006 Total No. of Proj.			**8**		**Total Amount**	**$22,694.00**
202007	DUFF	M2	5	1	132,000.00	$1.60	$211,200.00
		M2	11	1	4,970.00	$10.00	$49,700.00
	Unit Sub Total	**M2**		**2**	**136,970.00**	**$1.90**	**$260,900.00**
202007	DUFF	SQYD	1	1	9,200.00	$2.40	$22,080.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
202007	DUFF	SQYD	3	1	6,530.00	$2.00	$13,060.00
		SQYD	8	1	11,200.00	$1.25	$14,000.00
		SQYD	9	2	4,370.00	$2.58	$11,275.00
	Unit Sub Total	**SQYD**		**5**	**31,300.00**	**$1.93**	**$60,415.00**
	Item Code 202007 Total No. of Proj.			**7**		**Total Amount**	**$321,315.00**
202011	MULCH	CY	1	2	356.00	$59.21	$21,080.00
		CY	2	2	3,053.00	$17.46	$53,300.00
		CY	3	5	174.00	$105.52	$18,360.05
		CY	4	5	1,422.00	$41.51	$59,030.50
		CY	5	2	650.00	$34.04	$22,125.00
		CY	6	1	230.00	$28.00	$6,440.00
		CY	7	4	1,675.00	$38.47	$64,432.80
		CY	8	6	5,643.00	$27.22	$153,607.00
		CY	10	1	3,250.00	$28.00	$91,000.00
		CY	11	8	11,530.00	$30.57	$352,465.10
		CY	12	2	193.00	$36.28	$7,002.00
	Unit Sub Total	**CY**		**38**	**28,176.00**	**$30.13**	**$848,842.45**
202011	MULCH	SQFT	2	1	1,700.00	$1.10	$1,870.00
	Unit Sub Total	**SQFT**		**1**	**1,700.00**	**$1.10**	**$1,870.00**
	Item Code 202011 Total No. of Proj.			**39**		**Total Amount**	**$850,712.45**
202018	COMMERCIAL FERTILIZER	LB	8	1	1,420.00	$0.85	$1,207.00
	Unit Sub Total	**LB**		**1**	**1,420.00**	**$0.85**	**$1,207.00**
	Item Code 202018 Total No. of Proj.			**1**		**Total Amount**	**$1,207.00**
202030	COMMERCIAL FERTILIZER (GRANULAR)	LB	8	1	32.00	$10.00	$320.00
	Unit Sub Total	**LB**		**1**	**32.00**	**$10.00**	**$320.00**
	Item Code 202030 Total No. of Proj.			**1**		**Total Amount**	**$320.00**
202031	COMMERCIAL FERTILIZER (SLOW RELEASE)	LB	4	1	20.00	$5.00	$100.00
		LB	7	2	1,082.00	$0.97	$1,046.00
		LB	11	7	15,050.00	$0.66	$9,925.70
	Unit Sub Total	**LB**		**10**	**16,152.00**	**$0.69**	**$11,071.70**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 202031 Total No. of Proj.			**10**		**Total Amount**	**$11,071.70**
202033	COMMERCIAL FERTILIZER (PACKET)	EA	2	1	3,190.00	$1.00	$3,190.00
		EA	4	3	6,640.00	$0.36	$2,415.50
		EA	5	3	11,260.00	$0.19	$2,086.00
		EA	7	1	4,100.00	$1.00	$4,100.00
		EA	10	1	2,590.00	$1.00	$2,590.00
		EA	11	7	156,440.00	$0.13	$20,070.60
	Unit Sub Total	**EA**		**16**	**184,220.00**	**$0.19**	**$34,452.10**
	Item Code 202033 Total No. of Proj.			**16**		**Total Amount**	**$34,452.10**
203001	EROSION CONTROL (BLANKET)	M2	8	1	6,420.00	$5.00	$32,100.00
	Unit Sub Total	**M2**		**1**	**6,420.00**	**$5.00**	**$32,100.00**
	Item Code 203001 Total No. of Proj.			**1**		**Total Amount**	**$32,100.00**
203002	EROSION CONTROL (COMPOST BLANKET)	CY	1	12	5,789.60	$58.42	$338,206.00
		CY	2	1	560.00	$60.00	$33,600.00
		CY	3	5	336.00	$100.04	$33,612.00
		CY	4	21	6,737.50	$66.34	$446,933.78
		CY	5	9	8,388.00	$36.19	$303,598.00
		CY	6	4	15,480.00	$42.76	$661,850.00
		CY	8	3	20,800.00	$17.92	$372,700.00
		CY	10	2	562.00	$109.91	$61,768.00
		CY	11	6	35,861.00	$22.61	$810,795.50
	Unit Sub Total	**CY**		**63**	**94,514.10**	**$32.41**	**$3,063,063.28**
203002	EROSION CONTROL (COMPOST BLANKET)	M3	4	1	370.00	$60.00	$22,200.00
		M3	5	1	5,230.00	$58.00	$303,340.00
		M3	11	1	1,120.00	$40.00	$44,800.00
	Unit Sub Total	**M3**		**3**	**6,720.00**	**$55.11**	**$370,340.00**
	Item Code 203002 Total No. of Proj.			**66**		**Total Amount**	**$3,433,403.28**
203005	EROSION CONTROL (DRILL SEED) (ACRE)	ACRE	6	2	89.00	$878.65	$78,200.00
	Unit Sub Total	**ACRE**		**2**	**89.00**	**$878.65**	**$78,200.00**
	Item Code 203005 Total No. of Proj.			**2**		**Total Amount**	**$78,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
203006	EROSION CONTROL (DRY SEED) (SQFT)	SQFT	1	1	13,900.00	$0.15	$2,085.00
		SQFT	3	1	500.00	$1.00	$500.00
		SQFT	5	3	26,100.00	$0.23	$5,914.00
		SQFT	8	1	65,000.00	$0.04	$2,600.00
		SQFT	9	1	6,320.00	$0.10	$632.00
		SQFT	10	1	2,200.00	$1.00	$2,200.00
	Unit Sub Total	**SQFT**		**8**	**114,020.00**	**$0.12**	**$13,931.00**
	Item Code 203006 Total No. of Proj.			**8**		**Total Amount**	**$13,931.00**
203007	EROSION CONTROL (DRY SEED) (ACRE)	ACRE	5	1	14.00	$1,000.00	$14,000.00
		ACRE	8	2	17.80	$2,191.01	$39,000.00
		ACRE	9	1	0.30	$5,000.00	$1,500.00
		ACRE	11	1	13.00	$1,125.00	$14,625.00
	Unit Sub Total	**ACRE**		**5**	**45.10**	**$1,532.71**	**$69,125.00**
	Item Code 203007 Total No. of Proj.			**5**		**Total Amount**	**$69,125.00**
203008	EROSION CONTROL (PUNCHED STRAW) (SQFT)	SQFT	9	2	26,300.00	$1.26	$33,075.00
	Unit Sub Total	**SQFT**		**2**	**26,300.00**	**$1.26**	**$33,075.00**
	Item Code 203008 Total No. of Proj.			**2**		**Total Amount**	**$33,075.00**
203011	EROSION CONTROL (TYPE C)	M2	10	1	55,900.00	$1.80	$100,620.00
	Unit Sub Total	**M2**		**1**	**55,900.00**	**$1.80**	**$100,620.00**
	Item Code 203011 Total No. of Proj.			**1**		**Total Amount**	**$100,620.00**
203016	EROSION CONTROL (TYPE D)	M2	8	1	46,600.00	$2.10	$97,860.00
		M2	10	1	68,200.00	$1.65	$112,530.00
		M2	11	1	35,500.00	$0.50	$17,750.00
	Unit Sub Total	**M2**		**3**	**150,300.00**	**$1.52**	**$228,140.00**
203016	EROSION CONTROL (TYPE D)	SQYD	3	2	20,790.00	$0.71	$14,728.00
	Unit Sub Total	**SQYD**		**2**	**20,790.00**	**$0.71**	**$14,728.00**
	Item Code 203016 Total No. of Proj.			**5**		**Total Amount**	**$242,868.00**
203017	EROSION CONTROL (HYDRAULIC MATRIX)	M2	10	1	22,300.00	$0.90	$20,070.00
	Unit Sub Total	**M2**		**1**	**22,300.00**	**$0.90**	**$20,070.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 203017	**Total No. of Proj.**			**1**		**Total Amount**	**$20,070.00**
203018	EROSION CONTROL (NETTING)		M2	11	1	640.00	$1.00	$640.00
		Unit Sub Total	**M2**		**1**	**640.00**	**$1.00**	**$640.00**
	Item Code 203018	**Total No. of Proj.**			**1**		**Total Amount**	**$640.00**
203021	FIBER ROLLS		LF	1	7	80,780.00	$3.04	$245,545.00
			LF	2	1	3,950.00	$4.00	$15,800.00
			LF	3	1	31,400.00	$2.00	$62,800.00
			LF	4	28	138,175.00	$2.92	$403,662.90
			LF	5	2	1,500.00	$2.65	$3,975.00
			LF	6	3	195,980.00	$2.36	$461,637.50
			LF	10	2	4,470.00	$2.40	$10,725.00
			LF	11	11	165,600.00	$2.25	$372,666.40
			LF	12	1	43.00	$3.00	$129.00
		Unit Sub Total	**LF**		**56**	**621,898.00**	**$2.54**	**$1,576,940.80**
203021	FIBER ROLLS		M	4	1	1,790.00	$10.00	$17,900.00
			M	5	1	3,400.00	$12.00	$40,800.00
			M	8	1	3,680.00	$7.10	$26,128.00
			M	11	2	21,950.00	$6.28	$137,900.00
		Unit Sub Total	**M**		**5**	**30,820.00**	**$7.23**	**$222,728.00**
	Item Code 203021	**Total No. of Proj.**			**61**		**Total Amount**	**$1,799,668.80**
203022	EROSION CONTROL HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)		M2	11	1	43,500.00	$0.40	$17,400.00
		Unit Sub Total	**M2**		**1**	**43,500.00**	**$0.40**	**$17,400.00**
	Item Code 203022	**Total No. of Proj.**			**1**		**Total Amount**	**$17,400.00**
203023	COMPOST SOCK		LF	1	1	670.00	$10.00	$6,700.00
			LF	3	1	160.00	$30.00	$4,800.00
			LF	5	1	3,730.00	$14.00	$52,220.00
		Unit Sub Total	**LF**		**3**	**4,560.00**	**$13.97**	**$63,720.00**
203023	COMPOST SOCK		M	5	1	12,900.00	$11.00	$141,900.00
		Unit Sub Total	**M**		**1**	**12,900.00**	**$11.00**	**$141,900.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 203023	**Total No. of Proj.**			**4**		**Total Amount**	**$205,620.00**
203025	COMPOST (INCORPORATE)		M2	5	1	222,000.00	$2.70	$599,400.00
			M2	11	1	10,300.00	$0.75	$7,725.00
		Unit Sub Total	**M2**		**2**	**232,300.00**	**$2.61**	**$607,125.00**
203025	COMPOST (INCORPORATE)		SQYD	1	2	2,380.00	$35.79	$85,190.00
			SQYD	3	1	7,410.00	$5.00	$37,050.00
			SQYD	4	12	104,930.00	$5.38	$564,809.20
			SQYD	5	3	13,380.00	$3.31	$44,350.00
			SQYD	6	2	14,910.00	$5.60	$83,460.00
			SQYD	8	3	112,300.00	$4.25	$477,390.00
			SQYD	10	2	6,150.00	$5.00	$30,750.00
			SQYD	11	4	80,960.00	$3.30	$267,431.70
		Unit Sub Total	**SQYD**		**29**	**342,420.00**	**$4.64**	**$1,590,430.90**
	Item Code 203025	**Total No. of Proj.**			**31**		**Total Amount**	**$2,197,555.90**
203026	MOVE-IN/MOVE-OUT (EROSION CONTROL)		EA	1	4	20.00	$810.00	$16,200.00
			EA	2	2	8.00	$625.00	$5,000.00
			EA	3	3	23.00	$528.91	$12,165.00
			EA	4	11	81.00	$848.89	$68,760.00
			EA	5	3	40.00	$522.50	$20,900.00
			EA	6	6	26.00	$574.81	$14,945.00
			EA	8	4	26.00	$876.92	$22,800.00
			EA	10	5	33.00	$1,198.48	$39,550.00
			EA	11	7	33.00	$469.15	$15,482.00
			EA	12	2	15.00	$273.33	$4,100.00
		Unit Sub Total	**EA**		**47**	**305.00**	**$720.99**	**$219,902.00**
	Item Code 203026	**Total No. of Proj.**			**47**		**Total Amount**	**$219,902.00**
203027	EROSION CONTROL (BONDED FIBER MATRIX) (SQFT)		SQFT	2	2	446,600.00	$0.18	$82,020.00
			SQFT	3	3	121,030.00	$0.13	$15,225.70
			SQFT	4	1	39,000.00	$0.14	$5,460.00
			SQFT	11	2	244,000.00	$0.07	$18,090.00
		Unit Sub Total	**SQFT**		**8**	**850,630.00**	**$0.14**	**$120,795.70**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 203027 Total No. of Proj.			**8**		**Total Amount**	**$120,795.70**
203028	EROSION CONTROL (BONDED FIBER MATRIX) (ACRE)	ACRE	2	1	0.90	$5,610.00	$5,049.00
		ACRE	10	1	55.00	$7,200.00	$396,000.00
		ACRE	11	1	9.00	$5,552.00	$49,968.00
	Unit Sub Total	**ACRE**		**3**	**64.90**	**$6,949.41**	**$451,017.00**
203028	EROSION CONTROL (BONDED FIBER MATRIX) (ACRE)	SQFT	2	1	35,800.00	$0.17	$6,086.00
	Unit Sub Total	**SQFT**		**1**	**35,800.00**	**$0.17**	**$6,086.00**
	Item Code 203028 Total No. of Proj.			**4**		**Total Amount**	**$457,103.00**
203029	EROSION CONTROL (POLYMER STABILIZED FIBER MATRIX) (SQFT)	SQFT	6	2	19,200.00	$0.44	$8,424.00
		SQFT	8	2	542,000.00	$0.04	$22,980.00
		SQFT	11	1	29,400.00	$0.13	$3,822.00
	Unit Sub Total	**SQFT**		**5**	**590,600.00**	**$0.06**	**$35,226.00**
	Item Code 203029 Total No. of Proj.			**5**		**Total Amount**	**$35,226.00**
203030	EROSION CONTROL (POLYMER STABILIZED FIBER MATRIX) (ACRE)	ACRE	6	2	57.30	$1,343.80	$77,000.00
		ACRE	8	2	17.80	$1,969.66	$35,060.00
		ACRE	11	7	204.00	$3,954.47	$806,712.10
	Unit Sub Total	**ACRE**		**11**	**279.10**	**$3,291.91**	**$918,772.10**
	Item Code 203030 Total No. of Proj.			**11**		**Total Amount**	**$918,772.10**
203031	EROSION CONTROL (HYDROSEED) (SQFT)	SQFT	1	8	1,934,100.00	$0.11	$220,404.00
		SQFT	2	1	95,800.00	$0.16	$15,328.00
		SQFT	3	10	1,435,815.00	$0.09	$131,542.00
		SQFT	4	26	3,379,800.00	$0.11	$388,603.50
		SQFT	5	5	394,300.00	$0.09	$36,532.00
		SQFT	6	1	512,000.00	$0.07	$35,840.00
		SQFT	7	3	94,110.00	$0.39	$37,075.00
		SQFT	8	2	250,000.00	$0.11	$26,500.00
		SQFT	10	3	121,600.00	$0.15	$18,220.00
		SQFT	11	1	180,000.00	$0.06	$10,800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
203031	EROSION CONTROL (HYDROSEED) (SQFT)	SQFT	12	4	238,900.00	$0.07	$16,691.00
	Unit Sub Total	**SQFT**		**64**	**8,636,425.00**	**$0.11**	**$937,535.50**
	Item Code 203031 Total No. of Proj.			**64**		**Total Amount**	**$937,535.50**
203032	EROSION CONTROL (HYDROSEED) (ACRE)	ACRE	1	4	11.00	$8,216.36	$90,380.00
		ACRE	2	16	107.60	$3,939.20	$423,857.77
		ACRE	3	2	13.60	$2,213.82	$30,108.00
		ACRE	4	3	4.40	$9,391.86	$41,324.20
		ACRE	5	3	12.00	$2,520.42	$30,245.00
		ACRE	6	4	218.90	$1,632.64	$357,385.00
		ACRE	8	3	35.10	$2,730.48	$95,840.00
		ACRE	10	3	34.10	$4,148.68	$141,470.00
	Unit Sub Total	**ACRE**		**38**	**436.70**	**$2,772.18**	**$1,210,609.97**
	Item Code 203032 Total No. of Proj.			**38**		**Total Amount**	**$1,210,609.97**
203033	ROLLED EROSION CONTROL PRODUCT (BLANKET)	M2	7	1	960.00	$5.00	$4,800.00
	Unit Sub Total	**M2**		**1**	**960.00**	**$5.00**	**$4,800.00**
203033	ROLLED EROSION CONTROL PRODUCT (BLANKET)	SQFT	1	2	62,900.00	$0.70	$44,040.00
		SQFT	3	4	6,330.00	$0.92	$5,794.10
		SQFT	9	1	6,320.00	$0.40	$2,528.00
		SQFT	11	1	24,600.00	$0.41	$10,086.00
	Unit Sub Total	**SQFT**		**8**	**100,150.00**	**$0.62**	**$62,448.10**
	Item Code 203033 Total No. of Proj.			**9**		**Total Amount**	**$67,248.10**
203034	ROLLED EROSION CONTROL PRODUCT (NETTING)	M2	4	1	1,050.00	$6.00	$6,300.00
	Unit Sub Total	**M2**		**1**	**1,050.00**	**$6.00**	**$6,300.00**
203034	ROLLED EROSION CONTROL PRODUCT (NETTING)	SQFT	1	1	37,300.00	$0.50	$18,650.00
		SQFT	3	4	11,690.00	$1.09	$12,701.00
		SQFT	4	23	593,560.00	$0.50	$294,363.00
	Unit Sub Total	**SQFT**		**28**	**642,550.00**	**$0.51**	**$325,714.00**
	Item Code 203034 Total No. of Proj.			**29**		**Total Amount**	**$332,014.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
203038	ROLLED EROSION CONTROL PRODUCT (JUTE MESH)	M2	11	1	12,500.00	$1.60	$20,000.00
	Unit Sub Total	**M2**		**1**	**12,500.00**	**$1.60**	**$20,000.00**
203038	ROLLED EROSION CONTROL PRODUCT (JUTE MESH)	SQFT	5	1	210.00	$2.30	$483.00
		SQFT	10	1	1,150,000.00	$0.45	$517,500.00
		SQFT	11	1	4,790.00	$0.28	$1,341.20
	Unit Sub Total	**SQFT**		**3**	**1,155,000.00**	**$0.45**	**$519,324.20**
	Item Code 203038 Total No. of Proj.			**4**		**Total Amount**	**$539,324.20**
203070	ROCK STAIN	SQFT	4	1	6,540.00	$1.00	$6,540.00
	Unit Sub Total	**SQFT**		**1**	**6,540.00**	**$1.00**	**$6,540.00**
	Item Code 203070 Total No. of Proj.			**1**		**Total Amount**	**$6,540.00**
204006	PLANT (GROUP F)	EA	4	1	4,060.00	$1.50	$6,090.00
		EA	7	1	30,100.00	$0.44	$13,244.00
		EA	8	1	34,400.00	$0.32	$11,008.00
		EA	11	6	383,200.00	$0.38	$144,395.00
		EA	12	2	307,200.00	$0.40	$122,804.00
	Unit Sub Total	**EA**		**11**	**758,960.00**	**$0.39**	**$297,541.00**
	Item Code 204006 Total No. of Proj.			**11**		**Total Amount**	**$297,541.00**
204007	PLANT (GROUP G)	EA	11	6	1,168,300.00	$0.48	$556,764.00
	Unit Sub Total	**EA**		**6**	**1,168,300.00**	**$0.48**	**$556,764.00**
	Item Code 204007 Total No. of Proj.			**6**		**Total Amount**	**$556,764.00**
204008	PLANT (GROUP H)	EA	5	1	850.00	$1.00	$850.00
		EA	8	1	34,400.00	$0.17	$5,848.00
		EA	11	5	141,260.00	$0.36	$51,378.00
		EA	12	1	49,600.00	$0.36	$17,856.00
	Unit Sub Total	**EA**		**8**	**226,110.00**	**$0.34**	**$75,932.00**
	Item Code 204008 Total No. of Proj.			**8**		**Total Amount**	**$75,932.00**
204009	PLANT (GROUP I)	EA	4	3	2,640.00	$10.39	$27,430.60
		EA	5	2	2,970.00	$4.12	$12,222.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
204009	PLANT (GROUP I)	EA	8	1	12,400.00	$1.70	$21,080.00
	Unit Sub Total	**EA**		**6**	**18,010.00**	**$3.37**	**$60,732.60**
	Item Code 204009 Total No. of Proj.			**6**		**Total Amount**	**$60,732.60**
204011	PLANT (GROUP K)	EA	4	1	140.00	$280.00	$39,200.00
		EA	5	1	2.00	$1,250.00	$2,500.00
		EA	8	1	180.00	$150.00	$27,000.00
		EA	11	3	91.00	$180.96	$16,467.51
	Unit Sub Total	**EA**		**6**	**413.00**	**$206.22**	**$85,167.51**
	Item Code 204011 Total No. of Proj.			**6**		**Total Amount**	**$85,167.51**
204012	PLANTING PLANT (GROUP L)	EA	11	1	8,420.00	$2.25	$18,945.00
	Unit Sub Total	**EA**		**1**	**8,420.00**	**$2.25**	**$18,945.00**
	Item Code 204012 Total No. of Proj.			**1**		**Total Amount**	**$18,945.00**
204013	PLANT (GROUP M)	EA	4	4	9,005.00	$7.49	$67,455.15
		EA	11	6	166,440.00	$1.35	$224,282.80
	Unit Sub Total	**EA**		**10**	**175,445.00**	**$1.66**	**$291,737.95**
	Item Code 204013 Total No. of Proj.			**10**		**Total Amount**	**$291,737.95**
204017	PLANT (GROUP W)	EA	3	1	260.00	$44.00	$11,440.00
		EA	4	5	655.00	$16.80	$11,005.00
		EA	8	1	3,350.00	$4.00	$13,400.00
	Unit Sub Total	**EA**		**7**	**4,265.00**	**$8.40**	**$35,845.00**
	Item Code 204017 Total No. of Proj.			**7**		**Total Amount**	**$35,845.00**
204018	PLANTING PLANT (GROUP R)	LS	11	1	1.00	$10.00	$10.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$10.00**	**$10.00**
	Item Code 204018 Total No. of Proj.			**1**		**Total Amount**	**$10.00**
204022	PLANT (GROUP Z)	EA	12	1	120.00	$442.00	$53,040.00
	Unit Sub Total	**EA**		**1**	**120.00**	**$442.00**	**$53,040.00**
	Item Code 204022 Total No. of Proj.			**1**		**Total Amount**	**$53,040.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
204030	TRANSPLANT TREE		EA	5	1	3.00	$1,000.00	$3,000.00
		Unit Sub Total	**EA**		**1**	**3.00**	**$1,000.00**	**$3,000.00**
	Item Code 204030	**Total No. of Proj.**			**1**		**Total Amount**	**$3,000.00**
204031	TRANSPLANT PALM TREE		EA	6	1	2.00	$4,000.00	$8,000.00
			EA	8	1	10.00	$1,500.00	$15,000.00
			EA	12	2	56.00	$1,543.75	$86,450.00
		Unit Sub Total	**EA**		**4**	**68.00**	**$1,609.56**	**$109,450.00**
	Item Code 204031	**Total No. of Proj.**			**4**		**Total Amount**	**$109,450.00**
204035	PLANT (GROUP A)		EA	2	1	2,120.00	$8.00	$16,960.00
			EA	4	2	1,530.00	$10.78	$16,490.00
			EA	5	2	2,660.00	$7.37	$19,600.00
			EA	7	2	6,140.00	$5.59	$34,300.00
			EA	8	2	1,150.00	$2.54	$2,920.00
			EA	10	1	970.00	$9.00	$8,730.00
			EA	11	8	113,060.00	$6.04	$682,846.10
			EA	12	2	4,000.00	$7.50	$29,994.00
		Unit Sub Total	**EA**		**20**	**131,630.00**	**$6.17**	**$811,840.10**
	Item Code 204035	**Total No. of Proj.**			**20**		**Total Amount**	**$811,840.10**
204036	PLANT (GROUP B)		EA	2	1	420.00	$40.00	$16,800.00
			EA	4	1	540.00	$30.00	$16,200.00
			EA	5	3	777.00	$19.14	$14,868.00
			EA	7	1	44.00	$20.00	$880.00
			EA	8	6	7,430.00	$31.31	$232,670.00
			EA	10	1	540.00	$35.00	$18,900.00
			EA	11	7	3,790.00	$20.29	$76,897.80
			EA	12	2	261.00	$40.14	$10,477.00
		Unit Sub Total	**EA**		**22**	**13,802.00**	**$28.09**	**$387,692.80**
	Item Code 204036	**Total No. of Proj.**			**22**		**Total Amount**	**$387,692.80**
204038	PLANT (GROUP U)		EA	5	3	1,130.00	$73.58	$83,150.00
			EA	7	1	85.00	$75.00	$6,375.00
			EA	8	3	368.00	$86.45	$31,812.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
204038	PLANT (GROUP U)	EA	11	7	5,180.00	$75.12	$389,129.30
		EA	12	2	291.00	$119.60	$34,803.00
	Unit Sub Total	**EA**		**16**	**7,054.00**	**$77.30**	**$545,269.30**
	Item Code 204038 Total No. of Proj.			**16**		**Total Amount**	**$545,269.30**
204042	TURF (SOD)	SQYD	4	1	120.00	$20.00	$2,400.00
		SQYD	11	1	900.00	$6.00	$5,400.00
	Unit Sub Total	**SQYD**		**2**	**1,020.00**	**$7.65**	**$7,800.00**
	Item Code 204042 Total No. of Proj.			**2**		**Total Amount**	**$7,800.00**
204055	WILD FLOWER SEEDING (SQYD)	SQYD	4	1	10,600.00	$1.19	$12,614.00
	Unit Sub Total	**SQYD**		**1**	**10,600.00**	**$1.19**	**$12,614.00**
	Item Code 204055 Total No. of Proj.			**1**		**Total Amount**	**$12,614.00**
204096	MAINTAIN EXISTING PLANTED AREAS	LS	2	1	1.00	$10,000.00	$10,000.00
		LS	3	1	1.00	$650.00	$650.00
		LS	4	4	4.00	$9,415.00	$37,660.00
		LS	6	4	4.00	$18,275.00	$73,100.00
		LS	7	1	1.00	$3,800.00	$3,800.00
		LS	8	4	4.00	$3,625.00	$14,500.00
		LS	10	2	2.00	$55,000.00	$110,000.00
		LS	11	3	3.00	$10,600.00	$31,800.00
		LS	12	6	6.00	$91,066.67	$546,400.00
	Unit Sub Total	**LS**		**26**	**26.00**	**$31,842.69**	**$827,910.00**
	Item Code 204096 Total No. of Proj.			**26**		**Total Amount**	**$827,910.00**
204099	PLANT ESTABLISHMENT WORK	LS	1	1	1.00	$3,500.00	$3,500.00
		LS	2	1	1.00	$55,505.00	$55,505.00
		LS	3	6	6.00	$18,551.92	$111,311.50
		LS	4	11	11.00	$61,772.73	$679,500.00
		LS	5	9	9.00	$29,785.00	$268,065.00
		LS	6	4	4.00	$15,750.00	$63,000.00
		LS	7	11	11.00	$25,060.36	$275,664.00
		LS	8	9	9.00	$76,828.00	$691,452.00
		LS	10	2	2.00	$34,000.00	$68,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
204099	PLANT ESTABLISHMENT WORK	LS	11	16	16.00	$48,938.31	$783,013.00
		LS	12	6	6.00	$45,083.33	$270,500.00
	Unit Sub Total	**LS**		**76**	**76.00**	**$43,019.88**	**$3,269,510.50**
	Item Code 204099 Total No. of Proj.			**76**		**Total Amount**	**$3,269,510.50**
204101	EXTENDED PLANT ESTABLISHMENT WORK	LS	4	1	1.00	$50,880.00	$50,880.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$50,880.00**	**$50,880.00**
	Item Code 204101 Total No. of Proj.			**1**		**Total Amount**	**$50,880.00**
205051	FOLIAGE PROTECTOR	EA	4	2	1,760.00	$14.69	$25,850.00
	Unit Sub Total	**EA**		**2**	**1,760.00**	**$14.69**	**$25,850.00**
	Item Code 205051 Total No. of Proj.			**2**		**Total Amount**	**$25,850.00**
205061	ROOT PROTECTOR	EA	5	3	4,510.00	$7.99	$36,035.00
	Unit Sub Total	**EA**		**3**	**4,510.00**	**$7.99**	**$36,035.00**
	Item Code 205061 Total No. of Proj.			**3**		**Total Amount**	**$36,035.00**
205062	ROOT BARRIER	LF	5	1	130.00	$3.00	$390.00
	Unit Sub Total	**LF**		**1**	**130.00**	**$3.00**	**$390.00**
	Item Code 205062 Total No. of Proj.			**1**		**Total Amount**	**$390.00**
206003	HEADER BOARD	LF	3	1	190.00	$10.00	$1,900.00
		LF	10	1	740.00	$4.50	$3,330.00
	Unit Sub Total	**LF**		**2**	**930.00**	**$5.62**	**$5,230.00**
	Item Code 206003 Total No. of Proj.			**2**		**Total Amount**	**$5,230.00**
206401	MAINTAIN EXISTING IRRIGATION FACILITIES	LS	2	1	1.00	$6,000.00	$6,000.00
		LS	3	1	1.00	$6,198.00	$6,198.00
		LS	4	5	5.00	$8,888.00	$44,440.00
		LS	5	1	1.00	$12,400.00	$12,400.00
		LS	6	3	3.00	$5,700.00	$17,100.00
		LS	7	1	1.00	$3,800.00	$3,800.00
		LS	8	2	2.00	$3,550.00	$7,100.00
		LS	10	2	2.00	$21,500.00	$43,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
206401	MAINTAIN EXISTING IRRIGATION FACILITIES	LS	11	1	1.00	$5,213.00	$5,213.00
		LS	12	6	6.00	$11,387.17	$68,323.00
	Unit Sub Total	**LS**		**23**	**23.00**	**$9,285.83**	**$213,574.00**
	Item Code 206401 Total No. of Proj.			**23**		**Total Amount**	**$213,574.00**
206555	MODIFY IRRIGATION SYSTEM	LS	2	1	1.00	$3,000.00	$3,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$3,000.00**	**$3,000.00**
	Item Code 206555 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
206560	CONTROL AND NEUTRAL CONDUCTORS	LS	2	1	1.00	$21,600.00	$21,600.00
		LS	4	1	1.00	$10,000.00	$10,000.00
		LS	5	3	3.00	$36,400.00	$109,200.00
		LS	6	1	1.00	$14,200.00	$14,200.00
		LS	7	2	2.00	$49,250.00	$98,500.00
		LS	8	5	5.00	$39,780.00	$198,900.00
		LS	10	1	1.00	$26,500.00	$26,500.00
		LS	11	7	7.00	$55,911.71	$391,382.00
		LS	12	2	2.00	$25,397.00	$50,794.00
	Unit Sub Total	**LS**		**23**	**23.00**	**$40,046.78**	**$921,076.00**
	Item Code 206560 Total No. of Proj.			**23**		**Total Amount**	**$921,076.00**
206601	3/4" ELECTRIC REMOTE CONTROL VALVE	EA	2	1	1.00	$336.00	$336.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$336.00**	**$336.00**
	Item Code 206601 Total No. of Proj.			**1**		**Total Amount**	**$336.00**
206602	1" ELECTRIC REMOTE CONTROL VALVE	EA	2	1	6.00	$354.00	$2,124.00
		EA	4	1	8.00	$245.00	$1,960.00
		EA	5	3	41.00	$414.63	$17,000.00
		EA	7	2	97.00	$266.21	$25,822.50
		EA	8	5	68.00	$353.90	$24,065.00
		EA	10	1	1.00	$246.00	$246.00
		EA	11	6	176.00	$237.30	$41,765.00
		EA	12	2	10.00	$318.80	$3,188.00
	Unit Sub Total	**EA**		**21**	**407.00**	**$285.43**	**$116,170.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 206602 Total No. of Proj.			**21**		**Total Amount**	**$116,170.50**
206603	1 1/4" ELECTRIC REMOTE CONTROL VALVE	EA	2	1	2.00	$375.00	$750.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$375.00**	**$750.00**
	Item Code 206603 Total No. of Proj.			**1**		**Total Amount**	**$750.00**
206604	1 1/2" ELECTRIC REMOTE CONTROL VALVE	EA	2	1	3.00	$400.00	$1,200.00
		EA	4	1	10.00	$350.00	$3,500.00
		EA	5	3	91.00	$358.35	$32,610.00
		EA	7	2	71.00	$308.59	$21,910.00
		EA	8	4	51.00	$330.59	$16,860.00
		EA	10	1	25.00	$364.00	$9,100.00
		EA	11	8	803.00	$258.74	$207,766.00
		EA	12	2	78.00	$328.92	$25,656.00
	Unit Sub Total	**EA**		**22**	**1,132.00**	**$281.45**	**$318,602.00**
	Item Code 206604 Total No. of Proj.			**22**		**Total Amount**	**$318,602.00**
206605	2" ELECTRIC REMOTE CONTROL VALVE	EA	2	1	78.00	$423.00	$32,994.00
		EA	4	1	2.00	$410.00	$820.00
		EA	5	2	2.00	$530.00	$1,060.00
		EA	7	1	2.00	$315.00	$630.00
		EA	8	3	28.00	$499.64	$13,990.00
		EA	10	1	1.00	$409.00	$409.00
		EA	11	1	3.00	$267.00	$801.00
		EA	12	1	17.00	$285.00	$4,845.00
	Unit Sub Total	**EA**		**11**	**133.00**	**$417.66**	**$55,549.00**
	Item Code 206605 Total No. of Proj.			**11**		**Total Amount**	**$55,549.00**
206607	3" ELECTRIC REMOTE CONTROL VALVE	EA	12	2	4.00	$386.00	$1,544.00
	Unit Sub Total	**EA**		**2**	**4.00**	**$386.00**	**$1,544.00**
	Item Code 206607 Total No. of Proj.			**2**		**Total Amount**	**$1,544.00**
206751	12 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	7	2	9.00	$5,133.33	$46,200.00
	Unit Sub Total	**EA**		**2**	**9.00**	**$5,133.33**	**$46,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 206751 Total No. of Proj.			**2**		**Total Amount**	**$46,200.00**
206753	24 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	7	1	5.00	$7,970.00	$39,850.00
		EA	8	1	2.00	$2,000.00	$4,000.00
	Unit Sub Total	**EA**		**2**	**7.00**	**$6,264.29**	**$43,850.00**
	Item Code 206753 Total No. of Proj.			**2**		**Total Amount**	**$43,850.00**
206756	16 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	7	1	1.00	$1,250.00	$1,250.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,250.00**	**$1,250.00**
	Item Code 206756 Total No. of Proj.			**1**		**Total Amount**	**$1,250.00**
206929	IRRIGATION CONTROLLER (BATTERY)	EA	4	1	3.00	$500.00	$1,500.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$500.00**	**$1,500.00**
	Item Code 206929 Total No. of Proj.			**1**		**Total Amount**	**$1,500.00**
208000	IRRIGATION SYSTEM	LS	1	2	2.00	$26,570.00	$53,140.00
		LS	2	1	1.00	$2,000.00	$2,000.00
		LS	3	6	6.00	$136,844.00	$821,064.00
		LS	4	7	7.00	$160,414.29	$1,122,900.00
		LS	5	6	6.00	$33,102.50	$198,615.00
		LS	6	7	7.00	$49,214.29	$344,500.00
		LS	7	8	8.00	$76,125.00	$609,000.00
		LS	8	3	3.00	$23,333.33	$70,000.00
		LS	10	2	2.00	$202,500.00	$405,000.00
		LS	11	6	6.00	$124,250.00	$745,500.00
		LS	12	6	6.00	$64,021.17	$384,127.00
	Unit Sub Total	**LS**		**54**	**54.00**	**$88,071.22**	**$4,755,846.00**
	Item Code 208000 Total No. of Proj.			**54**		**Total Amount**	**$4,755,846.00**
208004	1 1/4" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	11	1	50.00	$16.00	$800.00
	Unit Sub Total	**LF**		**1**	**50.00**	**$16.00**	**$800.00**
	Item Code 208004 Total No. of Proj.			**1**		**Total Amount**	**$800.00**
208006	2" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	4	3	1,000.00	$19.26	$19,259.20

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208006	2" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	10	1	200.00	$18.50	$3,700.00
	Unit Sub Total	**LF**		**4**	**1,200.00**	**$19.13**	**$22,959.20**
	Item Code 208006 Total No. of Proj.			**4**		**Total Amount**	**$22,959.20**
208007	2 1/2" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	7	1	20.00	$50.00	$1,000.00
	Unit Sub Total	**LF**		**1**	**20.00**	**$50.00**	**$1,000.00**
	Item Code 208007 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
208008	3" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	12	1	150.00	$38.82	$5,823.00
	Unit Sub Total	**LF**		**1**	**150.00**	**$38.82**	**$5,823.00**
	Item Code 208008 Total No. of Proj.			**1**		**Total Amount**	**$5,823.00**
208009	4" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	5	1	250.00	$90.00	$22,500.00
	Unit Sub Total	**LF**		**1**	**250.00**	**$90.00**	**$22,500.00**
	Item Code 208009 Total No. of Proj.			**1**		**Total Amount**	**$22,500.00**
208023	75 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	M	5	1	56.00	$135.00	$7,560.00
	Unit Sub Total	**M**		**1**	**56.00**	**$135.00**	**$7,560.00**
	Item Code 208023 Total No. of Proj.			**1**		**Total Amount**	**$7,560.00**
208028	3" SUPPLY LINE (BRIDGE)	LF	3	1	70.00	$50.00	$3,500.00
		LF	7	1	482.00	$50.00	$24,100.00
		LF	12	2	470.00	$77.13	$36,250.00
	Unit Sub Total	**LF**		**4**	**1,022.00**	**$62.48**	**$63,850.00**
	Item Code 208028 Total No. of Proj.			**4**		**Total Amount**	**$63,850.00**
208029	4" SUPPLY LINE (BRIDGE)	LF	5	1	100.00	$80.00	$8,000.00
	Unit Sub Total	**LF**		**1**	**100.00**	**$80.00**	**$8,000.00**
	Item Code 208029 Total No. of Proj.			**1**		**Total Amount**	**$8,000.00**
208038	NPS 3 SUPPLY LINE (BRIDGE)	M	5	1	1,005.00	$200.00	$201,000.00
	Unit Sub Total	**M**		**1**	**1,005.00**	**$200.00**	**$201,000.00**
	Item Code 208038 Total No. of Proj.			**1**		**Total Amount**	**$201,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208044	3" GALVANIZED STEEL PIPE (SUPPLY LINE ON BRIDGE)	LF	12	1	145.00	$20.00	$2,900.00
	Unit Sub Total	**LF**		**1**	**145.00**	**$20.00**	**$2,900.00**
	Item Code 208044 Total No. of Proj.			**1**		**Total Amount**	**$2,900.00**
208211	1/2" PLASTIC PIPE (IRRIGATION LINE)	LF	4	1	20,285.00	$1.00	$20,285.00
		LF	5	1	7,200.00	$0.55	$3,960.00
	Unit Sub Total	**LF**		**2**	**27,485.00**	**$0.88**	**$24,245.00**
	Item Code 208211 Total No. of Proj.			**2**		**Total Amount**	**$24,245.00**
208262	3/4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	1	4,254.00	$1.70	$7,231.80
		LF	6	1	150.00	$7.00	$1,050.00
		LF	7	1	17,300.00	$2.50	$43,250.00
		LF	10	1	38,900.00	$1.25	$48,625.00
	Unit Sub Total	**LF**		**4**	**60,604.00**	**$1.65**	**$100,156.80**
	Item Code 208262 Total No. of Proj.			**4**		**Total Amount**	**$100,156.80**
208263	1" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	1	1,848.00	$2.30	$4,250.40
		LF	5	1	18,710.00	$2.00	$37,420.00
		LF	6	1	305.00	$7.00	$2,135.00
		LF	7	1	4,340.00	$2.75	$11,935.00
		LF	10	1	1,930.00	$1.50	$2,895.00
		LF	11	1	17,573.00	$1.75	$30,752.75
		LF	12	1	23,660.00	$2.25	$53,235.00
	Unit Sub Total	**LF**		**7**	**68,366.00**	**$2.09**	**$142,623.15**
	Item Code 208263 Total No. of Proj.			**7**		**Total Amount**	**$142,623.15**
208264	1 1/4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	1	1,177.00	$2.90	$3,413.30
		LF	6	1	210.00	$7.00	$1,470.00
		LF	7	1	2,840.00	$3.00	$8,520.00
		LF	10	1	4,520.00	$1.75	$7,910.00
		LF	11	1	1,330.00	$1.90	$2,527.00
		LF	12	1	9,295.00	$2.50	$23,237.50
	Unit Sub Total	**LF**		**6**	**19,372.00**	**$2.43**	**$47,077.80**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208264 Total No. of Proj.			**6**		**Total Amount**	**$47,077.80**
208265	1 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	1	205.00	$3.20	$656.00
		LF	5	1	11,000.00	$2.00	$22,000.00
		LF	6	1	203.00	$9.00	$1,827.00
		LF	7	1	330.00	$3.25	$1,072.50
		LF	10	1	5,260.00	$2.00	$10,520.00
		LF	11	1	644.00	$2.00	$1,288.00
		LF	12	1	10,050.00	$2.75	$27,637.50
	Unit Sub Total	**LF**		**7**	**27,692.00**	**$2.35**	**$65,001.00**
	Item Code 208265 Total No. of Proj.			**7**		**Total Amount**	**$65,001.00**
208266	2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	5	1	12,215.00	$2.50	$30,537.50
		LF	6	1	427.00	$14.00	$5,978.00
		LF	7	1	4,520.00	$4.00	$18,080.00
		LF	10	1	2,350.00	$2.50	$5,875.00
		LF	11	1	1,663.00	$2.30	$3,824.90
		LF	12	1	1,560.00	$3.00	$4,680.00
	Unit Sub Total	**LF**		**6**	**22,735.00**	**$3.03**	**$68,975.40**
	Item Code 208266 Total No. of Proj.			**6**		**Total Amount**	**$68,975.40**
208267	2 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	5	1	7,710.00	$2.50	$19,275.00
		LF	10	1	970.00	$3.00	$2,910.00
		LF	11	1	7,056.00	$3.00	$21,168.00
	Unit Sub Total	**LF**		**3**	**15,736.00**	**$2.76**	**$43,353.00**
	Item Code 208267 Total No. of Proj.			**3**		**Total Amount**	**$43,353.00**
208268	3" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	10	1	2,500.00	$4.00	$10,000.00
		LF	12	1	6,285.00	$3.25	$20,426.25
	Unit Sub Total	**LF**		**2**	**8,785.00**	**$3.46**	**$30,426.25**
	Item Code 208268 Total No. of Proj.			**2**		**Total Amount**	**$30,426.25**
208276	2" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	5	1	440.00	$3.80	$1,672.00
	Unit Sub Total	**LF**		**1**	**440.00**	**$3.80**	**$1,672.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208276 Total No. of Proj.			**1**		**Total Amount**	**$1,672.00**
208277	2 1/2" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	5	1	1,475.00	$3.00	$4,425.00
		LF	11	1	3,103.00	$3.25	$10,084.75
	Unit Sub Total	**LF**		**2**	**4,578.00**	**$3.17**	**$14,509.75**
	Item Code 208277 Total No. of Proj.			**2**		**Total Amount**	**$14,509.75**
208278	3" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	5	2	11,345.00	$4.18	$47,387.50
		LF	6	1	700.00	$17.00	$11,900.00
		LF	7	1	700.00	$4.50	$3,150.00
		LF	8	2	7,575.00	$8.40	$63,609.00
		LF	10	1	700.00	$4.00	$2,800.00
		LF	11	3	16,558.00	$4.64	$76,845.00
		LF	12	1	4,530.00	$6.75	$30,577.50
	Unit Sub Total	**LF**		**11**	**42,108.00**	**$5.61**	**$236,269.00**
	Item Code 208278 Total No. of Proj.			**11**		**Total Amount**	**$236,269.00**
208279	4" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	5	1	3,235.00	$4.00	$12,940.00
	Unit Sub Total	**LF**		**1**	**3,235.00**	**$4.00**	**$12,940.00**
	Item Code 208279 Total No. of Proj.			**1**		**Total Amount**	**$12,940.00**
208285	25 MM PLASTIC PIPE (PR 315) (SUPPLY LINE)	M	5	1	290.00	$10.00	$2,900.00
	Unit Sub Total	**M**		**1**	**290.00**	**$10.00**	**$2,900.00**
	Item Code 208285 Total No. of Proj.			**1**		**Total Amount**	**$2,900.00**
208301	IRRIGATION CONTROLLER ENCLOSURE CABINET	EA	4	1	1.00	$3,600.00	$3,600.00
		EA	7	2	12.00	$3,159.42	$37,913.00
		EA	8	1	2.00	$2,000.00	$4,000.00
		EA	12	1	1.00	$1,276.00	$1,276.00
	Unit Sub Total	**EA**		**5**	**16.00**	**$2,924.31**	**$46,789.00**
	Item Code 208301 Total No. of Proj.			**5**		**Total Amount**	**$46,789.00**
208304	WATER METER	EA	1	1	1.00	$6,000.00	$6,000.00
		EA	3	1	7.00	$3,000.00	$21,000.00
		EA	4	5	12.00	$26,132.08	$313,585.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208304	WATER METER	EA	5	1	1.00	$27,695.00	$27,695.00
		EA	7	1	4.00	$5,000.00	$20,000.00
		EA	11	5	8.00	$35,528.13	$284,225.00
		EA	12	1	1.00	$2,890.00	$2,890.00
	Unit Sub Total	**EA**		**15**	**34.00**	**$19,864.56**	**$675,395.00**
	Item Code 208304 Total No. of Proj.			**15**		**Total Amount**	**$675,395.00**
208310	IRRIGATION SLEEVE	LF	2	1	120.00	$60.00	$7,200.00
		LF	3	2	1,051.00	$21.93	$23,045.00
		LF	4	2	580.00	$23.72	$13,760.00
		LF	5	3	130.00	$15.69	$2,040.00
		LF	6	1	682.00	$14.00	$9,548.00
		LF	7	1	200.00	$40.00	$8,000.00
		LF	8	6	306.00	$45.29	$13,860.00
		LF	10	2	300.00	$18.85	$5,655.00
		LF	11	6	2,986.00	$12.13	$36,208.00
		LF	12	2	406.00	$10.81	$4,390.00
	Unit Sub Total	**LF**		**26**	**6,761.00**	**$18.30**	**$123,706.00**
208310	IRRIGATION SLEEVE	M	5	1	16.00	$10.00	$160.00
	Unit Sub Total	**M**		**1**	**16.00**	**$10.00**	**$160.00**
	Item Code 208310 Total No. of Proj.			**27**		**Total Amount**	**$123,866.00**
208421	BACKFLOW PREVENTER ASSEMBLY ENCLOSURE	EA	4	1	2.00	$2,000.00	$4,000.00
		EA	5	1	2.00	$1,500.00	$3,000.00
		EA	7	1	1.00	$3,333.00	$3,333.00
		EA	11	1	1.00	$1,806.00	$1,806.00
		EA	12	2	2.00	$1,539.00	$3,078.00
	Unit Sub Total	**EA**		**6**	**8.00**	**$1,902.13**	**$15,217.00**
	Item Code 208421 Total No. of Proj.			**6**		**Total Amount**	**$15,217.00**
208423	1" BACKFLOW PREVENTER ASSEMBLY	EA	5	1	1.00	$1,250.00	$1,250.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,250.00**	**$1,250.00**
	Item Code 208423 Total No. of Proj.			**1**		**Total Amount**	**$1,250.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208425	1 1/2" BACKFLOW PREVENTER ASSEMBLY	EA	4	1	2.00	$2,300.00	$4,600.00
		EA	5	1	1.00	$1,500.00	$1,500.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$2,033.33**	**$6,100.00**
	Item Code 208425 Total No. of Proj.			**2**		**Total Amount**	**$6,100.00**
208426	2" BACKFLOW PREVENTER ASSEMBLY	EA	7	1	1.00	$3,333.00	$3,333.00
		EA	11	1	1.00	$1,475.00	$1,475.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$2,404.00**	**$4,808.00**
	Item Code 208426 Total No. of Proj.			**2**		**Total Amount**	**$4,808.00**
208428	3" BACKFLOW PREVENTER ASSEMBLY	EA	12	2	2.00	$4,668.50	$9,337.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$4,668.50**	**$9,337.00**
	Item Code 208428 Total No. of Proj.			**2**		**Total Amount**	**$9,337.00**
208439	BACKFLOW PREVENTER ASSEMBLY BLANKETS	EA	5	1	1.00	$150.00	$150.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$150.00**	**$150.00**
	Item Code 208439 Total No. of Proj.			**1**		**Total Amount**	**$150.00**
208461	SPRINKLER (TYPE A-1)	EA	5	2	449.00	$45.00	$20,205.00
		EA	11	3	810.00	$26.57	$21,520.00
	Unit Sub Total	**EA**		**5**	**1,259.00**	**$33.14**	**$41,725.00**
	Item Code 208461 Total No. of Proj.			**5**		**Total Amount**	**$41,725.00**
208462	SPRINKLER (TYPE A-2)	EA	11	1	41.00	$55.00	$2,255.00
	Unit Sub Total	**EA**		**1**	**41.00**	**$55.00**	**$2,255.00**
	Item Code 208462 Total No. of Proj.			**1**		**Total Amount**	**$2,255.00**
208463	SPRINKLER (TYPE A-3)	EA	6	1	13.00	$300.00	$3,900.00
		EA	11	1	41.00	$30.00	$1,230.00
		EA	12	1	30.00	$40.00	$1,200.00
	Unit Sub Total	**EA**		**3**	**84.00**	**$75.36**	**$6,330.00**
	Item Code 208463 Total No. of Proj.			**3**		**Total Amount**	**$6,330.00**
208464	SPRINKLER (TYPE A-4)	EA	11	1	9.00	$55.00	$495.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**9.00**	**$55.00**	**$495.00**
	Item Code 208464	**Total No. of Proj.**			**1**		**Total Amount**	**$495.00**
208465	SPRINKLER (TYPE A-5)		EA	5	2	55.00	$36.55	$2,010.00
			EA	7	1	580.00	$38.61	$22,393.80
			EA	8	1	34.00	$17.00	$578.00
			EA	11	7	1,541.00	$29.70	$45,763.52
			EA	12	2	508.00	$40.04	$20,338.00
		Unit Sub Total	**EA**		**13**	**2,718.00**	**$33.51**	**$91,083.32**
	Item Code 208465	**Total No. of Proj.**			**13**		**Total Amount**	**$91,083.32**
208466	SPRINKLER (TYPE A-6)		EA	2	1	110.00	$30.00	$3,300.00
			EA	4	1	35.00	$37.00	$1,295.00
			EA	11	5	327.00	$45.17	$14,772.10
			EA	12	2	335.00	$45.45	$15,225.00
		Unit Sub Total	**EA**		**9**	**807.00**	**$42.87**	**$34,592.10**
	Item Code 208466	**Total No. of Proj.**			**9**		**Total Amount**	**$34,592.10**
208467	SPRINKLER (TYPE A-7)		EA	4	1	55.00	$40.00	$2,200.00
			EA	11	7	2,658.00	$28.69	$76,252.50
			EA	12	1	110.00	$39.50	$4,345.00
		Unit Sub Total	**EA**		**9**	**2,823.00**	**$29.33**	**$82,797.50**
	Item Code 208467	**Total No. of Proj.**			**9**		**Total Amount**	**$82,797.50**
208468	SPRINKLER (TYPE A-8)		EA	11	6	283.00	$45.02	$12,740.40
			EA	12	1	26.00	$63.00	$1,638.00
		Unit Sub Total	**EA**		**7**	**309.00**	**$46.53**	**$14,378.40**
	Item Code 208468	**Total No. of Proj.**			**7**		**Total Amount**	**$14,378.40**
208471	SPRINKLER (TYPE B-1)		EA	2	1	8.00	$25.00	$200.00
			EA	5	1	220.00	$22.00	$4,840.00
			EA	11	2	350.00	$19.84	$6,944.40
			EA	12	2	389.00	$18.94	$7,366.00
		Unit Sub Total	**EA**		**6**	**967.00**	**$20.01**	**$19,350.40**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208471 Total No. of Proj.			**6**		**Total Amount**	**$19,350.40**
208472	SPRINKLER (TYPE B-2)	EA	5	1	60.00	$25.00	$1,500.00
		EA	11	4	217.00	$28.07	$6,090.60
		EA	12	1	110.00	$37.00	$4,070.00
	Unit Sub Total	**EA**		**6**	**387.00**	**$30.13**	**$11,660.60**
	Item Code 208472 Total No. of Proj.			**6**		**Total Amount**	**$11,660.60**
208473	SPRINKLER (TYPE B-3)	EA	11	2	482.00	$20.67	$9,960.70
	Unit Sub Total	**EA**		**2**	**482.00**	**$20.67**	**$9,960.70**
	Item Code 208473 Total No. of Proj.			**2**		**Total Amount**	**$9,960.70**
208474	SPRINKLER (TYPE B-4)	EA	2	1	3.00	$25.00	$75.00
		EA	11	2	23.00	$38.48	$884.96
	Unit Sub Total	**EA**		**3**	**26.00**	**$36.92**	**$959.96**
	Item Code 208474 Total No. of Proj.			**3**		**Total Amount**	**$959.96**
208475	SPRINKLER (TYPE B-5)	EA	5	1	25.00	$39.00	$975.00
		EA	7	2	370.00	$41.80	$15,467.20
		EA	12	1	50.00	$22.00	$1,100.00
	Unit Sub Total	**EA**		**4**	**445.00**	**$39.42**	**$17,542.20**
	Item Code 208475 Total No. of Proj.			**4**		**Total Amount**	**$17,542.20**
208476	SPRINKLER (TYPE B-6)	EA	5	1	14.00	$40.00	$560.00
	Unit Sub Total	**EA**		**1**	**14.00**	**$40.00**	**$560.00**
	Item Code 208476 Total No. of Proj.			**1**		**Total Amount**	**$560.00**
208480	SPRINKLER (TYPE C-2 MOD)	EA	5	2	246.00	$51.22	$12,600.00
		EA	11	7	8,180.00	$28.02	$229,221.30
	Unit Sub Total	**EA**		**9**	**8,426.00**	**$28.70**	**$241,821.30**
	Item Code 208480 Total No. of Proj.			**9**		**Total Amount**	**$241,821.30**
208481	SPRINKLER (TYPE C-1)	EA	5	1	600.00	$10.00	$6,000.00
		EA	11	1	77.00	$15.00	$1,155.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**2**	**677.00**	**$10.57**	**$7,155.00**
	Item Code 208481	**Total No. of Proj.**			**2**		**Total Amount**	**$7,155.00**
208482	SPRINKLER (TYPE C-2)		EA	2	1	1,790.00	$8.00	$14,320.00
			EA	4	2	1,560.00	$16.29	$25,410.00
			EA	5	3	3,299.00	$17.01	$56,120.00
			EA	7	2	1,688.00	$24.20	$40,854.00
			EA	8	5	8,710.00	$12.66	$110,235.00
		Unit Sub Total	**EA**		**13**	**17,047.00**	**$14.49**	**$246,939.00**
	Item Code 208482	**Total No. of Proj.**			**13**		**Total Amount**	**$246,939.00**
208483	SPRINKLER (TYPE C-3)		EA	7	1	420.00	$25.00	$10,500.00
			EA	8	1	96.00	$55.00	$5,280.00
			EA	12	1	130.00	$24.00	$3,120.00
		Unit Sub Total	**EA**		**3**	**646.00**	**$29.26**	**$18,900.00**
	Item Code 208483	**Total No. of Proj.**			**3**		**Total Amount**	**$18,900.00**
208526	SPRINKLER (TYPE D-1)		EA	4	1	4,330.00	$3.50	$15,155.00
			EA	5	1	1,480.00	$0.60	$888.00
		Unit Sub Total	**EA**		**2**	**5,810.00**	**$2.76**	**$16,043.00**
	Item Code 208526	**Total No. of Proj.**			**2**		**Total Amount**	**$16,043.00**
208560	FILTER ASSEMBLY UNIT		EA	5	1	5.00	$520.00	$2,600.00
			EA	10	1	1.00	$280.00	$280.00
			EA	11	1	8.00	$320.00	$2,560.00
		Unit Sub Total	**EA**		**3**	**14.00**	**$388.57**	**$5,440.00**
	Item Code 208560	**Total No. of Proj.**			**3**		**Total Amount**	**$5,440.00**
208562	CAM COUPLER ASSEMBLY		EA	4	2	11.00	$285.64	$3,142.00
			EA	8	2	18.00	$396.50	$7,137.00
		Unit Sub Total	**EA**		**4**	**29.00**	**$354.45**	**$10,279.00**
	Item Code 208562	**Total No. of Proj.**			**4**		**Total Amount**	**$10,279.00**
208565	REPLACE VALVE BOX COVER		EA	11	3	71.00	$31.08	$2,206.82

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**3**	**71.00**	**$31.08**	**$2,206.82**
	Item Code 208565	**Total No. of Proj.**			**3**		**Total Amount**	**$2,206.82**
208574	1 1/2" GATE VALVE		EA	5	1	1.00	$375.00	$375.00
			EA	11	3	13.00	$242.46	$3,152.00
		Unit Sub Total	**EA**		**4**	**14.00**	**$251.93**	**$3,527.00**
	Item Code 208574	**Total No. of Proj.**			**4**		**Total Amount**	**$3,527.00**
208575	2" GATE VALVE		EA	2	1	27.00	$250.00	$6,750.00
			EA	4	1	8.00	$300.00	$2,400.00
			EA	5	2	6.00	$420.83	$2,525.00
			EA	8	2	16.00	$312.50	$5,000.00
			EA	11	7	213.00	$195.44	$41,628.00
			EA	12	1	4.00	$250.00	$1,000.00
		Unit Sub Total	**EA**		**14**	**274.00**	**$216.43**	**$59,303.00**
	Item Code 208575	**Total No. of Proj.**			**14**		**Total Amount**	**$59,303.00**
208576	2 1/2" GATE VALVE		EA	11	1	41.00	$291.00	$11,931.00
		Unit Sub Total	**EA**		**1**	**41.00**	**$291.00**	**$11,931.00**
	Item Code 208576	**Total No. of Proj.**			**1**		**Total Amount**	**$11,931.00**
208588	3" GATE VALVE		EA	5	2	20.00	$585.00	$11,700.00
			EA	8	1	1.00	$640.00	$640.00
			EA	10	1	9.00	$490.00	$4,410.00
			EA	11	7	92.00	$563.16	$51,811.00
			EA	12	2	11.00	$375.27	$4,128.00
		Unit Sub Total	**EA**		**13**	**133.00**	**$546.53**	**$72,689.00**
	Item Code 208588	**Total No. of Proj.**			**13**		**Total Amount**	**$72,689.00**
208589	4" GATE VALVE		EA	5	1	6.00	$650.00	$3,900.00
			EA	11	1	3.00	$900.00	$2,700.00
		Unit Sub Total	**EA**		**2**	**9.00**	**$733.33**	**$6,600.00**
	Item Code 208589	**Total No. of Proj.**			**2**		**Total Amount**	**$6,600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208594	3/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	2	1	16,000.00	$1.00	$16,000.00
		LF	4	1	5,730.00	$1.43	$8,193.90
		LF	7	1	13,192.00	$2.00	$26,384.00
		LF	8	1	13,800.00	$2.50	$34,500.00
	Unit Sub Total	**LF**		**4**	**48,722.00**	**$1.75**	**$85,077.90**
	Item Code 208594 Total No. of Proj.			**4**		**Total Amount**	**$85,077.90**
208595	1" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	2	1	6,988.00	$1.25	$8,735.00
		LF	4	1	670.00	$1.61	$1,078.70
		LF	5	2	36,669.00	$2.12	$77,731.50
		LF	7	1	3,265.00	$2.15	$7,019.75
		LF	8	4	32,010.00	$2.82	$90,182.50
		LF	11	7	261,210.00	$1.98	$517,161.10
		LF	12	1	10,515.00	$2.85	$29,967.75
	Unit Sub Total	**LF**		**17**	**351,327.00**	**$2.08**	**$731,876.30**
	Item Code 208595 Total No. of Proj.			**17**		**Total Amount**	**$731,876.30**
208596	1 1/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	2	1	6,500.00	$1.40	$9,100.00
		LF	4	1	1,620.00	$1.78	$2,883.60
		LF	7	1	4,720.00	$2.22	$10,478.40
		LF	8	2	3,260.00	$3.58	$11,655.00
		LF	11	7	107,473.00	$2.21	$237,347.19
		LF	12	1	2,485.00	$2.90	$7,206.50
	Unit Sub Total	**LF**		**13**	**126,058.00**	**$2.21**	**$278,670.69**
	Item Code 208596 Total No. of Proj.			**13**		**Total Amount**	**$278,670.69**
208597	1 1/2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	2	1	420.00	$1.50	$630.00
		LF	4	1	4,500.00	$1.93	$8,685.00
		LF	5	2	7,622.00	$2.98	$22,715.50
		LF	7	1	2,273.00	$2.33	$5,296.09
		LF	8	4	22,260.00	$3.52	$78,260.00
		LF	11	7	39,805.00	$2.23	$88,889.01
		LF	12	1	430.00	$2.95	$1,268.50
	Unit Sub Total	**LF**		**17**	**77,310.00**	**$2.66**	**$205,744.10**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208597 Total No. of Proj.			**17**		**Total Amount**	**$205,744.10**
208598	2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	EA	2	1	11.00	$25.00	$275.00
	Unit Sub Total	**EA**		**1**	**11.00**	**$25.00**	**$275.00**
208598	2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	2	1	1,600.00	$2.00	$3,200.00
		LF	4	2	2,345.00	$3.95	$9,254.70
		LF	5	2	1,918.00	$4.44	$8,518.00
		LF	7	1	4,306.00	$2.95	$12,702.70
		LF	8	3	9,340.00	$4.01	$37,420.00
		LF	11	7	77,966.00	$2.59	$201,638.22
		LF	12	1	3,555.00	$3.35	$11,909.25
	Unit Sub Total	**LF**		**17**	**101,030.00**	**$2.82**	**$284,642.87**
	Item Code 208598 Total No. of Proj.			**18**		**Total Amount**	**$284,917.87**
208599	2 1/2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	2	1	22,000.00	$2.25	$49,500.00
		LF	5	1	40.00	$11.00	$440.00
		LF	7	1	590.00	$3.15	$1,858.50
		LF	11	3	3,932.00	$3.11	$12,211.50
	Unit Sub Total	**LF**		**6**	**26,562.00**	**$2.41**	**$64,010.00**
	Item Code 208599 Total No. of Proj.			**6**		**Total Amount**	**$64,010.00**
208620	1 1/2" MANUAL CONTROL VALVE	EA	4	1	15.00	$122.00	$1,830.00
	Unit Sub Total	**EA**		**1**	**15.00**	**$122.00**	**$1,830.00**
	Item Code 208620 Total No. of Proj.			**1**		**Total Amount**	**$1,830.00**
208626	1" WYE STRAINER	EA	4	1	1.00	$230.00	$230.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$230.00**	**$230.00**
	Item Code 208626 Total No. of Proj.			**1**		**Total Amount**	**$230.00**
208628	1 1/2" WYE STRAINER	EA	4	2	12.00	$265.83	$3,190.00
		EA	8	2	18.00	$242.00	$4,356.00
		EA	10	1	8.00	$207.00	$1,656.00
	Unit Sub Total	**EA**		**5**	**38.00**	**$242.16**	**$9,202.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208628 Total No. of Proj.			**5**		**Total Amount**	**$9,202.00**
208630	2" WYE STRAINER	EA	2	1	23.00	$250.00	$5,750.00
		EA	5	1	1.00	$800.00	$800.00
		EA	8	2	11.00	$313.64	$3,450.00
	Unit Sub Total	**EA**		**4**	**35.00**	**$285.71**	**$10,000.00**
	Item Code 208630 Total No. of Proj.			**4**		**Total Amount**	**$10,000.00**
208645	3/4" QUICK COUPLING VALVE	EA	4	1	5.00	$260.00	$1,300.00
		EA	11	1	3.00	$266.00	$798.00
	Unit Sub Total	**EA**		**2**	**8.00**	**$262.25**	**$2,098.00**
	Item Code 208645 Total No. of Proj.			**2**		**Total Amount**	**$2,098.00**
208646	1 1/2" QUICK COUPLING VALVE	EA	5	1	1.00	$300.00	$300.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$300.00**	**$300.00**
	Item Code 208646 Total No. of Proj.			**1**		**Total Amount**	**$300.00**
208649	QUICK COUPLING VALVE	EA	4	1	65.00	$155.00	$10,075.00
	Unit Sub Total	**EA**		**1**	**65.00**	**$155.00**	**$10,075.00**
	Item Code 208649 Total No. of Proj.			**1**		**Total Amount**	**$10,075.00**
208670	CHECK VALVE	EA	4	1	16.00	$100.00	$1,600.00
	Unit Sub Total	**EA**		**1**	**16.00**	**$100.00**	**$1,600.00**
	Item Code 208670 Total No. of Proj.			**1**		**Total Amount**	**$1,600.00**
208683	BALL VALVE	EA	4	1	5.00	$90.00	$450.00
		EA	5	1	9.00	$500.00	$4,500.00
		EA	7	2	50.00	$355.54	$17,776.80
		EA	8	3	30.00	$242.50	$7,275.00
		EA	11	2	12.00	$393.00	$4,716.00
		EA	12	2	20.00	$198.00	$3,960.00
	Unit Sub Total	**EA**		**11**	**126.00**	**$306.97**	**$38,677.80**
	Item Code 208683 Total No. of Proj.			**11**		**Total Amount**	**$38,677.80**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208706	4" CONDUIT	LF	3	1	40.00	$30.00	$1,200.00
	Unit Sub Total	**LF**		**1**	**40.00**	**$30.00**	**$1,200.00**
	Item Code 208706 Total No. of Proj.			**1**		**Total Amount**	**$1,200.00**
208716	4" ALTERNATIVE CONDUIT	LF	3	1	270.00	$9.00	$2,430.00
	Unit Sub Total	**LF**		**1**	**270.00**	**$9.00**	**$2,430.00**
	Item Code 208716 Total No. of Proj.			**1**		**Total Amount**	**$2,430.00**
208718	8" ALTERNATIVE CONDUIT	LF	3	1	170.00	$16.00	$2,720.00
	Unit Sub Total	**LF**		**1**	**170.00**	**$16.00**	**$2,720.00**
	Item Code 208718 Total No. of Proj.			**1**		**Total Amount**	**$2,720.00**
208731	200 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	M	5	1	140.00	$100.00	$14,000.00
		M	7	1	12.00	$170.00	$2,040.00
		M	11	2	258.00	$127.56	$32,910.00
	Unit Sub Total	**M**		**4**	**410.00**	**$119.39**	**$48,950.00**
	Item Code 208731 Total No. of Proj.			**4**		**Total Amount**	**$48,950.00**
208732	250 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	M	5	1	140.00	$120.00	$16,800.00
		M	7	2	180.00	$167.78	$30,200.00
	Unit Sub Total	**M**		**3**	**320.00**	**$146.88**	**$47,000.00**
	Item Code 208732 Total No. of Proj.			**3**		**Total Amount**	**$47,000.00**
208733	300 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	M	5	1	110.00	$125.00	$13,750.00
	Unit Sub Total	**M**		**1**	**110.00**	**$125.00**	**$13,750.00**
	Item Code 208733 Total No. of Proj.			**1**		**Total Amount**	**$13,750.00**
208738	8" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	LF	1	1	68.00	$45.00	$3,060.00
		LF	3	2	680.00	$65.59	$44,600.00
		LF	4	4	1,690.00	$33.49	$56,594.40
		LF	5	1	200.00	$21.00	$4,200.00
		LF	6	1	99.00	$100.00	$9,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208738	8" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	LF	10	1	3,770.00	$30.00	$113,100.00
		LF	12	1	800.00	$24.00	$19,200.00
	Unit Sub Total	**LF**		**11**	**7,307.00**	**$34.30**	**$250,654.40**
	Item Code 208738 Total No. of Proj.			**11**		**Total Amount**	**$250,654.40**
208739	10" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	LF	4	1	130.00	$46.00	$5,980.00
		LF	12	1	230.00	$25.00	$5,750.00
	Unit Sub Total	**LF**		**2**	**360.00**	**$32.58**	**$11,730.00**
	Item Code 208739 Total No. of Proj.			**2**		**Total Amount**	**$11,730.00**
208740	12" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	LF	4	1	370.00	$49.98	$18,492.60
		LF	7	1	170.00	$70.00	$11,900.00
	Unit Sub Total	**LF**		**2**	**540.00**	**$56.28**	**$30,392.60**
	Item Code 208740 Total No. of Proj.			**2**		**Total Amount**	**$30,392.60**
208756	6" CORRUGATED STEEL PIPE CONDUIT (.064" THICK)	LF	1	1	140.00	$38.00	$5,320.00
		LF	8	1	50.00	$200.00	$10,000.00
	Unit Sub Total	**LF**		**2**	**190.00**	**$80.63**	**$15,320.00**
	Item Code 208756 Total No. of Proj.			**2**		**Total Amount**	**$15,320.00**
208762	12" CORRUGATED STEEL PIPE CONDUIT (.064" THICK)	LF	8	1	170.00	$8.00	$1,360.00
	Unit Sub Total	**LF**		**1**	**170.00**	**$8.00**	**$1,360.00**
	Item Code 208762 Total No. of Proj.			**1**		**Total Amount**	**$1,360.00**
208798	200 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	5	1	22.00	$600.00	$13,200.00
	Unit Sub Total	**M**		**1**	**22.00**	**$600.00**	**$13,200.00**
	Item Code 208798 Total No. of Proj.			**1**		**Total Amount**	**$13,200.00**
208801	4" WELDED STEEL PIPE CONDUIT (.237" THICK)	LF	11	1	30.00	$60.00	$1,800.00
	Unit Sub Total	**LF**		**1**	**30.00**	**$60.00**	**$1,800.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208801 Total No. of Proj.			**1**		**Total Amount**	**$1,800.00**
208808	8" WELDED STEEL PIPE CONDUIT (.250" THICK)	LF	3	1	34.00	$200.00	$6,800.00
		LF	4	5	1,410.00	$98.62	$139,053.00
		LF	5	1	65.00	$275.00	$17,875.00
		LF	11	1	110.00	$70.00	$7,700.00
		LF	12	1	42.00	$212.00	$8,904.00
	Unit Sub Total	**LF**		**9**	**1,661.00**	**$108.57**	**$180,332.00**
	Item Code 208808 Total No. of Proj.			**9**		**Total Amount**	**$180,332.00**
208809	10" WELDED STEEL PIPE CONDUIT (.250" THICK)	LF	5	1	370.00	$70.00	$25,900.00
		LF	11	3	234.00	$167.10	$39,102.00
	Unit Sub Total	**LF**		**4**	**604.00**	**$107.62**	**$65,002.00**
	Item Code 208809 Total No. of Proj.			**4**		**Total Amount**	**$65,002.00**
208812	12" WELDED STEEL PIPE CONDUIT (.250" THICK)	LF	4	1	38.00	$66.30	$2,519.40
		LF	5	1	310.00	$72.00	$22,320.00
		LF	12	1	50.00	$100.00	$5,000.00
	Unit Sub Total	**LF**		**3**	**398.00**	**$74.97**	**$29,839.40**
	Item Code 208812 Total No. of Proj.			**3**		**Total Amount**	**$29,839.40**
208905	EXTEND 6" CONDUIT	LF	3	2	480.00	$51.88	$24,900.00
		LF	6	1	10.00	$11.00	$110.00
		LF	12	2	160.00	$94.00	$15,040.00
	Unit Sub Total	**LF**		**5**	**650.00**	**$61.62**	**$40,050.00**
	Item Code 208905 Total No. of Proj.			**5**		**Total Amount**	**$40,050.00**
208906	EXTEND 8" CONDUIT	LF	2	1	16.00	$100.00	$1,600.00
		LF	3	1	56.00	$110.25	$6,174.00
		LF	4	2	317.00	$30.44	$9,648.65
		LF	6	1	130.00	$60.00	$7,800.00
		LF	12	1	640.00	$45.00	$28,800.00
	Unit Sub Total	**LF**		**6**	**1,159.00**	**$46.61**	**$54,022.65**
	Item Code 208906 Total No. of Proj.			**6**		**Total Amount**	**$54,022.65**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208907	EXTEND 10" CONDUIT	LF	2	1	550.00	$65.00	$35,750.00
		LF	11	1	70.00	$55.00	$3,850.00
		LF	12	1	490.00	$36.00	$17,640.00
	Unit Sub Total	**LF**		**3**	**1,110.00**	**$51.57**	**$57,240.00**
	Item Code 208907 Total No. of Proj.			**3**		**Total Amount**	**$57,240.00**
208909	EXTEND 200 MM CONDUIT	M	11	1	55.00	$725.00	$39,875.00
	Unit Sub Total	**M**		**1**	**55.00**	**$725.00**	**$39,875.00**
	Item Code 208909 Total No. of Proj.			**1**		**Total Amount**	**$39,875.00**
208910	EXTEND 250 MM CONDUIT	M	5	1	4.00	$200.00	$800.00
		M	7	1	1.00	$10.00	$10.00
	Unit Sub Total	**M**		**2**	**5.00**	**$162.00**	**$810.00**
	Item Code 208910 Total No. of Proj.			**2**		**Total Amount**	**$810.00**
209202	RECYCLED WATER WARNING SIGNS	LS	5	1	1.00	$1,300.00	$1,300.00
		LS	7	1	1.00	$1,000.00	$1,000.00
		LS	11	6	6.00	$1,589.83	$9,539.00
	Unit Sub Total	**LS**		**8**	**8.00**	**$1,479.88**	**$11,839.00**
	Item Code 209202 Total No. of Proj.			**8**		**Total Amount**	**$11,839.00**
209502	BOOSTER PUMP	EA	12	1	1.00	$30,000.00	$30,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$30,000.00**	**$30,000.00**
	Item Code 209502 Total No. of Proj.			**1**		**Total Amount**	**$30,000.00**
209801	MAINTENANCE VEHICLE PULLOUT	EA	8	1	2.00	$12,500.00	$25,000.00
		EA	11	1	2.00	$3,500.00	$7,000.00
	Unit Sub Total	**EA**		**2**	**4.00**	**$8,000.00**	**$32,000.00**
	Item Code 209801 Total No. of Proj.			**2**		**Total Amount**	**$32,000.00**
220101	FINISHING ROADWAY	LS	2	2	2.00	$1,500.00	$3,000.00
		LS	4	3	3.00	$28,264.00	$84,792.00
		LS	5	1	1.00	$200,000.00	$200,000.00
		LS	7	1	1.00	$9,900.00	$9,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
220101	FINISHING ROADWAY		LS	8	1	1.00	$75,000.00	$75,000.00
			LS	11	3	3.00	$31,333.33	$94,000.00
		Unit Sub Total	**LS**		**11**	**11.00**	**$42,426.55**	**$466,692.00**
	Item Code 220101	**Total No. of Proj.**			**11**		**Total Amount**	**$466,692.00**
250101	CLASS 1 AGGREGATE SUBBASE		CY	5	1	70.00	$115.00	$8,050.00
		Unit Sub Total	**CY**		**1**	**70.00**	**$115.00**	**$8,050.00**
250101	CLASS 1 AGGREGATE SUBBASE		M3	8	1	12,800.00	$13.00	$166,400.00
		Unit Sub Total	**M3**		**1**	**12,800.00**	**$13.00**	**$166,400.00**
	Item Code 250101	**Total No. of Proj.**			**2**		**Total Amount**	**$174,450.00**
250201	CLASS 2 AGGREGATE SUBBASE		CY	1	1	1,320.00	$85.00	$112,200.00
			CY	3	1	7,710.00	$28.00	$215,880.00
			CY	4	1	2,490.00	$40.00	$99,600.00
			CY	6	4	23,241.00	$13.90	$323,090.00
			CY	8	3	4,052.00	$23.71	$96,080.00
			CY	10	1	78,300.00	$28.00	$2,192,400.00
			CY	12	7	57,901.00	$12.78	$740,075.00
		Unit Sub Total	**CY**		**18**	**175,014.00**	**$21.59**	**$3,779,325.00**
250201	CLASS 2 AGGREGATE SUBBASE		M3	8	1	84.00	$22.00	$1,848.00
		Unit Sub Total	**M3**		**1**	**84.00**	**$22.00**	**$1,848.00**
	Item Code 250201	**Total No. of Proj.**			**19**		**Total Amount**	**$3,781,173.00**
250301	CLASS 3 AGGREGATE SUBBASE		CY	12	1	18,000.00	$8.50	$153,000.00
		Unit Sub Total	**CY**		**1**	**18,000.00**	**$8.50**	**$153,000.00**
	Item Code 250301	**Total No. of Proj.**			**1**		**Total Amount**	**$153,000.00**
250401	CLASS 4 AGGREGATE SUBBASE		CY	4	13	180,010.00	$13.74	$2,473,900.00
			CY	11	1	700.00	$9.75	$6,825.00
		Unit Sub Total	**CY**		**14**	**180,710.00**	**$13.73**	**$2,480,725.00**
250401	CLASS 4 AGGREGATE SUBBASE		M3	4	1	4,400.00	$25.00	$110,000.00
			M3	7	2	21,424.00	$30.11	$645,120.00
			M3	11	1	4,740.00	$23.00	$109,020.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**4**	**30,564.00**	**$28.27**	**$864,140.00**
	Item Code 250401	**Total No. of Proj.**			**18**		**Total Amount**	**$3,344,865.00**
260201	CLASS 2 AGGREGATE BASE		CY	1	15	51,868.00	$41.19	$2,136,470.00
			CY	2	16	123,008.00	$34.15	$4,201,013.81
			CY	3	18	390,941.00	$21.67	$8,470,778.70
			CY	4	7	3,437.00	$53.77	$184,795.00
			CY	5	6	27,260.00	$35.47	$967,005.00
			CY	6	15	546,791.00	$24.34	$13,310,168.00
			CY	7	1	2,180.00	$28.00	$61,040.00
			CY	8	7	68,470.00	$29.51	$2,020,665.00
			CY	9	3	1,964.00	$87.40	$171,650.00
			CY	10	9	22,162.00	$37.25	$825,509.00
			CY	11	9	21,472.00	$28.30	$607,660.00
			CY	12	5	18,784.00	$26.72	$501,850.00
		Unit Sub Total	**CY**		**111**	**1,278,337.00**	**$26.17**	**$33,458,604.51**
260201	CLASS 2 AGGREGATE BASE		M3	4	1	1,700.00	$50.00	$85,000.00
			M3	5	1	104,000.00	$25.00	$2,600,000.00
			M3	7	2	18,351.00	$40.24	$738,375.00
			M3	8	1	7,660.00	$40.00	$306,400.00
			M3	10	2	32,820.00	$36.73	$1,205,632.00
			M3	11	2	39,500.00	$23.28	$919,600.00
		Unit Sub Total	**M3**		**9**	**204,031.00**	**$28.70**	**$5,855,007.00**
260201	CLASS 2 AGGREGATE BASE		TON	2	1	18,600.00	$17.00	$316,200.00
		Unit Sub Total	**TON**		**1**	**18,600.00**	**$17.00**	**$316,200.00**
	Item Code 260201	**Total No. of Proj.**			**121**		**Total Amount**	**$39,629,811.51**
260210	AGGREGATE BASE (APPROACH SLAB)		CY	1	1	25.00	$825.00	$20,625.00
			CY	2	2	57.00	$232.89	$13,275.00
			CY	3	5	394.00	$136.76	$53,885.00
			CY	4	4	201.00	$43.63	$8,770.00
			CY	5	1	35.00	$35.00	$1,225.00
			CY	6	2	52.00	$255.77	$13,300.00
			CY	7	13	755.50	$576.89	$435,840.00
			CY	8	2	35.00	$511.71	$17,910.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
260210	AGGREGATE BASE (APPROACH SLAB)	CY	10	2	273.00	$75.16	$20,520.00
		CY	11	3	152.00	$85.11	$12,937.00
		CY	12	6	98.00	$328.57	$32,200.00
	Unit Sub Total	**CY**		**41**	**2,077.50**	**$303.48**	**$630,487.00**
260210	AGGREGATE BASE (APPROACH SLAB)	M3	7	1	5.00	$200.00	$1,000.00
		M3	11	1	18.00	$50.00	$900.00
	Unit Sub Total	**M3**		**2**	**23.00**	**$82.61**	**$1,900.00**
	Item Code 260210 Total No. of Proj.			**43**		**Total Amount**	**$632,387.00**
260301	CLASS 3 AGGREGATE BASE	CY	3	1	320.00	$112.00	$35,840.00
		CY	4	10	32,621.00	$32.66	$1,065,273.00
		CY	7	14	56,753.00	$31.10	$1,764,884.54
		CY	10	1	802.00	$40.00	$32,080.00
	Unit Sub Total	**CY**		**26**	**90,496.00**	**$32.02**	**$2,898,077.54**
260301	CLASS 3 AGGREGATE BASE	M3	7	5	51,430.00	$33.82	$1,739,245.00
	Unit Sub Total	**M3**		**5**	**51,430.00**	**$33.82**	**$1,739,245.00**
	Item Code 260301 Total No. of Proj.			**31**		**Total Amount**	**$4,637,322.54**
270011	CEMENT TREATED BASE (PLANT-MIXED, CLASS A)	CY	2	1	3,500.00	$90.00	$315,000.00
	Unit Sub Total	**CY**		**1**	**3,500.00**	**$90.00**	**$315,000.00**
	Item Code 270011 Total No. of Proj.			**1**		**Total Amount**	**$315,000.00**
270065	ASPHALTIC EMULSION (CURING SEAL)	TON	12	1	20.00	$600.00	$12,000.00
	Unit Sub Total	**TON**		**1**	**20.00**	**$600.00**	**$12,000.00**
	Item Code 270065 Total No. of Proj.			**1**		**Total Amount**	**$12,000.00**
280000	LEAN CONCRETE BASE	CY	1	1	290.00	$275.00	$79,750.00
		CY	4	8	91,730.00	$104.96	$9,628,150.00
		CY	5	1	70.00	$190.00	$13,300.00
		CY	6	3	45,010.00	$95.18	$4,283,920.00
		CY	7	8	28,520.00	$121.57	$3,467,217.78
		CY	8	3	2,825.00	$100.92	$285,100.00
		CY	12	3	22,289.00	$96.28	$2,146,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**CY**		**27**	**190,734.00**	**$104.35**	**$19,903,437.78**
280000	LEAN CONCRETE BASE		M3	4	1	1,110.00	$115.00	$127,650.00
			M3	5	1	5,810.00	$150.00	$871,500.00
			M3	7	4	40,300.00	$93.04	$3,749,500.00
			M3	8	1	60.00	$220.00	$13,200.00
		Unit Sub Total	**M3**		**7**	**47,280.00**	**$100.72**	**$4,761,850.00**
	Item Code 280000	**Total No. of Proj.**			**34**		**Total Amount**	**$24,665,287.78**
290201	ASPHALT TREATED PERMEABLE BASE		CY	4	3	1,502.00	$139.55	$209,605.00
			CY	12	1	200.00	$153.00	$30,600.00
		Unit Sub Total	**CY**		**4**	**1,702.00**	**$141.13**	**$240,205.00**
	Item Code 290201	**Total No. of Proj.**			**4**		**Total Amount**	**$240,205.00**
365001	SAND COVER		TON	1	3	770.00	$59.14	$45,540.00
			TON	2	6	1,570.00	$82.65	$129,760.00
			TON	3	6	1,737.00	$48.64	$84,487.00
			TON	5	1	50.00	$120.00	$6,000.00
			TON	6	5	798.00	$48.33	$38,571.00
			TON	7	1	510.00	$30.00	$15,300.00
			TON	8	2	460.00	$50.50	$23,230.00
			TON	9	3	1,925.00	$11.84	$22,800.00
			TON	10	1	330.00	$1.00	$330.00
			TON	11	2	1,520.00	$35.99	$54,700.00
		Unit Sub Total	**TON**		**30**	**9,670.00**	**$43.51**	**$420,718.00**
	Item Code 365001	**Total No. of Proj.**			**30**		**Total Amount**	**$420,718.00**
370120	ASPHALT-RUBBER BINDER		TON	2	3	1,650.00	$990.91	$1,635,000.00
			TON	4	1	18.00	$997.00	$17,946.00
			TON	7	3	2,830.00	$884.28	$2,502,500.00
			TON	9	1	1,460.00	$750.00	$1,095,000.00
			TON	11	3	2,390.00	$1,317.37	$3,148,520.00
		Unit Sub Total	**TON**		**11**	**8,348.00**	**$1,006.11**	**$8,398,966.00**
	Item Code 370120	**Total No. of Proj.**			**11**		**Total Amount**	**$8,398,966.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
373900	ASPHALTIC EMULSION	TON	3	1	300.00	$500.00	$150,000.00
		TON	9	2	270.00	$289.44	$78,150.00
	Unit Sub Total	**TON**		**3**	**570.00**	**$400.26**	**$228,150.00**
	Item Code 373900 Total No. of Proj.			**3**		**Total Amount**	**$228,150.00**
374002	ASPHALTIC EMULSION (FOG SEAL COAT)	TON	1	3	110.00	$704.55	$77,500.00
		TON	2	7	379.00	$523.92	$198,565.00
		TON	3	17	599.10	$526.15	$315,219.00
		TON	4	4	168.10	$589.26	$99,055.00
		TON	5	16	73.50	$528.71	$38,860.50
		TON	6	6	272.00	$255.08	$69,381.00
		TON	7	4	116.00	$770.89	$89,423.00
		TON	8	8	1,290.00	$508.87	$656,444.00
		TON	9	3	133.00	$509.66	$67,785.00
		TON	10	2	92.00	$298.04	$27,420.00
		TON	11	14	746.70	$529.93	$395,695.00
		TON	12	1	24.00	$500.00	$12,000.00
	Unit Sub Total	**TON**		**85**	**4,003.40**	**$511.40**	**$2,047,347.50**
374002	ASPHALTIC EMULSION (FOG SEAL COAT)	TONN	11	2	13.50	$1,466.67	$19,800.00
	Unit Sub Total	**TONN**		**2**	**13.50**	**$1,466.67**	**$19,800.00**
	Item Code 374002 Total No. of Proj.			**87**		**Total Amount**	**$2,067,147.50**
374207	CRACK TREATMENT	LNMI	1	5	190.00	$4,870.39	$925,374.00
		LNMI	3	19	410.50	$3,407.63	$1,398,834.00
		LNMI	4	17	147.00	$4,503.27	$661,980.00
		LNMI	6	5	29.80	$3,294.97	$98,190.00
		LNMI	7	6	242.30	$3,519.19	$852,699.44
		LNMI	10	1	4.10	$5,571.00	$22,841.10
	Unit Sub Total	**LNMI**		**53**	**1,023.70**	**$3,868.24**	**$3,959,918.54**
	Item Code 374207 Total No. of Proj.			**53**		**Total Amount**	**$3,959,918.54**
374492	ASPHALTIC EMULSION (POLYMER MODIFIED)	TON	1	2	460.00	$616.13	$283,420.00
		TON	3	1	910.00	$550.00	$500,500.00
		TON	6	1	490.00	$550.00	$269,500.00
		TON	9	1	50.00	$400.00	$20,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**TON**		**5**	**1,910.00**	**$562.00**	**$1,073,420.00**
	Item Code 374492	**Total No. of Proj.**			**5**		**Total Amount**	**$1,073,420.00**
375021	SCREENINGS (MEDIUM FINE)		TON	1	2	3,850.00	$50.08	$192,790.00
		Unit Sub Total	**TON**		**2**	**3,850.00**	**$50.08**	**$192,790.00**
	Item Code 375021	**Total No. of Proj.**			**2**		**Total Amount**	**$192,790.00**
375022	SCREENINGS (MEDIUM)		TON	3	1	8,150.00	$19.00	$154,850.00
			TON	6	1	4,400.00	$28.00	$123,200.00
			TON	9	1	420.00	$50.00	$21,000.00
		Unit Sub Total	**TON**		**3**	**12,970.00**	**$23.06**	**$299,050.00**
	Item Code 375022	**Total No. of Proj.**			**3**		**Total Amount**	**$299,050.00**
375030	SCREENINGS (HOT-APPLIED)		TON	2	5	12,920.00	$89.20	$1,152,440.00
			TON	3	2	3,980.00	$74.40	$296,100.00
			TON	4	1	130.00	$502.00	$65,260.00
			TON	7	3	19,620.00	$157.01	$3,080,550.00
			TON	9	1	9,120.00	$88.00	$802,560.00
			TON	11	3	19,130.00	$162.05	$3,100,040.00
		Unit Sub Total	**TON**		**15**	**64,900.00**	**$130.92**	**$8,496,950.00**
	Item Code 375030	**Total No. of Proj.**			**15**		**Total Amount**	**$8,496,950.00**
377501	SLURRY SEAL		TON	3	1	640.00	$130.00	$83,200.00
			TON	4	1	36.00	$1,200.00	$43,200.00
			TON	5	1	7.00	$982.00	$6,874.00
			TON	6	4	13,550.00	$131.38	$1,780,167.60
			TON	7	4	9,110.00	$153.58	$1,399,081.00
			TON	8	1	1,970.00	$222.00	$437,340.00
			TON	10	1	1,410.00	$86.50	$121,965.00
			TON	11	3	480.00	$284.38	$136,500.00
		Unit Sub Total	**TON**		**16**	**27,203.00**	**$147.35**	**$4,008,327.60**
	Item Code 377501	**Total No. of Proj.**			**16**		**Total Amount**	**$4,008,327.60**
378000	MICRO-SURFACING		TON	3	1	860.00	$146.00	$125,560.00
			TON	5	4	7,740.00	$154.14	$1,193,071.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**TON**		**5**	**8,600.00**	**$153.33**	**$1,318,631.00**
	Item Code 378000 Total No. of Proj.			**5**		**Total Amount**	**$1,318,631.00**
390095	REPLACE ASPHALT CONCRETE SURFACING	CY	1	8	10,160.00	$268.57	$2,728,678.20
		CY	2	11	18,720.00	$190.19	$3,560,330.00
		CY	3	23	53,638.00	$171.47	$9,197,190.00
		CY	4	13	11,347.00	$219.73	$2,493,306.45
		CY	5	2	980.00	$263.08	$257,820.00
		CY	6	5	12,721.00	$147.12	$1,871,462.00
		CY	7	4	3,063.00	$183.16	$561,030.00
		CY	8	8	34,840.00	$195.13	$6,798,210.00
		CY	10	1	3,410.00	$180.00	$613,800.00
		CY	11	3	1,558.00	$287.73	$448,289.00
	Unit Sub Total	**CY**		**78**	**150,437.00**	**$189.65**	**$28,530,115.65**
390095	REPLACE ASPHALT CONCRETE SURFACING	TON	3	1	40.00	$250.00	$10,000.00
	Unit Sub Total	**TON**		**1**	**40.00**	**$250.00**	**$10,000.00**
	Item Code 390095 Total No. of Proj.			**79**		**Total Amount**	**$28,540,115.65**
390126	RUBBERIZED ASPHALT CONCRETE (TYPE G)	TON	12	1	70.00	$198.00	$13,860.00
	Unit Sub Total	**TON**		**1**	**70.00**	**$198.00**	**$13,860.00**
	Item Code 390126 Total No. of Proj.			**1**		**Total Amount**	**$13,860.00**
390129	HOT MIX ASPHALT (TYPE C)	TON	7	1	15,100.00	$64.20	$969,420.00
		TON	8	6	130,120.00	$81.84	$10,648,900.00
		TON	11	2	13,890.00	$98.67	$1,370,460.00
	Unit Sub Total	**TON**		**9**	**159,110.00**	**$81.63**	**$12,988,780.00**
	Item Code 390129 Total No. of Proj.			**9**		**Total Amount**	**$12,988,780.00**
390130	HOT MIX ASPHALT	TON	12	2	214.00	$151.17	$32,350.00
	Unit Sub Total	**TON**		**2**	**214.00**	**$151.17**	**$32,350.00**
	Item Code 390130 Total No. of Proj.			**2**		**Total Amount**	**$32,350.00**
390131	HOT MIX ASPHALT	TON	1	3	119,200.00	$88.86	$10,592,300.00
		TON	2	13	561,250.00	$79.74	$44,752,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
390131	HOT MIX ASPHALT		TON	3	8	455,600.00	$62.16	$28,322,280.00
			TON	4	7	217,900.00	$76.53	$16,675,680.00
			TON	5	2	40,100.00	$77.84	$3,121,400.00
			TON	6	7	743,200.00	$61.62	$45,794,420.00
			TON	7	1	18,100.00	$85.00	$1,538,500.00
			TON	8	6	137,300.00	$94.21	$12,934,750.00
			TON	9	2	35,200.00	$99.32	$3,496,000.00
			TON	10	5	165,900.00	$71.23	$11,817,185.00
			TON	11	2	30,800.00	$70.00	$2,156,000.00
			TON	12	2	123,100.00	$67.10	$8,260,150.00
		Unit Sub Total	**TON**		**58**	**2,647,650.00**	**$71.56**	**$189,461,565.00**
390131	HOT MIX ASPHALT		TONN	5	1	155,000.00	$77.00	$11,935,000.00
			TONN	7	3	136,500.00	$78.25	$10,681,480.00
			TONN	8	1	29,700.00	$69.00	$2,049,300.00
			TONN	10	1	16,500.00	$81.50	$1,344,750.00
			TONN	11	1	24,900.00	$90.00	$2,241,000.00
		Unit Sub Total	**TONN**		**7**	**362,600.00**	**$77.91**	**$28,251,530.00**
	Item Code 390131	**Total No. of Proj.**			**65**		**Total Amount**	**$217,713,095.00**
390132	HOT MIX ASPHALT (TYPE A)		TON	1	20	46,945.60	$94.81	$4,450,768.70
			TON	2	18	50,500.00	$104.54	$5,279,230.48
			TON	3	23	125,378.40	$83.66	$10,488,894.00
			TON	4	34	275,902.00	$79.09	$21,820,064.60
			TON	5	21	68,646.00	$97.24	$6,675,376.00
			TON	6	20	72,770.00	$92.33	$6,718,742.00
			TON	7	4	11,219.00	$80.96	$908,295.00
			TON	8	11	20,338.00	$101.49	$2,064,100.00
			TON	9	8	42,490.00	$110.15	$4,680,100.00
			TON	10	17	24,420.00	$89.77	$2,192,155.00
			TON	11	9	48,440.00	$94.66	$4,585,470.00
			TON	12	11	15,008.00	$80.53	$1,208,548.00
		Unit Sub Total	**TON**		**196**	**802,057.00**	**$88.61**	**$71,071,743.78**
390132	HOT MIX ASPHALT (TYPE A)		TONN	4	1	5,380.00	$90.00	$484,200.00
			TONN	11	2	24,620.00	$83.40	$2,053,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**TONN**		**3**	**30,000.00**	**$84.59**	**$2,537,600.00**
	Item Code 390132	**Total No. of Proj.**			**199**		**Total Amount**	**$73,609,343.78**
390133	HOT MIX ASPHALT (TYPE B)		TON	2	1	56.00	$320.00	$17,920.00
			TON	3	1	60.00	$200.00	$12,000.00
			TON	4	2	89.00	$493.54	$43,925.00
			TON	6	3	543.00	$107.62	$58,437.00
			TON	7	10	105,878.00	$77.88	$8,245,828.40
			TON	10	1	1,200.00	$92.00	$110,400.00
		Unit Sub Total	**TON**		**18**	**107,826.00**	**$78.72**	**$8,488,510.40**
390133	HOT MIX ASPHALT (TYPE B)		TONN	7	2	3,920.00	$119.79	$469,570.00
			TONN	8	1	76.00	$100.00	$7,600.00
			TONN	10	1	1,800.00	$78.50	$141,300.00
		Unit Sub Total	**TONN**		**4**	**5,796.00**	**$106.71**	**$618,470.00**
	Item Code 390133	**Total No. of Proj.**			**22**		**Total Amount**	**$9,106,980.40**
390134	HOT MIX ASPHALT (OPEN GRADED)		TON	1	7	17,779.00	$101.64	$1,807,120.00
			TON	3	7	14,273.00	$89.52	$1,277,750.00
			TON	4	10	117,060.00	$78.76	$9,220,180.00
			TON	5	7	112,450.00	$104.69	$11,772,835.00
			TON	9	1	11,700.00	$133.00	$1,556,100.00
			TON	12	3	2,480.00	$134.88	$334,500.00
		Unit Sub Total	**TON**		**35**	**275,742.00**	**$94.18**	**$25,968,485.00**
390134	HOT MIX ASPHALT (OPEN GRADED)		TONN	8	1	2,390.00	$77.00	$184,030.00
		Unit Sub Total	**TONN**		**1**	**2,390.00**	**$77.00**	**$184,030.00**
	Item Code 390134	**Total No. of Proj.**			**36**		**Total Amount**	**$26,152,515.00**
390135	HOT MIX ASPHALT (LEVELING)		TON	1	1	20,000.00	$75.00	$1,500,000.00
			TON	3	3	4,123.00	$74.48	$307,100.00
			TON	4	1	2,300.00	$76.50	$175,950.00
			TON	6	1	6,550.00	$78.00	$510,900.00
			TON	8	1	24.00	$150.00	$3,600.00
		Unit Sub Total	**TON**		**7**	**32,997.00**	**$75.69**	**$2,497,550.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 390135	**Total No. of Proj.**			**7**		**Total Amount**	**$2,497,550.00**
390136	MINOR HOT MIX ASPHALT		TON	1	3	566.00	$216.70	$122,650.00
			TON	2	5	1,257.00	$106.91	$134,380.00
			TON	3	17	2,840.00	$141.89	$402,960.00
			TON	4	8	909.00	$101.86	$92,595.00
			TON	5	1	240.00	$262.00	$62,880.00
			TON	6	5	196.00	$355.38	$69,653.60
			TON	7	5	97.10	$283.19	$27,498.00
			TON	8	6	595.00	$185.91	$110,615.00
			TON	9	1	260.00	$120.00	$31,200.00
			TON	10	2	158.00	$141.17	$22,305.00
			TON	11	11	20,345.40	$93.93	$1,910,990.00
			TON	12	2	13.00	$242.31	$3,150.00
		Unit Sub Total	**TON**		**66**	**27,476.50**	**$108.85**	**$2,990,876.60**
390136	MINOR HOT MIX ASPHALT		TONN	7	1	4.00	$420.00	$1,680.00
			TONN	11	1	610.00	$115.00	$70,150.00
		Unit Sub Total	**TONN**		**2**	**614.00**	**$116.99**	**$71,830.00**
	Item Code 390136	**Total No. of Proj.**			**68**		**Total Amount**	**$3,062,706.60**
390137	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)		TON	1	3	83,030.00	$110.38	$9,164,640.00
			TON	3	2	20,260.00	$125.61	$2,544,800.00
			TON	4	6	41,450.00	$98.39	$4,078,450.00
			TON	6	2	16,360.00	$93.54	$1,530,240.00
			TON	7	2	8,110.00	$89.66	$727,170.00
			TON	8	1	7,030.00	$96.00	$674,880.00
			TON	10	5	41,710.00	$87.79	$3,661,760.00
			TON	12	10	57,315.00	$87.16	$4,995,532.00
		Unit Sub Total	**TON**		**31**	**275,265.00**	**$99.46**	**$27,377,472.00**
390137	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)		TONN	4	1	1,470.00	$130.00	$191,100.00
			TONN	10	2	9,390.00	$103.26	$969,580.00
		Unit Sub Total	**TONN**		**3**	**10,860.00**	**$106.88**	**$1,160,680.00**
	Item Code 390137	**Total No. of Proj.**			**34**		**Total Amount**	**$28,538,152.00**
390138	RUBBERIZED HOT MIX ASPHALT (OPEN GRADED)		TON	1	2	12,900.00	$95.70	$1,234,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
390138	RUBBERIZED HOT MIX ASPHALT (OPEN GRADED)	TON	3	15	131,290.00	$80.85	$10,615,070.00
		TON	6	1	2,880.00	$92.00	$264,960.00
		TON	8	1	35,900.00	$103.00	$3,697,700.00
		TON	12	6	23,957.00	$91.84	$2,200,208.00
	Unit Sub Total	**TON**		**25**	**206,927.00**	**$87.05**	**$18,012,438.00**
	Item Code 390138 Total No. of Proj.			**25**		**Total Amount**	**$18,012,438.00**
390139	RUBBERIZED HOT MIX ASPHALT (OPEN GRADED HIGH BINDER)	TON	2	4	109,600.00	$84.37	$9,247,000.00
		TON	5	1	21,100.00	$133.00	$2,806,300.00
		TON	6	1	16,500.00	$105.00	$1,732,500.00
	Unit Sub Total	**TON**		**6**	**147,200.00**	**$93.65**	**$13,785,800.00**
	Item Code 390139 Total No. of Proj.			**6**		**Total Amount**	**$13,785,800.00**
390140	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TON	1	4	89,710.00	$110.67	$9,928,250.00
		TON	2	1	46,100.00	$78.00	$3,595,800.00
		TON	3	4	107,000.00	$84.32	$9,022,420.00
		TON	4	8	172,500.00	$89.13	$15,375,440.00
		TON	6	6	145,100.00	$90.09	$13,072,550.00
		TON	7	10	587,400.00	$83.14	$48,835,520.00
		TON	8	1	125,000.00	$70.00	$8,750,000.00
		TON	10	10	196,400.00	$83.40	$16,380,300.00
		TON	11	5	145,400.00	$91.90	$13,362,550.00
		TON	12	3	56,800.00	$90.16	$5,121,200.00
	Unit Sub Total	**TON**		**52**	**1,671,410.00**	**$85.82**	**$143,444,030.00**
	Item Code 390140 Total No. of Proj.			**52**		**Total Amount**	**$143,444,030.00**
390141	HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	TON	3	2	51,000.00	$94.04	$4,796,250.00
		TON	4	5	32,280.00	$111.91	$3,612,330.80
		TON	6	1	35,800.00	$115.00	$4,117,000.00
		TON	11	1	9,370.00	$96.00	$899,520.00
	Unit Sub Total	**TON**		**9**	**128,450.00**	**$104.52**	**$13,425,100.80**
	Item Code 390141 Total No. of Proj.			**9**		**Total Amount**	**$13,425,100.80**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
390151	ASPHALTIC EMULSION MEMBRANE (BONDED WEARING COURSE)	TON	1	1	95.00	$909.00	$86,355.00
		TON	3	2	750.00	$722.00	$541,500.00
		TON	4	5	526.00	$667.73	$351,224.75
		TON	6	1	540.00	$750.00	$405,000.00
		TON	11	1	130.00	$1,400.00	$182,000.00
	Unit Sub Total	**TON**		**10**	**2,041.00**	**$767.31**	**$1,566,079.75**
	Item Code 390151 Total No. of Proj.			**10**		**Total Amount**	**$1,566,079.75**
391007	PAVING ASPHALT (BINDER, GEOSYNTHETIC PAVEMENT INTERLAYER)	TON	1	2	1.70	$1,717.65	$2,920.00
		TON	3	3	454.00	$1.00	$454.00
		TON	4	1	75.00	$1.00	$75.00
		TON	5	1	1.50	$1,500.00	$2,250.00
		TON	6	1	76.00	$600.00	$45,600.00
		TON	11	1	0.40	$500.00	$200.00
	Unit Sub Total	**TON**		**9**	**608.60**	**$84.62**	**$51,499.00**
	Item Code 391007 Total No. of Proj.			**9**		**Total Amount**	**$51,499.00**
393001	PAVEMENT REINFORCING FABRIC	SQYD	4	2	30,070.00	$1.57	$47,220.00
	Unit Sub Total	**SQYD**		**2**	**30,070.00**	**$1.57**	**$47,220.00**
	Item Code 393001 Total No. of Proj.			**2**		**Total Amount**	**$47,220.00**
393003	GEOSYNTHETIC PAVEMENT INTERLAYER	SQYD	1	7	15,218.00	$4.60	$69,950.00
		SQYD	3	3	390,830.00	$1.54	$599,994.00
		SQYD	4	1	70,000.00	$1.00	$70,000.00
		SQYD	5	1	16,300.00	$0.75	$12,225.00
		SQYD	6	2	81,600.00	$1.10	$89,600.00
		SQYD	11	1	320.00	$3.00	$960.00
	Unit Sub Total	**SQYD**		**15**	**574,268.00**	**$1.47**	**$842,729.00**
	Item Code 393003 Total No. of Proj.			**15**		**Total Amount**	**$842,729.00**
394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	SQYD	6	1	510.00	$30.00	$15,300.00
	Unit Sub Total	**SQYD**		**1**	**510.00**	**$30.00**	**$15,300.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 394002 Total No. of Proj.			**1**		**Total Amount**	**$15,300.00**
394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	LF	4	1	80.00	$40.00	$3,200.00
		LF	5	1	950.00	$4.00	$3,800.00
	Unit Sub Total	**LF**		**2**	**1,030.00**	**$6.80**	**$7,000.00**
	Item Code 394040 Total No. of Proj.			**2**		**Total Amount**	**$7,000.00**
394044	PLACE ASPHALT CONCRETE DIKE (TYPE C)	LF	7	1	130.00	$35.00	$4,550.00
		LF	8	1	1,930.00	$7.65	$14,764.50
	Unit Sub Total	**LF**		**2**	**2,060.00**	**$9.38**	**$19,314.50**
	Item Code 394044 Total No. of Proj.			**2**		**Total Amount**	**$19,314.50**
394046	PLACE ASPHALT CONCRETE DIKE (TYPE D)	LF	4	1	580.00	$1.00	$580.00
	Unit Sub Total	**LF**		**1**	**580.00**	**$1.00**	**$580.00**
	Item Code 394046 Total No. of Proj.			**1**		**Total Amount**	**$580.00**
394048	PLACE ASPHALT CONCRETE DIKE (TYPE E)	LF	3	1	750.00	$4.00	$3,000.00
		LF	5	1	5,350.00	$3.50	$18,725.00
		LF	8	1	1,350.00	$1.70	$2,295.00
		LF	10	1	5,380.00	$1.75	$9,415.00
	Unit Sub Total	**LF**		**4**	**12,830.00**	**$2.61**	**$33,435.00**
	Item Code 394048 Total No. of Proj.			**4**		**Total Amount**	**$33,435.00**
394049	PLACE ASPHALT CONCRETE DIKE (TYPE F)	LF	7	1	170.00	$30.00	$5,100.00
		LF	8	2	6,130.00	$4.84	$29,639.50
	Unit Sub Total	**LF**		**3**	**6,300.00**	**$5.51**	**$34,739.50**
	Item Code 394049 Total No. of Proj.			**3**		**Total Amount**	**$34,739.50**
394050	RUMBLE STRIP	LF	2	1	110.00	$42.00	$4,620.00
		LF	6	1	280.00	$11.50	$3,220.00
	Unit Sub Total	**LF**		**2**	**390.00**	**$20.10**	**$7,840.00**
394050	RUMBLE STRIP	STA	1	1	3,460.00	$35.00	$121,100.00
		STA	2	7	10,605.00	$13.81	$146,417.50
		STA	3	7	6,340.80	$18.32	$116,149.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394050	RUMBLE STRIP	STA	4	2	28.00	$433.00	$12,124.00
		STA	5	9	9,010.00	$22.84	$205,828.00
		STA	6	8	9,277.00	$27.69	$256,850.00
		STA	7	1	19.30	$200.00	$3,860.00
		STA	8	2	1,290.00	$12.06	$15,552.30
		STA	9	2	2,360.00	$12.36	$29,174.00
		STA	10	2	900.00	$15.90	$14,310.00
		STA	11	1	1,100.00	$12.00	$13,200.00
	Unit Sub Total	**STA**		**42**	**44,390.10**	**$21.05**	**$934,564.80**
	Item Code 394050 Total No. of Proj.			**44**		**Total Amount**	**$942,404.80**
394051	SHOULDER RUMBLE STRIP (HMA,ROLLED-IN INDENTATIONS)	STA	8	1	360.00	$26.00	$9,360.00
		STA	11	1	2,070.00	$13.00	$26,910.00
	Unit Sub Total	**STA**		**2**	**2,430.00**	**$14.93**	**$36,270.00**
	Item Code 394051 Total No. of Proj.			**2**		**Total Amount**	**$36,270.00**
394053	SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS)	STA	1	3	846.00	$25.37	$21,460.00
		STA	2	1	930.00	$22.00	$20,460.00
		STA	3	5	4,680.00	$13.91	$65,110.00
		STA	6	1	2,630.00	$23.00	$60,490.00
		STA	7	1	44.00	$134.00	$5,896.00
		STA	8	3	1,728.00	$39.41	$68,100.00
		STA	11	3	6,577.00	$10.10	$66,395.00
	Unit Sub Total	**STA**		**17**	**17,435.00**	**$17.66**	**$307,911.00**
	Item Code 394053 Total No. of Proj.			**17**		**Total Amount**	**$307,911.00**
394054	SHOULDER RUMBLE STRIP (AC, GROUND-IN INDENTATIONS)	STA	2	1	120.00	$35.00	$4,200.00
		STA	3	1	1,190.00	$20.00	$23,800.00
		STA	7	1	2,180.00	$21.00	$45,780.00
		STA	10	2	1,244.00	$60.82	$75,660.00
	Unit Sub Total	**STA**		**5**	**4,734.00**	**$31.57**	**$149,440.00**
	Item Code 394054 Total No. of Proj.			**5**		**Total Amount**	**$149,440.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394060	DATA CORE	LS	1	15	15.00	$7,436.47	$111,547.00
		LS	2	16	16.00	$3,356.25	$53,700.00
		LS	3	18	18.00	$5,090.00	$91,620.00
		LS	4	25	25.00	$3,892.40	$97,310.00
		LS	5	13	13.00	$5,194.46	$67,528.00
		LS	6	15	15.00	$7,720.00	$115,800.00
		LS	7	17	17.00	$9,417.78	$160,102.25
		LS	8	14	14.00	$1,835.07	$25,691.00
		LS	9	7	7.00	$3,850.00	$26,950.00
		LS	10	20	20.00	$4,887.50	$97,750.00
		LS	11	6	6.00	$14,925.00	$89,550.00
		LS	12	12	12.00	$7,741.67	$92,900.00
	Unit Sub Total	**LS**		**178**	**178.00**	**$5,789.04**	**$1,030,448.25**
	Item Code 394060 Total No. of Proj.			**178**		**Total Amount**	**$1,030,448.25**
394070	HOT MIX ASPHALT DIKE	LF	4	1	350.00	$16.00	$5,600.00
	Unit Sub Total	**LF**		**1**	**350.00**	**$16.00**	**$5,600.00**
	Item Code 394070 Total No. of Proj.			**1**		**Total Amount**	**$5,600.00**
394071	PLACE HOT MIX ASPHALT DIKE	LF	1	2	720.00	$15.79	$11,370.00
		LF	4	3	13,820.00	$2.38	$32,904.00
		LF	7	2	42,564.00	$1.18	$50,050.00
		LF	11	12	473,380.00	$0.93	$442,422.00
	Unit Sub Total	**LF**		**19**	**530,484.00**	**$1.01**	**$536,746.00**
394071	PLACE HOT MIX ASPHALT DIKE	M	7	1	400.00	$11.00	$4,400.00
		M	11	2	5,500.00	$8.02	$44,125.00
	Unit Sub Total	**M**		**3**	**5,900.00**	**$8.22**	**$48,525.00**
	Item Code 394071 Total No. of Proj.			**22**		**Total Amount**	**$585,271.00**
394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	LF	1	8	58,091.00	$1.71	$99,393.00
		LF	2	6	29,310.00	$2.00	$58,716.50
		LF	3	18	56,654.00	$1.44	$81,576.50
		LF	4	6	24,409.00	$1.01	$24,566.20
		LF	5	3	1,093.00	$4.38	$4,782.00
		LF	6	7	8,419.00	$2.69	$22,608.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	LF	7	4	93,420.00	$1.52	$142,170.00
		LF	8	2	19,100.00	$1.63	$31,100.00
		LF	9	1	170.00	$35.00	$5,950.00
		LF	10	2	1,320.00	$0.96	$1,266.00
		LF	12	1	2,510.00	$2.35	$5,898.50
	Unit Sub Total	**LF**		**58**	**294,496.00**	**$1.62**	**$478,026.70**
394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	M	5	1	3,290.00	$10.00	$32,900.00
	Unit Sub Total	**M**		**1**	**3,290.00**	**$10.00**	**$32,900.00**
	Item Code 394073 Total No. of Proj.			**59**		**Total Amount**	**$510,926.70**
394074	PLACE HOT MIX ASPHALT DIKE (TYPE C)	LF	1	4	613.00	$2.26	$1,387.00
		LF	2	3	512.00	$10.94	$5,602.00
		LF	3	16	5,056.00	$2.86	$14,462.75
		LF	4	15	12,636.00	$1.99	$25,201.10
		LF	5	1	530.00	$10.00	$5,300.00
		LF	6	8	2,040.00	$8.03	$16,381.00
		LF	7	5	2,979.00	$10.18	$30,318.00
		LF	8	6	6,109.00	$3.41	$20,847.40
		LF	10	4	770.00	$3.42	$2,630.00
		LF	12	12	12,673.00	$2.57	$32,602.50
	Unit Sub Total	**LF**		**74**	**43,918.00**	**$3.52**	**$154,731.75**
394074	PLACE HOT MIX ASPHALT DIKE (TYPE C)	M	5	1	520.00	$10.00	$5,200.00
		M	8	1	87.00	$6.75	$587.25
		M	10	1	11.00	$3.10	$34.10
	Unit Sub Total	**M**		**3**	**618.00**	**$9.42**	**$5,821.35**
	Item Code 394074 Total No. of Proj.			**77**		**Total Amount**	**$160,553.10**
394075	PLACE HOT MIX ASPHALT DIKE (TYPE D)	LF	1	3	13,620.00	$3.40	$46,280.00
		LF	2	3	8,850.00	$2.37	$20,943.50
		LF	3	7	13,445.00	$1.26	$16,986.25
		LF	4	6	15,470.00	$1.88	$29,087.50
		LF	8	2	6,790.00	$1.64	$11,103.80
		LF	12	2	815.00	$6.14	$5,003.00
	Unit Sub Total	**LF**		**23**	**58,990.00**	**$2.19**	**$129,404.05**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394075	PLACE HOT MIX ASPHALT DIKE (TYPE D)	M	5	1	480.00	$10.00	$4,800.00
		M	10	1	50.00	$3.10	$155.00
	Unit Sub Total	**M**		**2**	**530.00**	**$9.35**	**$4,955.00**
	Item Code 394075 Total No. of Proj.			**25**		**Total Amount**	**$134,359.05**
394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	LF	1	8	39,280.00	$1.37	$53,743.00
		LF	2	7	47,490.00	$1.20	$57,099.00
		LF	3	23	74,950.00	$1.34	$100,479.00
		LF	4	18	77,783.00	$1.60	$124,604.70
		LF	5	3	19,840.00	$1.89	$37,560.00
		LF	6	12	122,158.00	$1.24	$151,135.00
		LF	7	2	670.00	$10.69	$7,160.00
		LF	8	4	11,120.00	$2.45	$27,199.50
		LF	9	5	16,500.00	$2.93	$48,295.00
		LF	10	7	47,138.00	$2.33	$109,911.10
		LF	12	7	32,490.00	$2.54	$82,672.50
	Unit Sub Total	**LF**		**96**	**489,419.00**	**$1.63**	**$799,858.80**
394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	M	5	1	3,310.00	$10.00	$33,100.00
		M	7	1	620.00	$14.00	$8,680.00
		M	8	1	1,290.00	$6.75	$8,707.50
		M	10	1	1,770.00	$3.10	$5,487.00
	Unit Sub Total	**M**		**4**	**6,990.00**	**$8.01**	**$55,974.50**
	Item Code 394076 Total No. of Proj.			**100**		**Total Amount**	**$855,833.30**
394077	PLACE HOT MIX ASPHALT DIKE (TYPE F)	LF	1	7	11,010.00	$1.67	$18,441.00
		LF	2	15	51,121.00	$2.37	$121,095.80
		LF	3	18	33,000.00	$1.63	$53,768.00
		LF	4	14	32,753.00	$1.40	$45,755.20
		LF	5	4	5,840.00	$4.70	$27,430.00
		LF	6	8	3,645.00	$8.60	$31,338.00
		LF	7	5	5,005.00	$3.68	$18,437.00
		LF	8	7	18,010.00	$3.16	$56,986.20
		LF	10	5	9,590.00	$1.49	$14,269.40
		LF	12	12	75,615.00	$1.87	$141,467.00
	Unit Sub Total	**LF**		**95**	**245,589.00**	**$2.15**	**$528,987.60**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394077	PLACE HOT MIX ASPHALT DIKE (TYPE F)	M	5	1	4,790.00	$10.00	$47,900.00
		M	7	1	21.00	$44.00	$924.00
		M	8	1	110.00	$6.75	$742.50
	Unit Sub Total	**M**		**3**	**4,921.00**	**$10.07**	**$49,566.50**
	Item Code 394077 Total No. of Proj.			**98**		**Total Amount**	**$578,554.10**
394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	M2	4	1	24.00	$60.00	$1,440.00
		M2	5	1	1,680.00	$35.00	$58,800.00
		M2	7	2	2,670.00	$16.85	$44,980.00
		M2	8	1	3,470.00	$13.00	$45,110.00
		M2	10	2	2,350.00	$13.10	$30,782.00
		M2	11	2	1,420.00	$20.60	$29,255.00
	Unit Sub Total	**M2**		**9**	**11,614.00**	**$18.11**	**$210,367.00**
394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQFT	10	1	1,090.00	$2.40	$2,616.00
	Unit Sub Total	**SQFT**		**1**	**1,090.00**	**$2.40**	**$2,616.00**
394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	1	14	1,954.90	$44.52	$87,040.80
		SQYD	2	10	7,489.00	$21.98	$164,635.00
		SQYD	3	16	22,534.00	$13.58	$306,068.20
		SQYD	4	12	3,362.50	$18.62	$62,624.50
		SQYD	5	7	441.00	$59.08	$26,056.00
		SQYD	6	9	3,152.00	$37.14	$117,075.00
		SQYD	7	3	337.00	$52.10	$17,558.00
		SQYD	8	4	444.00	$34.08	$15,133.00
		SQYD	9	2	236.00	$42.03	$9,920.00
		SQYD	10	9	2,804.00	$19.33	$54,190.00
		SQYD	11	5	31,183.00	$5.47	$170,572.50
		SQYD	12	5	5,502.00	$12.66	$69,676.00
	Unit Sub Total	**SQYD**		**96**	**79,439.40**	**$13.85**	**$1,100,549.00**
	Item Code 394090 Total No. of Proj.			**106**		**Total Amount**	**$1,313,532.00**
394095	ROADSIDE PAVING (MISCELLANEOUS AREAS)	SQYD	3	2	224.00	$42.50	$9,520.00
		SQYD	5	1	750.00	$73.00	$54,750.00
		SQYD	6	1	1,080.00	$54.75	$59,130.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394095	ROADSIDE PAVING (MISCELLANEOUS AREAS)	SQYD	11	1	60.00	$50.00	$3,000.00
	Unit Sub Total	**SQYD**		**5**	**2,114.00**	**$59.79**	**$126,400.00**
	Item Code 394095 Total No. of Proj.			**5**		**Total Amount**	**$126,400.00**
395000	LIQUID ASPHALT (PRIME COAT)	TON	4	3	7.10	$1,347.04	$9,564.00
		TON	8	5	138.00	$459.51	$63,413.00
	Unit Sub Total	**TON**		**8**	**145.10**	**$502.94**	**$72,977.00**
395000	LIQUID ASPHALT (PRIME COAT)	TONN	8	1	38.00	$900.00	$34,200.00
	Unit Sub Total	**TONN**		**1**	**38.00**	**$900.00**	**$34,200.00**
	Item Code 395000 Total No. of Proj.			**9**		**Total Amount**	**$107,177.00**
397001	ASPHALTIC EMULSION (PAINT BINDER)	TON	1	1	0.60	$1,675.00	$1,005.00
		TON	3	1	110.00	$1.00	$110.00
		TON	4	3	107.80	$818.92	$88,280.00
		TON	6	1	90.00	$1.00	$90.00
		TON	12	1	48.00	$586.00	$28,128.00
	Unit Sub Total	**TON**		**7**	**356.40**	**$330.00**	**$117,613.00**
397001	ASPHALTIC EMULSION (PAINT BINDER)	TONN	8	1	3.30	$690.00	$2,277.00
	Unit Sub Total	**TONN**		**1**	**3.30**	**$690.00**	**$2,277.00**
	Item Code 397001 Total No. of Proj.			**8**		**Total Amount**	**$119,890.00**
397005	TACK COAT	TON	1	23	1,345.70	$697.63	$938,800.50
		TON	2	25	3,341.50	$365.14	$1,220,126.50
		TON	3	32	4,235.80	$221.81	$939,547.40
		TON	4	32	2,611.70	$554.17	$1,447,332.50
		TON	5	23	1,080.00	$334.18	$360,913.70
		TON	6	24	1,715.10	$169.62	$290,918.00
		TON	7	14	2,142.00	$612.18	$1,311,291.40
		TON	8	17	1,354.30	$545.54	$738,825.10
		TON	9	8	438.50	$184.09	$80,724.00
		TON	10	20	1,867.00	$69.08	$128,970.00
		TON	11	16	526.20	$688.53	$362,303.00
		TON	12	14	595.90	$525.32	$313,036.00
	Unit Sub Total	**TON**		**248**	**21,253.70**	**$382.65**	**$8,132,788.10**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
397005	TACK COAT	TONN	4	1	6.00	$600.00	$3,600.00
		TONN	5	1	290.00	$1.00	$290.00
		TONN	7	4	222.00	$612.82	$136,047.00
		TONN	8	1	3.30	$690.00	$2,277.00
		TONN	10	2	51.00	$334.71	$17,070.00
		TONN	11	2	41.00	$667.07	$27,350.00
	Unit Sub Total	**TONN**		**11**	**613.30**	**$304.31**	**$186,634.00**
	Item Code 397005 Total No. of Proj.			**259**		**Total Amount**	**$8,319,422.10**
397100	COLD FOAM IN-PLACE RECYCLING	SQYD	3	1	400,000.00	$3.50	$1,400,000.00
		SQYD	9	2	263,000.00	$4.39	$1,155,000.00
	Unit Sub Total	**SQYD**		**3**	**663,000.00**	**$3.85**	**$2,555,000.00**
	Item Code 397100 Total No. of Proj.			**3**		**Total Amount**	**$2,555,000.00**
397200	STABILIZING AGENT (FOAMED ASPHALT)	TON	3	1	5,890.00	$625.00	$3,681,250.00
		TON	9	2	3,060.00	$602.94	$1,845,000.00
	Unit Sub Total	**TON**		**3**	**8,950.00**	**$617.46**	**$5,526,250.00**
	Item Code 397200 Total No. of Proj.			**3**		**Total Amount**	**$5,526,250.00**
397205	STABILIZING AGENT (CEMENTITIOUS MATERIAL)	TON	3	1	3,930.00	$125.00	$491,250.00
		TON	9	2	2,210.00	$127.71	$282,250.00
	Unit Sub Total	**TON**		**3**	**6,140.00**	**$125.98**	**$773,500.00**
	Item Code 397205 Total No. of Proj.			**3**		**Total Amount**	**$773,500.00**
400050	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT	CY	2	1	95,400.00	$225.00	$21,465,000.00
		CY	10	1	93,400.00	$166.00	$15,504,400.00
	Unit Sub Total	**CY**		**2**	**188,800.00**	**$195.81**	**$36,969,400.00**
	Item Code 400050 Total No. of Proj.			**2**		**Total Amount**	**$36,969,400.00**
400061	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE A)	LF	2	1	84.00	$30.00	$2,520.00
		LF	10	1	150.00	$4.00	$600.00
	Unit Sub Total	**LF**		**2**	**234.00**	**$13.33**	**$3,120.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 400061 Total No. of Proj.			**2**		**Total Amount**	**$3,120.00**
400062	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE B)	LF	10	1	60.00	$80.00	$4,800.00
	Unit Sub Total	**LF**		**1**	**60.00**	**$80.00**	**$4,800.00**
	Item Code 400062 Total No. of Proj.			**1**		**Total Amount**	**$4,800.00**
400063	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE C)	LF	10	1	72.00	$75.00	$5,400.00
	Unit Sub Total	**LF**		**1**	**72.00**	**$75.00**	**$5,400.00**
	Item Code 400063 Total No. of Proj.			**1**		**Total Amount**	**$5,400.00**
400064	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE D)	LF	2	1	280.00	$35.00	$9,800.00
	Unit Sub Total	**LF**		**1**	**280.00**	**$35.00**	**$9,800.00**
	Item Code 400064 Total No. of Proj.			**1**		**Total Amount**	**$9,800.00**
400065	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE E)	LF	10	1	3,080.00	$16.00	$49,280.00
	Unit Sub Total	**LF**		**1**	**3,080.00**	**$16.00**	**$49,280.00**
	Item Code 400065 Total No. of Proj.			**1**		**Total Amount**	**$49,280.00**
400075	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (PAVEMENT ANCHOR)	LF	2	1	280.00	$150.00	$42,000.00
	Unit Sub Total	**LF**		**1**	**280.00**	**$150.00**	**$42,000.00**
	Item Code 400075 Total No. of Proj.			**1**		**Total Amount**	**$42,000.00**
400080	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (WIDE FLANGE BEAM TERMINAL)	LF	10	1	3,040.00	$600.00	$1,824,000.00
	Unit Sub Total	**LF**		**1**	**3,040.00**	**$600.00**	**$1,824,000.00**
	Item Code 400080 Total No. of Proj.			**1**		**Total Amount**	**$1,824,000.00**
400090	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (EXPANSION JOINT, TYPE AN)	LF	2	1	280.00	$125.00	$35,000.00
	Unit Sub Total	**LF**		**1**	**280.00**	**$125.00**	**$35,000.00**
	Item Code 400090 Total No. of Proj.			**1**		**Total Amount**	**$35,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
400092	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (EXPANSION JOINT, TYPE WF)	LF	10	1	3,040.00	$150.00	$456,000.00
	Unit Sub Total	**LF**		**1**	**3,040.00**	**$150.00**	**$456,000.00**
	Item Code 400092 Total No. of Proj.			**1**		**Total Amount**	**$456,000.00**
401000	CONCRETE PAVEMENT	CY	7	2	30.00	$507.28	$15,218.40
	Unit Sub Total	**CY**		**2**	**30.00**	**$507.28**	**$15,218.40**
401000	CONCRETE PAVEMENT	M3	5	1	7,590.00	$190.00	$1,442,100.00
		M3	7	2	36,090.00	$182.79	$6,597,000.00
		M3	11	2	21,700.00	$183.06	$3,972,400.00
	Unit Sub Total	**M3**		**5**	**65,380.00**	**$183.72**	**$12,011,500.00**
	Item Code 401000 Total No. of Proj.			**7**		**Total Amount**	**$12,026,718.40**
401050	JOINTED PLAIN CONCRETE PAVEMENT	CY	1	1	570.00	$540.00	$307,800.00
		CY	2	1	11,100.00	$180.00	$1,998,000.00
		CY	3	2	184,000.00	$107.09	$19,705,000.00
		CY	4	3	21,690.00	$147.56	$3,200,600.00
		CY	5	1	110.00	$320.00	$35,200.00
		CY	6	4	145,210.00	$100.23	$14,554,900.00
		CY	7	5	41,450.00	$182.49	$7,564,105.00
		CY	8	2	6,580.00	$141.73	$932,555.00
		CY	10	2	7,550.00	$183.25	$1,383,500.00
		CY	11	2	7,880.00	$149.00	$1,174,100.00
		CY	12	2	50,400.00	$143.66	$7,240,500.00
	Unit Sub Total	**CY**		**25**	**476,540.00**	**$121.91**	**$58,096,260.00**
401050	JOINTED PLAIN CONCRETE PAVEMENT	M3	7	1	1,240.00	$239.00	$296,360.00
	Unit Sub Total	**M3**		**1**	**1,240.00**	**$239.00**	**$296,360.00**
	Item Code 401050 Total No. of Proj.			**26**		**Total Amount**	**$58,392,620.00**
401066	CONCRETE PAVEMENT (RAMP TERMINI)	CY	8	1	73.00	$600.00	$43,800.00
		CY	12	2	320.00	$316.75	$101,360.00
	Unit Sub Total	**CY**		**3**	**393.00**	**$369.36**	**$145,160.00**
401066	CONCRETE PAVEMENT (RAMP TERMINI)	M3	8	1	140.00	$250.00	$35,000.00
	Unit Sub Total	**M3**		**1**	**140.00**	**$250.00**	**$35,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 401066 Total No. of Proj.			**4**		**Total Amount**	**$180,160.00**
401081	SHOULDER RUMBLE STRIP (CONCRETE PAVEMENT, ROLLED-IN	STA	11	1	170.00	$15.00	$2,550.00
	Unit Sub Total	**STA**		**1**	**170.00**	**$15.00**	**$2,550.00**
	Item Code 401081 Total No. of Proj.			**1**		**Total Amount**	**$2,550.00**
401083	SHOULDER RUMBLE STRIP (CONCRETE PAVEMENT, GROUND-IN	STA	2	1	1,410.00	$50.00	$70,500.00
		STA	4	1	86.00	$150.00	$12,900.00
	SHOULDER RUMBLE STRIP (CONCRETE PAVEMENT, GROUND-IN INDENTATIONS)	STA	6	2	1,400.00	$69.11	$96,750.00
	SHOULDER RUMBLE STRIP (CONCRETE PAVEMENT, GROUND-IN	STA	8	1	74.00	$81.00	$5,994.00
		STA	10	1	680.00	$40.00	$27,200.00
	Unit Sub Total	**STA**		**6**	**3,650.00**	**$58.45**	**$213,344.00**
	Item Code 401083 Total No. of Proj.			**6**		**Total Amount**	**$213,344.00**
401102	CONCRETE PAVEMENT (WEIGH-IN-MOTION)	CY	2	1	450.00	$275.00	$123,750.00
	Unit Sub Total	**CY**		**1**	**450.00**	**$275.00**	**$123,750.00**
	Item Code 401102 Total No. of Proj.			**1**		**Total Amount**	**$123,750.00**
401108	REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	CY	2	1	210.00	$545.00	$114,450.00
		CY	3	6	28,678.00	$370.93	$10,637,600.00
		CY	4	10	12,482.00	$524.88	$6,551,540.00
		CY	5	1	70.00	$850.00	$59,500.00
		CY	6	4	5,430.00	$448.88	$2,437,400.00
		CY	7	12	68,110.00	$381.09	$25,955,938.00
		CY	8	3	1,970.00	$482.99	$951,500.00
		CY	10	2	4,470.00	$381.48	$1,705,200.00
		CY	11	5	2,909.00	$456.94	$1,329,250.00
		CY	12	2	4,230.00	$704.70	$2,980,900.00
	Unit Sub Total	**CY**		**46**	**128,559.00**	**$410.11**	**$52,723,278.00**
401108	REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	M3	7	1	340.00	$350.00	$119,000.00
		M3	11	1	71.00	$900.00	$63,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**2**	**411.00**	**$445.01**	**$182,900.00**
	Item Code 401108	**Total No. of Proj.**			**48**		**Total Amount**	**$52,906,178.00**
404092	SEAL PAVEMENT JOINT		LF	1	1	4,530.00	$4.00	$18,120.00
			LF	2	2	167,540.00	$1.84	$308,450.00
			LF	3	3	815,200.00	$1.90	$1,550,720.00
			LF	4	3	85,420.00	$1.73	$147,452.00
			LF	5	1	260.00	$9.00	$2,340.00
			LF	6	5	234,290.00	$2.96	$694,630.00
			LF	7	11	832,992.00	$2.59	$2,154,434.00
			LF	8	2	7,840.00	$2.94	$23,037.00
			LF	10	1	261,000.00	$1.35	$352,350.00
			LF	11	2	18,940.00	$1.72	$32,630.00
			LF	12	3	193,500.00	$3.31	$640,785.00
		Unit Sub Total	**LF**		**34**	**2,621,512.00**	**$2.26**	**$5,924,948.00**
404092	SEAL PAVEMENT JOINT		M	5	1	6,770.00	$16.00	$108,320.00
			M	7	4	39,432.00	$7.78	$306,855.00
			M	8	1	270.00	$20.00	$5,400.00
			M	11	2	34,800.00	$5.64	$196,320.00
		Unit Sub Total	**M**		**8**	**81,272.00**	**$7.59**	**$616,895.00**
	Item Code 404092	**Total No. of Proj.**			**42**		**Total Amount**	**$6,541,843.00**
404093	SEAL ISOLATION JOINT		LF	2	1	75,900.00	$3.00	$227,700.00
			LF	4	3	4,470.00	$8.74	$39,067.50
			LF	5	1	650.00	$14.00	$9,100.00
			LF	6	2	122,100.00	$3.51	$428,150.00
			LF	7	8	249,370.00	$8.87	$2,211,764.00
			LF	8	2	7,610.00	$6.36	$48,386.10
			LF	10	1	7,660.00	$8.00	$61,280.00
			LF	12	3	67,910.00	$4.09	$277,485.00
		Unit Sub Total	**LF**		**21**	**535,670.00**	**$6.17**	**$3,302,932.60**
	Item Code 404093	**Total No. of Proj.**			**21**		**Total Amount**	**$3,302,932.60**
404094	SEAL LONGITUDINAL ISOLATION JOINT		LF	3	1	151,000.00	$6.00	$906,000.00
			LF	7	4	39,500.00	$9.93	$392,345.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
404094	SEAL LONGITUDINAL ISOLATION JOINT	LF	11	1	16,860.00	$1.75	$29,505.00
	Unit Sub Total	**LF**		**6**	**207,360.00**	**$6.40**	**$1,327,850.00**
404094	SEAL LONGITUDINAL ISOLATION JOINT	M	5	1	330.00	$27.00	$8,910.00
		M	7	2	1,580.00	$23.16	$36,585.00
		M	8	1	11.00	$100.00	$1,100.00
		M	11	2	8,660.00	$22.96	$198,810.00
	Unit Sub Total	**M**		**6**	**10,581.00**	**$23.19**	**$245,405.00**
	Item Code 404094 Total No. of Proj.			**12**		**Total Amount**	**$1,573,255.00**
405030	PORTLAND CEMENT CONCRETE BASE	CY	4	1	3,170.00	$165.00	$523,050.00
	Unit Sub Total	**CY**		**1**	**3,170.00**	**$165.00**	**$523,050.00**
	Item Code 405030 Total No. of Proj.			**1**		**Total Amount**	**$523,050.00**
406001	TIE BAR	EA	7	8	94,850.00	$11.44	$1,085,302.00
	Unit Sub Total	**EA**		**8**	**94,850.00**	**$11.44**	**$1,085,302.00**
	Item Code 406001 Total No. of Proj.			**8**		**Total Amount**	**$1,085,302.00**
406003	TIE BAR (DRILL AND BOND)	EA	7	1	18,200.00	$6.00	$109,200.00
	Unit Sub Total	**EA**		**1**	**18,200.00**	**$6.00**	**$109,200.00**
	Item Code 406003 Total No. of Proj.			**1**		**Total Amount**	**$109,200.00**
406050	DOWEL BAR (DRILL AND BOND)	EA	2	1	130.00	$35.00	$4,550.00
		EA	4	1	570.00	$30.00	$17,100.00
		EA	6	1	10,700.00	$10.00	$107,000.00
		EA	7	2	10,300.00	$10.05	$103,510.00
		EA	8	3	6,700.00	$17.77	$119,058.00
		EA	11	4	2,000.00	$30.03	$60,050.00
	Unit Sub Total	**EA**		**12**	**30,400.00**	**$13.53**	**$411,268.00**
406050	DOWEL BAR (DRILL AND BOND)	LF	10	1	3,570.00	$18.00	$64,260.00
	Unit Sub Total	**LF**		**1**	**3,570.00**	**$18.00**	**$64,260.00**
	Item Code 406050 Total No. of Proj.			**13**		**Total Amount**	**$475,528.00**
406100	DOWEL BAR RETROFIT	EA	3	2	22,850.00	$66.74	$1,525,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**2**	**22,850.00**	**$66.74**	**$1,525,000.00**
	Item Code 406100	**Total No. of Proj.**			**2**		**Total Amount**	**$1,525,000.00**
411105	INDIVIDUAL SLAB REPLACEMENT (RSC)		CY	3	1	160.00	$765.00	$122,400.00
			CY	10	1	1,730.00	$513.50	$888,355.00
		Unit Sub Total	**CY**		**2**	**1,890.00**	**$534.79**	**$1,010,755.00**
	Item Code 411105	**Total No. of Proj.**			**2**		**Total Amount**	**$1,010,755.00**
413111	REPAIR SPALLED JOINTS		SQYD	3	2	20.00	$1,460.00	$29,200.00
			SQYD	4	1	5,000.00	$80.00	$400,000.00
			SQYD	7	2	180.00	$857.38	$154,327.80
			SQYD	8	1	5.00	$2,940.00	$14,700.00
			SQYD	11	2	760.00	$821.25	$624,150.00
			SQYD	12	2	4,770.00	$14.61	$69,678.00
		Unit Sub Total	**SQYD**		**10**	**10,735.00**	**$120.36**	**$1,292,055.80**
	Item Code 413111	**Total No. of Proj.**			**10**		**Total Amount**	**$1,292,055.80**
413115	SEAL JOINT (EXISTING CONCRETE PAVEMENT)		LF	3	2	593,000.00	$1.44	$851,400.00
			LF	4	1	57,100.00	$3.00	$171,300.00
			LF	6	1	219,000.00	$2.20	$481,800.00
			LF	7	8	3,150,430.00	$1.76	$5,538,705.00
			LF	11	4	473,200.00	$1.77	$838,400.00
		Unit Sub Total	**LF**		**16**	**4,492,730.00**	**$1.75**	**$7,881,605.00**
	Item Code 413115	**Total No. of Proj.**			**16**		**Total Amount**	**$7,881,605.00**
415101	CRACK EXISTING CONCRETE PAVEMENT		SQYD	2	1	105,000.00	$0.72	$75,600.00
			SQYD	3	1	316,000.00	$0.40	$126,400.00
			SQYD	4	1	20,800.00	$1.25	$26,000.00
			SQYD	6	1	71,900.00	$0.75	$53,925.00
		Unit Sub Total	**SQYD**		**4**	**513,700.00**	**$0.55**	**$281,925.00**
	Item Code 415101	**Total No. of Proj.**			**4**		**Total Amount**	**$281,925.00**
416101	PAVEMENT TRANSITION TAPER		SQYD	4	1	2,190.00	$17.00	$37,230.00
		Unit Sub Total	**SQYD**		**1**	**2,190.00**	**$17.00**	**$37,230.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 416101 Total No. of Proj.			**1**		**Total Amount**	**$37,230.00**
420102	GROOVE EXISTING CONCRETE PAVEMENT	LF	2	1	4,180.00	$5.25	$21,945.00
	Unit Sub Total	**LF**		**1**	**4,180.00**	**$5.25**	**$21,945.00**
420102	GROOVE EXISTING CONCRETE PAVEMENT	SQYD	3	1	101,000.00	$3.00	$303,000.00
		SQYD	8	2	365,000.00	$2.14	$779,950.00
		SQYD	12	5	718,040.00	$2.22	$1,591,860.00
	Unit Sub Total	**SQYD**		**8**	**1,184,040.00**	**$2.26**	**$2,674,810.00**
	Item Code 420102 Total No. of Proj.			**9**		**Total Amount**	**$2,696,755.00**
420201	GRIND EXISTING CONCRETE PAVEMENT	M2	7	1	5,500.00	$5.00	$27,500.00
		M2	11	2	46,270.00	$5.30	$245,168.00
	Unit Sub Total	**M2**		**3**	**51,770.00**	**$5.27**	**$272,668.00**
420201	GRIND EXISTING CONCRETE PAVEMENT	SQYD	3	8	778,320.00	$4.60	$3,577,025.00
		SQYD	4	3	319,200.00	$4.89	$1,562,400.00
		SQYD	5	1	37,000.00	$5.00	$185,000.00
		SQYD	6	2	248,200.00	$3.16	$783,640.00
		SQYD	7	10	4,658,320.00	$3.83	$17,863,850.00
		SQYD	8	3	981,000.00	$4.00	$3,923,040.00
		SQYD	11	6	1,886,250.00	$3.83	$7,224,050.00
		SQYD	12	5	584,960.00	$3.72	$2,175,240.00
	Unit Sub Total	**SQYD**		**38**	**9,493,250.00**	**$3.93**	**$37,294,245.00**
	Item Code 420201 Total No. of Proj.			**41**		**Total Amount**	**$37,566,913.00**
490503	FURNISH STEEL PILING (HP 10 X 42)	LF	12	1	619.00	$30.00	$18,570.00
	Unit Sub Total	**LF**		**1**	**619.00**	**$30.00**	**$18,570.00**
	Item Code 490503 Total No. of Proj.			**1**		**Total Amount**	**$18,570.00**
490504	DRIVE STEEL PILE (HP 10 X 42)	EA	12	1	11.00	$2,300.00	$25,300.00
	Unit Sub Total	**EA**		**1**	**11.00**	**$2,300.00**	**$25,300.00**
	Item Code 490504 Total No. of Proj.			**1**		**Total Amount**	**$25,300.00**
490508	FURNISH STEEL PILING (HP 10 X 57)	LF	3	1	7,987.00	$31.00	$247,597.00
	Unit Sub Total	**LF**		**1**	**7,987.00**	**$31.00**	**$247,597.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 490508 Total No. of Proj.			**1**		**Total Amount**	**$247,597.00**
490509	DRIVE STEEL PILE (HP 10 X 57)	EA	3	1	132.00	$2,200.00	$290,400.00
	Unit Sub Total	**EA**		**1**	**132.00**	**$2,200.00**	**$290,400.00**
	Item Code 490509 Total No. of Proj.			**1**		**Total Amount**	**$290,400.00**
490511	FURNISH STEEL PILING (HP 250 X 85)	M	5	1	274.00	$120.00	$32,880.00
		M	11	1	557.00	$100.00	$55,700.00
	Unit Sub Total	**M**		**2**	**831.00**	**$106.59**	**$88,580.00**
	Item Code 490511 Total No. of Proj.			**2**		**Total Amount**	**$88,580.00**
490512	DRIVE STEEL PILE (HP 250 X 85)	EA	5	1	12.00	$3,800.00	$45,600.00
		EA	11	1	48.00	$1,700.00	$81,600.00
	Unit Sub Total	**EA**		**2**	**60.00**	**$2,120.00**	**$127,200.00**
	Item Code 490512 Total No. of Proj.			**2**		**Total Amount**	**$127,200.00**
490528	FURNISH STEEL PILING (HP 14 X 89)	LF	3	1	4,151.00	$50.00	$207,550.00
		LF	6	1	3,259.00	$50.00	$162,950.00
	Unit Sub Total	**LF**		**2**	**7,410.00**	**$50.00**	**$370,500.00**
	Item Code 490528 Total No. of Proj.			**2**		**Total Amount**	**$370,500.00**
490529	DRIVE STEEL PILE (HP 14 X 89)	EA	3	1	123.00	$2,000.00	$246,000.00
		EA	6	1	68.00	$1,600.00	$108,800.00
	Unit Sub Total	**EA**		**2**	**191.00**	**$1,857.59**	**$354,800.00**
	Item Code 490529 Total No. of Proj.			**2**		**Total Amount**	**$354,800.00**
490538	FURNISH STEEL PILING (HP 14 X 117)	LF	2	1	1,005.00	$10.00	$10,050.00
	Unit Sub Total	**LF**		**1**	**1,005.00**	**$10.00**	**$10,050.00**
	Item Code 490538 Total No. of Proj.			**1**		**Total Amount**	**$10,050.00**
490539	DRIVE STEEL PILE (HP 14 X 117)	EA	2	1	32.00	$4,500.00	$144,000.00
	Unit Sub Total	**EA**		**1**	**32.00**	**$4,500.00**	**$144,000.00**
	Item Code 490539 Total No. of Proj.			**1**		**Total Amount**	**$144,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
490584	FURNISH STEEL PIPE PILING (610 MM)	M	7	1	28,973.00	$287.00	$8,315,251.00
	Unit Sub Total	**M**		**1**	**28,973.00**	**$287.00**	**$8,315,251.00**
	Item Code 490584 Total No. of Proj.			**1**		**Total Amount**	**$8,315,251.00**
490585	DRIVE STEEL PIPE PILE (610 MM)	EA	7	1	1,489.00	$520.00	$774,280.00
	Unit Sub Total	**EA**		**1**	**1,489.00**	**$520.00**	**$774,280.00**
	Item Code 490585 Total No. of Proj.			**1**		**Total Amount**	**$774,280.00**
490591	60" PERMANENT STEEL CASING	LF	4	1	100.00	$1,500.00	$150,000.00
	Unit Sub Total	**LF**		**1**	**100.00**	**$1,500.00**	**$150,000.00**
	Item Code 490591 Total No. of Proj.			**1**		**Total Amount**	**$150,000.00**
490592	72" PERMANENT STEEL CASING	LF	2	1	387.00	$1,800.00	$696,600.00
	Unit Sub Total	**LF**		**1**	**387.00**	**$1,800.00**	**$696,600.00**
	Item Code 490592 Total No. of Proj.			**1**		**Total Amount**	**$696,600.00**
490601	16" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	3	1	2,965.00	$30.00	$88,950.00
		LF	7	1	3,024.00	$40.62	$122,834.88
	Unit Sub Total	**LF**		**2**	**5,989.00**	**$35.36**	**$211,784.88**
	Item Code 490601 Total No. of Proj.			**2**		**Total Amount**	**$211,784.88**
490603	24" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	1	1	891.00	$255.00	$227,205.00
		LF	3	1	890.00	$120.00	$106,800.00
		LF	4	5	7,646.00	$171.83	$1,313,840.00
		LF	6	1	763.00	$30.00	$22,890.00
		LF	7	3	11,786.00	$93.63	$1,103,540.00
		LF	8	1	3,484.00	$130.00	$452,920.00
		LF	10	1	4,762.00	$185.00	$880,970.00
		LF	12	1	859.00	$90.00	$77,310.00
	Unit Sub Total	**LF**		**14**	**31,081.00**	**$134.66**	**$4,185,475.00**
	Item Code 490603 Total No. of Proj.			**14**		**Total Amount**	**$4,185,475.00**
490604	30" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	7	2	7,661.00	$149.85	$1,147,962.80
		LF	10	1	2,966.00	$125.00	$370,750.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**3**	**10,627.00**	**$142.91**	**$1,518,712.80**
	Item Code 490604 Total No. of Proj.			**3**		**Total Amount**	**$1,518,712.80**
490605	36" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	2	1	150.00	$1,375.06	$206,258.55
		LF	4	1	483.00	$525.00	$253,575.00
		LF	7	1	2,366.00	$195.00	$461,370.00
		LF	10	1	1,094.00	$145.00	$158,630.00
	Unit Sub Total	**LF**		**4**	**4,093.00**	**$263.82**	**$1,079,833.55**
	Item Code 490605 Total No. of Proj.			**4**		**Total Amount**	**$1,079,833.55**
490606	42" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	2	1	211.00	$1,210.00	$255,310.00
	Unit Sub Total	**LF**		**1**	**211.00**	**$1,210.00**	**$255,310.00**
	Item Code 490606 Total No. of Proj.			**1**		**Total Amount**	**$255,310.00**
490607	48" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	4	1	150.00	$650.00	$97,500.00
		LF	7	1	1,648.00	$310.00	$510,880.00
		LF	10	1	824.00	$275.00	$226,600.00
	Unit Sub Total	**LF**		**3**	**2,622.00**	**$318.45**	**$834,980.00**
	Item Code 490607 Total No. of Proj.			**3**		**Total Amount**	**$834,980.00**
490609	60" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	1	1	535.00	$855.00	$457,425.00
		LF	10	1	210.00	$385.00	$80,850.00
		LF	12	1	35.00	$520.00	$18,200.00
	Unit Sub Total	**LF**		**3**	**780.00**	**$713.43**	**$556,475.00**
	Item Code 490609 Total No. of Proj.			**3**		**Total Amount**	**$556,475.00**
490611	72" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	2	1	387.00	$990.00	$383,130.00
		LF	4	1	208.00	$1,500.00	$312,000.00
	Unit Sub Total	**LF**		**2**	**595.00**	**$1,168.29**	**$695,130.00**
	Item Code 490611 Total No. of Proj.			**2**		**Total Amount**	**$695,130.00**
490614	78" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	3	1	1,745.00	$600.00	$1,047,000.00
		LF	4	1	392.00	$1,000.00	$392,000.00
	Unit Sub Total	**LF**		**2**	**2,137.00**	**$673.37**	**$1,439,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 490614 Total No. of Proj.			**2**		**Total Amount**	**$1,439,000.00**
490617	90" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	4	1	131.00	$1,250.00	$163,750.00
	Unit Sub Total	**LF**		**1**	**131.00**	**$1,250.00**	**$163,750.00**
	Item Code 490617 Total No. of Proj.			**1**		**Total Amount**	**$163,750.00**
490618	96" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	4	1	105.00	$2,200.00	$231,000.00
		LF	7	1	504.00	$1,000.00	$504,000.00
		LF	8	1	258.00	$2,800.00	$722,400.00
	Unit Sub Total	**LF**		**3**	**867.00**	**$1,680.97**	**$1,457,400.00**
	Item Code 490618 Total No. of Proj.			**3**		**Total Amount**	**$1,457,400.00**
490620	108" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	8	1	601.00	$800.00	$480,800.00
	Unit Sub Total	**LF**		**1**	**601.00**	**$800.00**	**$480,800.00**
	Item Code 490620 Total No. of Proj.			**1**		**Total Amount**	**$480,800.00**
490622	120" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	7	1	6,374.00	$1,000.00	$6,374,000.00
	Unit Sub Total	**LF**		**1**	**6,374.00**	**$1,000.00**	**$6,374,000.00**
	Item Code 490622 Total No. of Proj.			**1**		**Total Amount**	**$6,374,000.00**
490623	156" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	7	1	1,072.00	$1,400.00	$1,500,800.00
	Unit Sub Total	**LF**		**1**	**1,072.00**	**$1,400.00**	**$1,500,800.00**
	Item Code 490623 Total No. of Proj.			**1**		**Total Amount**	**$1,500,800.00**
490655	400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	5	1	785.00	$130.00	$102,050.00
		M	7	1	1,319.00	$280.00	$369,320.00
		M	8	1	928.00	$100.00	$92,800.00
	Unit Sub Total	**M**		**3**	**3,032.00**	**$186.07**	**$564,170.00**
	Item Code 490655 Total No. of Proj.			**3**		**Total Amount**	**$564,170.00**
490656	450 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	5	1	341.00	$165.00	$56,265.00
	Unit Sub Total	**M**		**1**	**341.00**	**$165.00**	**$56,265.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 490656 Total No. of Proj.			**1**		**Total Amount**	**$56,265.00**
490657	600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	5	1	362.00	$175.00	$63,350.00
		M	7	1	2,142.00	$666.00	$1,426,572.00
		M	8	1	843.00	$190.00	$160,170.00
	Unit Sub Total	**M**		**3**	**3,347.00**	**$493.01**	**$1,650,092.00**
	Item Code 490657 Total No. of Proj.			**3**		**Total Amount**	**$1,650,092.00**
490658	750 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	7	1	43.00	$1,600.00	$68,800.00
	Unit Sub Total	**M**		**1**	**43.00**	**$1,600.00**	**$68,800.00**
	Item Code 490658 Total No. of Proj.			**1**		**Total Amount**	**$68,800.00**
490661	1.2 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	7	1	65.00	$1,815.00	$117,975.00
		M	11	1	1,518.00	$370.00	$561,660.00
	Unit Sub Total	**M**		**2**	**1,583.00**	**$429.33**	**$679,635.00**
	Item Code 490661 Total No. of Proj.			**2**		**Total Amount**	**$679,635.00**
490663	1.5 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	7	1	72.00	$3,060.00	$220,320.00
		M	11	1	335.00	$700.00	$234,500.00
	Unit Sub Total	**M**		**2**	**407.00**	**$1,117.49**	**$454,820.00**
	Item Code 490663 Total No. of Proj.			**2**		**Total Amount**	**$454,820.00**
490669	2.1 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	7	1	40.00	$5,030.00	$201,200.00
	Unit Sub Total	**M**		**1**	**40.00**	**$5,030.00**	**$201,200.00**
	Item Code 490669 Total No. of Proj.			**1**		**Total Amount**	**$201,200.00**
490671	2.4 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	8	1	81.00	$4,500.00	$364,500.00
		M	11	1	769.00	$3,000.00	$2,307,000.00
	Unit Sub Total	**M**		**2**	**850.00**	**$3,142.94**	**$2,671,500.00**
	Item Code 490671 Total No. of Proj.			**2**		**Total Amount**	**$2,671,500.00**
490675	900 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	11	1	722.00	$230.00	$166,060.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**1**	**722.00**	**$230.00**	**$166,060.00**
	Item Code 490675 Total No. of Proj.			**1**		**Total Amount**	**$166,060.00**
490684	48" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	LF	4	1	32.00	$1,250.00	$40,000.00
	Unit Sub Total	**LF**		**1**	**32.00**	**$1,250.00**	**$40,000.00**
	Item Code 490684 Total No. of Proj.			**1**		**Total Amount**	**$40,000.00**
490685	60" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	LF	2	1	194.00	$1,400.00	$271,600.00
	Unit Sub Total	**LF**		**1**	**194.00**	**$1,400.00**	**$271,600.00**
	Item Code 490685 Total No. of Proj.			**1**		**Total Amount**	**$271,600.00**
490700	FURNISH PILING (CLASS 900) (ALTERNATIVE W)	M	5	1	2,541.00	$190.00	$482,790.00
	Unit Sub Total	**M**		**1**	**2,541.00**	**$190.00**	**$482,790.00**
	Item Code 490700 Total No. of Proj.			**1**		**Total Amount**	**$482,790.00**
490701	DRIVE PILE (CLASS 900) (ALTERNATIVE W)	EA	5	1	214.00	$2,200.00	$470,800.00
	Unit Sub Total	**EA**		**1**	**214.00**	**$2,200.00**	**$470,800.00**
	Item Code 490701 Total No. of Proj.			**1**		**Total Amount**	**$470,800.00**
490736	FURNISH PILING (CLASS 90)	LF	12	1	721.00	$25.00	$18,025.00
	Unit Sub Total	**LF**		**1**	**721.00**	**$25.00**	**$18,025.00**
	Item Code 490736 Total No. of Proj.			**1**		**Total Amount**	**$18,025.00**
490737	DRIVE PILE (CLASS 90)	EA	12	1	14.00	$2,200.00	$30,800.00
	Unit Sub Total	**EA**		**1**	**14.00**	**$2,200.00**	**$30,800.00**
	Item Code 490737 Total No. of Proj.			**1**		**Total Amount**	**$30,800.00**
490738	FURNISH PILING (CLASS 140)	LF	12	2	6,901.00	$17.80	$122,829.90
	Unit Sub Total	**LF**		**2**	**6,901.00**	**$17.80**	**$122,829.90**
	Item Code 490738 Total No. of Proj.			**2**		**Total Amount**	**$122,829.90**
490739	DRIVE PILE (CLASS 140)	EA	12	2	158.00	$1,870.89	$295,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**2**	**158.00**	**$1,870.89**	**$295,600.00**
	Item Code 490739 Total No. of Proj.			**2**		**Total Amount**	**$295,600.00**
490740	FURNISH PILING (CLASS 90) (ALTERNATIVE V)	LF	3	1	1,176.00	$52.00	$61,152.00
	Unit Sub Total	**LF**		**1**	**1,176.00**	**$52.00**	**$61,152.00**
	Item Code 490740 Total No. of Proj.			**1**		**Total Amount**	**$61,152.00**
490741	DRIVE PILE (CLASS 90) (ALTERNATIVE V)	EA	3	1	42.00	$2,000.00	$84,000.00
	Unit Sub Total	**EA**		**1**	**42.00**	**$2,000.00**	**$84,000.00**
	Item Code 490741 Total No. of Proj.			**1**		**Total Amount**	**$84,000.00**
490742	FURNISH PILING (CLASS 90) (ALTERNATIVE W)	LF	7	1	10,939.00	$37.00	$404,743.00
	Unit Sub Total	**LF**		**1**	**10,939.00**	**$37.00**	**$404,743.00**
	Item Code 490742 Total No. of Proj.			**1**		**Total Amount**	**$404,743.00**
490743	DRIVE PILE (CLASS 90) (ALTERNATIVE W)	EA	7	1	221.00	$900.00	$198,900.00
	Unit Sub Total	**EA**		**1**	**221.00**	**$900.00**	**$198,900.00**
	Item Code 490743 Total No. of Proj.			**1**		**Total Amount**	**$198,900.00**
490746	FURNISH PILING (CLASS 140) (ALTERNATIVE W)	LF	4	1	4,269.00	$55.00	$234,795.00
		LF	7	1	21,583.00	$43.00	$928,069.00
		LF	10	1	1,963.00	$60.00	$117,780.00
	Unit Sub Total	**LF**		**3**	**27,815.00**	**$46.04**	**$1,280,644.00**
	Item Code 490746 Total No. of Proj.			**3**		**Total Amount**	**$1,280,644.00**
490747	DRIVE PILE (CLASS 140) (ALTERNATIVE W)	EA	4	1	93.00	$1,050.00	$97,650.00
		EA	7	1	412.00	$800.00	$329,600.00
		EA	10	1	28.00	$1,250.00	$35,000.00
	Unit Sub Total	**EA**		**3**	**533.00**	**$867.26**	**$462,250.00**
	Item Code 490747 Total No. of Proj.			**3**		**Total Amount**	**$462,250.00**
490751	FURNISH PILE (CLASS 200)	LF	12	1	400.00	$23.00	$9,200.00
	Unit Sub Total	**LF**		**1**	**400.00**	**$23.00**	**$9,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 490751 Total No. of Proj.			**1**		**Total Amount**	**$9,200.00**
490752	DRIVE PILING (CLASS 200)	EA	12	1	8.00	$8,600.00	$68,800.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$8,600.00**	**$68,800.00**
	Item Code 490752 Total No. of Proj.			**1**		**Total Amount**	**$68,800.00**
490772	FURNISH PILING (CLASS 625) (ALTERNATIVE W)	M	5	1	4,006.00	$123.00	$492,738.00
	Unit Sub Total	**M**		**1**	**4,006.00**	**$123.00**	**$492,738.00**
	Item Code 490772 Total No. of Proj.			**1**		**Total Amount**	**$492,738.00**
490773	DRIVE PILE (CLASS 625) (ALTERNATIVE W)	EA	5	1	229.00	$2,400.00	$549,600.00
	Unit Sub Total	**EA**		**1**	**229.00**	**$2,400.00**	**$549,600.00**
	Item Code 490773 Total No. of Proj.			**1**		**Total Amount**	**$549,600.00**
490782	FURNISH PILING (CLASS 200) (ALTERNATIVE W)	LF	4	1	1,614.00	$60.00	$96,840.00
		LF	7	1	6,454.00	$55.00	$354,970.00
		LF	10	2	3,708.00	$79.80	$295,890.00
	Unit Sub Total	**LF**		**4**	**11,776.00**	**$63.49**	**$747,700.00**
	Item Code 490782 Total No. of Proj.			**4**		**Total Amount**	**$747,700.00**
490783	DRIVE PILE (CLASS 200) (ALTERNATIVE W)	EA	4	1	32.00	$1,100.00	$35,200.00
		EA	7	1	128.00	$900.00	$115,200.00
		EA	10	2	49.00	$1,657.14	$81,200.00
	Unit Sub Total	**EA**		**4**	**209.00**	**$1,108.13**	**$231,600.00**
	Item Code 490783 Total No. of Proj.			**4**		**Total Amount**	**$231,600.00**
490801	STEEL SHEET PILING	SQFT	4	1	990.00	$97.00	$96,030.00
	Unit Sub Total	**SQFT**		**1**	**990.00**	**$97.00**	**$96,030.00**
	Item Code 490801 Total No. of Proj.			**1**		**Total Amount**	**$96,030.00**
491009	FURNISH PILING (CLASS 400) (ALTERNATIVE V)	M	7	1	12,331.00	$106.00	$1,307,086.00
	Unit Sub Total	**M**		**1**	**12,331.00**	**$106.00**	**$1,307,086.00**
	Item Code 491009 Total No. of Proj.			**1**		**Total Amount**	**$1,307,086.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
491010	DRIVE PILE (CLASS 400) (ALTERNATIVE V)	EA	7	1	846.00	$1,150.00	$972,900.00
	Unit Sub Total	**EA**		**1**	**846.00**	**$1,150.00**	**$972,900.00**
	Item Code 491010 Total No. of Proj.			**1**		**Total Amount**	**$972,900.00**
491012	FURNISH PILING (CLASS 400) (ALTERNATIVE W)	M	5	1	1,162.00	$110.00	$127,820.00
	Unit Sub Total	**M**		**1**	**1,162.00**	**$110.00**	**$127,820.00**
	Item Code 491012 Total No. of Proj.			**1**		**Total Amount**	**$127,820.00**
491013	DRIVE PILE (CLASS 400) (ALTERNATIVE W)	EA	5	1	97.00	$1,000.00	$97,000.00
	Unit Sub Total	**EA**		**1**	**97.00**	**$1,000.00**	**$97,000.00**
	Item Code 491013 Total No. of Proj.			**1**		**Total Amount**	**$97,000.00**
495106	FURNISH 18" CAST-IN-STEEL SHELL CONCRETE PILING	LF	4	2	1,032.00	$172.06	$177,570.00
		LF	10	1	470.00	$120.00	$56,400.00
	Unit Sub Total	**LF**		**3**	**1,502.00**	**$155.77**	**$233,970.00**
	Item Code 495106 Total No. of Proj.			**3**		**Total Amount**	**$233,970.00**
495107	DRIVE 18" CAST-IN-STEEL SHELL CONCRETE PILE	EA	4	2	18.00	$4,666.67	$84,000.00
		EA	10	1	8.00	$13,000.00	$104,000.00
	Unit Sub Total	**EA**		**3**	**26.00**	**$7,230.77**	**$188,000.00**
	Item Code 495107 Total No. of Proj.			**3**		**Total Amount**	**$188,000.00**
495115	FURNISH 24" CAST-IN-STEEL SHELL CONCRETE PILING	LF	4	2	2,172.00	$144.24	$313,280.00
		LF	5	1	83.00	$155.00	$12,865.00
	Unit Sub Total	**LF**		**3**	**2,255.00**	**$144.63**	**$326,145.00**
	Item Code 495115 Total No. of Proj.			**3**		**Total Amount**	**$326,145.00**
495116	DRIVE 24" CAST-IN-STEEL SHELL CONCRETE PILE	EA	4	2	32.00	$13,500.00	$432,000.00
		EA	5	1	2.00	$3,600.00	$7,200.00
	Unit Sub Total	**EA**		**3**	**34.00**	**$12,917.65**	**$439,200.00**
	Item Code 495116 Total No. of Proj.			**3**		**Total Amount**	**$439,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
495133	FURNISH 36" CAST-IN-STEEL SHELL CONCRETE PILING	LF	10	1	1,888.00	$225.00	$424,800.00
	Unit Sub Total	**LF**		**1**	**1,888.00**	**$225.00**	**$424,800.00**
	Item Code 495133 Total No. of Proj.			**1**		**Total Amount**	**$424,800.00**
495134	DRIVE 36" CAST-IN-STEEL SHELL CONCRETE PILE	EA	10	1	16.00	$22,000.00	$352,000.00
	Unit Sub Total	**EA**		**1**	**16.00**	**$22,000.00**	**$352,000.00**
	Item Code 495134 Total No. of Proj.			**1**		**Total Amount**	**$352,000.00**
495149	FURNISH 48" CAST-IN-STEEL SHELL CONCRETE PILING	LF	5	1	13,909.00	$275.00	$3,824,975.00
		LF	6	1	2,267.00	$400.00	$906,800.00
	Unit Sub Total	**LF**		**2**	**16,176.00**	**$292.52**	**$4,731,775.00**
	Item Code 495149 Total No. of Proj.			**2**		**Total Amount**	**$4,731,775.00**
495150	DRIVE 48" CAST-IN-STEEL SHELL CONCRETE PILE	EA	5	1	187.00	$9,930.00	$1,856,910.00
		EA	6	1	18.00	$5,000.00	$90,000.00
	Unit Sub Total	**EA**		**2**	**205.00**	**$9,497.12**	**$1,946,910.00**
	Item Code 495150 Total No. of Proj.			**2**		**Total Amount**	**$1,946,910.00**
498009	16" CAST-IN-DRILLED-HOLE CONCRETE PILING (BARRIER)	LF	6	1	26,500.00	$38.00	$1,007,000.00
	Unit Sub Total	**LF**		**1**	**26,500.00**	**$38.00**	**$1,007,000.00**
	Item Code 498009 Total No. of Proj.			**1**		**Total Amount**	**$1,007,000.00**
498016	16" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	LF	3	2	40,600.00	$40.47	$1,643,000.00
		LF	4	3	18,161.00	$53.38	$969,410.00
		LF	10	1	13,500.00	$50.00	$675,000.00
	Unit Sub Total	**LF**		**6**	**72,261.00**	**$45.49**	**$3,287,410.00**
	Item Code 498016 Total No. of Proj.			**6**		**Total Amount**	**$3,287,410.00**
498018	18" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	LF	12	1	287.00	$460.00	$132,020.00
	Unit Sub Total	**LF**		**1**	**287.00**	**$460.00**	**$132,020.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 498018 Total No. of Proj.			**1**		**Total Amount**	**$132,020.00**
498022	24" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	LF	3	1	730.00	$90.00	$65,700.00
		LF	4	2	127.00	$103.54	$13,150.00
	Unit Sub Total	**LF**		**3**	**857.00**	**$92.01**	**$78,850.00**
	Item Code 498022 Total No. of Proj.			**3**		**Total Amount**	**$78,850.00**
498027	400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	M	7	2	2,310.00	$157.01	$362,700.00
	Unit Sub Total	**M**		**2**	**2,310.00**	**$157.01**	**$362,700.00**
	Item Code 498027 Total No. of Proj.			**2**		**Total Amount**	**$362,700.00**
499030	FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (610 MM)	M	5	1	252.00	$280.00	$70,560.00
	Unit Sub Total	**M**		**1**	**252.00**	**$280.00**	**$70,560.00**
	Item Code 499030 Total No. of Proj.			**1**		**Total Amount**	**$70,560.00**
499031	DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (610 MM)	EA	5	1	14.00	$1,500.00	$21,000.00
	Unit Sub Total	**EA**		**1**	**14.00**	**$1,500.00**	**$21,000.00**
	Item Code 499031 Total No. of Proj.			**1**		**Total Amount**	**$21,000.00**
500001	PRESTRESSING CAST-IN-PLACE CONCRETE	LS	1	1	1.00	$128,000.00	$128,000.00
		LS	2	1	1.00	$36,000.00	$36,000.00
		LS	3	3	3.00	$123,916.67	$371,750.00
		LS	4	4	4.00	$64,250.00	$257,000.00
		LS	5	1	1.00	$500,000.00	$500,000.00
		LS	6	2	2.00	$140,000.00	$280,000.00
		LS	7	4	4.00	$1,123,500.00	$4,494,000.00
		LS	8	3	3.00	$204,200.00	$612,600.00
		LS	10	2	2.00	$327,500.00	$655,000.00
		LS	11	2	2.00	$462,000.00	$924,000.00
		LS	12	3	3.00	$67,866.67	$203,600.00
	Unit Sub Total	**LS**		**26**	**26.00**	**$325,459.62**	**$8,461,950.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 500001 Total No. of Proj.			**26**		**Total Amount**	**$8,461,950.00**
500050	TIEBACK ANCHOR	EA	1	1	49.00	$4,500.00	$220,500.00
		EA	3	2	84.00	$2,495.24	$209,600.00
		EA	4	1	40.00	$5,000.00	$200,000.00
		EA	5	1	108.00	$5,500.00	$594,000.00
		EA	7	1	8.00	$4,147.81	$33,182.48
		EA	8	2	276.00	$2,292.75	$632,800.00
		EA	11	1	46.00	$4,000.00	$184,000.00
		EA	12	3	216.00	$1,745.00	$376,920.00
	Unit Sub Total	**EA**		**12**	**827.00**	**$2,963.73**	**$2,451,002.48**
	Item Code 500050 Total No. of Proj.			**12**		**Total Amount**	**$2,451,002.48**
500060	TIEDOWN ANCHOR	EA	10	1	18.00	$4,200.00	$75,600.00
	Unit Sub Total	**EA**		**1**	**18.00**	**$4,200.00**	**$75,600.00**
	Item Code 500060 Total No. of Proj.			**1**		**Total Amount**	**$75,600.00**
510000	SEAL COURSE CONCRETE	CY	3	1	132.00	$300.00	$39,600.00
		CY	4	1	82.00	$120.00	$9,840.00
		CY	7	1	4,878.00	$75.00	$365,850.00
	Unit Sub Total	**CY**		**3**	**5,092.00**	**$81.56**	**$415,290.00**
	Item Code 510000 Total No. of Proj.			**3**		**Total Amount**	**$415,290.00**
510040	STRUCTURAL CONCRETE, WALL FACING	CY	12	1	36.00	$1,250.00	$45,000.00
	Unit Sub Total	**CY**		**1**	**36.00**	**$1,250.00**	**$45,000.00**
	Item Code 510040 Total No. of Proj.			**1**		**Total Amount**	**$45,000.00**
510050	STRUCTURAL CONCRETE	CY	1	1	135.00	$1,250.00	$168,750.00
		CY	12	1	9.00	$730.00	$6,570.00
	Unit Sub Total	**CY**		**2**	**144.00**	**$1,217.50**	**$175,320.00**
510050	STRUCTURAL CONCRETE	M3	7	1	4.10	$1,900.00	$7,790.00
	Unit Sub Total	**M3**		**1**	**4.10**	**$1,900.00**	**$7,790.00**
	Item Code 510050 Total No. of Proj.			**3**		**Total Amount**	**$183,110.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	CY	1	1	446.00	$500.00	$223,000.00
		CY	2	5	450.00	$663.51	$298,579.30
		CY	3	3	1,612.00	$524.50	$845,487.50
		CY	4	5	2,928.00	$387.81	$1,135,500.00
		CY	5	1	4,207.00	$250.00	$1,051,750.00
		CY	6	2	301.00	$286.05	$86,100.00
		CY	7	2	2,653.00	$241.20	$639,900.00
		CY	8	2	416.00	$377.04	$156,850.00
		CY	10	3	813.00	$329.03	$267,500.00
		CY	12	4	387.00	$357.44	$138,330.00
	Unit Sub Total	**CY**		**28**	**14,213.00**	**$340.74**	**$4,842,996.80**
510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	M3	4	1	141.00	$320.00	$45,120.00
		M3	5	1	1,036.00	$430.00	$445,480.00
		M3	7	2	4,360.00	$310.40	$1,353,325.00
		M3	8	1	1,369.00	$330.00	$451,770.00
		M3	11	2	845.00	$263.43	$222,600.00
	Unit Sub Total	**M3**		**7**	**7,751.00**	**$324.90**	**$2,518,295.00**
	Item Code 510051 Total No. of Proj.			**35**		**Total Amount**	**$7,361,291.80**
510053	STRUCTURAL CONCRETE, BRIDGE	CF	3	1	648.00	$40.00	$25,920.00
	Unit Sub Total	**CF**		**1**	**648.00**	**$40.00**	**$25,920.00**
510053	STRUCTURAL CONCRETE, BRIDGE	CY	1	1	2,397.00	$1,050.00	$2,516,850.00
		CY	2	8	2,172.00	$1,029.51	$2,236,096.43
		CY	3	6	15,260.00	$448.15	$6,838,783.00
		CY	4	13	7,279.00	$607.29	$4,420,430.00
		CY	5	2	12,901.00	$480.28	$6,196,120.00
		CY	6	6	6,329.00	$546.46	$3,458,532.75
		CY	7	11	79,310.00	$536.54	$42,553,270.16
		CY	8	4	7,904.00	$966.89	$7,642,260.00
		CY	10	4	14,620.00	$626.27	$9,156,010.00
		CY	12	6	2,528.00	$736.10	$1,860,851.00
	Unit Sub Total	**CY**		**61**	**150,700.00**	**$576.50**	**$86,879,203.34**
510053	STRUCTURAL CONCRETE, BRIDGE	M3	4	1	385.00	$1,050.00	$404,250.00
		M3	5	1	7,640.00	$855.00	$6,532,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
510053	STRUCTURAL CONCRETE, BRIDGE	M3	7	2	17,308.00	$591.35	$10,235,100.00
		M3	8	1	5,377.00	$520.00	$2,796,040.00
		M3	11	2	13,628.00	$652.83	$8,896,700.00
	Unit Sub Total	**M3**		**7**	**44,338.00**	**$651.01**	**$28,864,290.00**
	Item Code 510053 Total No. of Proj.			**69**		**Total Amount**	**$115,769,413.34**
510058	STRUCTURAL CONCRETE, WALL	CY	4	1	96.00	$700.00	$67,200.00
	Unit Sub Total	**CY**		**1**	**96.00**	**$700.00**	**$67,200.00**
	Item Code 510058 Total No. of Proj.			**1**		**Total Amount**	**$67,200.00**
510060	STRUCTURAL CONCRETE, RETAINING WALL	CY	1	2	102.00	$854.90	$87,200.00
		CY	3	3	343.00	$696.36	$238,850.00
		CY	4	8	11,523.00	$428.56	$4,938,274.00
		CY	5	1	160.00	$750.00	$120,000.00
		CY	6	3	546.00	$800.49	$437,070.00
		CY	7	3	5,743.00	$285.55	$1,639,918.60
		CY	8	2	1,479.00	$499.68	$739,020.00
		CY	10	2	16,834.00	$381.39	$6,420,300.00
		CY	11	2	286.00	$682.66	$195,242.00
		CY	12	4	5,961.00	$325.79	$1,942,050.00
	Unit Sub Total	**CY**		**30**	**42,977.00**	**$389.93**	**$16,757,924.60**
510060	STRUCTURAL CONCRETE, RETAINING WALL	M3	4	1	190.00	$950.00	$180,500.00
		M3	5	1	1,027.00	$700.00	$718,900.00
		M3	7	3	4,072.00	$490.76	$1,998,390.00
		M3	8	1	1,619.00	$510.00	$825,690.00
		M3	11	1	3,539.00	$500.00	$1,769,500.00
	Unit Sub Total	**M3**		**7**	**10,447.00**	**$525.79**	**$5,492,980.00**
	Item Code 510060 Total No. of Proj.			**37**		**Total Amount**	**$22,250,904.60**
510061	STRUCTURAL CONCRETE, SOUND WALL	CY	12	1	87.00	$550.00	$47,850.00
	Unit Sub Total	**CY**		**1**	**87.00**	**$550.00**	**$47,850.00**
	Item Code 510061 Total No. of Proj.			**1**		**Total Amount**	**$47,850.00**
510067	STRUCTURAL CONCRETE, BRIDGE (CHANNEL)	CY	3	1	14.00	$400.00	$5,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**CY**		**1**	**14.00**	**$400.00**	**$5,600.00**
	Item Code 510067 Total No. of Proj.			**1**		**Total Amount**	**$5,600.00**
510072	STRUCTURAL CONCRETE, BARRIER SLAB	CY	1	1	22.00	$600.00	$13,200.00
		CY	3	2	1,579.00	$769.08	$1,214,380.00
		CY	4	2	1,952.00	$519.43	$1,013,918.00
		CY	5	1	550.00	$480.00	$264,000.00
		CY	7	3	1,496.00	$296.72	$443,900.00
	Unit Sub Total	**CY**		**9**	**5,599.00**	**$526.77**	**$2,949,398.00**
510072	STRUCTURAL CONCRETE, BARRIER SLAB	M3	4	1	620.00	$500.00	$310,000.00
		M3	5	1	359.00	$575.00	$206,425.00
		M3	7	2	263.00	$470.27	$123,680.00
	Unit Sub Total	**M3**		**4**	**1,242.00**	**$515.38**	**$640,105.00**
	Item Code 510072 Total No. of Proj.			**13**		**Total Amount**	**$3,589,503.00**
510085	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE EQ)	CY	4	1	13.00	$1,188.00	$15,444.00
	Unit Sub Total	**CY**		**1**	**13.00**	**$1,188.00**	**$15,444.00**
510085	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE EQ)	M3	7	1	4.00	$1,700.00	$6,800.00
	Unit Sub Total	**M3**		**1**	**4.00**	**$1,700.00**	**$6,800.00**
	Item Code 510085 Total No. of Proj.			**2**		**Total Amount**	**$22,244.00**
510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	CY	2	1	71.00	$900.00	$63,900.00
		CY	3	3	715.00	$657.34	$470,000.00
		CY	4	1	467.00	$450.00	$210,150.00
		CY	5	1	171.00	$600.00	$102,600.00
		CY	6	1	473.00	$600.00	$283,800.00
		CY	7	2	1,344.00	$339.73	$456,600.00
		CY	8	2	281.00	$301.46	$84,710.00
		CY	10	2	1,414.00	$526.73	$744,800.00
		CY	12	4	412.00	$688.93	$283,840.00
	Unit Sub Total	**CY**		**17**	**5,348.00**	**$504.94**	**$2,700,400.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	M3	5	1	736.00	$800.00	$588,800.00
		M3	7	2	439.00	$691.67	$303,645.00
		M3	8	1	476.00	$600.00	$285,600.00
		M3	11	2	525.00	$163.14	$85,650.00
	Unit Sub Total	**M3**		**6**	**2,176.00**	**$580.74**	**$1,263,695.00**
	Item Code 510086 Total No. of Proj.			**23**		**Total Amount**	**$3,964,095.00**
510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	CY	1	1	251.00	$575.00	$144,325.00
		CY	2	2	553.00	$1,033.82	$571,700.00
		CY	3	5	3,942.00	$754.51	$2,974,275.00
		CY	4	4	2,007.00	$790.96	$1,587,450.00
		CY	5	1	201.00	$425.00	$85,425.00
		CY	6	2	527.00	$857.68	$451,996.00
		CY	7	13	7,176.00	$834.28	$5,986,825.02
		CY	8	2	338.00	$1,347.71	$455,526.00
		CY	10	2	2,705.00	$525.34	$1,421,040.00
		CY	11	3	1,533.00	$779.16	$1,194,450.00
		CY	12	6	1,098.00	$988.05	$1,084,880.00
	Unit Sub Total	**CY**		**41**	**20,331.00**	**$784.90**	**$15,957,892.02**
510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	M3	7	1	50.00	$765.00	$38,250.00
		M3	11	2	176.00	$218.98	$38,540.00
	Unit Sub Total	**M3**		**3**	**226.00**	**$339.78**	**$76,790.00**
	Item Code 510087 Total No. of Proj.			**44**		**Total Amount**	**$16,034,682.02**
510088	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N MODIFIED)	CY	1	1	97.00	$1,200.00	$116,400.00
		CY	4	1	86.00	$500.00	$43,000.00
	Unit Sub Total	**CY**		**2**	**183.00**	**$871.04**	**$159,400.00**
510088	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N MODIFIED)	M3	4	1	37.00	$1,050.00	$38,850.00
		M3	11	1	15.00	$130.00	$1,950.00
	Unit Sub Total	**M3**		**2**	**52.00**	**$784.62**	**$40,800.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 510088 Total No. of Proj.			**4**		**Total Amount**	**$200,200.00**
510090	STRUCTURAL CONCRETE, BOX CULVERT	CY	1	1	110.00	$550.00	$60,500.00
		CY	3	2	73.00	$1,324.66	$96,700.00
		CY	4	5	1,052.00	$981.52	$1,032,555.00
		CY	6	4	1,806.00	$560.66	$1,012,550.00
		CY	7	1	264.00	$1,000.00	$264,000.00
		CY	8	1	120.00	$1,590.00	$190,800.00
		CY	10	1	102.00	$800.00	$81,600.00
	Unit Sub Total	**CY**		**15**	**3,527.00**	**$776.50**	**$2,738,705.00**
510090	STRUCTURAL CONCRETE, BOX CULVERT	M3	7	1	133.60	$750.00	$100,200.00
	Unit Sub Total	**M3**		**1**	**133.60**	**$750.00**	**$100,200.00**
	Item Code 510090 Total No. of Proj.			**16**		**Total Amount**	**$2,838,905.00**
510092	STRUCTURAL CONCRETE, HEADWALL	CY	3	1	12.00	$2,000.00	$24,000.00
		CY	4	1	3.00	$1,500.00	$4,500.00
		CY	11	1	8.00	$1,700.00	$13,600.00
	Unit Sub Total	**CY**		**3**	**23.00**	**$1,830.43**	**$42,100.00**
	Item Code 510092 Total No. of Proj.			**3**		**Total Amount**	**$42,100.00**
510126	CLASS 2 CONCRETE (MINOR STRUCTURE)	M3	11	1	5.00	$1,100.00	$5,500.00
	Unit Sub Total	**M3**		**1**	**5.00**	**$1,100.00**	**$5,500.00**
	Item Code 510126 Total No. of Proj.			**1**		**Total Amount**	**$5,500.00**
510135	CLASS 2 CONCRETE (HEADWALL)	CY	6	1	2.00	$1,000.00	$2,000.00
	Unit Sub Total	**CY**		**1**	**2.00**	**$1,000.00**	**$2,000.00**
	Item Code 510135 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**
510138	CLASS 2 CONCRETE (WINGWALLS)	M3	5	1	32.00	$1,900.00	$60,800.00
	Unit Sub Total	**M3**		**1**	**32.00**	**$1,900.00**	**$60,800.00**
	Item Code 510138 Total No. of Proj.			**1**		**Total Amount**	**$60,800.00**
510314	CLASS 4 CONCRETE (BACKFILL)	CY	3	2	18.30	$216.39	$3,960.00
	Unit Sub Total	**CY**		**2**	**18.30**	**$216.39**	**$3,960.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
510314	CLASS 4 CONCRETE (BACKFILL)	M3	10	1	190.00	$80.00	$15,200.00
	Unit Sub Total	**M3**		**1**	**190.00**	**$80.00**	**$15,200.00**
	Item Code 510314 Total No. of Proj.			**3**		**Total Amount**	**$19,160.00**
510409	CLASS 1 CONCRETE (MINOR STRUCTURE)	M3	10	1	75.00	$1,500.00	$112,500.00
	Unit Sub Total	**M3**		**1**	**75.00**	**$1,500.00**	**$112,500.00**
	Item Code 510409 Total No. of Proj.			**1**		**Total Amount**	**$112,500.00**
510410	CLASS 1 CONCRETE (STRUCTURE)	M3	8	1	136.00	$730.00	$99,280.00
	Unit Sub Total	**M3**		**1**	**136.00**	**$730.00**	**$99,280.00**
	Item Code 510410 Total No. of Proj.			**1**		**Total Amount**	**$99,280.00**
510413	CLASS 1 CONCRETE (BOX CULVERT)	M3	5	1	654.00	$1,000.00	$654,000.00
	Unit Sub Total	**M3**		**1**	**654.00**	**$1,000.00**	**$654,000.00**
	Item Code 510413 Total No. of Proj.			**1**		**Total Amount**	**$654,000.00**
510501	MINOR CONCRETE	CY	4	1	44.00	$400.00	$17,600.00
		CY	8	1	16.00	$700.00	$11,200.00
	Unit Sub Total	**CY**		**2**	**60.00**	**$480.00**	**$28,800.00**
	Item Code 510501 Total No. of Proj.			**2**		**Total Amount**	**$28,800.00**
510502	MINOR CONCRETE (MINOR STRUCTURE)	CY	1	14	322.90	$1,611.42	$520,327.50
		CY	2	14	822.40	$1,415.88	$1,164,417.00
		CY	3	23	952.00	$1,773.99	$1,688,834.00
		CY	4	19	3,191.70	$898.83	$2,868,792.40
		CY	5	7	101.20	$1,444.76	$146,210.00
		CY	6	15	952.00	$835.88	$795,760.00
		CY	7	13	1,064.40	$1,035.24	$1,101,909.48
		CY	8	7	352.40	$2,111.14	$743,964.00
		CY	9	2	10.70	$948.60	$10,150.00
		CY	10	6	655.30	$1,134.05	$743,140.00
		CY	11	11	113.50	$1,843.44	$209,230.00
		CY	12	8	371.50	$1,593.78	$592,090.00
	Unit Sub Total	**CY**		**139**	**8,910.00**	**$1,187.97**	**$10,584,824.38**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	4	1	55.00	$1,250.00	$68,750.00
		M3	5	1	723.00	$1,300.00	$939,900.00
		M3	7	6	506.20	$1,675.05	$847,910.00
		M3	8	1	323.00	$1,100.00	$355,300.00
		M3	10	1	13.00	$955.00	$12,415.00
		M3	11	2	324.00	$1,184.26	$383,700.00
	Unit Sub Total	**M3**		**12**	**1,944.20**	**$1,341.41**	**$2,607,975.00**
	Item Code 510502 Total No. of Proj.			**151**		**Total Amount**	**$13,192,799.38**
510504	MINOR CONCRETE (PIPE ENCASEMENT)	M3	7	1	18.00	$200.00	$3,600.00
	Unit Sub Total	**M3**		**1**	**18.00**	**$200.00**	**$3,600.00**
	Item Code 510504 Total No. of Proj.			**1**		**Total Amount**	**$3,600.00**
510524	MINOR CONCRETE (SOUND WALL)	CY	3	2	1,792.00	$328.13	$588,000.00
		CY	4	3	384.00	$698.44	$268,200.00
		CY	6	1	56.00	$500.00	$28,000.00
		CY	12	1	1,910.00	$320.00	$611,200.00
	Unit Sub Total	**CY**		**7**	**4,142.00**	**$361.03**	**$1,495,400.00**
	Item Code 510524 Total No. of Proj.			**7**		**Total Amount**	**$1,495,400.00**
510526	MINOR CONCRETE (BACKFILL)	CY	1	2	97.00	$143.92	$13,960.00
		CY	2	2	58.00	$113.79	$6,600.00
		CY	3	5	2,911.20	$139.98	$407,520.00
		CY	4	9	5,191.30	$151.81	$788,086.20
		CY	5	1	40.00	$100.00	$4,000.00
		CY	6	4	102.00	$114.13	$11,641.00
		CY	7	2	50.00	$112.60	$5,630.00
		CY	9	3	580.00	$153.45	$89,000.00
		CY	10	2	23.00	$123.48	$2,840.00
		CY	11	1	40.00	$370.00	$14,800.00
		CY	12	1	240.00	$105.00	$25,200.00
	Unit Sub Total	**CY**		**32**	**9,332.50**	**$146.72**	**$1,369,277.20**
510526	MINOR CONCRETE (BACKFILL)	M3	7	3	377.00	$117.04	$44,125.00
		M3	8	1	33.00	$135.00	$4,455.00
		M3	10	1	50.00	$100.00	$5,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**5**	**460.00**	**$116.48**	**$53,580.00**
	Item Code 510526	**Total No. of Proj.**			**37**		**Total Amount**	**$1,422,857.20**
510530	MINOR CONCRETE (WALL)		CY	2	1	92.00	$720.00	$66,240.00
		Unit Sub Total	**CY**		**1**	**92.00**	**$720.00**	**$66,240.00**
	Item Code 510530	**Total No. of Proj.**			**1**		**Total Amount**	**$66,240.00**
510705	PILASTER, SOUND WALL		M3	7	1	43.00	$2,100.00	$90,300.00
		Unit Sub Total	**M3**		**1**	**43.00**	**$2,100.00**	**$90,300.00**
	Item Code 510705	**Total No. of Proj.**			**1**		**Total Amount**	**$90,300.00**
510800	PAVING NOTCH EXTENSION		CF	1	1	162.00	$200.00	$32,400.00
			CF	2	2	381.00	$99.02	$37,725.00
			CF	3	5	2,750.00	$129.43	$355,945.00
			CF	4	4	585.00	$61.55	$36,005.00
			CF	6	2	354.00	$108.05	$38,248.00
			CF	7	11	3,168.00	$105.56	$334,405.00
			CF	8	1	56.00	$124.00	$6,944.00
			CF	10	2	1,191.00	$221.51	$263,815.00
			CF	11	2	975.00	$223.62	$218,025.00
			CF	12	6	704.00	$184.52	$129,900.00
		Unit Sub Total	**CF**		**36**	**10,326.00**	**$140.75**	**$1,453,412.00**
510800	PAVING NOTCH EXTENSION		M3	7	1	2.00	$1,900.00	$3,800.00
			M3	11	1	5.00	$3,000.00	$15,000.00
		Unit Sub Total	**M3**		**2**	**7.00**	**$2,685.71**	**$18,800.00**
	Item Code 510800	**Total No. of Proj.**			**38**		**Total Amount**	**$1,472,212.00**
510805	DIAPHRAGM BOLSTER		EA	3	1	18.00	$3,000.00	$54,000.00
			EA	4	1	20.00	$1,000.00	$20,000.00
			EA	10	1	98.00	$2,800.00	$274,400.00
		Unit Sub Total	**EA**		**3**	**136.00**	**$2,561.76**	**$348,400.00**
	Item Code 510805	**Total No. of Proj.**			**3**		**Total Amount**	**$348,400.00**
511001	LIGHTWEIGHT CONCRETE		CY	7	1	50.00	$449.34	$22,467.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**CY**		**1**	**50.00**	**$449.34**	**$22,467.00**
	Item Code 511001	**Total No. of Proj.**			**1**		**Total Amount**	**$22,467.00**
511035	ARCHITECTURAL TREATMENT		LF	5	2	17,600.00	$21.95	$386,400.00
			LF	7	1	8,130.00	$9.40	$76,422.00
		Unit Sub Total	**LF**		**3**	**25,730.00**	**$17.99**	**$462,822.00**
511035	ARCHITECTURAL TREATMENT		M2	7	2	5,208.00	$113.92	$593,292.00
		Unit Sub Total	**M2**		**2**	**5,208.00**	**$113.92**	**$593,292.00**
511035	ARCHITECTURAL TREATMENT		SQFT	3	2	3,913.00	$9.52	$37,265.00
			SQFT	4	3	70,236.00	$6.79	$476,806.00
			SQFT	7	1	37,187.00	$15.00	$557,805.00
			SQFT	12	1	5,041.00	$26.00	$131,066.00
		Unit Sub Total	**SQFT**		**7**	**116,377.00**	**$10.34**	**$1,202,942.00**
	Item Code 511035	**Total No. of Proj.**			**12**		**Total Amount**	**$2,259,056.00**
511036	ARCHITECTURAL SURFACE (BARRIER)		SQFT	7	1	8,750.00	$5.00	$43,750.00
		Unit Sub Total	**SQFT**		**1**	**8,750.00**	**$5.00**	**$43,750.00**
	Item Code 511036	**Total No. of Proj.**			**1**		**Total Amount**	**$43,750.00**
511045	EXPOSED AGGREGATE FINISH		SQFT	4	1	842.00	$10.00	$8,420.00
		Unit Sub Total	**SQFT**		**1**	**842.00**	**$10.00**	**$8,420.00**
	Item Code 511045	**Total No. of Proj.**			**1**		**Total Amount**	**$8,420.00**
511047	ANTI-GRAFFITI COATING		M2	7	1	2,330.00	$7.00	$16,310.00
			M2	11	1	100.00	$10.00	$1,000.00
		Unit Sub Total	**M2**		**2**	**2,430.00**	**$7.12**	**$17,310.00**
511047	ANTI-GRAFFITI COATING		SQFT	2	1	952.00	$1.00	$952.00
			SQFT	4	2	103,400.00	$0.60	$62,116.00
			SQFT	10	1	3,600.00	$1.00	$3,600.00
		Unit Sub Total	**SQFT**		**4**	**107,952.00**	**$0.62**	**$66,668.00**
	Item Code 511047	**Total No. of Proj.**			**6**		**Total Amount**	**$83,978.00**
511063	FRACTURED FIN TEXTURE		SQFT	4	1	5,710.00	$9.45	$53,959.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**SQFT**		**1**	**5,710.00**	**$9.45**	**$53,959.50**
	Item Code 511063	**Total No. of Proj.**			**1**		**Total Amount**	**$53,959.50**
511064	FRACTURED RIB TEXTURE		M2	8	1	1,258.00	$65.00	$81,770.00
		Unit Sub Total	**M2**		**1**	**1,258.00**	**$65.00**	**$81,770.00**
511064	FRACTURED RIB TEXTURE		SQFT	1	1	432.00	$25.00	$10,800.00
			SQFT	4	2	1,422.00	$17.57	$24,990.00
			SQFT	10	1	156,000.00	$1.10	$171,600.00
			SQFT	12	2	15,029.00	$5.91	$88,748.00
		Unit Sub Total	**SQFT**		**6**	**172,883.00**	**$1.71**	**$296,138.00**
	Item Code 511064	**Total No. of Proj.**			**7**		**Total Amount**	**$377,908.00**
511106	DRILL AND BOND DOWEL		LF	2	5	6,384.00	$24.97	$159,411.74
			LF	3	4	5,442.00	$36.26	$197,313.00
			LF	4	8	1,494.00	$41.95	$62,675.00
			LF	5	2	31,023.00	$19.06	$591,325.00
			LF	6	2	4,158.00	$23.27	$96,760.00
			LF	7	5	2,213.00	$19.73	$43,658.40
			LF	8	4	3,852.00	$22.90	$88,221.00
			LF	10	2	4,410.00	$17.11	$75,450.00
			LF	12	5	919.00	$27.36	$25,142.00
		Unit Sub Total	**LF**		**37**	**59,895.00**	**$22.37**	**$1,339,956.14**
511106	DRILL AND BOND DOWEL		M	5	1	53.00	$100.00	$5,300.00
			M	7	1	68.00	$75.00	$5,100.00
			M	8	1	65.00	$50.00	$3,250.00
			M	11	1	1,708.00	$90.00	$153,720.00
		Unit Sub Total	**M**		**4**	**1,894.00**	**$88.37**	**$167,370.00**
	Item Code 511106	**Total No. of Proj.**			**41**		**Total Amount**	**$1,507,326.14**
511110	DRILL AND BOND DOWEL (CHEMICAL ADHESIVE)		EA	4	1	270.00	$21.00	$5,670.00
			EA	6	1	1,132.00	$40.00	$45,280.00
			EA	7	1	75.00	$100.00	$7,500.00
			EA	8	1	336.00	$30.00	$10,080.00
			EA	11	1	182.00	$94.00	$17,108.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**5**	**1,995.00**	**$42.93**	**$85,638.00**
	Item Code 511110	**Total No. of Proj.**			**5**		**Total Amount**	**$85,638.00**
511115	EPOXY ADHESIVE (BOND COAT)		GAL	8	1	5.00	$500.00	$2,500.00
		Unit Sub Total	**GAL**		**1**	**5.00**	**$500.00**	**$2,500.00**
	Item Code 511115	**Total No. of Proj.**			**1**		**Total Amount**	**$2,500.00**
511118	CLEAN EXPANSION JOINT		LF	1	3	1,040.00	$20.80	$21,627.00
			LF	2	9	3,149.00	$21.40	$67,387.00
			LF	3	15	7,699.00	$19.49	$150,049.00
			LF	4	12	9,521.00	$13.45	$128,042.00
			LF	5	4	607.00	$14.50	$8,799.73
			LF	6	6	4,913.00	$15.00	$73,711.00
			LF	7	24	50,135.00	$11.75	$589,253.56
			LF	8	7	7,091.00	$14.13	$100,210.60
			LF	10	3	1,738.00	$17.62	$30,630.00
			LF	11	5	4,296.00	$9.24	$39,676.56
			LF	12	6	2,414.00	$19.74	$47,659.50
		Unit Sub Total	**LF**		**94**	**92,603.00**	**$13.57**	**$1,257,045.95**
511118	CLEAN EXPANSION JOINT		M	5	1	36.00	$95.00	$3,420.00
		Unit Sub Total	**M**		**1**	**36.00**	**$95.00**	**$3,420.00**
	Item Code 511118	**Total No. of Proj.**			**95**		**Total Amount**	**$1,260,465.95**
511121	PORTLAND CEMENT CONCRETE (PATCH)		CF	8	1	31.00	$235.00	$7,285.00
		Unit Sub Total	**CF**		**1**	**31.00**	**$235.00**	**$7,285.00**
	Item Code 511121	**Total No. of Proj.**			**1**		**Total Amount**	**$7,285.00**
511124	RAPID SETTING CONCRETE (PATCH)		CF	1	3	972.00	$55.33	$53,781.00
			CF	2	10	3,138.00	$32.79	$102,885.00
			CF	3	12	4,044.00	$19.97	$80,744.00
			CF	4	11	5,085.00	$25.85	$131,431.00
			CF	5	3	1,846.00	$24.59	$45,392.00
			CF	6	6	3,890.00	$9.95	$38,689.00
			CF	7	25	19,312.00	$18.99	$366,711.05

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
511124	RAPID SETTING CONCRETE (PATCH)	CF	8	8	5,759.00	$26.14	$150,538.00
		CF	10	3	3,389.00	$92.29	$312,765.00
		CF	11	4	1,644.00	$33.63	$55,281.73
		CF	12	4	1,465.00	$36.39	$53,315.00
	Unit Sub Total	**CF**		**89**	**50,544.00**	**$27.53**	**$1,391,532.78**
	Item Code 511124 Total No. of Proj.			**89**		**Total Amount**	**$1,391,532.78**
511125	CLOSE ACCESS, DECK	EA	4	1	20.00	$500.00	$10,000.00
	Unit Sub Total	**EA**		**1**	**20.00**	**$500.00**	**$10,000.00**
	Item Code 511125 Total No. of Proj.			**1**		**Total Amount**	**$10,000.00**
511130	INJECT CRACK (EPOXY)	LF	1	1	5,910.00	$30.45	$179,959.50
		LF	3	1	150.00	$12.00	$1,800.00
		LF	5	1	18.00	$275.00	$4,950.00
		LF	6	1	4.00	$1,000.00	$4,000.00
		LF	7	3	538.00	$76.46	$41,135.60
		LF	8	1	110.00	$140.00	$15,400.00
	Unit Sub Total	**LF**		**8**	**6,730.00**	**$36.74**	**$247,245.10**
	Item Code 511130 Total No. of Proj.			**8**		**Total Amount**	**$247,245.10**
512202	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (30'-40')	EA	2	1	12.00	$5,120.00	$61,440.00
		EA	10	1	4.00	$4,700.00	$18,800.00
	Unit Sub Total	**EA**		**2**	**16.00**	**$5,015.00**	**$80,240.00**
	Item Code 512202 Total No. of Proj.			**2**		**Total Amount**	**$80,240.00**
512203	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (40'-50')	EA	10	1	26.00	$5,400.00	$140,400.00
	Unit Sub Total	**EA**		**1**	**26.00**	**$5,400.00**	**$140,400.00**
	Item Code 512203 Total No. of Proj.			**1**		**Total Amount**	**$140,400.00**
512205	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (60'-70')	EA	4	1	4.00	$14,000.00	$56,000.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$14,000.00**	**$56,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 512205 Total No. of Proj.			**1**		**Total Amount**	**$56,000.00**
512206	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (70'-80')	EA	5	1	261.00	$9,150.00	$2,388,150.00
	Unit Sub Total	**EA**		**1**	**261.00**	**$9,150.00**	**$2,388,150.00**
	Item Code 512206 Total No. of Proj.			**1**		**Total Amount**	**$2,388,150.00**
512207	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (80'-90')	EA	6	1	12.00	$10,000.00	$120,000.00
	Unit Sub Total	**EA**		**1**	**12.00**	**$10,000.00**	**$120,000.00**
	Item Code 512207 Total No. of Proj.			**1**		**Total Amount**	**$120,000.00**
512208	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (90'-100')	EA	2	1	6.00	$14,000.00	$84,000.00
	Unit Sub Total	**EA**		**1**	**6.00**	**$14,000.00**	**$84,000.00**
	Item Code 512208 Total No. of Proj.			**1**		**Total Amount**	**$84,000.00**
512224	FURNISH PRECAST PRESTRESSED CONCRETE BOX GIRDER (70'-80')	EA	12	2	9.00	$19,222.22	$173,000.00
	Unit Sub Total	**EA**		**2**	**9.00**	**$19,222.22**	**$173,000.00**
	Item Code 512224 Total No. of Proj.			**2**		**Total Amount**	**$173,000.00**
512226	FURNISH PRECAST PRESTRESSED CONCRETE BOX GIRDER (90'-100')	EA	12	1	2.00	$20,000.00	$40,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$20,000.00**	**$40,000.00**
	Item Code 512226 Total No. of Proj.			**1**		**Total Amount**	**$40,000.00**
512256	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (35 M-40 M)	EA	4	1	4.00	$35,000.00	$140,000.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$35,000.00**	**$140,000.00**
	Item Code 512256 Total No. of Proj.			**1**		**Total Amount**	**$140,000.00**
512277	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (80'-90')	EA	10	1	28.00	$85.00	$2,380.00
	Unit Sub Total	**EA**		**1**	**28.00**	**$85.00**	**$2,380.00**
	Item Code 512277 Total No. of Proj.			**1**		**Total Amount**	**$2,380.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
512279	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (100'-110')	EA	7	1	10.00	$30,000.00	$300,000.00
	Unit Sub Total	**EA**		**1**	**10.00**	**$30,000.00**	**$300,000.00**
	Item Code 512279 Total No. of Proj.			**1**		**Total Amount**	**$300,000.00**
512280	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (110'-120')	EA	7	1	24.00	$33,000.00	$792,000.00
	Unit Sub Total	**EA**		**1**	**24.00**	**$33,000.00**	**$792,000.00**
	Item Code 512280 Total No. of Proj.			**1**		**Total Amount**	**$792,000.00**
512290	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (60'-70')	EA	10	1	7.00	$13,500.00	$94,500.00
	Unit Sub Total	**EA**		**1**	**7.00**	**$13,500.00**	**$94,500.00**
	Item Code 512290 Total No. of Proj.			**1**		**Total Amount**	**$94,500.00**
512350	FURNISH PRECAST PRESTRESSED CONCRETE SLAB	SQFT	2	1	10,110.00	$60.87	$615,347.17
	Unit Sub Total	**SQFT**		**1**	**10,110.00**	**$60.87**	**$615,347.17**
	Item Code 512350 Total No. of Proj.			**1**		**Total Amount**	**$615,347.17**
512352	FURNISH PRECAST PRESTRESSED CONCRETE SLAB (TYPE SII)	SQFT	10	1	13,570.00	$25.00	$339,250.00
	Unit Sub Total	**SQFT**		**1**	**13,570.00**	**$25.00**	**$339,250.00**
	Item Code 512352 Total No. of Proj.			**1**		**Total Amount**	**$339,250.00**
512401	ERECT PRECAST CONCRETE GIRDER	EA	6	1	12.00	$1,000.00	$12,000.00
		EA	7	1	34.00	$2,200.00	$74,800.00
	Unit Sub Total	**EA**		**2**	**46.00**	**$1,886.96**	**$86,800.00**
	Item Code 512401 Total No. of Proj.			**2**		**Total Amount**	**$86,800.00**
512500	ERECT PRECAST PRESTRESSED CONCRETE GIRDER	EA	2	1	18.00	$1,400.00	$25,200.00
		EA	4	2	8.00	$13,000.00	$104,000.00
		EA	5	1	261.00	$1,100.00	$287,100.00
		EA	10	2	65.00	$1,000.00	$65,000.00
	Unit Sub Total	**EA**		**6**	**352.00**	**$1,367.33**	**$481,300.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 512500 Total No. of Proj.			**6**		**Total Amount**	**$481,300.00**
512502	ERECT PRECAST PRESTRESSED CONCRETE BOX GIRDER	EA	12	2	15.00	$2,013.33	$30,200.00
	Unit Sub Total	**EA**		**2**	**15.00**	**$2,013.33**	**$30,200.00**
	Item Code 512502 Total No. of Proj.			**2**		**Total Amount**	**$30,200.00**
512510	ERECT PRECAST PRESTRESSED CONCRETE DECK UNIT	EA	4	1	68.00	$600.00	$40,800.00
		EA	10	1	119.00	$1,100.00	$130,900.00
	Unit Sub Total	**EA**		**2**	**187.00**	**$918.18**	**$171,700.00**
	Item Code 512510 Total No. of Proj.			**2**		**Total Amount**	**$171,700.00**
513551	RETAINING WALL STEM (TYPE 6)	SQFT	6	1	833.00	$67.00	$55,811.00
		SQFT	8	1	210.00	$36.00	$7,560.00
	Unit Sub Total	**SQFT**		**2**	**1,043.00**	**$60.76**	**$63,371.00**
	Item Code 513551 Total No. of Proj.			**2**		**Total Amount**	**$63,371.00**
513553	RETAINING WALL (MASONRY WALL)	LF	8	1	45.00	$625.00	$28,125.00
	Unit Sub Total	**LF**		**1**	**45.00**	**$625.00**	**$28,125.00**
	Item Code 513553 Total No. of Proj.			**1**		**Total Amount**	**$28,125.00**
513601	REINFORCED CONCRETE CRIB WALL (TYPE A)	M2	11	1	74.00	$200.00	$14,800.00
	Unit Sub Total	**M2**		**1**	**74.00**	**$200.00**	**$14,800.00**
513601	REINFORCED CONCRETE CRIB WALL (TYPE A)	SQFT	10	1	2,000.00	$60.00	$120,000.00
	Unit Sub Total	**SQFT**		**1**	**2,000.00**	**$60.00**	**$120,000.00**
	Item Code 513601 Total No. of Proj.			**2**		**Total Amount**	**$134,800.00**
515020	REFINISH BRIDGE DECK	M2	7	1	39.00	$380.00	$14,820.00
		M2	8	1	53.00	$250.00	$13,250.00
	Unit Sub Total	**M2**		**2**	**92.00**	**$305.11**	**$28,070.00**
515020	REFINISH BRIDGE DECK	SQFT	3	1	226.00	$30.00	$6,780.00
		SQFT	4	2	1,652.00	$7.27	$12,010.00
		SQFT	7	2	10,744.00	$5.46	$58,660.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**SQFT**		**5**	**12,622.00**	**$6.14**	**$77,450.00**
	Item Code 515020	**Total No. of Proj.**			**7**		**Total Amount**	**$105,520.00**
515028	REPAIR SPALLED SURFACE AREA		SQFT	1	1	1,221.00	$36.75	$44,871.75
			SQFT	2	1	104.00	$150.00	$15,600.00
			SQFT	3	2	618.00	$53.40	$33,000.00
			SQFT	4	2	4,657.00	$89.72	$417,825.00
			SQFT	7	7	1,153.00	$55.52	$64,020.00
			SQFT	8	2	30.00	$208.33	$6,250.00
		Unit Sub Total	**SQFT**		**15**	**7,783.00**	**$74.72**	**$581,566.75**
	Item Code 515028	**Total No. of Proj.**			**15**		**Total Amount**	**$581,566.75**
515041	FURNISH POLYESTER CONCRETE OVERLAY		CF	1	3	9,882.00	$79.45	$785,095.00
			CF	2	14	49,858.00	$73.07	$3,643,338.34
			CF	3	11	73,324.00	$68.51	$5,023,474.00
			CF	4	9	42,079.00	$58.79	$2,473,850.00
			CF	5	2	434.00	$87.13	$37,816.00
			CF	6	3	3,815.00	$76.08	$290,262.26
			CF	7	7	20,673.00	$94.39	$1,951,381.65
			CF	8	8	41,699.00	$78.79	$3,285,593.40
			CF	10	3	30,143.00	$80.11	$2,414,843.02
			CF	11	1	2,841.00	$86.00	$244,326.00
			CF	12	2	2,657.00	$75.77	$201,326.00
		Unit Sub Total	**CF**		**63**	**277,405.00**	**$73.36**	**$20,351,305.67**
	Item Code 515041	**Total No. of Proj.**			**63**		**Total Amount**	**$20,351,305.67**
515042	PLACE POLYESTER CONCRETE OVERLAY		SQFT	1	3	93,565.00	$3.09	$289,572.00
			SQFT	2	14	509,537.00	$1.52	$772,602.76
			SQFT	3	11	882,126.00	$1.24	$1,097,167.05
			SQFT	4	9	572,945.00	$1.34	$766,149.30
			SQFT	5	2	6,566.00	$1.87	$12,260.00
			SQFT	6	3	33,256.00	$2.54	$84,552.30
			SQFT	7	7	226,373.00	$1.04	$235,368.89
			SQFT	8	8	575,810.00	$1.24	$714,752.34
			SQFT	10	3	204,538.00	$1.07	$219,573.40

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
515042	PLACE POLYESTER CONCRETE OVERLAY	SQFT	11	1	16,697.00	$1.85	$30,889.45
		SQFT	12	2	29,758.00	$2.50	$74,330.40
	Unit Sub Total	**SQFT**		**63**	**3,151,171.00**	**$1.36**	**$4,297,217.89**
	Item Code 515042 Total No. of Proj.			**63**		**Total Amount**	**$4,297,217.89**
515050	GRIND BRIDGE DECK	SQFT	3	1	1,361.00	$15.00	$20,415.00
	Unit Sub Total	**SQFT**		**1**	**1,361.00**	**$15.00**	**$20,415.00**
	Item Code 515050 Total No. of Proj.			**1**		**Total Amount**	**$20,415.00**
515061	CORE CONCRETE (2")	LF	5	1	9,274.00	$28.50	$264,309.00
		LF	6	1	6.00	$200.00	$1,200.00
		LF	10	1	10.00	$110.00	$1,100.00
	Unit Sub Total	**LF**		**3**	**9,290.00**	**$28.70**	**$266,609.00**
	Item Code 515061 Total No. of Proj.			**3**		**Total Amount**	**$266,609.00**
515065	CORE CONCRETE (6")	LF	3	1	198.00	$400.00	$79,200.00
		LF	4	1	16.00	$200.00	$3,200.00
	Unit Sub Total	**LF**		**2**	**214.00**	**$385.05**	**$82,400.00**
	Item Code 515065 Total No. of Proj.			**2**		**Total Amount**	**$82,400.00**
515066	CORE CONCRETE (7")	LF	4	1	364.00	$100.00	$36,400.00
	Unit Sub Total	**LF**		**1**	**364.00**	**$100.00**	**$36,400.00**
	Item Code 515066 Total No. of Proj.			**1**		**Total Amount**	**$36,400.00**
515067	CORE CONCRETE (8")	LF	10	1	4.00	$180.00	$720.00
	Unit Sub Total	**LF**		**1**	**4.00**	**$180.00**	**$720.00**
	Item Code 515067 Total No. of Proj.			**1**		**Total Amount**	**$720.00**
515068	CORE CONCRETE (9")	LF	3	1	5.00	$850.00	$4,250.00
		LF	10	1	75.00	$200.00	$15,000.00
	Unit Sub Total	**LF**		**2**	**80.00**	**$240.63**	**$19,250.00**
	Item Code 515068 Total No. of Proj.			**2**		**Total Amount**	**$19,250.00**
515069	CORE CONCRETE (12")	LF	10	1	2.00	$280.00	$560.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**1**	**2.00**	**$280.00**	**$560.00**
	Item Code 515069 Total No. of Proj.			**1**		**Total Amount**	**$560.00**
515070	CORE CONCRETE (10")	LF	10	1	2.00	$260.00	$520.00
	Unit Sub Total	**LF**		**1**	**2.00**	**$260.00**	**$520.00**
	Item Code 515070 Total No. of Proj.			**1**		**Total Amount**	**$520.00**
515157	CORE CONCRETE (1 1/8")	LF	2	1	816.00	$33.00	$26,928.00
	Unit Sub Total	**LF**		**1**	**816.00**	**$33.00**	**$26,928.00**
	Item Code 515157 Total No. of Proj.			**1**		**Total Amount**	**$26,928.00**
515160	CORE CONCRETE (1 1/2")	LF	8	1	7,727.00	$36.00	$278,172.00
	Unit Sub Total	**LF**		**1**	**7,727.00**	**$36.00**	**$278,172.00**
	Item Code 515160 Total No. of Proj.			**1**		**Total Amount**	**$278,172.00**
517961	SOUND WALL (BARRIER) (MASONRY BLOCK)	M2	5	1	2,195.00	$175.00	$384,125.00
		M2	7	1	902.00	$110.00	$99,220.00
	Unit Sub Total	**M2**		**2**	**3,097.00**	**$156.07**	**$483,345.00**
517961	SOUND WALL (BARRIER) (MASONRY BLOCK)	SQFT	4	1	13,200.00	$15.00	$198,000.00
		SQFT	6	1	35,568.00	$16.00	$569,088.00
		SQFT	10	1	181,000.00	$15.00	$2,715,000.00
	Unit Sub Total	**SQFT**		**3**	**229,768.00**	**$15.15**	**$3,482,088.00**
	Item Code 517961 Total No. of Proj.			**5**		**Total Amount**	**$3,965,433.00**
518002	SOUND WALL (MASONRY BLOCK)	M2	5	1	709.00	$175.00	$124,075.00
		M2	7	1	1,790.00	$139.00	$248,810.00
	Unit Sub Total	**M2**		**2**	**2,499.00**	**$149.21**	**$372,885.00**
518002	SOUND WALL (MASONRY BLOCK)	SQFT	3	2	211,700.00	$13.05	$2,762,300.00
		SQFT	4	2	106,852.00	$16.10	$1,720,596.00
		SQFT	6	1	6,888.00	$16.00	$110,208.00
		SQFT	7	2	22,933.00	$13.62	$312,434.40
		SQFT	10	1	9,780.00	$16.00	$156,480.00
		SQFT	12	1	106,390.00	$12.02	$1,278,807.80

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**SQFT**		**9**	**464,543.00**	**$13.65**	**$6,340,826.20**
	Item Code 518002	**Total No. of Proj.**			**11**		**Total Amount**	**$6,713,711.20**
518010	ACCESS GATE (SOUND WALL)		EA	3	1	7.00	$2,500.00	$17,500.00
		Unit Sub Total	**EA**		**1**	**7.00**	**$2,500.00**	**$17,500.00**
	Item Code 518010	**Total No. of Proj.**			**1**		**Total Amount**	**$17,500.00**
518040	REPLACE BEARING PAD		EA	4	1	14.00	$4,000.00	$56,000.00
			EA	8	1	1,786.00	$170.00	$303,620.00
		Unit Sub Total	**EA**		**2**	**1,800.00**	**$199.79**	**$359,620.00**
	Item Code 518040	**Total No. of Proj.**			**2**		**Total Amount**	**$359,620.00**
518050	PTFE BEARING		EA	3	1	24.00	$3,500.00	$84,000.00
		Unit Sub Total	**EA**		**1**	**24.00**	**$3,500.00**	**$84,000.00**
	Item Code 518050	**Total No. of Proj.**			**1**		**Total Amount**	**$84,000.00**
518051	PTFE SPHERICAL BEARING		EA	7	3	123.00	$6,743.90	$829,500.00
			EA	8	1	8.00	$7,500.00	$60,000.00
			EA	10	1	6.00	$7,000.00	$42,000.00
		Unit Sub Total	**EA**		**5**	**137.00**	**$6,799.27**	**$931,500.00**
	Item Code 518051	**Total No. of Proj.**			**5**		**Total Amount**	**$931,500.00**
519078	SNOWPLOW DEFLECTOR		EA	1	1	12.00	$1,000.00	$12,000.00
			EA	2	2	94.00	$400.00	$37,600.00
			EA	3	3	621.00	$106.70	$66,260.00
		Unit Sub Total	**EA**		**6**	**727.00**	**$159.37**	**$115,860.00**
	Item Code 519078	**Total No. of Proj.**			**6**		**Total Amount**	**$115,860.00**
519081	JOINT SEAL (MR 1/2")		LF	1	1	308.00	$33.00	$10,164.00
			LF	2	3	462.00	$33.46	$15,460.00
			LF	3	5	1,262.00	$22.55	$28,453.00
			LF	4	5	2,901.00	$24.89	$72,202.00
			LF	6	6	2,919.00	$25.67	$74,921.25
			LF	7	21	20,329.00	$22.78	$463,158.75

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
519081	JOINT SEAL (MR 1/2")	LF	8	6	1,804.00	$26.34	$47,518.40
		LF	10	3	661.00	$21.86	$14,446.75
		LF	11	4	3,467.00	$36.43	$126,285.89
		LF	12	4	1,450.00	$25.99	$37,687.60
	Unit Sub Total	**LF**		**58**	**35,563.00**	**$25.03**	**$890,297.64**
	Item Code 519081 Total No. of Proj.			**58**		**Total Amount**	**$890,297.64**
519088	JOINT SEAL (MR 1")	LF	1	3	701.00	$30.69	$21,516.00
		LF	2	8	2,347.00	$39.25	$92,128.00
		LF	3	17	7,611.00	$24.68	$187,811.50
		LF	4	9	5,752.00	$23.68	$136,225.00
		LF	5	3	488.00	$37.32	$18,214.00
		LF	6	6	2,102.00	$21.29	$44,758.25
		LF	7	17	17,530.00	$24.00	$420,680.32
		LF	8	4	2,596.00	$22.95	$59,571.60
		LF	10	3	3,423.00	$22.45	$76,850.00
		LF	11	3	1,241.00	$44.42	$55,125.60
		LF	12	6	912.00	$75.37	$68,740.00
	Unit Sub Total	**LF**		**79**	**44,703.00**	**$26.43**	**$1,181,620.27**
	Item Code 519088 Total No. of Proj.			**79**		**Total Amount**	**$1,181,620.27**
519091	JOINT SEAL (MR 1 1/2")	LF	1	2	149.00	$61.21	$9,120.00
		LF	2	3	543.00	$47.06	$25,554.31
		LF	3	10	2,680.00	$49.66	$133,101.00
		LF	4	6	1,680.00	$43.49	$73,066.00
		LF	6	3	538.00	$42.42	$22,824.25
		LF	7	14	8,845.00	$49.87	$441,128.15
		LF	8	2	337.00	$50.00	$16,850.00
		LF	10	3	715.00	$53.73	$38,415.00
		LF	11	4	761.00	$347.96	$264,800.00
		LF	12	2	224.00	$65.66	$14,708.00
	Unit Sub Total	**LF**		**49**	**16,472.00**	**$63.11**	**$1,039,566.71**
	Item Code 519091 Total No. of Proj.			**49**		**Total Amount**	**$1,039,566.71**
519092	JOINT SEAL ASSEMBLY (MR 2 1/2")	LF	3	1	182.00	$200.00	$36,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
519092	JOINT SEAL ASSEMBLY (MR 2 1/2")	LF	4	1	72.00	$400.00	$28,800.00
		LF	6	1	78.00	$95.00	$7,410.00
		LF	7	2	367.00	$166.62	$61,150.00
		LF	10	1	115.00	$250.00	$28,750.00
	Unit Sub Total	**LF**		**6**	**814.00**	**$199.64**	**$162,510.00**
	Item Code 519092 Total No. of Proj.			**6**		**Total Amount**	**$162,510.00**
519093	JOINT SEAL ASSEMBLY (MR 3")	LF	1	1	43.00	$220.00	$9,460.00
		LF	3	1	41.00	$200.00	$8,200.00
		LF	4	2	326.00	$154.97	$50,520.00
		LF	6	1	230.00	$80.00	$18,400.00
		LF	7	1	777.00	$175.00	$135,975.00
		LF	8	1	108.00	$195.00	$21,060.00
	Unit Sub Total	**LF**		**7**	**1,525.00**	**$159.75**	**$243,615.00**
	Item Code 519093 Total No. of Proj.			**7**		**Total Amount**	**$243,615.00**
519094	JOINT SEAL ASSEMBLY (MR 3 1/2")	LF	7	1	76.00	$470.00	$35,720.00
	Unit Sub Total	**LF**		**1**	**76.00**	**$470.00**	**$35,720.00**
	Item Code 519094 Total No. of Proj.			**1**		**Total Amount**	**$35,720.00**
519095	JOINT SEAL ASSEMBLY (MR 4")	LF	1	1	43.00	$220.00	$9,460.00
		LF	3	1	82.00	$200.00	$16,400.00
		LF	4	2	348.00	$197.76	$68,820.00
		LF	7	1	80.00	$253.00	$20,240.00
	Unit Sub Total	**LF**		**5**	**553.00**	**$207.81**	**$114,920.00**
	Item Code 519095 Total No. of Proj.			**5**		**Total Amount**	**$114,920.00**
519096	JOINT SEAL ASSEMBLY (MR 4 1/2")	LF	8	1	40.00	$710.00	$28,400.00
		LF	10	1	45.00	$700.00	$31,500.00
	Unit Sub Total	**LF**		**2**	**85.00**	**$704.71**	**$59,900.00**
	Item Code 519096 Total No. of Proj.			**2**		**Total Amount**	**$59,900.00**
519097	JOINT SEAL ASSEMBLY (MR 5")	LF	3	1	47.00	$200.00	$9,400.00
		LF	12	1	57.00	$755.00	$43,035.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**2**	**104.00**	**$504.18**	**$52,435.00**
	Item Code 519097	**Total No. of Proj.**			**2**		**Total Amount**	**$52,435.00**
519099	JOINT SEAL ASSEMBLY (MR 6")		LF	7	1	325.00	$700.00	$227,500.00
			LF	8	1	130.00	$350.00	$45,500.00
			LF	10	1	538.00	$900.00	$484,200.00
		Unit Sub Total	**LF**		**3**	**993.00**	**$762.54**	**$757,200.00**
	Item Code 519099	**Total No. of Proj.**			**3**		**Total Amount**	**$757,200.00**
519100	JOINT SEAL (MR 2")		LF	1	1	144.00	$92.50	$13,320.00
			LF	2	3	371.00	$76.50	$28,380.00
			LF	3	5	1,137.00	$62.91	$71,525.00
			LF	4	3	336.00	$81.64	$27,432.00
			LF	5	2	120.00	$82.59	$9,911.20
			LF	6	3	378.00	$54.21	$20,492.00
			LF	7	11	6,779.00	$79.79	$540,925.85
			LF	8	2	729.00	$58.25	$42,463.10
			LF	10	1	687.00	$75.00	$51,525.00
			LF	11	2	318.00	$80.53	$25,610.00
			LF	12	5	1,236.00	$66.36	$82,020.00
		Unit Sub Total	**LF**		**38**	**12,235.00**	**$74.67**	**$913,604.15**
	Item Code 519100	**Total No. of Proj.**			**38**		**Total Amount**	**$913,604.15**
519102	JOINT SEAL (TYPE AL)		LF	3	2	641.00	$18.51	$11,866.00
			LF	7	1	148.00	$19.00	$2,812.00
			LF	10	1	4.00	$90.00	$360.00
		Unit Sub Total	**LF**		**4**	**793.00**	**$18.96**	**$15,038.00**
	Item Code 519102	**Total No. of Proj.**			**4**		**Total Amount**	**$15,038.00**
519105	JOINT SEAL ASSEMBLY (MR 7")		LF	10	1	45.00	$900.00	$40,500.00
		Unit Sub Total	**LF**		**1**	**45.00**	**$900.00**	**$40,500.00**
	Item Code 519105	**Total No. of Proj.**			**1**		**Total Amount**	**$40,500.00**
519118	JOINT SEAL ASSEMBLY (MR 9")		LF	10	1	935.00	$1,350.00	$1,262,250.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**1**	**935.00**	**$1,350.00**	**$1,262,250.00**
	Item Code 519118 Total No. of Proj.			**1**		**Total Amount**	**$1,262,250.00**
519120	JOINT SEAL (MR 15 MM)	M	11	1	15.00	$175.00	$2,625.00
	Unit Sub Total	**M**		**1**	**15.00**	**$175.00**	**$2,625.00**
	Item Code 519120 Total No. of Proj.			**1**		**Total Amount**	**$2,625.00**
519124	JOINT SEAL ASSEMBLY (MR 60 MM)	M	7	1	27.00	$870.00	$23,490.00
		M	8	1	18.00	$1,000.00	$18,000.00
	Unit Sub Total	**M**		**2**	**45.00**	**$922.00**	**$41,490.00**
	Item Code 519124 Total No. of Proj.			**2**		**Total Amount**	**$41,490.00**
519126	JOINT SEAL ASSEMBLY (MR 80 MM)	M	5	1	37.00	$700.00	$25,900.00
		M	7	1	91.00	$1,050.00	$95,550.00
		M	8	1	9.00	$1,000.00	$9,000.00
	Unit Sub Total	**M**		**3**	**137.00**	**$952.19**	**$130,450.00**
	Item Code 519126 Total No. of Proj.			**3**		**Total Amount**	**$130,450.00**
519127	JOINT SEAL ASSEMBLY (MR 90 MM)	M	5	1	12.00	$725.00	$8,700.00
		M	8	1	9.00	$1,000.00	$9,000.00
	Unit Sub Total	**M**		**2**	**21.00**	**$842.86**	**$17,700.00**
	Item Code 519127 Total No. of Proj.			**2**		**Total Amount**	**$17,700.00**
519128	JOINT SEAL ASSEMBLY (MR 100 MM)	M	11	1	25.00	$490.00	$12,250.00
	Unit Sub Total	**M**		**1**	**25.00**	**$490.00**	**$12,250.00**
	Item Code 519128 Total No. of Proj.			**1**		**Total Amount**	**$12,250.00**
519129	JOINT SEAL ASSEMBLY (MR 101 MM - 160 MM)	M	7	1	44.00	$3,000.00	$132,000.00
		M	11	1	51.00	$1,600.00	$81,600.00
	Unit Sub Total	**M**		**2**	**95.00**	**$2,248.42**	**$213,600.00**
	Item Code 519129 Total No. of Proj.			**2**		**Total Amount**	**$213,600.00**
519130	JOINT SEAL ASSEMBLY (MR 161 MM - 240 MM)	M	11	1	25.00	$2,600.00	$65,000.00
	Unit Sub Total	**M**		**1**	**25.00**	**$2,600.00**	**$65,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 519130 Total No. of Proj.			**1**		**Total Amount**	**$65,000.00**
519133	JOINT SEAL (ASPHALTIC PLUG)	LF	4	1	608.00	$75.00	$45,600.00
		LF	6	1	186.00	$100.00	$18,600.00
	Unit Sub Total	**LF**		**2**	**794.00**	**$80.86**	**$64,200.00**
	Item Code 519133 Total No. of Proj.			**2**		**Total Amount**	**$64,200.00**
519142	JOINT SEAL (MR 40 MM)	M	5	1	124.00	$200.00	$24,800.00
		M	7	2	67.00	$277.43	$18,588.00
		M	8	1	96.00	$270.00	$25,920.00
		M	11	1	125.00	$180.00	$22,500.00
	Unit Sub Total	**M**		**5**	**412.00**	**$222.83**	**$91,808.00**
	Item Code 519142 Total No. of Proj.			**5**		**Total Amount**	**$91,808.00**
519144	JOINT SEAL (MR 50 MM)	M	5	1	132.00	$260.00	$34,320.00
		M	7	1	29.00	$380.00	$11,020.00
		M	11	1	59.00	$240.00	$14,160.00
	Unit Sub Total	**M**		**3**	**220.00**	**$270.45**	**$59,500.00**
	Item Code 519144 Total No. of Proj.			**3**		**Total Amount**	**$59,500.00**
520101	BAR REINFORCING STEEL	KG	4	1	9,050.00	$2.00	$18,100.00
		KG	5	1	13,350.00	$2.50	$33,375.00
		KG	8	1	11,263.00	$2.40	$27,031.20
	Unit Sub Total	**KG**		**3**	**33,663.00**	**$2.33**	**$78,506.20**
520101	BAR REINFORCING STEEL	LB	1	1	11,960.00	$1.00	$11,960.00
		LB	2	1	1,689.00	$1.55	$2,617.95
		LB	3	1	1,922.00	$2.00	$3,844.00
		LB	4	3	20,720.00	$1.32	$27,268.00
		LB	6	1	1,220.00	$0.10	$122.00
		LB	7	1	28,700.00	$0.87	$24,969.00
		LB	8	3	30,740.00	$1.31	$40,370.00
		LB	12	1	1,040.00	$2.25	$2,340.00
	Unit Sub Total	**LB**		**12**	**97,991.00**	**$1.16**	**$113,490.95**
	Item Code 520101 Total No. of Proj.			**15**		**Total Amount**	**$191,997.15**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
520102	BAR REINFORCING STEEL (BRIDGE)	KG	4	1	39,450.00	$2.00	$78,900.00
		KG	5	1	1,214,300.00	$1.80	$2,185,740.00
		KG	7	2	3,887,129.00	$1.59	$6,164,229.95
		KG	8	1	1,037,100.00	$1.70	$1,763,070.00
		KG	11	2	3,348,850.00	$1.70	$5,704,595.00
	Unit Sub Total	**KG**		**7**	**9,526,829.00**	**$1.67**	**$15,896,534.95**
520102	BAR REINFORCING STEEL (BRIDGE)	LB	1	1	817,193.00	$0.96	$784,505.28
		LB	2	5	700,865.00	$1.21	$849,049.38
		LB	3	6	5,775,418.00	$0.90	$5,197,471.15
		LB	4	13	3,470,104.00	$0.90	$3,133,533.00
		LB	5	2	4,764,582.00	$1.04	$4,957,800.48
		LB	6	6	1,796,555.00	$0.75	$1,355,089.00
		LB	7	9	29,529,628.00	$0.71	$20,822,368.28
		LB	8	5	2,840,962.00	$0.82	$2,328,315.50
		LB	10	4	3,670,350.00	$0.91	$3,355,380.00
		LB	12	6	728,532.00	$0.82	$593,785.55
	Unit Sub Total	**LB**		**57**	**###########**	**$0.80**	**$43,377,297.62**
	Item Code 520102	**Total No. of Proj.**		**64**		**Total Amount**	**$59,273,832.57**
520103	BAR REINFORCING STEEL (RETAINING WALL)	KG	4	1	7,870.00	$2.00	$15,740.00
		KG	5	1	74,350.00	$2.25	$167,287.50
		KG	7	2	293,909.00	$1.82	$536,042.50
		KG	8	1	95,235.00	$2.45	$233,325.75
		KG	11	1	720,564.00	$1.70	$1,224,958.80
	Unit Sub Total	**KG**		**6**	**1,191,928.00**	**$1.83**	**$2,177,354.55**
520103	BAR REINFORCING STEEL (RETAINING WALL)	LB	1	2	25,270.00	$1.15	$29,121.50
		LB	2	2	23,935.00	$2.21	$52,901.75
		LB	3	3	107,607.00	$1.17	$125,787.00
		LB	4	9	1,204,231.00	$1.13	$1,361,431.24
		LB	5	1	43,600.00	$1.75	$76,300.00
		LB	6	4	50,594.00	$2.02	$102,168.50
		LB	7	3	785,391.00	$0.97	$760,277.20
		LB	8	1	232,150.00	$0.80	$185,720.00
		LB	10	2	1,609,146.00	$1.00	$1,609,146.00
		LB	11	2	17,883.00	$1.26	$22,534.74

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
520103	BAR REINFORCING STEEL (RETAINING WALL)	LB	12	4	715,403.00	$0.83	$595,149.76
	Unit Sub Total	**LB**		**33**	**4,815,210.00**	**$1.02**	**$4,920,537.69**
	Item Code 520103 Total No. of Proj.			**39**		**Total Amount**	**$7,097,892.24**
520105	BAR REINFORCING STEEL (SOUND WALL)	LB	3	1	26,494.00	$1.00	$26,494.00
	Unit Sub Total	**LB**		**1**	**26,494.00**	**$1.00**	**$26,494.00**
	Item Code 520105 Total No. of Proj.			**1**		**Total Amount**	**$26,494.00**
520106	BAR REINFORCING STEEL (EPOXY COATED)	LB	1	1	28,172.00	$1.75	$49,301.00
	Unit Sub Total	**LB**		**1**	**28,172.00**	**$1.75**	**$49,301.00**
	Item Code 520106 Total No. of Proj.			**1**		**Total Amount**	**$49,301.00**
520107	BAR REINFORCING STEEL (BOX CULVERT)	KG	5	1	102,162.00	$1.75	$178,783.50
		KG	7	2	187,728.00	$1.69	$316,375.80
	Unit Sub Total	**KG**		**3**	**289,890.00**	**$1.71**	**$495,159.30**
520107	BAR REINFORCING STEEL (BOX CULVERT)	LB	3	1	15,683.00	$1.00	$15,683.00
		LB	4	5	255,296.00	$1.08	$275,708.00
		LB	6	4	332,191.00	$0.97	$322,622.60
		LB	7	2	110,303.00	$1.24	$136,628.00
		LB	10	1	24,500.00	$1.00	$24,500.00
	Unit Sub Total	**LB**		**13**	**737,973.00**	**$1.05**	**$775,141.60**
	Item Code 520107 Total No. of Proj.			**16**		**Total Amount**	**$1,270,300.90**
520110	BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	LB	2	3	110,801.00	$1.94	$214,851.20
		LB	3	1	261.00	$2.00	$522.00
		LB	7	1	690,000.00	$0.90	$621,000.00
		LB	8	1	4,800.00	$2.00	$9,600.00
		LB	10	1	562,800.00	$1.00	$562,800.00
	Unit Sub Total	**LB**		**7**	**1,368,662.00**	**$1.03**	**$1,408,773.20**
	Item Code 520110 Total No. of Proj.			**7**		**Total Amount**	**$1,408,773.20**
520114	BAR REINFORCING STEEL, RETAINING WALL (SOUND WALL)	KG	7	1	16,885.00	$1.70	$28,704.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION			UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
			Unit Sub Total	**KG**		**1**	**16,885.00**	**$1.70**	**$28,704.50**
		Item Code 520114	**Total No. of Proj.**			**1**		**Total Amount**	**$28,704.50**
520120	HEADED BAR REINFORCEMENT			EA	1	1	1,324.00	$12.00	$15,888.00
				EA	2	2	1,539.00	$7.38	$11,352.00
				EA	3	1	35,700.00	$10.00	$357,000.00
				EA	4	2	3,468.00	$17.94	$62,220.00
				EA	7	4	22,355.00	$22.88	$511,406.00
				EA	8	1	189.00	$75.00	$14,175.00
				EA	10	1	1,980.00	$18.00	$35,640.00
				EA	11	1	190.00	$20.00	$3,800.00
			Unit Sub Total	**EA**		**13**	**66,745.00**	**$15.15**	**$1,011,481.00**
		Item Code 520120	**Total No. of Proj.**			**13**		**Total Amount**	**$1,011,481.00**
530100	SHOTCRETE			CY	2	1	49.00	$1,527.00	$74,823.00
				CY	3	2	155.00	$578.23	$89,625.00
				CY	4	2	215.00	$365.12	$78,500.00
				CY	5	1	230.00	$685.00	$157,550.00
				CY	8	1	178.00	$460.00	$81,880.00
				CY	12	3	443.00	$489.19	$216,710.00
			Unit Sub Total	**CY**		**10**	**1,270.00**	**$550.46**	**$699,088.00**
530100	SHOTCRETE			M3	5	1	113.00	$625.00	$70,625.00
				M3	7	1	94.00	$500.00	$47,000.00
				M3	8	1	143.00	$650.00	$92,950.00
				M3	11	1	410.00	$468.00	$191,880.00
			Unit Sub Total	**M3**		**4**	**760.00**	**$529.55**	**$402,455.00**
		Item Code 530100	**Total No. of Proj.**			**14**		**Total Amount**	**$1,101,543.00**
540100	DECK SEAL			SQFT	2	1	3,017.00	$5.50	$16,593.50
			Unit Sub Total	**SQFT**		**1**	**3,017.00**	**$5.50**	**$16,593.50**
		Item Code 540100	**Total No. of Proj.**			**1**		**Total Amount**	**$16,593.50**
540101	ASPHALT MEMBRANE WATERPROOFING			M2	7	1	180.00	$102.00	$18,360.00
			Unit Sub Total	**M2**		**1**	**180.00**	**$102.00**	**$18,360.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
540101	ASPHALT MEMBRANE WATERPROOFING	SQFT	2	1	890.00	$5.00	$4,450.00
		SQFT	4	1	1,652.00	$5.00	$8,260.00
		SQFT	7	2	970.00	$21.26	$20,620.80
	Unit Sub Total	**SQFT**		**4**	**3,512.00**	**$9.49**	**$33,330.80**
	Item Code 540101 Total No. of Proj.			**5**		**Total Amount**	**$51,690.80**
540102	TREAT BRIDGE DECK	SQFT	1	2	90,284.00	$0.21	$19,320.80
		SQFT	2	4	56,839.00	$0.45	$25,593.00
		SQFT	3	13	798,412.00	$0.33	$262,634.72
		SQFT	4	9	953,352.00	$0.31	$295,377.48
		SQFT	5	3	582,146.00	$0.17	$101,631.90
		SQFT	6	7	1,079,018.00	$0.17	$181,102.85
		SQFT	7	20	6,667,848.00	$0.14	$951,724.13
		SQFT	8	6	1,382,178.00	$0.16	$219,808.82
		SQFT	10	2	82,998.00	$0.19	$15,604.28
		SQFT	11	4	809,645.00	$0.08	$63,531.33
		SQFT	12	3	390,325.00	$0.24	$94,171.25
	Unit Sub Total	**SQFT**		**73**	**############**	**$0.17**	**$2,230,500.56**
	Item Code 540102 Total No. of Proj.			**73**		**Total Amount**	**$2,230,500.56**
540108	FURNISH BRIDGE DECK TREATMENT MATERIAL	GAL	1	2	1,004.00	$51.16	$51,366.00
		GAL	2	4	646.00	$63.62	$41,100.00
		GAL	3	13	8,112.00	$62.86	$509,945.92
		GAL	4	9	10,697.00	$59.28	$634,084.00
		GAL	5	1	1,774.00	$55.00	$97,570.00
		GAL	6	7	12,024.00	$57.01	$685,437.24
		GAL	7	20	83,198.00	$52.10	$4,334,640.27
		GAL	8	6	15,890.00	$49.89	$792,783.00
		GAL	10	2	957.00	$66.08	$63,242.52
		GAL	11	4	10,185.00	$30.26	$308,163.57
		GAL	12	3	5,050.00	$40.60	$205,010.00
	Unit Sub Total	**GAL**		**71**	**149,537.00**	**$51.65**	**$7,723,342.52**
	Item Code 540108 Total No. of Proj.			**71**		**Total Amount**	**$7,723,342.52**
540109	FURNISH BRIDGE DECK TREATMENT MATERIAL (LOW ODOR)	GAL	5	2	5,720.00	$52.21	$298,620.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**GAL**		**2**	**5,720.00**	**$52.21**	**$298,620.00**
	Item Code 540109	**Total No. of Proj.**			**2**		**Total Amount**	**$298,620.00**
550101	STRUCTURAL STEEL		LB	8	1	41,000.00	$2.00	$82,000.00
		Unit Sub Total	**LB**		**1**	**41,000.00**	**$2.00**	**$82,000.00**
	Item Code 550101	**Total No. of Proj.**			**1**		**Total Amount**	**$82,000.00**
550102	STRUCTURAL STEEL (BRIDGE)		LB	3	1	2,675.00	$6.00	$16,050.00
			LB	4	1	80.00	$300.00	$24,000.00
			LB	8	1	153,000.00	$3.10	$474,300.00
			LB	12	1	210.00	$12.00	$2,520.00
		Unit Sub Total	**LB**		**4**	**155,965.00**	**$3.31**	**$516,870.00**
	Item Code 550102	**Total No. of Proj.**			**4**		**Total Amount**	**$516,870.00**
550110	COLUMN CASING		KG	7	1	72,430.00	$8.20	$593,926.00
		Unit Sub Total	**KG**		**1**	**72,430.00**	**$8.20**	**$593,926.00**
550110	COLUMN CASING		LB	2	1	26,200.00	$5.00	$131,000.00
			LB	4	1	350,500.00	$2.00	$701,000.00
			LB	7	2	61,745.00	$5.23	$322,811.00
		Unit Sub Total	**LB**		**4**	**438,445.00**	**$2.63**	**$1,154,811.00**
	Item Code 550110	**Total No. of Proj.**			**5**		**Total Amount**	**$1,748,737.00**
550203	FURNISH STRUCTURAL STEEL (BRIDGE)		LB	3	1	5,300.00	$10.00	$53,000.00
		Unit Sub Total	**LB**		**1**	**5,300.00**	**$10.00**	**$53,000.00**
	Item Code 550203	**Total No. of Proj.**			**1**		**Total Amount**	**$53,000.00**
550204	ERECT STRUCTURAL STEEL (BRIDGE)		LB	3	1	5,300.00	$10.00	$53,000.00
		Unit Sub Total	**LB**		**1**	**5,300.00**	**$10.00**	**$53,000.00**
	Item Code 550204	**Total No. of Proj.**			**1**		**Total Amount**	**$53,000.00**
560203	FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)		KG	11	1	958.00	$16.00	$15,328.00
		Unit Sub Total	**KG**		**1**	**958.00**	**$16.00**	**$15,328.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560203	FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	LB	3	3	83,965.00	$4.86	$407,989.50
		LB	4	1	12,810.00	$3.00	$38,430.00
		LB	12	2	29,586.00	$2.00	$59,172.00
	Unit Sub Total	**LB**		**6**	**126,361.00**	**$4.00**	**$505,591.50**
	Item Code 560203 Total No. of Proj.			**7**		**Total Amount**	**$520,919.50**
560204	INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	KG	11	1	958.00	$3.00	$2,874.00
	Unit Sub Total	**KG**		**1**	**958.00**	**$3.00**	**$2,874.00**
560204	INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	LB	3	3	83,965.00	$1.07	$89,564.90
		LB	4	1	12,810.00	$0.50	$6,405.00
		LB	12	2	29,586.00	$1.16	$34,172.00
	Unit Sub Total	**LB**		**6**	**126,361.00**	**$1.03**	**$130,141.90**
	Item Code 560204 Total No. of Proj.			**7**		**Total Amount**	**$133,015.90**
560208	FURNISH SIGN STRUCTURE (TUBULAR)	KG	5	1	54,597.00	$9.00	$491,373.00
		KG	8	1	3,668.00	$10.00	$36,680.00
	Unit Sub Total	**KG**		**2**	**58,265.00**	**$9.06**	**$528,053.00**
560208	FURNISH SIGN STRUCTURE (TUBULAR)	LB	2	1	27,145.00	$4.85	$131,653.25
	Unit Sub Total	**LB**		**1**	**27,145.00**	**$4.85**	**$131,653.25**
	Item Code 560208 Total No. of Proj.			**3**		**Total Amount**	**$659,706.25**
560209	INSTALL SIGN STRUCTURE (TUBULAR)	KG	5	1	54,597.00	$1.00	$54,597.00
		KG	8	1	3,668.00	$1.00	$3,668.00
	Unit Sub Total	**KG**		**2**	**58,265.00**	**$1.00**	**$58,265.00**
560209	INSTALL SIGN STRUCTURE (TUBULAR)	LB	2	1	27,145.00	$0.40	$10,858.00
	Unit Sub Total	**LB**		**1**	**27,145.00**	**$0.40**	**$10,858.00**
	Item Code 560209 Total No. of Proj.			**3**		**Total Amount**	**$69,123.00**
560213	FURNISH SIGN STRUCTURE (LIGHTWEIGHT)	KG	7	2	15,322.00	$10.97	$168,114.00
		KG	11	1	15,704.00	$8.00	$125,632.00
	Unit Sub Total	**KG**		**3**	**31,026.00**	**$9.47**	**$293,746.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560213	FURNISH SIGN STRUCTURE (LIGHTWEIGHT)	LB	3	2	19,039.00	$5.39	$102,642.29
		LB	7	1	3,352.00	$5.75	$19,274.00
		LB	12	4	36,895.00	$5.84	$215,424.00
	Unit Sub Total	**LB**		**7**	**59,286.00**	**$5.69**	**$337,340.29**
	Item Code 560213 Total No. of Proj.			**10**		**Total Amount**	**$631,086.29**
560214	INSTALL SIGN STRUCTURE (LIGHTWEIGHT)	KG	7	2	15,322.00	$1.91	$29,298.40
		KG	11	1	15,704.00	$1.00	$15,704.00
	Unit Sub Total	**KG**		**3**	**31,026.00**	**$1.45**	**$45,002.40**
560214	INSTALL SIGN STRUCTURE (LIGHTWEIGHT)	LB	3	2	19,039.00	$1.55	$29,533.27
		LB	7	1	3,352.00	$1.00	$3,352.00
		LB	12	4	36,895.00	$1.02	$37,519.90
	Unit Sub Total	**LB**		**7**	**59,286.00**	**$1.19**	**$70,405.17**
	Item Code 560214 Total No. of Proj.			**10**		**Total Amount**	**$115,407.57**
560218	FURNISH SIGN STRUCTURE (TRUSS)	KG	7	3	159,001.00	$8.39	$1,334,343.20
		KG	11	2	124,066.00	$7.03	$871,822.50
	Unit Sub Total	**KG**		**5**	**283,067.00**	**$7.79**	**$2,206,165.70**
560218	FURNISH SIGN STRUCTURE (TRUSS)	LB	1	1	9,617.00	$4.00	$38,468.00
		LB	2	2	74,535.00	$3.34	$249,155.00
		LB	3	8	906,148.00	$3.67	$3,323,729.51
		LB	4	8	767,173.00	$3.90	$2,991,757.94
		LB	5	1	41,100.00	$4.80	$197,280.00
		LB	6	4	319,146.00	$2.81	$896,660.10
		LB	7	5	273,999.00	$3.99	$1,092,077.10
		LB	8	1	49,340.00	$4.20	$207,228.00
		LB	10	3	257,170.00	$2.69	$692,779.15
		LB	11	2	79,560.00	$4.15	$330,375.00
		LB	12	5	798,054.00	$3.77	$3,010,651.52
	Unit Sub Total	**LB**		**40**	**3,575,842.00**	**$3.64**	**$13,030,161.32**
	Item Code 560218 Total No. of Proj.			**45**		**Total Amount**	**$15,236,327.02**
560219	INSTALL SIGN STRUCTURE (TRUSS)	KG	7	3	159,001.00	$0.43	$68,659.05
		KG	11	2	123,521.00	$0.74	$90,866.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**KG**		**5**	**282,522.00**	**$0.56**	**$159,525.05**
560219	INSTALL SIGN STRUCTURE (TRUSS)	LB	1	1	9,617.00	$1.00	$9,617.00
		LB	2	2	74,535.00	$0.71	$52,635.00
		LB	3	8	896,271.00	$0.23	$208,636.25
		LB	4	8	767,173.00	$0.21	$163,267.16
		LB	5	1	41,100.00	$0.25	$10,275.00
		LB	6	4	319,146.00	$1.14	$364,522.50
		LB	7	5	273,999.00	$0.24	$66,232.91
		LB	8	1	49,340.00	$0.15	$7,401.00
		LB	10	3	257,170.00	$0.50	$128,436.55
		LB	11	2	79,560.00	$0.20	$15,912.00
		LB	12	5	798,054.00	$0.21	$165,761.88
	Unit Sub Total	**LB**		**40**	**3,565,965.00**	**$0.33**	**$1,192,697.25**
	Item Code 560219 Total No. of Proj.			**45**		**Total Amount**	**$1,352,222.30**
560223	FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY)	KG	11	1	1,205.00	$16.00	$19,280.00
	Unit Sub Total	**KG**		**1**	**1,205.00**	**$16.00**	**$19,280.00**
560223	FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY)	LB	2	1	340.00	$9.00	$3,060.00
		LB	3	1	696.00	$10.40	$7,238.40
		LB	12	2	6,067.00	$1.60	$9,701.00
	Unit Sub Total	**LB**		**4**	**7,103.00**	**$2.82**	**$19,999.40**
	Item Code 560223 Total No. of Proj.			**5**		**Total Amount**	**$39,279.40**
560224	INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY)	KG	11	1	1,205.00	$4.00	$4,820.00
	Unit Sub Total	**KG**		**1**	**1,205.00**	**$4.00**	**$4,820.00**
560224	INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY)	LB	2	1	340.00	$38.00	$12,920.00
		LB	3	1	696.00	$3.00	$2,088.00
		LB	12	2	6,067.00	$1.02	$6,201.00
	Unit Sub Total	**LB**		**4**	**7,103.00**	**$2.99**	**$21,209.00**
	Item Code 560224 Total No. of Proj.			**5**		**Total Amount**	**$26,029.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560233	FURNISH FORMED PANEL SIGN (OVERHEAD)	M2	7	3	394.00	$123.50	$48,660.00
	Unit Sub Total	**M2**		**3**	**394.00**	**$123.50**	**$48,660.00**
560233	FURNISH FORMED PANEL SIGN (OVERHEAD)	SQFT	3	1	2,370.00	$10.00	$23,700.00
		SQFT	4	7	6,795.00	$14.00	$95,100.00
		SQFT	5	1	680.00	$12.00	$8,160.00
		SQFT	7	5	1,740.00	$15.73	$27,363.00
		SQFT	8	1	4,260.00	$11.30	$48,138.00
		SQFT	10	1	1,700.00	$13.00	$22,100.00
	Unit Sub Total	**SQFT**		**16**	**17,545.00**	**$12.80**	**$224,561.00**
	Item Code 560233 Total No. of Proj.			**19**		**Total Amount**	**$273,221.00**
560234	FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE A)	M2	5	1	130.00	$215.00	$27,950.00
		M2	7	1	54.00	$120.00	$6,480.00
		M2	11	2	450.00	$200.00	$90,000.00
	Unit Sub Total	**M2**		**4**	**634.00**	**$196.26**	**$124,430.00**
	Item Code 560234 Total No. of Proj.			**4**		**Total Amount**	**$124,430.00**
560235	FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE B)	M2	5	1	6.00	$210.00	$1,260.00
		M2	7	1	33.50	$240.00	$8,040.00
	Unit Sub Total	**M2**		**2**	**39.50**	**$235.44**	**$9,300.00**
	Item Code 560235 Total No. of Proj.			**2**		**Total Amount**	**$9,300.00**
560236	FURNISH LAMINATED PANEL SIGN (63.5 MM-TYPE B)	M2	5	1	28.00	$230.00	$6,440.00
		M2	7	1	7.20	$260.00	$1,872.00
	Unit Sub Total	**M2**		**2**	**35.20**	**$236.14**	**$8,312.00**
	Item Code 560236 Total No. of Proj.			**2**		**Total Amount**	**$8,312.00**
560237	FURNISH LAMINATED PANEL SIGN (63.5 MM-TYPE H)	M2	11	1	10.00	$200.00	$2,000.00
	Unit Sub Total	**M2**		**1**	**10.00**	**$200.00**	**$2,000.00**
	Item Code 560237 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560238	FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-UNFRAMED)	M2	4	1	17.00	$130.00	$2,210.00
		M2	5	1	170.00	$115.00	$19,550.00
		M2	7	4	133.60	$119.46	$15,960.00
		M2	8	1	38.00	$140.00	$5,320.00
		M2	10	2	30.80	$178.12	$5,486.00
		M2	11	2	121.00	$91.36	$11,055.00
	Unit Sub Total	**M2**		**11**	**510.40**	**$116.73**	**$59,581.00**
560238	FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-UNFRAMED)	SQFT	4	1	120.00	$18.00	$2,160.00
	Unit Sub Total	**SQFT**		**1**	**120.00**	**$18.00**	**$2,160.00**
	Item Code 560238 **Total No. of Proj.**			**12**		**Total Amount**	**$61,741.00**
560239	FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-UNFRAMED)	M2	4	1	18.00	$130.00	$2,340.00
		M2	5	1	110.00	$125.00	$13,750.00
		M2	7	4	68.30	$149.78	$10,230.00
		M2	10	1	15.00	$143.00	$2,145.00
		M2	11	2	63.00	$96.75	$6,095.00
	Unit Sub Total	**M2**		**9**	**274.30**	**$125.99**	**$34,560.00**
	Item Code 560239 **Total No. of Proj.**			**9**		**Total Amount**	**$34,560.00**
560241	FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-FRAMED)	M2	4	1	5.00	$170.00	$850.00
		M2	5	1	48.00	$150.00	$7,200.00
		M2	7	4	43.10	$220.84	$9,518.00
		M2	10	1	4.00	$167.00	$668.00
		M2	11	1	8.00	$100.00	$800.00
	Unit Sub Total	**M2**		**8**	**108.10**	**$176.10**	**$19,036.00**
	Item Code 560241 **Total No. of Proj.**			**8**		**Total Amount**	**$19,036.00**
560242	FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-FRAMED)	M2	4	1	4.00	$170.00	$680.00
		M2	5	1	28.00	$150.00	$4,200.00
		M2	7	3	31.60	$170.00	$5,372.00
		M2	10	1	10.00	$183.00	$1,830.00
		M2	11	1	62.00	$120.00	$7,440.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M2**		**7**	**135.60**	**$143.97**	**$19,522.00**
	Item Code 560242	**Total No. of Proj.**			**7**		**Total Amount**	**$19,522.00**
560244	FURNISH LAMINATED PANEL SIGN (1"-TYPE A)		SQFT	2	2	1,010.00	$14.14	$14,280.00
			SQFT	3	6	13,900.00	$16.86	$234,335.00
			SQFT	4	2	640.00	$22.19	$14,200.00
			SQFT	6	2	2,090.00	$10.63	$22,220.00
			SQFT	7	2	1,710.00	$19.32	$33,040.00
			SQFT	8	2	3,840.00	$19.24	$73,888.00
			SQFT	10	1	480.00	$23.00	$11,040.00
			SQFT	11	2	600.00	$24.17	$14,500.00
			SQFT	12	6	9,078.00	$24.50	$222,382.00
		Unit Sub Total	**SQFT**		**25**	**33,348.00**	**$19.19**	**$639,885.00**
	Item Code 560244	**Total No. of Proj.**			**25**		**Total Amount**	**$639,885.00**
560245	FURNISH LAMINATED PANEL SIGN (1"-TYPE B)		SQFT	2	1	450.00	$20.85	$9,382.50
			SQFT	3	3	540.00	$19.59	$10,580.00
			SQFT	4	3	586.00	$20.01	$11,727.60
			SQFT	8	1	770.00	$18.50	$14,245.00
			SQFT	11	1	160.00	$28.00	$4,480.00
			SQFT	12	2	220.00	$6.73	$1,480.00
		Unit Sub Total	**SQFT**		**11**	**2,726.00**	**$19.04**	**$51,895.10**
	Item Code 560245	**Total No. of Proj.**			**11**		**Total Amount**	**$51,895.10**
560246	FURNISH LAMINATED PANEL SIGN (2 1/2"-TYPE B)		SQFT	2	1	970.00	$25.25	$24,492.50
			SQFT	3	1	240.00	$25.00	$6,000.00
			SQFT	8	2	1,230.00	$22.88	$28,140.00
			SQFT	10	1	240.00	$20.00	$4,800.00
		Unit Sub Total	**SQFT**		**5**	**2,680.00**	**$23.67**	**$63,432.50**
	Item Code 560246	**Total No. of Proj.**			**5**		**Total Amount**	**$63,432.50**
560248	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)		SQFT	1	1	243.00	$15.00	$3,645.00
			SQFT	2	4	885.00	$22.55	$19,957.00
			SQFT	3	14	3,006.00	$15.05	$45,232.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560248	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	SQFT	4	14	3,952.00	$12.35	$48,823.72
		SQFT	5	4	240.00	$14.40	$3,455.00
		SQFT	6	11	1,326.00	$15.40	$20,422.00
		SQFT	7	7	1,157.00	$11.38	$13,165.04
		SQFT	8	8	1,055.50	$17.46	$18,425.20
		SQFT	9	2	720.00	$15.38	$11,070.00
		SQFT	10	6	1,035.00	$14.51	$15,022.75
		SQFT	11	9	986.00	$14.60	$14,394.00
		SQFT	12	23	4,066.00	$10.83	$44,029.70
	Unit Sub Total	**SQFT**		**103**	**18,671.50**	**$13.80**	**$257,641.41**
	Item Code 560248 Total No. of Proj.			**103**		**Total Amount**	**$257,641.41**
560249	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED)	SQFT	1	1	91.00	$20.00	$1,820.00
		SQFT	2	4	1,282.00	$20.10	$25,768.00
		SQFT	3	12	3,451.00	$12.76	$44,052.00
		SQFT	4	8	3,660.00	$12.58	$46,029.60
		SQFT	5	1	12.00	$15.00	$180.00
		SQFT	6	7	483.00	$23.58	$11,387.00
		SQFT	7	5	321.00	$14.85	$4,765.60
		SQFT	8	2	967.50	$9.31	$9,003.00
		SQFT	9	4	579.00	$17.84	$10,329.00
		SQFT	10	5	403.00	$14.42	$5,810.30
		SQFT	11	7	963.00	$14.91	$14,359.00
		SQFT	12	10	2,642.00	$11.25	$29,729.70
	Unit Sub Total	**SQFT**		**66**	**14,854.50**	**$13.68**	**$203,233.20**
	Item Code 560249 Total No. of Proj.			**66**		**Total Amount**	**$203,233.20**
560251	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-FRAMED)	SQFT	1	1	67.00	$35.00	$2,345.00
		SQFT	2	1	22.00	$20.00	$440.00
		SQFT	3	2	260.00	$12.69	$3,300.00
		SQFT	4	5	553.00	$14.69	$8,123.00
		SQFT	5	1	74.00	$33.00	$2,442.00
		SQFT	6	2	560.00	$15.79	$8,840.00
		SQFT	7	1	1,740.00	$10.00	$17,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560251	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-FRAMED)	SQFT	9	1	47.00	$16.75	$787.25
		SQFT	10	3	1,115.00	$17.78	$19,827.00
		SQFT	11	2	75.00	$15.99	$1,199.00
		SQFT	12	6	851.00	$11.12	$9,460.00
	Unit Sub Total	**SQFT**		**25**	**5,364.00**	**$13.83**	**$74,163.25**
	Item Code 560251 Total No. of Proj.			**25**		**Total Amount**	**$74,163.25**
560252	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED)	SQFT	1	1	39.00	$50.00	$1,950.00
		SQFT	2	3	898.00	$24.31	$21,831.50
		SQFT	3	5	708.00	$14.81	$10,483.00
		SQFT	4	7	1,315.00	$16.37	$21,523.00
		SQFT	6	2	305.00	$15.31	$4,670.00
		SQFT	7	1	330.00	$21.00	$6,930.00
		SQFT	8	2	146.00	$13.70	$2,000.00
		SQFT	9	3	195.00	$20.59	$4,016.00
		SQFT	10	1	91.00	$18.00	$1,638.00
		SQFT	11	4	438.00	$36.98	$16,197.00
		SQFT	12	8	1,189.00	$14.33	$17,039.80
	Unit Sub Total	**SQFT**		**37**	**5,654.00**	**$19.15**	**$108,278.30**
	Item Code 560252 Total No. of Proj.			**37**		**Total Amount**	**$108,278.30**
561004	30" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	3	3	88.00	$451.99	$39,774.79
		LF	12	1	70.00	$150.00	$10,500.00
	Unit Sub Total	**LF**		**4**	**158.00**	**$318.19**	**$50,274.79**
	Item Code 561004 Total No. of Proj.			**4**		**Total Amount**	**$50,274.79**
561005	36" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	3	1	26.00	$500.00	$13,000.00
		LF	4	1	120.00	$750.00	$90,000.00
		LF	6	1	15.00	$600.00	$9,000.00
		LF	7	1	30.00	$1,650.00	$49,500.00
		LF	12	3	85.00	$499.18	$42,430.00
	Unit Sub Total	**LF**		**7**	**276.00**	**$738.88**	**$203,930.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 561005 Total No. of Proj.			**7**		**Total Amount**	**$203,930.00**
561009	920 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	7	1	16.00	$1,400.00	$22,400.00
	Unit Sub Total	**M**		**1**	**16.00**	**$1,400.00**	**$22,400.00**
	Item Code 561009 Total No. of Proj.			**1**		**Total Amount**	**$22,400.00**
561011	48" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	1	1	20.00	$1,300.00	$26,000.00
		LF	2	1	18.00	$1,100.00	$19,800.00
		LF	10	1	31.00	$1,300.00	$40,300.00
		LF	12	1	25.00	$522.00	$13,050.00
	Unit Sub Total	**LF**		**4**	**94.00**	**$1,054.79**	**$99,150.00**
	Item Code 561011 Total No. of Proj.			**4**		**Total Amount**	**$99,150.00**
561013	1372 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	7	1	9.00	$2,100.00	$18,900.00
	Unit Sub Total	**M**		**1**	**9.00**	**$2,100.00**	**$18,900.00**
	Item Code 561013 Total No. of Proj.			**1**		**Total Amount**	**$18,900.00**
561014	54" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	3	6	404.00	$686.06	$277,170.00
		LF	4	2	136.00	$727.57	$98,950.00
		LF	6	1	140.00	$700.00	$98,000.00
		LF	10	1	51.00	$500.00	$25,500.00
		LF	12	1	18.00	$880.00	$15,840.00
	Unit Sub Total	**LF**		**11**	**749.00**	**$688.20**	**$515,460.00**
	Item Code 561014 Total No. of Proj.			**11**		**Total Amount**	**$515,460.00**
561015	1524 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	5	1	79.00	$2,200.00	$173,800.00
		M	7	3	111.00	$2,595.50	$288,100.00
		M	8	1	18.00	$2,400.00	$43,200.00
		M	11	2	98.00	$1,851.02	$181,400.00
	Unit Sub Total	**M**		**7**	**306.00**	**$2,243.46**	**$686,500.00**
	Item Code 561015 Total No. of Proj.			**7**		**Total Amount**	**$686,500.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
561016	60" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	2	3	156.00	$901.28	$140,600.00
		LF	3	5	864.00	$781.84	$675,511.50
		LF	4	8	942.00	$919.59	$866,251.00
		LF	5	1	48.00	$1,000.00	$48,000.00
		LF	6	3	408.00	$949.51	$387,402.00
		LF	7	4	227.00	$819.33	$185,989.00
		LF	8	1	50.00	$1,300.00	$65,000.00
		LF	10	2	300.00	$660.00	$198,000.00
		LF	11	2	96.00	$540.63	$51,900.00
		LF	12	5	1,044.00	$905.10	$944,920.00
	Unit Sub Total	**LF**		**34**	**4,135.00**	**$861.81**	**$3,563,573.50**
	Item Code 561016 Total No. of Proj.			**34**		**Total Amount**	**$3,563,573.50**
562001	METAL (ROADSIDE SIGN)	EA	4	1	4.00	$204.00	$816.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$204.00**	**$816.00**
	Item Code 562001 Total No. of Proj.			**1**		**Total Amount**	**$816.00**
562002	METAL (BARRIER MOUNTED SIGN)	KG	7	2	1,360.00	$29.87	$40,620.00
		KG	8	1	640.00	$14.00	$8,960.00
	Unit Sub Total	**KG**		**3**	**2,000.00**	**$24.79**	**$49,580.00**
562002	METAL (BARRIER MOUNTED SIGN)	LB	3	1	410.00	$12.00	$4,920.00
		LB	4	4	11,812.00	$11.70	$138,213.80
		LB	7	2	3,130.00	$10.12	$31,672.80
		LB	10	1	4,590.00	$9.00	$41,310.00
	Unit Sub Total	**LB**		**8**	**19,942.00**	**$10.84**	**$216,116.60**
	Item Code 562002 Total No. of Proj.			**11**		**Total Amount**	**$265,696.60**
562004	METAL (RAIL MOUNTED SIGN)	KG	4	1	1,117.00	$18.00	$20,106.00
		KG	5	1	460.00	$25.00	$11,500.00
		KG	11	1	2,220.00	$10.00	$22,200.00
	Unit Sub Total	**KG**		**3**	**3,797.00**	**$14.17**	**$53,806.00**
562004	METAL (RAIL MOUNTED SIGN)	LB	4	2	3,080.00	$10.27	$31,640.00
		LB	5	1	240.00	$14.00	$3,360.00
		LB	6	1	240.00	$10.00	$2,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
562004	METAL (RAIL MOUNTED SIGN)	LB	12	2	4,060.00	$8.07	$32,760.00
	Unit Sub Total	**LB**		**6**	**7,620.00**	**$9.21**	**$70,160.00**
	Item Code 562004 Total No. of Proj.			**9**		**Total Amount**	**$123,966.00**
566011	ROADSIDE SIGN - ONE POST	EA	1	6	88.00	$366.48	$32,250.00
		EA	2	5	192.00	$219.38	$42,120.00
		EA	3	13	332.00	$226.72	$75,272.00
		EA	4	16	373.00	$232.30	$86,648.00
		EA	5	4	309.00	$299.43	$92,524.00
		EA	6	11	104.00	$223.42	$23,235.20
		EA	7	9	189.00	$308.29	$58,266.80
		EA	8	9	155.00	$252.90	$39,200.00
		EA	9	4	87.00	$242.78	$21,122.00
		EA	10	9	156.00	$239.07	$37,295.00
		EA	11	10	124.00	$261.05	$32,370.00
		EA	12	14	258.00	$351.94	$90,800.00
	Unit Sub Total	**EA**		**110**	**2,367.00**	**$266.63**	**$631,103.00**
	Item Code 566011 Total No. of Proj.			**110**		**Total Amount**	**$631,103.00**
566012	ROADSIDE SIGN - TWO POST	EA	1	3	22.00	$631.82	$13,900.00
		EA	2	3	23.00	$271.30	$6,240.00
		EA	3	5	32.00	$542.81	$17,370.00
		EA	4	8	63.00	$546.28	$34,415.80
		EA	5	2	27.00	$697.78	$18,840.00
		EA	6	3	24.00	$304.17	$7,300.00
		EA	7	5	28.00	$773.21	$21,650.00
		EA	8	3	7.00	$566.14	$3,963.00
		EA	9	3	7.00	$581.43	$4,070.00
		EA	10	4	21.00	$259.52	$5,450.00
		EA	11	4	23.00	$512.17	$11,780.00
		EA	12	7	62.00	$1,052.68	$65,266.00
	Unit Sub Total	**EA**		**50**	**339.00**	**$620.19**	**$210,244.80**
	Item Code 566012 Total No. of Proj.			**50**		**Total Amount**	**$210,244.80**
568001	INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	1	1	6.00	$250.00	$1,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
568001	INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	2	1	1.00	$250.00	$250.00
		EA	3	11	107.00	$165.54	$17,712.50
		EA	4	7	92.00	$105.16	$9,675.00
		EA	5	1	38.00	$200.00	$7,600.00
		EA	6	1	16.00	$80.00	$1,280.00
		EA	7	9	102.00	$201.17	$20,519.72
		EA	8	1	12.00	$200.00	$2,400.00
		EA	10	1	6.00	$125.00	$750.00
		EA	11	6	70.00	$161.14	$11,280.00
		EA	12	8	120.00	$146.77	$17,612.00
	Unit Sub Total	**EA**		**47**	**570.00**	**$158.91**	**$90,579.22**
	Item Code 568001 Total No. of Proj.			**47**		**Total Amount**	**$90,579.22**
568007	INSTALL SIGN OVERLAY	SQFT	4	1	197.00	$15.30	$3,014.10
		SQFT	7	1	12.00	$10.51	$126.12
		SQFT	8	1	94.00	$25.00	$2,350.00
		SQFT	10	1	16.00	$16.00	$256.00
	Unit Sub Total	**SQFT**		**4**	**319.00**	**$18.01**	**$5,746.22**
	Item Code 568007 Total No. of Proj.			**4**		**Total Amount**	**$5,746.22**
568015	INSTALL SIGN (MAST-ARM HANGER METHOD)	EA	4	2	13.00	$2,069.23	$26,900.00
		EA	11	1	2.00	$300.00	$600.00
	Unit Sub Total	**EA**		**3**	**15.00**	**$1,833.33**	**$27,500.00**
	Item Code 568015 Total No. of Proj.			**3**		**Total Amount**	**$27,500.00**
568016	INSTALL SIGN PANEL ON EXISTING FRAME	EA	8	1	58.00	$940.00	$54,520.00
		EA	12	1	3.00	$2,300.00	$6,900.00
	Unit Sub Total	**EA**		**2**	**61.00**	**$1,006.89**	**$61,420.00**
568016	INSTALL SIGN PANEL ON EXISTING FRAME	SQFT	3	3	3,800.00	$9.44	$35,880.00
		SQFT	4	2	1,844.00	$5.08	$9,373.10
		SQFT	5	1	250.00	$20.00	$5,000.00
		SQFT	7	1	480.00	$10.66	$5,116.80
		SQFT	12	1	790.00	$15.00	$11,850.00
	Unit Sub Total	**SQFT**		**8**	**7,164.00**	**$9.38**	**$67,219.90**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 568016 Total No. of Proj.			**10**		**Total Amount**	**$128,639.90**
568017	INSTALL ROADSIDE SIGN PANEL ON EXISTING POST	EA	2	1	2.00	$175.00	$350.00
		EA	3	1	4.00	$95.00	$380.00
		EA	4	1	1.00	$204.00	$204.00
		EA	5	1	1.00	$375.00	$375.00
		EA	6	2	20.00	$82.25	$1,645.00
		EA	7	1	5.00	$89.30	$446.50
		EA	11	7	93.00	$253.12	$23,540.00
		EA	12	12	307.00	$109.77	$33,700.00
	Unit Sub Total	**EA**		**26**	**433.00**	**$140.05**	**$60,640.50**
	Item Code 568017 Total No. of Proj.			**26**		**Total Amount**	**$60,640.50**
568023	INSTALL ROADSIDE SIGN (LAMINATED WOOD BOX POST)	EA	2	1	12.00	$699.00	$8,388.00
		EA	3	2	5.00	$1,380.00	$6,900.00
		EA	4	2	3.00	$2,463.33	$7,390.00
		EA	5	1	5.00	$200.00	$1,000.00
		EA	6	1	6.00	$300.00	$1,800.00
		EA	8	2	14.00	$4,196.79	$58,755.00
		EA	10	1	2.00	$1,300.00	$2,600.00
		EA	11	1	2.00	$2,000.00	$4,000.00
		EA	12	1	2.00	$5,100.00	$10,200.00
	Unit Sub Total	**EA**		**12**	**51.00**	**$1,981.04**	**$101,033.00**
	Item Code 568023 Total No. of Proj.			**12**		**Total Amount**	**$101,033.00**
570115	ABUTMENT LUMBER BLOCKING	MFBM	3	1	11.00	$1,200.00	$13,200.00
	Unit Sub Total	**MFBM**		**1**	**11.00**	**$1,200.00**	**$13,200.00**
	Item Code 570115 Total No. of Proj.			**1**		**Total Amount**	**$13,200.00**
570120	TREATED LUMBER AND TIMBER	MFBM	7	1	11.00	$1,500.00	$16,500.00
	Unit Sub Total	**MFBM**		**1**	**11.00**	**$1,500.00**	**$16,500.00**
	Item Code 570120 Total No. of Proj.			**1**		**Total Amount**	**$16,500.00**
575004	TIMBER LAGGING	M3	5	1	77.00	$750.00	$57,750.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**1**	**77.00**	**$750.00**	**$57,750.00**
575004	TIMBER LAGGING		MFBM	1	3	48.80	$3,334.02	$162,700.00
			MFBM	4	4	34.30	$2,734.84	$93,805.00
			MFBM	5	1	102.00	$4,000.00	$408,000.00
		Unit Sub Total	**MFBM**		**8**	**185.10**	**$3,589.98**	**$664,505.00**
	Item Code 575004	**Total No. of Proj.**			**9**		**Total Amount**	**$722,255.00**
590106	CLEAN STRUCTURAL STEEL (EXISTING BRIDGE)		LS	2	2	2.00	$70,000.00	$140,000.00
			LS	3	1	1.00	$2,308,936.00	$2,308,936.00
			LS	4	1	1.00	$489,580.00	$489,580.00
			LS	10	1	1.00	$88,250.00	$88,250.00
			LS	12	1	1.00	$234,602.00	$234,602.00
		Unit Sub Total	**LS**		**6**	**6.00**	**$543,561.33**	**$3,261,368.00**
	Item Code 590106	**Total No. of Proj.**			**6**		**Total Amount**	**$3,261,368.00**
590111	PAINT STRUCTURAL STEEL (EXISTING BRIDGE)		LS	2	2	2.00	$92,500.00	$185,000.00
			LS	3	1	1.00	$1,794,542.40	$1,794,542.40
			LS	4	1	1.00	$450,000.00	$450,000.00
			LS	10	1	1.00	$294,450.00	$294,450.00
			LS	12	1	1.00	$234,602.00	$234,602.00
		Unit Sub Total	**LS**		**6**	**6.00**	**$493,099.07**	**$2,958,594.40**
	Item Code 590111	**Total No. of Proj.**			**6**		**Total Amount**	**$2,958,594.40**
590115	CLEAN AND PAINT STRUCTURAL STEEL		LS	3	2	2.00	$29,500.00	$59,000.00
			LS	4	1	1.00	$10,000.00	$10,000.00
			LS	12	1	1.00	$1,000.00	$1,000.00
		Unit Sub Total	**LS**		**4**	**4.00**	**$17,500.00**	**$70,000.00**
	Item Code 590115	**Total No. of Proj.**			**4**		**Total Amount**	**$70,000.00**
590116	CLEAN AND PAINT STRUCTURAL STEEL (EXISTING BRIDGE)		LS	3	1	1.00	$628,353.60	$628,353.60
			LS	5	1	1.00	$317,800.00	$317,800.00
			LS	7	1	1.00	$736,000.00	$736,000.00
		Unit Sub Total	**LS**		**3**	**3.00**	**$560,717.87**	**$1,682,153.60**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 590116 Total No. of Proj.			**3**		**Total Amount**	**$1,682,153.60**
590135	SPOT BLAST CLEAN AND PAINT UNDERCOAT	SQFT	2	2	4,910.00	$12.20	$59,895.00
		SQFT	3	2	18,460.00	$38.64	$713,216.00
		SQFT	4	1	11.00	$1,250.00	$13,750.00
		SQFT	10	1	6,265.00	$20.40	$127,806.00
		SQFT	12	1	3,800.00	$50.00	$190,000.00
	Unit Sub Total	**SQFT**		**7**	**33,446.00**	**$33.03**	**$1,104,667.00**
	Item Code 590135 Total No. of Proj.			**7**		**Total Amount**	**$1,104,667.00**
590280	PAINT CONCRETE SURFACES	SQFT	12	1	610.00	$4.50	$2,745.00
	Unit Sub Total	**SQFT**		**1**	**610.00**	**$4.50**	**$2,745.00**
	Item Code 590280 Total No. of Proj.			**1**		**Total Amount**	**$2,745.00**
590301	WORK AREA MONITORING	LS	1	1	1.00	$8,400.00	$8,400.00
		LS	2	2	2.00	$6,325.00	$12,650.00
		LS	3	1	1.00	$9,350.00	$9,350.00
		LS	4	1	1.00	$10,000.00	$10,000.00
		LS	5	1	1.00	$2,500.00	$2,500.00
		LS	7	1	1.00	$4,500.00	$4,500.00
		LS	10	2	2.00	$2,500.00	$5,000.00
		LS	12	1	1.00	$10,000.00	$10,000.00
	Unit Sub Total	**LS**		**10**	**10.00**	**$6,240.00**	**$62,400.00**
	Item Code 590301 Total No. of Proj.			**10**		**Total Amount**	**$62,400.00**
597401	PAINT CURB (2-COAT)	LF	2	1	16.00	$29.15	$466.40
		LF	12	1	240.00	$1.65	$396.00
	Unit Sub Total	**LF**		**2**	**256.00**	**$3.37**	**$862.40**
597401	PAINT CURB (2-COAT)	SQFT	4	1	90.00	$2.00	$180.00
	Unit Sub Total	**SQFT**		**1**	**90.00**	**$2.00**	**$180.00**
	Item Code 597401 Total No. of Proj.			**3**		**Total Amount**	**$1,042.40**
597600	PREPARE AND PAINT CONCRETE	SQFT	1	1	122,100.00	$0.49	$59,829.00
		SQFT	3	1	10,154.00	$3.00	$30,462.00
		SQFT	4	1	5,000.00	$7.00	$35,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
597600	PREPARE AND PAINT CONCRETE	SQFT	5	2	17,880.00	$1.00	$17,880.00
		SQFT	6	2	4,829.00	$2.07	$9,999.50
		SQFT	10	1	3,600.00	$2.00	$7,200.00
	Unit Sub Total	**SQFT**		**8**	**163,563.00**	**$0.98**	**$160,370.50**
	Item Code 597600 Total No. of Proj.			**8**		**Total Amount**	**$160,370.50**
597601	PREPARE AND STAIN CONCRETE	M2	11	1	100.00	$42.00	$4,200.00
	Unit Sub Total	**M2**		**1**	**100.00**	**$42.00**	**$4,200.00**
597601	PREPARE AND STAIN CONCRETE	SQFT	4	1	1,730.00	$2.00	$3,460.00
		SQFT	6	1	17,164.00	$2.00	$34,328.00
	Unit Sub Total	**SQFT**		**2**	**18,894.00**	**$2.00**	**$37,788.00**
	Item Code 597601 Total No. of Proj.			**3**		**Total Amount**	**$41,988.00**
601001	RAILROAD TRACK	LS	7	1	1.00	$450,000.00	$450,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$450,000.00**	**$450,000.00**
	Item Code 601001 Total No. of Proj.			**1**		**Total Amount**	**$450,000.00**
620002	6" ALTERNATIVE PIPE CULVERT	LF	2	1	220.00	$18.00	$3,960.00
		LF	9	1	31.00	$100.00	$3,100.00
	Unit Sub Total	**LF**		**2**	**251.00**	**$28.13**	**$7,060.00**
	Item Code 620002 Total No. of Proj.			**2**		**Total Amount**	**$7,060.00**
620060	12" ALTERNATIVE PIPE CULVERT	LF	1	2	140.00	$52.14	$7,300.00
		LF	3	1	30.00	$55.00	$1,650.00
		LF	4	7	399.00	$47.45	$18,934.25
		LF	7	1	2,800.00	$74.00	$207,200.00
		LF	10	2	118.00	$88.81	$10,480.00
	Unit Sub Total	**LF**		**13**	**3,487.00**	**$70.42**	**$245,564.25**
	Item Code 620060 Total No. of Proj.			**13**		**Total Amount**	**$245,564.25**
620061	12" ALTERNATIVE PIPE CULVERT (TYPE A)	LF	4	1	38.00	$94.00	$3,572.00
	Unit Sub Total	**LF**		**1**	**38.00**	**$94.00**	**$3,572.00**
	Item Code 620061 Total No. of Proj.			**1**		**Total Amount**	**$3,572.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
620080	15" ALTERNATIVE PIPE CULVERT	LF	4	1	13.00	$150.00	$1,950.00
	Unit Sub Total	**LF**		**1**	**13.00**	**$150.00**	**$1,950.00**
	Item Code 620080 Total No. of Proj.			**1**		**Total Amount**	**$1,950.00**
620100	18" ALTERNATIVE PIPE CULVERT	LF	1	2	241.00	$108.61	$26,175.00
		LF	2	1	81.00	$275.00	$22,275.00
		LF	3	4	7,200.00	$42.40	$305,260.00
		LF	4	7	20,131.00	$45.99	$925,754.00
		LF	5	2	750.00	$50.00	$37,500.00
		LF	6	2	2,830.00	$34.00	$96,220.00
		LF	8	1	390.00	$31.00	$12,090.00
		LF	10	2	5,110.00	$45.68	$233,400.00
		LF	11	1	460.00	$61.00	$28,060.00
		LF	12	3	6,210.00	$53.24	$330,640.00
	Unit Sub Total	**LF**		**25**	**43,403.00**	**$46.48**	**$2,017,374.00**
	Item Code 620100 Total No. of Proj.			**25**		**Total Amount**	**$2,017,374.00**
620101	18" ALTERNATIVE PIPE CULVERT (TYPE A)	LF	4	4	12,674.00	$68.33	$866,050.00
	Unit Sub Total	**LF**		**4**	**12,674.00**	**$68.33**	**$866,050.00**
	Item Code 620101 Total No. of Proj.			**4**		**Total Amount**	**$866,050.00**
620102	18" ALTERNATIVE PIPE CULVERT (TYPE B)	LF	4	4	15,630.00	$50.96	$796,440.00
	Unit Sub Total	**LF**		**4**	**15,630.00**	**$50.96**	**$796,440.00**
	Item Code 620102 Total No. of Proj.			**4**		**Total Amount**	**$796,440.00**
620140	24" ALTERNATIVE PIPE CULVERT	LF	1	4	4,090.00	$137.32	$561,650.00
		LF	3	4	4,210.00	$133.41	$561,670.00
		LF	4	5	11,413.00	$47.98	$547,578.00
		LF	5	2	258.00	$127.48	$32,890.00
		LF	6	2	13,180.00	$44.38	$584,956.00
		LF	8	1	310.00	$37.00	$11,470.00
		LF	10	3	10,220.00	$72.38	$739,750.00
		LF	11	3	1,680.00	$97.71	$164,150.00
		LF	12	2	4,590.00	$57.11	$262,140.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**26**	**49,951.00**	**$69.39**	**$3,466,254.00**
	Item Code 620140 Total No. of Proj.			**26**		**Total Amount**	**$3,466,254.00**
620141	24" ALTERNATIVE PIPE CULVERT (TYPE A)	LF	4	3	2,160.00	$98.24	$212,190.00
	Unit Sub Total	**LF**		**3**	**2,160.00**	**$98.24**	**$212,190.00**
	Item Code 620141 Total No. of Proj.			**3**		**Total Amount**	**$212,190.00**
620142	24" ALTERNATIVE PIPE CULVERT (TYPE B)	LF	4	3	5,890.00	$70.74	$416,630.00
	Unit Sub Total	**LF**		**3**	**5,890.00**	**$70.74**	**$416,630.00**
	Item Code 620142 Total No. of Proj.			**3**		**Total Amount**	**$416,630.00**
620160	27" ALTERNATIVE PIPE CULVERT	LF	4	1	10.00	$220.00	$2,200.00
	Unit Sub Total	**LF**		**1**	**10.00**	**$220.00**	**$2,200.00**
	Item Code 620160 Total No. of Proj.			**1**		**Total Amount**	**$2,200.00**
620180	30" ALTERNATIVE PIPE CULVERT	LF	1	1	79.00	$135.00	$10,665.00
		LF	3	2	221.00	$131.99	$29,170.00
		LF	4	3	1,378.00	$65.82	$90,698.00
	Unit Sub Total	**LF**		**6**	**1,678.00**	**$77.79**	**$130,533.00**
	Item Code 620180 Total No. of Proj.			**6**		**Total Amount**	**$130,533.00**
620181	30" ALTERNATIVE PIPE CULVERT (TYPE A)	LF	4	1	52.00	$113.00	$5,876.00
	Unit Sub Total	**LF**		**1**	**52.00**	**$113.00**	**$5,876.00**
	Item Code 620181 Total No. of Proj.			**1**		**Total Amount**	**$5,876.00**
620182	30" ALTERNATIVE PIPE CULVERT (TYPE B)	LF	4	2	1,030.00	$87.73	$90,360.00
	Unit Sub Total	**LF**		**2**	**1,030.00**	**$87.73**	**$90,360.00**
	Item Code 620182 Total No. of Proj.			**2**		**Total Amount**	**$90,360.00**
620220	36" ALTERNATIVE PIPE CULVERT	LF	1	2	460.00	$164.78	$75,800.00
		LF	3	1	5.00	$217.00	$1,085.00
		LF	4	1	1,010.00	$71.60	$72,316.00
		LF	5	1	170.00	$100.00	$17,000.00
		LF	6	1	1,340.00	$61.50	$82,410.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
620220	36" ALTERNATIVE PIPE CULVERT	LF	10	1	340.00	$140.00	$47,600.00
		LF	11	1	350.00	$97.00	$33,950.00
		LF	12	2	2,110.00	$74.58	$157,370.00
	Unit Sub Total	**LF**		**10**	**5,785.00**	**$84.28**	**$487,531.00**
	Item Code 620220 Total No. of Proj.			**10**		**Total Amount**	**$487,531.00**
620221	36" ALTERNATIVE PIPE CULVERT (TYPE A)	LF	4	1	50.00	$98.00	$4,900.00
	Unit Sub Total	**LF**		**1**	**50.00**	**$98.00**	**$4,900.00**
	Item Code 620221 Total No. of Proj.			**1**		**Total Amount**	**$4,900.00**
620222	36" ALTERNATIVE PIPE CULVERT (TYPE B)	LF	4	1	2,080.00	$90.00	$187,200.00
	Unit Sub Total	**LF**		**1**	**2,080.00**	**$90.00**	**$187,200.00**
	Item Code 620222 Total No. of Proj.			**1**		**Total Amount**	**$187,200.00**
620260	42" ALTERNATIVE PIPE CULVERT	LF	1	2	96.00	$178.85	$17,170.00
		LF	2	1	220.00	$95.00	$20,900.00
		LF	4	2	2,292.00	$106.80	$244,788.00
	Unit Sub Total	**LF**		**5**	**2,608.00**	**$108.46**	**$282,858.00**
	Item Code 620260 Total No. of Proj.			**5**		**Total Amount**	**$282,858.00**
620262	42" ALTERNATIVE PIPE CULVERT (TYPE B)	LF	4	1	280.00	$120.00	$33,600.00
	Unit Sub Total	**LF**		**1**	**280.00**	**$120.00**	**$33,600.00**
	Item Code 620262 Total No. of Proj.			**1**		**Total Amount**	**$33,600.00**
620300	48" ALTERNATIVE PIPE CULVERT	LF	1	2	216.00	$223.24	$48,220.00
		LF	6	1	170.00	$84.80	$14,416.00
		LF	12	1	220.00	$137.00	$30,140.00
	Unit Sub Total	**LF**		**4**	**606.00**	**$153.10**	**$92,776.00**
	Item Code 620300 Total No. of Proj.			**4**		**Total Amount**	**$92,776.00**
620340	54" ALTERNATIVE PIPE CULVERT	LF	4	1	5.00	$800.00	$4,000.00
	Unit Sub Total	**LF**		**1**	**5.00**	**$800.00**	**$4,000.00**
	Item Code 620340 Total No. of Proj.			**1**		**Total Amount**	**$4,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
620460	72" ALTERNATIVE PIPE CULVERT	LF	1	1	110.00	$575.00	$63,250.00
	Unit Sub Total	**LF**		**1**	**110.00**	**$575.00**	**$63,250.00**
	Item Code 620460 Total No. of Proj.			**1**		**Total Amount**	**$63,250.00**
620715	18" ALTERNATIVE SLOTTED PIPE	LF	4	3	13,190.00	$104.42	$1,377,270.00
		LF	7	1	3,430.00	$51.00	$174,930.00
	Unit Sub Total	**LF**		**4**	**16,620.00**	**$93.39**	**$1,552,200.00**
	Item Code 620715 Total No. of Proj.			**4**		**Total Amount**	**$1,552,200.00**
620902	200 MM ALTERNATIVE PIPE CULVERT	M	8	1	86.00	$85.00	$7,310.00
		M	11	2	129.00	$108.22	$13,960.00
	Unit Sub Total	**M**		**3**	**215.00**	**$98.93**	**$21,270.00**
	Item Code 620902 Total No. of Proj.			**3**		**Total Amount**	**$21,270.00**
620904	300 MM ALTERNATIVE PIPE CULVERT	M	4	1	16.00	$180.00	$2,880.00
	Unit Sub Total	**M**		**1**	**16.00**	**$180.00**	**$2,880.00**
	Item Code 620904 Total No. of Proj.			**1**		**Total Amount**	**$2,880.00**
620909	450 MM ALTERNATIVE PIPE CULVERT	M	4	1	530.00	$180.00	$95,400.00
		M	5	1	200.00	$140.00	$28,000.00
		M	8	1	16.00	$240.00	$3,840.00
		M	10	1	300.00	$123.00	$36,900.00
		M	11	1	140.00	$120.00	$16,800.00
	Unit Sub Total	**M**		**5**	**1,186.00**	**$152.56**	**$180,940.00**
	Item Code 620909 Total No. of Proj.			**5**		**Total Amount**	**$180,940.00**
620913	600 MM ALTERNATIVE PIPE CULVERT	M	4	1	36.00	$240.00	$8,640.00
		M	5	1	5,050.00	$145.00	$732,250.00
		M	8	1	71.00	$210.00	$14,910.00
		M	11	1	2,180.00	$140.00	$305,200.00
	Unit Sub Total	**M**		**4**	**7,337.00**	**$144.61**	**$1,061,000.00**
	Item Code 620913 Total No. of Proj.			**4**		**Total Amount**	**$1,061,000.00**
620919	750 MM ALTERNATIVE PIPE CULVERT	M	11	1	22.00	$160.00	$3,520.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION			UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total		**M**		**1**	**22.00**	**$160.00**	**$3,520.00**
	Item Code 620919	**Total No. of Proj.**				**1**		**Total Amount**	**$3,520.00**
620924	900 MM ALTERNATIVE PIPE CULVERT			M	4	1	10.00	$525.00	$5,250.00
				M	5	1	170.00	$160.00	$27,200.00
				M	11	1	20.00	$180.00	$3,600.00
		Unit Sub Total		**M**		**3**	**200.00**	**$180.25**	**$36,050.00**
	Item Code 620924	**Total No. of Proj.**				**3**		**Total Amount**	**$36,050.00**
641101	12" PLASTIC PIPE			LF	2	1	10.00	$400.00	$4,000.00
				LF	3	1	32.00	$110.00	$3,520.00
		Unit Sub Total		**LF**		**2**	**42.00**	**$179.05**	**$7,520.00**
	Item Code 641101	**Total No. of Proj.**				**2**		**Total Amount**	**$7,520.00**
641104	15" PLASTIC PIPE			LF	3	1	1,500.00	$50.00	$75,000.00
				LF	4	1	40.00	$27.12	$1,084.80
		Unit Sub Total		**LF**		**2**	**1,540.00**	**$49.41**	**$76,084.80**
	Item Code 641104	**Total No. of Proj.**				**2**		**Total Amount**	**$76,084.80**
641107	18" PLASTIC PIPE			LF	2	1	1,480.00	$100.00	$148,000.00
				LF	3	2	14,534.00	$61.49	$893,750.00
				LF	4	4	684.00	$102.49	$70,100.00
				LF	9	1	52.00	$187.40	$9,744.80
				LF	10	1	18.00	$90.00	$1,620.00
		Unit Sub Total		**LF**		**9**	**16,768.00**	**$66.99**	**$1,123,214.80**
	Item Code 641107	**Total No. of Proj.**				**9**		**Total Amount**	**$1,123,214.80**
641113	24" PLASTIC PIPE			LF	2	1	1,800.00	$150.00	$270,000.00
				LF	4	2	108.00	$133.33	$14,400.00
				LF	9	2	1,910.00	$145.75	$278,374.00
		Unit Sub Total		**LF**		**5**	**3,818.00**	**$147.40**	**$562,774.00**
	Item Code 641113	**Total No. of Proj.**				**5**		**Total Amount**	**$562,774.00**
641119	30" PLASTIC PIPE			LF	9	1	490.00	$165.00	$80,850.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**1**	**490.00**	**$165.00**	**$80,850.00**
	Item Code 641119	**Total No. of Proj.**			**1**		**Total Amount**	**$80,850.00**
641125	36" PLASTIC PIPE		LF	2	1	890.00	$260.00	$231,400.00
			LF	9	2	510.00	$192.50	$98,175.00
		Unit Sub Total	**LF**		**3**	**1,400.00**	**$235.41**	**$329,575.00**
	Item Code 641125	**Total No. of Proj.**			**3**		**Total Amount**	**$329,575.00**
641131	48" PLASTIC PIPE		LF	2	1	40.00	$400.00	$16,000.00
		Unit Sub Total	**LF**		**1**	**40.00**	**$400.00**	**$16,000.00**
	Item Code 641131	**Total No. of Proj.**			**1**		**Total Amount**	**$16,000.00**
641132	300 MM PLASTIC PIPE		M	7	1	65.00	$25.00	$1,625.00
		Unit Sub Total	**M**		**1**	**65.00**	**$25.00**	**$1,625.00**
	Item Code 641132	**Total No. of Proj.**			**1**		**Total Amount**	**$1,625.00**
650010	12" REINFORCED CONCRETE PIPE		LF	4	3	186.00	$72.33	$13,454.00
			LF	12	2	19.00	$406.32	$7,720.00
		Unit Sub Total	**LF**		**5**	**205.00**	**$103.29**	**$21,174.00**
	Item Code 650010	**Total No. of Proj.**			**5**		**Total Amount**	**$21,174.00**
650012	15" REINFORCED CONCRETE PIPE		LF	3	1	330.00	$80.00	$26,400.00
			LF	6	1	4.00	$670.00	$2,680.00
			LF	7	1	350.00	$73.00	$25,550.00
			LF	10	1	2.00	$90.00	$180.00
		Unit Sub Total	**LF**		**4**	**686.00**	**$79.90**	**$54,810.00**
	Item Code 650012	**Total No. of Proj.**			**4**		**Total Amount**	**$54,810.00**
650014	18" REINFORCED CONCRETE PIPE		LF	1	1	10.00	$270.00	$2,700.00
			LF	2	2	1,896.00	$80.89	$153,370.00
			LF	3	4	2,782.00	$65.85	$183,200.00
			LF	4	3	602.00	$86.63	$52,150.00
			LF	5	1	6.00	$270.00	$1,620.00
			LF	6	3	453.00	$89.80	$40,680.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
650014	18" REINFORCED CONCRETE PIPE	LF	7	7	4,946.00	$92.12	$455,604.00
		LF	8	1	66.00	$82.00	$5,412.00
		LF	10	2	640.00	$50.94	$32,600.00
		LF	11	1	11.00	$185.00	$2,035.00
		LF	12	3	263.00	$75.94	$19,971.00
	Unit Sub Total	**LF**		**28**	**11,675.00**	**$81.31**	**$949,342.00**
	Item Code 650014 Total No. of Proj.			**28**		**Total Amount**	**$949,342.00**
650018	24" REINFORCED CONCRETE PIPE	LF	1	1	8.00	$180.00	$1,440.00
		LF	2	1	130.00	$270.00	$35,100.00
		LF	3	3	519.00	$94.97	$49,290.00
		LF	4	2	300.00	$88.00	$26,400.00
		LF	5	3	257.50	$141.68	$36,483.00
		LF	6	2	478.00	$86.97	$41,570.00
		LF	7	4	5,686.00	$121.78	$692,458.64
		LF	11	1	3.00	$285.00	$855.00
		LF	12	2	87.00	$140.00	$12,180.00
	Unit Sub Total	**LF**		**19**	**7,468.50**	**$119.94**	**$895,776.64**
	Item Code 650018 Total No. of Proj.			**19**		**Total Amount**	**$895,776.64**
650022	30" REINFORCED CONCRETE PIPE	LF	4	1	9.00	$105.00	$945.00
		LF	5	2	7.10	$688.59	$4,889.00
		LF	7	2	620.00	$187.74	$116,400.00
		LF	12	2	124.00	$120.16	$14,900.00
	Unit Sub Total	**LF**		**7**	**760.10**	**$180.42**	**$137,134.00**
	Item Code 650022 Total No. of Proj.			**7**		**Total Amount**	**$137,134.00**
650026	36" REINFORCED CONCRETE PIPE	LF	2	1	200.00	$250.00	$50,000.00
		LF	4	3	49.00	$240.04	$11,762.00
		LF	5	1	4.50	$795.00	$3,577.50
		LF	6	1	170.00	$94.00	$15,980.00
		LF	7	1	140.00	$290.00	$40,600.00
		LF	10	2	520.00	$125.50	$65,260.00
		LF	11	1	31.00	$220.00	$6,820.00
		LF	12	2	92.00	$198.65	$18,276.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**12**	**1,206.50**	**$175.94**	**$212,275.50**
	Item Code 650026	**Total No. of Proj.**			**12**		**Total Amount**	**$212,275.50**
650030	42" REINFORCED CONCRETE PIPE		LF	4	1	61.00	$95.00	$5,795.00
		Unit Sub Total	**LF**		**1**	**61.00**	**$95.00**	**$5,795.00**
	Item Code 650030	**Total No. of Proj.**			**1**		**Total Amount**	**$5,795.00**
650034	48" REINFORCED CONCRETE PIPE		LF	7	1	250.00	$550.00	$137,500.00
			LF	10	1	590.00	$215.00	$126,850.00
			LF	12	2	2,841.00	$123.20	$350,009.00
		Unit Sub Total	**LF**		**4**	**3,681.00**	**$166.90**	**$614,359.00**
	Item Code 650034	**Total No. of Proj.**			**4**		**Total Amount**	**$614,359.00**
650036	51" REINFORCED CONCRETE PIPE		LF	7	1	900.00	$560.00	$504,000.00
		Unit Sub Total	**LF**		**1**	**900.00**	**$560.00**	**$504,000.00**
	Item Code 650036	**Total No. of Proj.**			**1**		**Total Amount**	**$504,000.00**
650038	54" REINFORCED CONCRETE PIPE		LF	1	1	180.00	$270.00	$48,600.00
			LF	4	1	230.00	$500.00	$115,000.00
			LF	11	1	15.00	$315.00	$4,725.00
		Unit Sub Total	**LF**		**3**	**425.00**	**$396.06**	**$168,325.00**
	Item Code 650038	**Total No. of Proj.**			**3**		**Total Amount**	**$168,325.00**
650042	60" REINFORCED CONCRETE PIPE		LF	10	1	290.00	$300.00	$87,000.00
		Unit Sub Total	**LF**		**1**	**290.00**	**$300.00**	**$87,000.00**
	Item Code 650042	**Total No. of Proj.**			**1**		**Total Amount**	**$87,000.00**
650046	66" REINFORCED CONCRETE PIPE		LF	12	1	78.00	$350.00	$27,300.00
		Unit Sub Total	**LF**		**1**	**78.00**	**$350.00**	**$27,300.00**
	Item Code 650046	**Total No. of Proj.**			**1**		**Total Amount**	**$27,300.00**
650050	72" REINFORCED CONCRETE PIPE		LF	4	1	43.00	$200.00	$8,600.00
		Unit Sub Total	**LF**		**1**	**43.00**	**$200.00**	**$8,600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 650050 Total No. of Proj.			**1**		**Total Amount**	**$8,600.00**
650067	300 MM REINFORCED CONCRETE PIPE	M	7	1	3.00	$300.00	$900.00
	Unit Sub Total	**M**		**1**	**3.00**	**$300.00**	**$900.00**
	Item Code 650067 Total No. of Proj.			**1**		**Total Amount**	**$900.00**
650069	450 MM REINFORCED CONCRETE PIPE	M	7	4	1,241.00	$253.79	$314,957.50
		M	8	1	400.00	$160.00	$64,000.00
		M	11	1	160.00	$165.00	$26,400.00
	Unit Sub Total	**M**		**6**	**1,801.00**	**$225.07**	**$405,357.50**
	Item Code 650069 Total No. of Proj.			**6**		**Total Amount**	**$405,357.50**
650072	525 MM REINFORCED CONCRETE PIPE	M	7	1	25.00	$260.00	$6,500.00
	Unit Sub Total	**M**		**1**	**25.00**	**$260.00**	**$6,500.00**
	Item Code 650072 Total No. of Proj.			**1**		**Total Amount**	**$6,500.00**
650075	600 MM REINFORCED CONCRETE PIPE	M	7	5	4,778.00	$264.12	$1,261,965.00
		M	8	1	300.00	$210.00	$63,000.00
		M	11	1	600.00	$265.00	$159,000.00
	Unit Sub Total	**M**		**7**	**5,678.00**	**$261.35**	**$1,483,965.00**
	Item Code 650075 Total No. of Proj.			**7**		**Total Amount**	**$1,483,965.00**
650077	750 MM REINFORCED CONCRETE PIPE	M	7	1	930.00	$250.00	$232,500.00
		M	8	1	57.00	$250.00	$14,250.00
		M	11	1	2.80	$850.00	$2,380.00
	Unit Sub Total	**M**		**3**	**989.80**	**$251.70**	**$249,130.00**
	Item Code 650077 Total No. of Proj.			**3**		**Total Amount**	**$249,130.00**
650079	900 MM REINFORCED CONCRETE PIPE	M	7	2	96.00	$323.19	$31,026.00
		M	8	1	120.00	$295.00	$35,400.00
	Unit Sub Total	**M**		**3**	**216.00**	**$307.53**	**$66,426.00**
	Item Code 650079 Total No. of Proj.			**3**		**Total Amount**	**$66,426.00**
650081	1050 MM REINFORCED CONCRETE PIPE	M	7	1	73.00	$510.00	$37,230.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**1**	**73.00**	**$510.00**	**$37,230.00**
	Item Code 650081 Total No. of Proj.			**1**		**Total Amount**	**$37,230.00**
650084	1200 MM REINFORCED CONCRETE PIPE	M	7	2	319.00	$405.78	$129,445.00
	Unit Sub Total	**M**		**2**	**319.00**	**$405.78**	**$129,445.00**
	Item Code 650084 Total No. of Proj.			**2**		**Total Amount**	**$129,445.00**
650086	1350 MM REINFORCED CONCRETE PIPE	M	8	1	450.00	$550.00	$247,500.00
	Unit Sub Total	**M**		**1**	**450.00**	**$550.00**	**$247,500.00**
	Item Code 650086 Total No. of Proj.			**1**		**Total Amount**	**$247,500.00**
650089	1500 MM REINFORCED CONCRETE PIPE	M	8	1	230.00	$775.00	$178,250.00
	Unit Sub Total	**M**		**1**	**230.00**	**$775.00**	**$178,250.00**
	Item Code 650089 Total No. of Proj.			**1**		**Total Amount**	**$178,250.00**
650092	1800 MM REINFORCED CONCRETE PIPE	M	8	1	170.00	$1,100.00	$187,000.00
	Unit Sub Total	**M**		**1**	**170.00**	**$1,100.00**	**$187,000.00**
	Item Code 650092 Total No. of Proj.			**1**		**Total Amount**	**$187,000.00**
650105	18" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	LF	10	1	129.00	$272.00	$35,088.00
	Unit Sub Total	**LF**		**1**	**129.00**	**$272.00**	**$35,088.00**
	Item Code 650105 Total No. of Proj.			**1**		**Total Amount**	**$35,088.00**
650107	24" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	LF	10	1	718.00	$413.00	$296,534.00
	Unit Sub Total	**LF**		**1**	**718.00**	**$413.00**	**$296,534.00**
	Item Code 650107 Total No. of Proj.			**1**		**Total Amount**	**$296,534.00**
650109	36" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	LF	6	1	79.00	$100.00	$7,900.00
	Unit Sub Total	**LF**		**1**	**79.00**	**$100.00**	**$7,900.00**
	Item Code 650109 Total No. of Proj.			**1**		**Total Amount**	**$7,900.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
650111	42" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	LF	10	1	47.00	$540.00	$25,380.00
	Unit Sub Total	**LF**		**1**	**47.00**	**$540.00**	**$25,380.00**
	Item Code 650111 Total No. of Proj.			**1**		**Total Amount**	**$25,380.00**
650127	450 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	5	1	150.00	$120.00	$18,000.00
		M	10	1	130.00	$210.00	$27,300.00
	Unit Sub Total	**M**		**2**	**280.00**	**$161.79**	**$45,300.00**
	Item Code 650127 Total No. of Proj.			**2**		**Total Amount**	**$45,300.00**
650128	600 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	5	1	3,340.00	$155.00	$517,700.00
		M	10	1	490.00	$275.00	$134,750.00
	Unit Sub Total	**M**		**2**	**3,830.00**	**$170.35**	**$652,450.00**
	Item Code 650128 Total No. of Proj.			**2**		**Total Amount**	**$652,450.00**
650129	750 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	5	1	800.00	$210.00	$168,000.00
	Unit Sub Total	**M**		**1**	**800.00**	**$210.00**	**$168,000.00**
	Item Code 650129 Total No. of Proj.			**1**		**Total Amount**	**$168,000.00**
650130	900 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	5	1	660.00	$270.00	$178,200.00
	Unit Sub Total	**M**		**1**	**660.00**	**$270.00**	**$178,200.00**
	Item Code 650130 Total No. of Proj.			**1**		**Total Amount**	**$178,200.00**
650131	1050 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	5	1	76.00	$350.00	$26,600.00
	Unit Sub Total	**M**		**1**	**76.00**	**$350.00**	**$26,600.00**
	Item Code 650131 Total No. of Proj.			**1**		**Total Amount**	**$26,600.00**
650132	1200 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	5	1	130.00	$420.00	$54,600.00
		M	10	1	24.00	$485.00	$11,640.00
	Unit Sub Total	**M**		**2**	**154.00**	**$430.13**	**$66,240.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 650132 Total No. of Proj.			**2**		**Total Amount**	**$66,240.00**
650134	1500 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	5	1	74.00	$600.00	$44,400.00
	Unit Sub Total	**M**		**1**	**74.00**	**$600.00**	**$44,400.00**
	Item Code 650134 Total No. of Proj.			**1**		**Total Amount**	**$44,400.00**
650211	18" REINFORCED CONCRETE PIPE (CLASS II)	LF	2	2	1,930.00	$75.17	$145,080.00
	Unit Sub Total	**LF**		**2**	**1,930.00**	**$75.17**	**$145,080.00**
	Item Code 650211 Total No. of Proj.			**2**		**Total Amount**	**$145,080.00**
650311	18" REINFORCED CONCRETE PIPE (CLASS III)	LF	6	1	2,030.00	$40.00	$81,200.00
	Unit Sub Total	**LF**		**1**	**2,030.00**	**$40.00**	**$81,200.00**
	Item Code 650311 Total No. of Proj.			**1**		**Total Amount**	**$81,200.00**
650316	24" REINFORCED CONCRETE PIPE (CLASS III)	LF	6	1	2,160.00	$60.00	$129,600.00
	Unit Sub Total	**LF**		**1**	**2,160.00**	**$60.00**	**$129,600.00**
	Item Code 650316 Total No. of Proj.			**1**		**Total Amount**	**$129,600.00**
650511	18" REINFORCED CONCRETE PIPE (CLASS V)	LF	4	1	78.00	$95.00	$7,410.00
	Unit Sub Total	**LF**		**1**	**78.00**	**$95.00**	**$7,410.00**
	Item Code 650511 Total No. of Proj.			**1**		**Total Amount**	**$7,410.00**
650516	24" REINFORCED CONCRETE PIPE (CLASS V)	LF	4	1	20.00	$120.00	$2,400.00
	Unit Sub Total	**LF**		**1**	**20.00**	**$120.00**	**$2,400.00**
	Item Code 650516 Total No. of Proj.			**1**		**Total Amount**	**$2,400.00**
652215	24" REINFORCED CONCRETE PIPE (CLASS II, RUBBER GASKET JOINT)	LF	2	2	66.00	$259.09	$17,100.00
		LF	4	1	420.00	$97.00	$40,740.00
	Unit Sub Total	**LF**		**3**	**486.00**	**$119.01**	**$57,840.00**
	Item Code 652215 Total No. of Proj.			**3**		**Total Amount**	**$57,840.00**
652424	36" REINFORCED CONCRETE PIPE (CLASS IV, RUBBER GASKET JOINT)	LF	2	1	260.00	$130.00	$33,800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**1**	**260.00**	**$130.00**	**$33,800.00**
	Item Code 652424 Total No. of Proj.			**1**		**Total Amount**	**$33,800.00**
655212	JACKED 24" REINFORCED CONCRETE PIPE (CLASS II)	LF	6	1	1,170.00	$400.00	$468,000.00
	Unit Sub Total	**LF**		**1**	**1,170.00**	**$400.00**	**$468,000.00**
	Item Code 655212 Total No. of Proj.			**1**		**Total Amount**	**$468,000.00**
655311	JACKED 18" REINFORCED CONCRETE PIPE (CLASS III)	LF	3	2	237.00	$600.00	$142,200.00
	Unit Sub Total	**LF**		**2**	**237.00**	**$600.00**	**$142,200.00**
	Item Code 655311 Total No. of Proj.			**2**		**Total Amount**	**$142,200.00**
655324	JACKED 36" REINFORCED CONCRETE PIPE (CLASS III)	LF	10	1	190.00	$1,100.00	$209,000.00
	Unit Sub Total	**LF**		**1**	**190.00**	**$1,100.00**	**$209,000.00**
	Item Code 655324 Total No. of Proj.			**1**		**Total Amount**	**$209,000.00**
655367	JACKED 600 MM REINFORCED CONCRETE PIPE (CLASS III)	M	5	1	690.00	$1,300.00	$897,000.00
	Unit Sub Total	**M**		**1**	**690.00**	**$1,300.00**	**$897,000.00**
	Item Code 655367 Total No. of Proj.			**1**		**Total Amount**	**$897,000.00**
655368	JACKED 750 MM REINFORCED CONCRETE PIPE (CLASS III)	M	5	1	290.00	$1,400.00	$406,000.00
	Unit Sub Total	**M**		**1**	**290.00**	**$1,400.00**	**$406,000.00**
	Item Code 655368 Total No. of Proj.			**1**		**Total Amount**	**$406,000.00**
655369	JACKED 900 MM REINFORCED CONCRETE PIPE (CLASS III)	M	5	1	81.00	$1,880.00	$152,280.00
	Unit Sub Total	**M**		**1**	**81.00**	**$1,880.00**	**$152,280.00**
	Item Code 655369 Total No. of Proj.			**1**		**Total Amount**	**$152,280.00**
655370	JACKED 1050 MM REINFORCED CONCRETE PIPE (CLASS III)	M	5	1	150.00	$1,900.00	$285,000.00
	Unit Sub Total	**M**		**1**	**150.00**	**$1,900.00**	**$285,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 655370 Total No. of Proj.			**1**		**Total Amount**	**$285,000.00**
655416	JACKED 24" REINFORCED CONCRETE PIPE (CLASS IV)	LF	10	1	710.00	$350.00	$248,500.00
	Unit Sub Total	**LF**		**1**	**710.00**	**$350.00**	**$248,500.00**
	Item Code 655416 Total No. of Proj.			**1**		**Total Amount**	**$248,500.00**
655516	JACKED 24" REINFORCED CONCRETE PIPE (CLASS V)	LF	4	1	200.00	$1,990.00	$398,000.00
	Unit Sub Total	**LF**		**1**	**200.00**	**$1,990.00**	**$398,000.00**
	Item Code 655516 Total No. of Proj.			**1**		**Total Amount**	**$398,000.00**
655532	JACKED 48" REINFORCED CONCRETE PIPE (CLASS V)	LF	4	1	470.00	$640.00	$300,800.00
	Unit Sub Total	**LF**		**1**	**470.00**	**$640.00**	**$300,800.00**
	Item Code 655532 Total No. of Proj.			**1**		**Total Amount**	**$300,800.00**
655572	JACKED 450 MM REINFORCED CONCRETE PIPE (CLASS V)	M	8	1	71.00	$2,500.00	$177,500.00
	Unit Sub Total	**M**		**1**	**71.00**	**$2,500.00**	**$177,500.00**
	Item Code 655572 Total No. of Proj.			**1**		**Total Amount**	**$177,500.00**
655576	JACKED 900 MM REINFORCED CONCRETE PIPE (CLASS V)	M	8	1	68.00	$3,000.00	$204,000.00
	Unit Sub Total	**M**		**1**	**68.00**	**$3,000.00**	**$204,000.00**
	Item Code 655576 Total No. of Proj.			**1**		**Total Amount**	**$204,000.00**
655581	JACKED 1800 MM REINFORCED CONCRETE PIPE (CLASS V)	M	8	1	200.00	$5,500.00	$1,100,000.00
	Unit Sub Total	**M**		**1**	**200.00**	**$5,500.00**	**$1,100,000.00**
	Item Code 655581 Total No. of Proj.			**1**		**Total Amount**	**$1,100,000.00**
657342	365 MM X 575 MM OVAL SHAPED REINFORCED CONCRETE PIPE (CLASS III)	M	10	1	12.00	$600.00	$7,200.00
	Unit Sub Total	**M**		**1**	**12.00**	**$600.00**	**$7,200.00**
	Item Code 657342 Total No. of Proj.			**1**		**Total Amount**	**$7,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
664009	300 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	M	10	1	240.00	$146.00	$35,040.00
	Unit Sub Total	**M**		**1**	**240.00**	**$146.00**	**$35,040.00**
	Item Code 664009 Total No. of Proj.			**1**		**Total Amount**	**$35,040.00**
664010	300 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	M	5	1	30.00	$170.00	$5,100.00
	Unit Sub Total	**M**		**1**	**30.00**	**$170.00**	**$5,100.00**
	Item Code 664010 Total No. of Proj.			**1**		**Total Amount**	**$5,100.00**
664015	450 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	M	10	1	7.00	$174.00	$1,218.00
		M	11	1	1.00	$300.00	$300.00
	Unit Sub Total	**M**		**2**	**8.00**	**$189.75**	**$1,518.00**
	Item Code 664015 Total No. of Proj.			**2**		**Total Amount**	**$1,518.00**
664028	750 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	M	11	1	3.00	$300.00	$900.00
	Unit Sub Total	**M**		**1**	**3.00**	**$300.00**	**$900.00**
	Item Code 664028 Total No. of Proj.			**1**		**Total Amount**	**$900.00**
664035	900 MM CORRUGATED STEEL PIPE (3.51 MM THICK)	M	11	1	4.40	$840.00	$3,696.00
	Unit Sub Total	**M**		**1**	**4.40**	**$840.00**	**$3,696.00**
	Item Code 664035 Total No. of Proj.			**1**		**Total Amount**	**$3,696.00**
664047	1350 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	M	11	1	4.20	$900.00	$3,780.00
	Unit Sub Total	**M**		**1**	**4.20**	**$900.00**	**$3,780.00**
	Item Code 664047 Total No. of Proj.			**1**		**Total Amount**	**$3,780.00**
664097	600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK)	M	7	1	68.00	$500.00	$34,000.00
	Unit Sub Total	**M**		**1**	**68.00**	**$500.00**	**$34,000.00**
	Item Code 664097 Total No. of Proj.			**1**		**Total Amount**	**$34,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
664105	750 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK)	M	7	1	11.00	$520.00	$5,720.00
	Unit Sub Total	**M**		**1**	**11.00**	**$520.00**	**$5,720.00**
	Item Code 664105 Total No. of Proj.			**1**		**Total Amount**	**$5,720.00**
664110	900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK)	M	7	1	110.00	$508.50	$55,935.00
	Unit Sub Total	**M**		**1**	**110.00**	**$508.50**	**$55,935.00**
	Item Code 664110 Total No. of Proj.			**1**		**Total Amount**	**$55,935.00**
665005	8" CORRUGATED STEEL PIPE (.064" THICK)	LF	2	1	11.00	$100.00	$1,100.00
		LF	3	1	9.00	$150.00	$1,350.00
	Unit Sub Total	**LF**		**2**	**20.00**	**$122.50**	**$2,450.00**
	Item Code 665005 Total No. of Proj.			**2**		**Total Amount**	**$2,450.00**
665006	8" CORRUGATED STEEL PIPE (.079" THICK)	LF	1	1	68.00	$14.00	$952.00
		LF	2	1	15.00	$75.00	$1,125.00
		LF	3	1	43.00	$28.00	$1,204.00
	Unit Sub Total	**LF**		**3**	**126.00**	**$26.04**	**$3,281.00**
	Item Code 665006 Total No. of Proj.			**3**		**Total Amount**	**$3,281.00**
665009	10" CORRUGATED STEEL PIPE (.079" THICK)	LF	3	1	130.00	$30.00	$3,900.00
	Unit Sub Total	**LF**		**1**	**130.00**	**$30.00**	**$3,900.00**
	Item Code 665009 Total No. of Proj.			**1**		**Total Amount**	**$3,900.00**
665010	12" CORRUGATED STEEL PIPE	LF	4	1	19.00	$100.00	$1,900.00
		LF	6	1	44.00	$135.00	$5,940.00
	Unit Sub Total	**LF**		**2**	**63.00**	**$124.44**	**$7,840.00**
	Item Code 665010 Total No. of Proj.			**2**		**Total Amount**	**$7,840.00**
665011	12" CORRUGATED STEEL PIPE (.064" THICK)	LF	10	1	20.00	$20.00	$400.00
	Unit Sub Total	**LF**		**1**	**20.00**	**$20.00**	**$400.00**
	Item Code 665011 Total No. of Proj.			**1**		**Total Amount**	**$400.00**
665012	12" CORRUGATED STEEL PIPE (.079" THICK)	LF	1	2	59.00	$49.31	$2,909.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
665012	12" CORRUGATED STEEL PIPE (.079" THICK)	LF	2	2	159.00	$82.08	$13,050.00
	Unit Sub Total	**LF**		**4**	**218.00**	**$73.21**	**$15,959.00**
	Item Code 665012 Total No. of Proj.			**4**		**Total Amount**	**$15,959.00**
665014	15" CORRUGATED STEEL PIPE (.079" THICK)	LF	8	1	180.00	$39.00	$7,020.00
	Unit Sub Total	**LF**		**1**	**180.00**	**$39.00**	**$7,020.00**
	Item Code 665014 Total No. of Proj.			**1**		**Total Amount**	**$7,020.00**
665016	18" CORRUGATED STEEL PIPE (.064" THICK)	LF	2	1	59.00	$107.00	$6,313.00
		LF	3	1	27.00	$135.00	$3,645.00
		LF	4	3	100.00	$68.60	$6,859.60
		LF	10	1	170.00	$20.00	$3,400.00
		LF	12	1	75.00	$108.00	$8,100.00
	Unit Sub Total	**LF**		**7**	**431.00**	**$65.70**	**$28,317.60**
	Item Code 665016 Total No. of Proj.			**7**		**Total Amount**	**$28,317.60**
665018	18" CORRUGATED STEEL PIPE (.109" THICK)	LF	1	2	499.00	$59.27	$29,578.00
		LF	2	3	1,467.00	$69.83	$102,446.00
		LF	3	1	12.00	$56.15	$673.80
		LF	4	1	260.00	$40.15	$10,439.00
		LF	6	2	69.00	$91.30	$6,300.00
		LF	10	1	10.00	$165.00	$1,650.00
	Unit Sub Total	**LF**		**10**	**2,317.00**	**$65.21**	**$151,086.80**
	Item Code 665018 Total No. of Proj.			**10**		**Total Amount**	**$151,086.80**
665022	24" CORRUGATED STEEL PIPE (.064" THICK)	LF	3	1	6.00	$162.00	$972.00
	Unit Sub Total	**LF**		**1**	**6.00**	**$162.00**	**$972.00**
	Item Code 665022 Total No. of Proj.			**1**		**Total Amount**	**$972.00**
665023	24" CORRUGATED STEEL PIPE (.079" THICK)	LF	1	1	87.00	$250.00	$21,750.00
		LF	2	1	58.00	$90.00	$5,220.00
		LF	8	1	340.00	$78.00	$26,520.00
		LF	12	1	9.00	$425.00	$3,825.00
	Unit Sub Total	**LF**		**4**	**494.00**	**$116.02**	**$57,315.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 665023 Total No. of Proj.			**4**		**Total Amount**	**$57,315.00**
665024	24" CORRUGATED STEEL PIPE (.109" THICK)	LF	1	2	86.00	$193.49	$16,640.00
		LF	2	4	2,894.00	$128.07	$370,630.00
		LF	3	1	25.00	$200.00	$5,000.00
		LF	6	1	50.00	$130.00	$6,500.00
	Unit Sub Total	**LF**		**8**	**3,055.00**	**$130.53**	**$398,770.00**
	Item Code 665024 Total No. of Proj.			**8**		**Total Amount**	**$398,770.00**
665025	24" CORRUGATED STEEL PIPE (.138" THICK)	LF	1	3	570.00	$125.19	$71,360.00
		LF	3	4	179.00	$130.71	$23,397.40
		LF	6	2	930.00	$80.81	$75,150.00
		LF	10	1	10.00	$180.00	$1,800.00
	Unit Sub Total	**LF**		**10**	**1,689.00**	**$101.66**	**$171,707.40**
	Item Code 665025 Total No. of Proj.			**10**		**Total Amount**	**$171,707.40**
665031	30" CORRUGATED STEEL PIPE (.079" THICK)	LF	8	1	41.00	$132.00	$5,412.00
	Unit Sub Total	**LF**		**1**	**41.00**	**$132.00**	**$5,412.00**
	Item Code 665031 Total No. of Proj.			**1**		**Total Amount**	**$5,412.00**
665032	30" CORRUGATED STEEL PIPE (.109" THICK)	LF	2	1	360.00	$140.00	$50,400.00
		LF	6	1	230.00	$140.00	$32,200.00
	Unit Sub Total	**LF**		**2**	**590.00**	**$140.00**	**$82,600.00**
	Item Code 665032 Total No. of Proj.			**2**		**Total Amount**	**$82,600.00**
665033	30" CORRUGATED STEEL PIPE (.138" THICK)	LF	3	3	235.00	$115.53	$27,150.00
	Unit Sub Total	**LF**		**3**	**235.00**	**$115.53**	**$27,150.00**
	Item Code 665033 Total No. of Proj.			**3**		**Total Amount**	**$27,150.00**
665037	36" CORRUGATED STEEL PIPE (.109" THICK)	LF	2	2	1,030.00	$114.47	$117,900.00
		LF	6	1	8.00	$250.00	$2,000.00
	Unit Sub Total	**LF**		**3**	**1,038.00**	**$115.51**	**$119,900.00**
	Item Code 665037 Total No. of Proj.			**3**		**Total Amount**	**$119,900.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
665039	36" CORRUGATED STEEL PIPE (.168" THICK)	LF	1	1	110.00	$412.00	$45,320.00
	Unit Sub Total	**LF**		**1**	**110.00**	**$412.00**	**$45,320.00**
	Item Code 665039 Total No. of Proj.			**1**		**Total Amount**	**$45,320.00**
665042	42" CORRUGATED STEEL PIPE (.109" THICK)	LF	6	1	73.00	$165.00	$12,045.00
	Unit Sub Total	**LF**		**1**	**73.00**	**$165.00**	**$12,045.00**
	Item Code 665042 Total No. of Proj.			**1**		**Total Amount**	**$12,045.00**
665043	42" CORRUGATED STEEL PIPE (.138" THICK)	LF	1	1	29.00	$220.00	$6,380.00
	Unit Sub Total	**LF**		**1**	**29.00**	**$220.00**	**$6,380.00**
	Item Code 665043 Total No. of Proj.			**1**		**Total Amount**	**$6,380.00**
665046	48" CORRUGATED STEEL PIPE (.079" THICK)	LF	12	1	12.00	$1,360.00	$16,320.00
	Unit Sub Total	**LF**		**1**	**12.00**	**$1,360.00**	**$16,320.00**
	Item Code 665046 Total No. of Proj.			**1**		**Total Amount**	**$16,320.00**
665047	48" CORRUGATED STEEL PIPE (.109" THICK)	LF	4	1	4.00	$2,200.00	$8,800.00
	Unit Sub Total	**LF**		**1**	**4.00**	**$2,200.00**	**$8,800.00**
	Item Code 665047 Total No. of Proj.			**1**		**Total Amount**	**$8,800.00**
665048	48" CORRUGATED STEEL PIPE (.138" THICK)	LF	6	1	93.00	$200.00	$18,600.00
	Unit Sub Total	**LF**		**1**	**93.00**	**$200.00**	**$18,600.00**
	Item Code 665048 Total No. of Proj.			**1**		**Total Amount**	**$18,600.00**
665049	48" CORRUGATED STEEL PIPE (.168" THICK)	LF	2	1	16.00	$187.50	$3,000.00
	Unit Sub Total	**LF**		**1**	**16.00**	**$187.50**	**$3,000.00**
	Item Code 665049 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
665056	60" CORRUGATED STEEL PIPE (.138" THICK)	LF	6	1	8.00	$250.00	$2,000.00
	Unit Sub Total	**LF**		**1**	**8.00**	**$250.00**	**$2,000.00**
	Item Code 665056 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**
665111	12" BITUMINOUS COATED CORRUGATED STEEL PIPE (.064" THICK)	LF	4	1	80.00	$25.00	$2,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**1**	**80.00**	**$25.00**	**$2,000.00**
	Item Code 665111 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**
665112	12" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	LF	8	1	550.00	$39.00	$21,450.00
	Unit Sub Total	**LF**		**1**	**550.00**	**$39.00**	**$21,450.00**
	Item Code 665112 Total No. of Proj.			**1**		**Total Amount**	**$21,450.00**
665116	18" BITUMINOUS COATED CORRUGATED STEEL PIPE (.064" THICK)	LF	4	1	38.00	$40.00	$1,520.00
	Unit Sub Total	**LF**		**1**	**38.00**	**$40.00**	**$1,520.00**
	Item Code 665116 Total No. of Proj.			**1**		**Total Amount**	**$1,520.00**
665123	24" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	LF	4	1	77.00	$45.00	$3,465.00
	Unit Sub Total	**LF**		**1**	**77.00**	**$45.00**	**$3,465.00**
	Item Code 665123 Total No. of Proj.			**1**		**Total Amount**	**$3,465.00**
665124	24" BITUMINOUS COATED CORRUGATED STEEL PIPE (.109" THICK)	LF	11	1	440.00	$43.50	$19,140.00
	Unit Sub Total	**LF**		**1**	**440.00**	**$43.50**	**$19,140.00**
	Item Code 665124 Total No. of Proj.			**1**		**Total Amount**	**$19,140.00**
665135	36" BITUMINOUS COATED CORRUGATED STEEL PIPE (.064" THICK)	LF	4	1	4.00	$485.00	$1,940.00
	Unit Sub Total	**LF**		**1**	**4.00**	**$485.00**	**$1,940.00**
	Item Code 665135 Total No. of Proj.			**1**		**Total Amount**	**$1,940.00**
665713	12" SLOTTED CORRUGATED STEEL PIPE (.109" THICK)	LF	2	1	650.00	$57.00	$37,050.00
	Unit Sub Total	**LF**		**1**	**650.00**	**$57.00**	**$37,050.00**
	Item Code 665713 Total No. of Proj.			**1**		**Total Amount**	**$37,050.00**
665716	18" SLOTTED CORRUGATED STEEL PIPE (.064" THICK)	LF	11	1	54.00	$150.00	$8,100.00
	Unit Sub Total	**LF**		**1**	**54.00**	**$150.00**	**$8,100.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 665716 Total No. of Proj.			**1**		**Total Amount**	**$8,100.00**
665717	18" SLOTTED CORRUGATED STEEL PIPE (.079" THICK)	LF	4	1	1,460.00	$100.00	$146,000.00
	Unit Sub Total	**LF**		**1**	**1,460.00**	**$100.00**	**$146,000.00**
	Item Code 665717 Total No. of Proj.			**1**		**Total Amount**	**$146,000.00**
665733	450 MM SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK)	M	7	1	20.00	$300.00	$6,000.00
	Unit Sub Total	**M**		**1**	**20.00**	**$300.00**	**$6,000.00**
	Item Code 665733 Total No. of Proj.			**1**		**Total Amount**	**$6,000.00**
665828	18" BITUMINOUS COATED SLOTTED CORRUGATED STEEL PIPE (.168" THICK)	LF	11	1	30.00	$300.00	$9,000.00
	Unit Sub Total	**LF**		**1**	**30.00**	**$300.00**	**$9,000.00**
	Item Code 665828 Total No. of Proj.			**1**		**Total Amount**	**$9,000.00**
667001	17" X 13" CORRUGATED STEEL PIPE ARCH (.079" THICK)	LF	2	1	200.00	$51.00	$10,200.00
	Unit Sub Total	**LF**		**1**	**200.00**	**$51.00**	**$10,200.00**
	Item Code 667001 Total No. of Proj.			**1**		**Total Amount**	**$10,200.00**
667006	21" X 15" CORRUGATED STEEL PIPE ARCH (.109" THICK)	LF	3	1	260.00	$90.00	$23,400.00
	Unit Sub Total	**LF**		**1**	**260.00**	**$90.00**	**$23,400.00**
	Item Code 667006 Total No. of Proj.			**1**		**Total Amount**	**$23,400.00**
667024	42" X 29" CORRUGATED STEEL PIPE ARCH (.109" THICK)	LF	11	1	42.00	$150.00	$6,300.00
	Unit Sub Total	**LF**		**1**	**42.00**	**$150.00**	**$6,300.00**
	Item Code 667024 Total No. of Proj.			**1**		**Total Amount**	**$6,300.00**
667035	57" X 38" CORRUGATED STEEL PIPE ARCH (.138" THICK)	LF	3	1	83.00	$200.00	$16,600.00
	Unit Sub Total	**LF**		**1**	**83.00**	**$200.00**	**$16,600.00**
	Item Code 667035 Total No. of Proj.			**1**		**Total Amount**	**$16,600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
680207	3" PLASTIC PIPE	LF	1	1	9.00	$100.00	$900.00
		LF	3	1	90.00	$10.00	$900.00
		LF	12	1	240.00	$25.00	$6,000.00
	Unit Sub Total	**LF**		**3**	**339.00**	**$23.01**	**$7,800.00**
	Item Code 680207 Total No. of Proj.			**3**		**Total Amount**	**$7,800.00**
680240	3" PLASTIC PIPE (OUTLET)	LF	10	1	670.00	$25.00	$16,750.00
	Unit Sub Total	**LF**		**1**	**670.00**	**$25.00**	**$16,750.00**
	Item Code 680240 Total No. of Proj.			**1**		**Total Amount**	**$16,750.00**
680254	CLEANOUT ASSEMBLY	EA	8	1	4.00	$500.00	$2,000.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$500.00**	**$2,000.00**
	Item Code 680254 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**
680405	8" PERFORATED STEEL PIPE UNDERDRAIN (.064" THICK)	LF	4	1	48.00	$18.00	$864.00
	Unit Sub Total	**LF**		**1**	**48.00**	**$18.00**	**$864.00**
	Item Code 680405 Total No. of Proj.			**1**		**Total Amount**	**$864.00**
680406	8" PERFORATED STEEL PIPE UNDERDRAIN (.079" THICK)	LF	3	1	1.00	$300.00	$300.00
	Unit Sub Total	**LF**		**1**	**1.00**	**$300.00**	**$300.00**
	Item Code 680406 Total No. of Proj.			**1**		**Total Amount**	**$300.00**
680902	6" PERFORATED PLASTIC PIPE UNDERDRAIN	LF	2	1	210.00	$6.00	$1,260.00
		LF	4	6	4,245.00	$19.82	$84,120.00
		LF	10	1	24,900.00	$15.00	$373,500.00
	Unit Sub Total	**LF**		**8**	**29,355.00**	**$15.63**	**$458,880.00**
	Item Code 680902 Total No. of Proj.			**8**		**Total Amount**	**$458,880.00**
680903	6" NON-PERFORATED PLASTIC PIPE UNDERDRAIN	LF	7	1	50.00	$60.00	$3,000.00
	Unit Sub Total	**LF**		**1**	**50.00**	**$60.00**	**$3,000.00**
	Item Code 680903 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
680905	8" PERFORATED PLASTIC PIPE UNDERDRAIN	LF	1	3	1,370.00	$58.33	$79,910.00
		LF	2	2	3,830.00	$35.24	$134,960.00
		LF	3	1	470.00	$40.00	$18,800.00
		LF	4	3	5,040.00	$17.58	$88,610.00
		LF	11	1	16,500.00	$12.50	$206,250.00
	Unit Sub Total	**LF**		**10**	**27,210.00**	**$19.42**	**$528,530.00**
	Item Code 680905 Total No. of Proj.			**10**		**Total Amount**	**$528,530.00**
680931	150 MM PERFORATED PLASTIC PIPE UNDERDRAIN	M	4	1	51.00	$60.00	$3,060.00
	Unit Sub Total	**M**		**1**	**51.00**	**$60.00**	**$3,060.00**
	Item Code 680931 Total No. of Proj.			**1**		**Total Amount**	**$3,060.00**
681023	6" PLASTIC PIPE	LF	3	1	8.00	$68.00	$544.00
		LF	4	1	370.00	$17.00	$6,290.00
		LF	10	1	2,440.00	$25.00	$61,000.00
	Unit Sub Total	**LF**		**3**	**2,818.00**	**$24.07**	**$67,834.00**
	Item Code 681023 Total No. of Proj.			**3**		**Total Amount**	**$67,834.00**
681103	3" PLASTIC PIPE (EDGE DRAIN)	LF	2	2	50,220.00	$15.04	$755,100.00
		LF	4	2	10,770.00	$5.12	$55,100.00
		LF	8	1	17,700.00	$31.00	$548,700.00
		LF	11	1	380.00	$16.00	$6,080.00
	Unit Sub Total	**LF**		**6**	**79,070.00**	**$17.26**	**$1,364,980.00**
	Item Code 681103 Total No. of Proj.			**6**		**Total Amount**	**$1,364,980.00**
681107	3" PLASTIC PIPE (EDGE DRAIN OUTLET)	LF	2	1	12,200.00	$17.00	$207,400.00
		LF	4	2	335.00	$35.88	$12,020.00
		LF	8	1	1,700.00	$9.00	$15,300.00
		LF	11	1	64.00	$25.00	$1,600.00
	Unit Sub Total	**LF**		**5**	**14,299.00**	**$16.53**	**$236,320.00**
	Item Code 681107 Total No. of Proj.			**5**		**Total Amount**	**$236,320.00**
681108	6" PLASTIC PIPE (EDGE DRAIN)	LF	2	1	2,220.00	$72.00	$159,840.00
	Unit Sub Total	**LF**		**1**	**2,220.00**	**$72.00**	**$159,840.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 681108 Total No. of Proj.			**1**		**Total Amount**	**$159,840.00**
681113	6" PLASTIC PIPE (EDGE DRAIN OUTLET)	LF	2	1	150.00	$100.00	$15,000.00
	Unit Sub Total	**LF**		**1**	**150.00**	**$100.00**	**$15,000.00**
	Item Code 681113 Total No. of Proj.			**1**		**Total Amount**	**$15,000.00**
681132	GEOCOMPOSITE DRAIN	M2	8	1	56.00	$10.00	$560.00
	Unit Sub Total	**M2**		**1**	**56.00**	**$10.00**	**$560.00**
681132	GEOCOMPOSITE DRAIN	SQFT	4	1	320.00	$3.50	$1,120.00
	Unit Sub Total	**SQFT**		**1**	**320.00**	**$3.50**	**$1,120.00**
	Item Code 681132 Total No. of Proj.			**2**		**Total Amount**	**$1,680.00**
681501	FURNISH AND INSTALL DRAIN PIPE (HORIZONTAL DRAIN)	LF	4	1	170.00	$18.00	$3,060.00
	Unit Sub Total	**LF**		**1**	**170.00**	**$18.00**	**$3,060.00**
	Item Code 681501 Total No. of Proj.			**1**		**Total Amount**	**$3,060.00**
681990	FILTER FABRIC	SQYD	7	1	1,190.00	$6.00	$7,140.00
	Unit Sub Total	**SQYD**		**1**	**1,190.00**	**$6.00**	**$7,140.00**
	Item Code 681990 Total No. of Proj.			**1**		**Total Amount**	**$7,140.00**
682001	PERMEABLE MATERIAL	CY	1	1	15.00	$180.00	$2,700.00
		CY	2	1	650.00	$35.00	$22,750.00
		CY	3	1	1.60	$500.00	$800.00
	Unit Sub Total	**CY**		**3**	**666.60**	**$39.38**	**$26,250.00**
	Item Code 682001 Total No. of Proj.			**3**		**Total Amount**	**$26,250.00**
682003	PERMEABLE MATERIAL (STABILIZATION TRENCH)	CY	1	1	240.00	$65.50	$15,720.00
	Unit Sub Total	**CY**		**1**	**240.00**	**$65.50**	**$15,720.00**
	Item Code 682003 Total No. of Proj.			**1**		**Total Amount**	**$15,720.00**
682007	IMPERMEABLE MEMBRANE	SQYD	8	1	35,350.00	$11.60	$410,060.00
	Unit Sub Total	**SQYD**		**1**	**35,350.00**	**$11.60**	**$410,060.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 682007 Total No. of Proj.			**1**		**Total Amount**	**$410,060.00**
682008	PERMEABLE MATERIAL (BLANKET)	CY	1	1	2,380.00	$70.00	$166,600.00
		CY	4	3	2,740.00	$65.74	$180,122.00
	Unit Sub Total	**CY**		**4**	**5,120.00**	**$67.72**	**$346,722.00**
	Item Code 682008 Total No. of Proj.			**4**		**Total Amount**	**$346,722.00**
682020	CLASS 1 PERMEABLE MATERIAL	CY	4	3	152.00	$108.55	$16,500.00
		CY	6	1	2.00	$1,000.00	$2,000.00
	Unit Sub Total	**CY**		**4**	**154.00**	**$120.13**	**$18,500.00**
	Item Code 682020 Total No. of Proj.			**4**		**Total Amount**	**$18,500.00**
682022	CLASS 1 PERMEABLE MATERIAL (BLANKET)	CY	2	1	1,160.00	$85.00	$98,600.00
	Unit Sub Total	**CY**		**1**	**1,160.00**	**$85.00**	**$98,600.00**
	Item Code 682022 Total No. of Proj.			**1**		**Total Amount**	**$98,600.00**
682045	CLASS 3 PERMEABLE MATERIAL	CY	4	1	10.00	$175.00	$1,750.00
	Unit Sub Total	**CY**		**1**	**10.00**	**$175.00**	**$1,750.00**
	Item Code 682045 Total No. of Proj.			**1**		**Total Amount**	**$1,750.00**
682049	CLASS 3 PERMEABLE MATERIAL (BLANKET)	CY	4	1	170.00	$48.00	$8,160.00
	Unit Sub Total	**CY**		**1**	**170.00**	**$48.00**	**$8,160.00**
	Item Code 682049 Total No. of Proj.			**1**		**Total Amount**	**$8,160.00**
685020	8" ALTERNATIVE PIPE UNDERDRAIN	LF	4	1	2,430.00	$35.00	$85,050.00
	Unit Sub Total	**LF**		**1**	**2,430.00**	**$35.00**	**$85,050.00**
	Item Code 685020 Total No. of Proj.			**1**		**Total Amount**	**$85,050.00**
690104	8" CORRUGATED STEEL PIPE DOWNDRAIN	LF	1	3	81.00	$43.90	$3,556.00
	Unit Sub Total	**LF**		**3**	**81.00**	**$43.90**	**$3,556.00**
	Item Code 690104 Total No. of Proj.			**3**		**Total Amount**	**$3,556.00**
690105	8" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	LF	2	1	10.00	$45.00	$450.00
		LF	4	1	53.00	$17.00	$901.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
690105	8" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	LF	12	1	164.00	$50.00	$8,200.00
	Unit Sub Total	**LF**		**3**	**227.00**	**$42.07**	**$9,551.00**
	Item Code 690105 Total No. of Proj.			**3**		**Total Amount**	**$9,551.00**
690106	8" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	3	1	37.00	$60.00	$2,220.00
	Unit Sub Total	**LF**		**1**	**37.00**	**$60.00**	**$2,220.00**
	Item Code 690106 Total No. of Proj.			**1**		**Total Amount**	**$2,220.00**
690110	12" CORRUGATED STEEL PIPE DOWNDRAIN	LF	3	1	280.00	$35.00	$9,800.00
		LF	6	2	187.00	$61.18	$11,440.00
	Unit Sub Total	**LF**		**3**	**467.00**	**$45.48**	**$21,240.00**
	Item Code 690110 Total No. of Proj.			**3**		**Total Amount**	**$21,240.00**
690112	12" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	1	1	28.00	$92.00	$2,576.00
		LF	3	1	28.00	$60.00	$1,680.00
		LF	4	1	1,740.00	$100.00	$174,000.00
		LF	8	3	1,066.00	$96.63	$103,010.00
	Unit Sub Total	**LF**		**6**	**2,862.00**	**$98.28**	**$281,266.00**
	Item Code 690112 Total No. of Proj.			**6**		**Total Amount**	**$281,266.00**
690114	15" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	8	1	230.00	$65.00	$14,950.00
	Unit Sub Total	**LF**		**1**	**230.00**	**$65.00**	**$14,950.00**
	Item Code 690114 Total No. of Proj.			**1**		**Total Amount**	**$14,950.00**
690116	18" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	LF	5	1	130.00	$65.00	$8,450.00
	Unit Sub Total	**LF**		**1**	**130.00**	**$65.00**	**$8,450.00**
	Item Code 690116 Total No. of Proj.			**1**		**Total Amount**	**$8,450.00**
690117	18" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	4	1	540.00	$107.00	$57,780.00
		LF	6	1	64.00	$77.44	$4,956.16

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**2**	**604.00**	**$103.87**	**$62,736.16**
	Item Code 690117 Total No. of Proj.			**2**		**Total Amount**	**$62,736.16**
690118	18" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	1	1	20.00	$54.00	$1,080.00
	Unit Sub Total	**LF**		**1**	**20.00**	**$54.00**	**$1,080.00**
	Item Code 690118 Total No. of Proj.			**1**		**Total Amount**	**$1,080.00**
690123	24" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	1	1	18.00	$85.00	$1,530.00
	Unit Sub Total	**LF**		**1**	**18.00**	**$85.00**	**$1,530.00**
	Item Code 690123 Total No. of Proj.			**1**		**Total Amount**	**$1,530.00**
690124	24" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	2	2	156.00	$42.12	$6,570.00
		LF	4	1	330.00	$123.00	$40,590.00
	Unit Sub Total	**LF**		**3**	**486.00**	**$97.04**	**$47,160.00**
	Item Code 690124 Total No. of Proj.			**3**		**Total Amount**	**$47,160.00**
690125	24" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	LF	1	1	90.00	$98.00	$8,820.00
		LF	3	1	710.00	$116.50	$82,715.00
	Unit Sub Total	**LF**		**2**	**800.00**	**$114.42**	**$91,535.00**
	Item Code 690125 Total No. of Proj.			**2**		**Total Amount**	**$91,535.00**
690131	30" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	2	1	84.00	$31.00	$2,604.00
	Unit Sub Total	**LF**		**1**	**84.00**	**$31.00**	**$2,604.00**
	Item Code 690131 Total No. of Proj.			**1**		**Total Amount**	**$2,604.00**
690132	30" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	4	1	110.00	$130.00	$14,300.00
	Unit Sub Total	**LF**		**1**	**110.00**	**$130.00**	**$14,300.00**
	Item Code 690132 Total No. of Proj.			**1**		**Total Amount**	**$14,300.00**
690137	36" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	1	1	80.00	$75.00	$6,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
690137	36" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	4	1	220.00	$137.00	$30,140.00
	Unit Sub Total	**LF**		**2**	**300.00**	**$120.47**	**$36,140.00**
	Item Code 690137 Total No. of Proj.			**2**		**Total Amount**	**$36,140.00**
690142	42" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	1	1	40.00	$150.00	$6,000.00
	Unit Sub Total	**LF**		**1**	**40.00**	**$150.00**	**$6,000.00**
	Item Code 690142 Total No. of Proj.			**1**		**Total Amount**	**$6,000.00**
690155	200 MM CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK)	M	11	1	40.00	$96.00	$3,840.00
	Unit Sub Total	**M**		**1**	**40.00**	**$96.00**	**$3,840.00**
	Item Code 690155 Total No. of Proj.			**1**		**Total Amount**	**$3,840.00**
690160	300 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	M	5	1	170.00	$180.00	$30,600.00
	Unit Sub Total	**M**		**1**	**170.00**	**$180.00**	**$30,600.00**
	Item Code 690160 Total No. of Proj.			**1**		**Total Amount**	**$30,600.00**
690171	600 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK)	M	5	1	740.00	$280.00	$207,200.00
	Unit Sub Total	**M**		**1**	**740.00**	**$280.00**	**$207,200.00**
	Item Code 690171 Total No. of Proj.			**1**		**Total Amount**	**$207,200.00**
690217	18" BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	8	1	36.00	$52.00	$1,872.00
	Unit Sub Total	**LF**		**1**	**36.00**	**$52.00**	**$1,872.00**
	Item Code 690217 Total No. of Proj.			**1**		**Total Amount**	**$1,872.00**
690964	18" PLASTIC PIPE DOWNDRAIN	LF	3	1	480.00	$75.00	$36,000.00
	Unit Sub Total	**LF**		**1**	**480.00**	**$75.00**	**$36,000.00**
	Item Code 690964 Total No. of Proj.			**1**		**Total Amount**	**$36,000.00**
691001	CORRUGATED STEEL FLUME DOWNDRAIN	LF	6	1	2,280.00	$50.00	$114,000.00
	Unit Sub Total	**LF**		**1**	**2,280.00**	**$50.00**	**$114,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 691001 Total No. of Proj.			**1**		**Total Amount**	**$114,000.00**
691003	8" CORRUGATED STEEL FLUME DOWNDRAIN	LF	2	1	37.00	$15.00	$555.00
	Unit Sub Total	**LF**		**1**	**37.00**	**$15.00**	**$555.00**
	Item Code 691003 Total No. of Proj.			**1**		**Total Amount**	**$555.00**
691900	FLUME DOWNDRAIN	LF	5	1	10.00	$100.00	$1,000.00
	Unit Sub Total	**LF**		**1**	**10.00**	**$100.00**	**$1,000.00**
	Item Code 691900 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
692001	ENTRANCE TAPER	EA	1	1	1.00	$1,250.00	$1,250.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,250.00**	**$1,250.00**
	Item Code 692001 Total No. of Proj.			**1**		**Total Amount**	**$1,250.00**
692003	8" ENTRANCE TAPER	EA	1	2	2.00	$423.50	$847.00
		EA	2	1	1.00	$80.00	$80.00
		EA	3	1	3.00	$240.00	$720.00
	Unit Sub Total	**EA**		**4**	**6.00**	**$274.50**	**$1,647.00**
	Item Code 692003 Total No. of Proj.			**4**		**Total Amount**	**$1,647.00**
692005	12" ENTRANCE TAPER	EA	1	1	1.00	$1,200.00	$1,200.00
		EA	3	1	2.00	$800.00	$1,600.00
		EA	6	2	11.00	$390.91	$4,300.00
		EA	8	1	14.00	$350.00	$4,900.00
	Unit Sub Total	**EA**		**5**	**28.00**	**$428.57**	**$12,000.00**
	Item Code 692005 Total No. of Proj.			**5**		**Total Amount**	**$12,000.00**
692006	15" ENTRANCE TAPER	EA	8	2	7.00	$522.86	$3,660.00
	Unit Sub Total	**EA**		**2**	**7.00**	**$522.86**	**$3,660.00**
	Item Code 692006 Total No. of Proj.			**2**		**Total Amount**	**$3,660.00**
692007	18" ENTRANCE TAPER	EA	3	1	9.00	$800.00	$7,200.00
		EA	6	1	3.00	$1,166.00	$3,498.00
	Unit Sub Total	**EA**		**2**	**12.00**	**$891.50**	**$10,698.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 692007 Total No. of Proj.			**2**		**Total Amount**	**$10,698.00**
692037	18" BITUMINOUS COATED ENTRANCE TAPER	EA	8	1	1.00	$550.00	$550.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$550.00**	**$550.00**
	Item Code 692037 Total No. of Proj.			**1**		**Total Amount**	**$550.00**
692088	300 MM ENTRANCE TAPER	EA	5	1	15.00	$250.00	$3,750.00
	Unit Sub Total	**EA**		**1**	**15.00**	**$250.00**	**$3,750.00**
	Item Code 692088 Total No. of Proj.			**1**		**Total Amount**	**$3,750.00**
692101	TAPERED INLET	EA	5	1	1.00	$500.00	$500.00
		EA	6	1	78.00	$350.00	$27,300.00
	Unit Sub Total	**EA**		**2**	**79.00**	**$351.90**	**$27,800.00**
	Item Code 692101 Total No. of Proj.			**2**		**Total Amount**	**$27,800.00**
692107	18" TAPERED INLET	EA	2	2	11.00	$510.00	$5,610.00
	Unit Sub Total	**EA**		**2**	**11.00**	**$510.00**	**$5,610.00**
	Item Code 692107 Total No. of Proj.			**2**		**Total Amount**	**$5,610.00**
692203	8" DOWNDRAIN SLIP JOINT	EA	3	1	3.00	$135.00	$405.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$135.00**	**$405.00**
	Item Code 692203 Total No. of Proj.			**1**		**Total Amount**	**$405.00**
692205	12" DOWNDRAIN SLIP JOINT	EA	6	1	7.00	$300.00	$2,100.00
	Unit Sub Total	**EA**		**1**	**7.00**	**$300.00**	**$2,100.00**
	Item Code 692205 Total No. of Proj.			**1**		**Total Amount**	**$2,100.00**
692209	24" DOWNDRAIN SLIP JOINT	EA	1	1	1.00	$800.00	$800.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$800.00**	**$800.00**
	Item Code 692209 Total No. of Proj.			**1**		**Total Amount**	**$800.00**
692211	30" DOWNDRAIN SLIP JOINT	EA	2	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,000.00**	**$1,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 692211 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
692301	ANCHOR ASSEMBLY	EA	1	2	39.00	$377.69	$14,730.00
		EA	2	1	11.00	$369.00	$4,059.00
		EA	3	1	28.00	$450.00	$12,600.00
		EA	4	1	175.00	$500.00	$87,500.00
		EA	6	1	3.00	$768.90	$2,306.70
	Unit Sub Total	**EA**		**6**	**256.00**	**$473.42**	**$121,195.70**
	Item Code 692301 Total No. of Proj.			**6**		**Total Amount**	**$121,195.70**
692303	8" ANCHOR ASSEMBLY	EA	1	2	6.00	$178.33	$1,070.00
		EA	2	1	2.00	$20.00	$40.00
		EA	3	1	4.00	$360.00	$1,440.00
	Unit Sub Total	**EA**		**4**	**12.00**	**$212.50**	**$2,550.00**
	Item Code 692303 Total No. of Proj.			**4**		**Total Amount**	**$2,550.00**
692305	12" ANCHOR ASSEMBLY	EA	2	1	3.00	$1,000.00	$3,000.00
		EA	4	2	8.00	$260.00	$2,080.00
		EA	10	1	28.00	$1,000.00	$28,000.00
	Unit Sub Total	**EA**		**4**	**39.00**	**$848.21**	**$33,080.00**
	Item Code 692305 Total No. of Proj.			**4**		**Total Amount**	**$33,080.00**
692307	18" ANCHOR ASSEMBLY	EA	1	1	2.00	$187.00	$374.00
		EA	2	1	6.00	$350.00	$2,100.00
		EA	3	1	72.00	$450.00	$32,400.00
		EA	4	1	2.00	$160.10	$320.20
	Unit Sub Total	**EA**		**4**	**82.00**	**$429.20**	**$35,194.20**
	Item Code 692307 Total No. of Proj.			**4**		**Total Amount**	**$35,194.20**
692309	24" ANCHOR ASSEMBLY	EA	2	2	5.00	$260.00	$1,300.00
		EA	3	1	29.00	$528.00	$15,312.00
	Unit Sub Total	**EA**		**3**	**34.00**	**$488.59**	**$16,612.00**
	Item Code 692309 Total No. of Proj.			**3**		**Total Amount**	**$16,612.00**
692313	36" ANCHOR ASSEMBLY	EA	2	1	2.00	$400.00	$800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**2.00**	**$400.00**	**$800.00**
	Item Code 692313	**Total No. of Proj.**			**1**		**Total Amount**	**$800.00**
692361	FLUME ANCHOR ASSEMBLY		EA	2	1	4.00	$275.00	$1,100.00
		Unit Sub Total	**EA**		**1**	**4.00**	**$275.00**	**$1,100.00**
	Item Code 692361	**Total No. of Proj.**			**1**		**Total Amount**	**$1,100.00**
692409	CABLE ANCHORAGE SYSTEM		EA	1	1	1.00	$12,000.00	$12,000.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$12,000.00**	**$12,000.00**
692409	CABLE ANCHORAGE SYSTEM		LF	3	1	210.00	$160.00	$33,600.00
		Unit Sub Total	**LF**		**1**	**210.00**	**$160.00**	**$33,600.00**
	Item Code 692409	**Total No. of Proj.**			**2**		**Total Amount**	**$45,600.00**
698060	12" ALTERNATIVE PIPE DOWNDRAIN		LF	10	1	3,200.00	$30.00	$96,000.00
		Unit Sub Total	**LF**		**1**	**3,200.00**	**$30.00**	**$96,000.00**
	Item Code 698060	**Total No. of Proj.**			**1**		**Total Amount**	**$96,000.00**
698100	18" ALTERNATIVE PIPE DOWNDRAIN		LF	2	1	41.00	$100.00	$4,100.00
			LF	3	1	36.00	$74.00	$2,664.00
			LF	10	2	1,030.00	$52.77	$54,350.00
		Unit Sub Total	**LF**		**4**	**1,107.00**	**$55.21**	**$61,114.00**
	Item Code 698100	**Total No. of Proj.**			**4**		**Total Amount**	**$61,114.00**
698140	24" ALTERNATIVE PIPE DOWNDRAIN		LF	1	1	210.00	$130.00	$27,300.00
			LF	11	2	134.00	$84.93	$11,380.00
		Unit Sub Total	**LF**		**3**	**344.00**	**$112.44**	**$38,680.00**
	Item Code 698140	**Total No. of Proj.**			**3**		**Total Amount**	**$38,680.00**
698162	450 MM ALTERNATIVE PIPE DOWNDRAIN		M	11	1	110.00	$250.00	$27,500.00
		Unit Sub Total	**M**		**1**	**110.00**	**$250.00**	**$27,500.00**
	Item Code 698162	**Total No. of Proj.**			**1**		**Total Amount**	**$27,500.00**
698169	600 MM ALTERNATIVE PIPE DOWNDRAIN		M	11	1	40.00	$100.00	$4,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**1**	**40.00**	**$100.00**	**$4,000.00**
	Item Code 698169 Total No. of Proj.			**1**		**Total Amount**	**$4,000.00**
700617	DRAINAGE INLET MARKER	EA	1	1	10.00	$15.00	$150.00
		EA	3	1	130.00	$55.00	$7,150.00
		EA	4	4	58.00	$46.64	$2,705.00
		EA	5	2	28.00	$58.68	$1,643.00
		EA	6	2	57.00	$83.51	$4,760.00
		EA	7	1	25.00	$100.00	$2,500.00
		EA	8	1	1.00	$100.00	$100.00
		EA	9	1	2.00	$350.00	$700.00
		EA	10	2	34.00	$45.29	$1,540.00
		EA	11	3	27.00	$90.74	$2,450.00
	Unit Sub Total	**EA**		**18**	**372.00**	**$63.70**	**$23,698.00**
	Item Code 700617 Total No. of Proj.			**18**		**Total Amount**	**$23,698.00**
700619	INSTALL DRAINAGE INLET MARKER	EA	4	1	3.00	$70.00	$210.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$70.00**	**$210.00**
	Item Code 700619 Total No. of Proj.			**1**		**Total Amount**	**$210.00**
700638	36" CORRUGATED STEEL PIPE INLET (.079" THICK)	LF	1	1	11.00	$350.00	$3,850.00
		LF	2	1	43.00	$300.00	$12,900.00
	Unit Sub Total	**LF**		**2**	**54.00**	**$310.19**	**$16,750.00**
	Item Code 700638 Total No. of Proj.			**2**		**Total Amount**	**$16,750.00**
700639	36" CORRUGATED STEEL PIPE INLET (.109" THICK)	LF	2	1	12.00	$328.50	$3,942.00
		LF	6	1	140.00	$200.00	$28,000.00
	Unit Sub Total	**LF**		**2**	**152.00**	**$210.14**	**$31,942.00**
	Item Code 700639 Total No. of Proj.			**2**		**Total Amount**	**$31,942.00**
700640	36" CORRUGATED STEEL PIPE INLET (.138" THICK)	LF	1	1	5.00	$620.00	$3,100.00
		LF	3	2	31.00	$746.77	$23,150.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**3**	**36.00**	**$729.17**	**$26,250.00**
	Item Code 700640 Total No. of Proj.			**3**		**Total Amount**	**$26,250.00**
700641	36" CORRUGATED STEEL PIPE INLET (.168" THICK)	LF	1	1	60.00	$260.00	$15,600.00
	Unit Sub Total	**LF**		**1**	**60.00**	**$260.00**	**$15,600.00**
	Item Code 700641 Total No. of Proj.			**1**		**Total Amount**	**$15,600.00**
700656	48" CORRUGATED STEEL PIPE INLET (.138" THICK)	LF	2	1	10.00	$541.00	$5,410.00
	Unit Sub Total	**LF**		**1**	**10.00**	**$541.00**	**$5,410.00**
	Item Code 700656 Total No. of Proj.			**1**		**Total Amount**	**$5,410.00**
700659	900 MM CORRUGATED STEEL PIPE INLET (2.77 MM THICK)	M	4	1	2.00	$1,500.00	$3,000.00
		M	5	1	73.00	$800.00	$58,400.00
	Unit Sub Total	**M**		**2**	**75.00**	**$818.67**	**$61,400.00**
	Item Code 700659 Total No. of Proj.			**2**		**Total Amount**	**$61,400.00**
702123	24" TO 18" CORRUGATED STEEL ECCENTRIC REDUCER (.079" THICK)	EA	4	1	1.00	$4,200.00	$4,200.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$4,200.00**	**$4,200.00**
	Item Code 702123 Total No. of Proj.			**1**		**Total Amount**	**$4,200.00**
702634	36" CORRUGATED STEEL PIPE ENERGY DISSIPATOR	EA	1	1	1.00	$2,000.00	$2,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$2,000.00**	**$2,000.00**
	Item Code 702634 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**
703210	12" CORRUGATED STEEL PIPE RISER (.064" THICK)	LF	12	1	2.00	$55.00	$110.00
	Unit Sub Total	**LF**		**1**	**2.00**	**$55.00**	**$110.00**
	Item Code 703210 Total No. of Proj.			**1**		**Total Amount**	**$110.00**
703211	12" CORRUGATED STEEL PIPE RISER (.079" THICK)	LF	12	1	3.00	$150.00	$450.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**1**	**3.00**	**$150.00**	**$450.00**
	Item Code 703211 Total No. of Proj.			**1**		**Total Amount**	**$450.00**
703220	18" CORRUGATED STEEL PIPE RISER (.168" THICK)	LF	7	1	4.40	$800.00	$3,520.00
	Unit Sub Total	**LF**		**1**	**4.40**	**$800.00**	**$3,520.00**
	Item Code 703220 Total No. of Proj.			**1**		**Total Amount**	**$3,520.00**
703233	GRATED LINE DRAIN	LF	2	1	56.00	$100.00	$5,600.00
		LF	4	3	4,130.00	$82.77	$341,852.00
		LF	7	1	1,660.00	$75.00	$124,500.00
		LF	9	1	110.00	$100.00	$11,000.00
		LF	11	1	110.00	$115.00	$12,650.00
		LF	12	3	1,310.00	$73.63	$96,460.00
	Unit Sub Total	**LF**		**10**	**7,376.00**	**$80.27**	**$592,062.00**
703233	GRATED LINE DRAIN	M	7	2	151.00	$450.07	$67,960.00
		M	8	1	31.00	$250.00	$7,750.00
		M	11	2	163.00	$306.44	$49,950.00
	Unit Sub Total	**M**		**5**	**345.00**	**$364.23**	**$125,660.00**
	Item Code 703233 Total No. of Proj.			**15**		**Total Amount**	**$717,722.00**
703237	36" CORRUGATED STEEL PIPE RISER (.064" THICK)	LF	4	1	6.00	$538.35	$3,230.10
	Unit Sub Total	**LF**		**1**	**6.00**	**$538.35**	**$3,230.10**
	Item Code 703237 Total No. of Proj.			**1**		**Total Amount**	**$3,230.10**
703288	1200 MM CORRUGATED STEEL PIPE RISER (2.77 MM THICK)	M	5	1	16.00	$1,500.00	$24,000.00
	Unit Sub Total	**M**		**1**	**16.00**	**$1,500.00**	**$24,000.00**
	Item Code 703288 Total No. of Proj.			**1**		**Total Amount**	**$24,000.00**
703311	12" BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (.079" THICK)	LF	12	1	2.00	$165.00	$330.00
	Unit Sub Total	**LF**		**1**	**2.00**	**$165.00**	**$330.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 703311 Total No. of Proj.			**1**		**Total Amount**	**$330.00**
703317	18" BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (.079" THICK)	LF	7	1	13.00	$120.00	$1,560.00
	Unit Sub Total	**LF**		**1**	**13.00**	**$120.00**	**$1,560.00**
	Item Code 703317 Total No. of Proj.			**1**		**Total Amount**	**$1,560.00**
703340	36" BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (.138" THICK)	EA	8	1	1.00	$750.00	$750.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$750.00**	**$750.00**
	Item Code 703340 Total No. of Proj.			**1**		**Total Amount**	**$750.00**
703450	WELDED STEEL PIPE CASING (BRIDGE)	LF	2	1	77.00	$150.00	$11,550.00
		LF	8	1	86.00	$160.00	$13,760.00
		LF	12	1	152.00	$310.00	$47,120.00
	Unit Sub Total	**LF**		**3**	**315.00**	**$229.94**	**$72,430.00**
703450	WELDED STEEL PIPE CASING (BRIDGE)	M	5	1	96.00	$150.00	$14,400.00
		M	11	1	71.00	$400.00	$28,400.00
	Unit Sub Total	**M**		**2**	**167.00**	**$256.29**	**$42,800.00**
	Item Code 703450 Total No. of Proj.			**5**		**Total Amount**	**$115,230.00**
703460	24" WELDED STEEL PIPE CASING (BRIDGE)	LF	1	1	81.00	$300.00	$24,300.00
		LF	4	1	83.00	$160.00	$13,280.00
		LF	6	1	158.00	$150.00	$23,700.00
	Unit Sub Total	**LF**		**3**	**322.00**	**$190.31**	**$61,280.00**
	Item Code 703460 Total No. of Proj.			**3**		**Total Amount**	**$61,280.00**
703481	600 MM WELDED STEEL PIPE CASING (BRIDGE)	M	8	1	46.00	$620.00	$28,520.00
	Unit Sub Total	**M**		**1**	**46.00**	**$620.00**	**$28,520.00**
	Item Code 703481 Total No. of Proj.			**1**		**Total Amount**	**$28,520.00**
703508	6" WELDED STEEL PIPE (.105" THICK)	LF	4	1	140.00	$205.00	$28,700.00
	Unit Sub Total	**LF**		**1**	**140.00**	**$205.00**	**$28,700.00**
	Item Code 703508 Total No. of Proj.			**1**		**Total Amount**	**$28,700.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
703533	12" WELDED STEEL PIPE (.250" THICK)	LF	4	1	130.00	$120.00	$15,600.00
	Unit Sub Total	**LF**		**1**	**130.00**	**$120.00**	**$15,600.00**
	Item Code 703533 Total No. of Proj.			**1**		**Total Amount**	**$15,600.00**
703555	18" WELDED STEEL PIPE (.250" THICK)	LF	6	1	250.00	$150.00	$37,500.00
	Unit Sub Total	**LF**		**1**	**250.00**	**$150.00**	**$37,500.00**
	Item Code 703555 Total No. of Proj.			**1**		**Total Amount**	**$37,500.00**
703575	24" WELDED STEEL PIPE (.250" THICK)	LF	2	1	220.00	$225.75	$49,665.00
		LF	7	1	1,630.00	$270.00	$440,100.00
	Unit Sub Total	**LF**		**2**	**1,850.00**	**$264.74**	**$489,765.00**
	Item Code 703575 Total No. of Proj.			**2**		**Total Amount**	**$489,765.00**
703598	30" WELDED STEEL PIPE (.250" THICK)	LF	2	1	70.00	$313.50	$21,945.00
	Unit Sub Total	**LF**		**1**	**70.00**	**$313.50**	**$21,945.00**
	Item Code 703598 Total No. of Proj.			**1**		**Total Amount**	**$21,945.00**
703618	36" WELDED STEEL PIPE (.250" THICK)	LF	2	1	200.00	$332.50	$66,500.00
	Unit Sub Total	**LF**		**1**	**200.00**	**$332.50**	**$66,500.00**
	Item Code 703618 Total No. of Proj.			**1**		**Total Amount**	**$66,500.00**
703656	48" WELDED STEEL PIPE (.375" THICK)	LF	2	1	80.00	$579.00	$46,320.00
		LF	4	1	31.00	$70.00	$2,170.00
	Unit Sub Total	**LF**		**2**	**111.00**	**$436.85**	**$48,490.00**
	Item Code 703656 Total No. of Proj.			**2**		**Total Amount**	**$48,490.00**
703699	1500 MM WELDED STEEL PIPE (9.53 MM THICK)	M	5	1	17.00	$2,400.00	$40,800.00
	Unit Sub Total	**M**		**1**	**17.00**	**$2,400.00**	**$40,800.00**
	Item Code 703699 Total No. of Proj.			**1**		**Total Amount**	**$40,800.00**
703715	72" WELDED STEEL PIPE (.250" THICK)	LF	2	1	84.00	$583.50	$49,014.00
	Unit Sub Total	**LF**		**1**	**84.00**	**$583.50**	**$49,014.00**
	Item Code 703715 Total No. of Proj.			**1**		**Total Amount**	**$49,014.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
704245	JACKED 42" WELDED STEEL PIPE (.375" THICK)	LF	1	1	80.00	$1,135.00	$90,800.00
	Unit Sub Total	**LF**		**1**	**80.00**	**$1,135.00**	**$90,800.00**
	Item Code 704245 Total No. of Proj.			**1**		**Total Amount**	**$90,800.00**
705007	12" STEEL FLARED END SECTION	EA	1	1	4.00	$75.00	$300.00
		EA	2	1	2.00	$92.00	$184.00
		EA	4	1	1.00	$853.00	$853.00
		EA	6	1	4.00	$270.00	$1,080.00
		EA	8	1	14.00	$55.00	$770.00
		EA	10	1	1.00	$100.00	$100.00
	Unit Sub Total	**EA**		**6**	**26.00**	**$126.42**	**$3,287.00**
	Item Code 705007 Total No. of Proj.			**6**		**Total Amount**	**$3,287.00**
705009	15" STEEL FLARED END SECTION	EA	8	1	6.00	$70.00	$420.00
	Unit Sub Total	**EA**		**1**	**6.00**	**$70.00**	**$420.00**
	Item Code 705009 Total No. of Proj.			**1**		**Total Amount**	**$420.00**
705011	18" STEEL FLARED END SECTION	EA	1	1	7.00	$100.00	$700.00
		EA	2	1	5.00	$150.00	$750.00
		EA	3	1	9.00	$900.00	$8,100.00
		EA	4	3	15.00	$738.67	$11,080.00
		EA	6	1	1.00	$600.00	$600.00
		EA	7	1	1.00	$1,100.00	$1,100.00
		EA	10	2	3.00	$406.67	$1,220.00
	Unit Sub Total	**EA**		**10**	**41.00**	**$574.39**	**$23,550.00**
	Item Code 705011 Total No. of Proj.			**10**		**Total Amount**	**$23,550.00**
705015	24" STEEL FLARED END SECTION	EA	1	3	6.00	$350.00	$2,100.00
		EA	2	3	6.00	$429.33	$2,576.00
		EA	3	2	4.00	$455.50	$1,822.00
		EA	4	1	4.00	$930.00	$3,720.00
		EA	8	1	2.00	$540.00	$1,080.00
		EA	10	1	1.00	$425.00	$425.00
	Unit Sub Total	**EA**		**11**	**23.00**	**$509.70**	**$11,723.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 705015 Total No. of Proj.			**11**		**Total Amount**	**$11,723.00**
705019	30" STEEL FLARED END SECTION	EA	4	1	2.00	$1,050.00	$2,100.00
		EA	8	1	1.00	$1,040.00	$1,040.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$1,046.67**	**$3,140.00**
	Item Code 705019 Total No. of Proj.			**2**		**Total Amount**	**$3,140.00**
705023	36" STEEL FLARED END SECTION	EA	1	1	1.00	$900.00	$900.00
		EA	4	1	1.00	$1,225.00	$1,225.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$1,062.50**	**$2,125.00**
	Item Code 705023 Total No. of Proj.			**2**		**Total Amount**	**$2,125.00**
705042	300 MM STEEL FLARED END SECTION	EA	10	1	58.00	$150.00	$8,700.00
	Unit Sub Total	**EA**		**1**	**58.00**	**$150.00**	**$8,700.00**
	Item Code 705042 Total No. of Proj.			**1**		**Total Amount**	**$8,700.00**
705044	450 MM STEEL FLARED END SECTION	EA	10	1	2.00	$250.00	$500.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$250.00**	**$500.00**
	Item Code 705044 Total No. of Proj.			**1**		**Total Amount**	**$500.00**
705045	600 MM STEEL FLARED END SECTION	EA	10	1	2.00	$300.00	$600.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$300.00**	**$600.00**
	Item Code 705045 Total No. of Proj.			**1**		**Total Amount**	**$600.00**
705061	18" BITUMINOUS COATED STEEL FLARED END SECTION	EA	8	1	2.00	$450.00	$900.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$450.00**	**$900.00**
	Item Code 705061 Total No. of Proj.			**1**		**Total Amount**	**$900.00**
705081	48" BITUMINOUS COATED STEEL FLARED END SECTION	EA	8	1	1.00	$530.00	$530.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$530.00**	**$530.00**
	Item Code 705081 Total No. of Proj.			**1**		**Total Amount**	**$530.00**
705201	12" CONCRETE FLARED END SECTION	EA	12	1	2.00	$580.00	$1,160.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**1**	**2.00**	**$580.00**	**$1,160.00**
	Item Code 705201 Total No. of Proj.			**1**		**Total Amount**	**$1,160.00**
705202	15" CONCRETE FLARED END SECTION	EA	6	1	1.00	$2,450.00	$2,450.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$2,450.00**	**$2,450.00**
	Item Code 705202 Total No. of Proj.			**1**		**Total Amount**	**$2,450.00**
705204	18" CONCRETE FLARED END SECTION	EA	2	1	3.00	$500.00	$1,500.00
		EA	3	2	11.00	$760.91	$8,370.00
		EA	6	1	1.00	$2,650.00	$2,650.00
		EA	7	1	1.00	$1,550.00	$1,550.00
		EA	10	3	9.00	$774.44	$6,970.00
		EA	12	3	5.00	$500.00	$2,500.00
	Unit Sub Total	**EA**		**11**	**30.00**	**$784.67**	**$23,540.00**
	Item Code 705204 Total No. of Proj.			**11**		**Total Amount**	**$23,540.00**
705206	24" CONCRETE FLARED END SECTION	EA	3	1	2.00	$900.00	$1,800.00
		EA	4	1	1.00	$550.00	$550.00
		EA	6	1	2.00	$590.00	$1,180.00
		EA	7	1	1.00	$1,800.00	$1,800.00
	Unit Sub Total	**EA**		**4**	**6.00**	**$888.33**	**$5,330.00**
	Item Code 705206 Total No. of Proj.			**4**		**Total Amount**	**$5,330.00**
705222	450 MM CONCRETE FLARED END SECTION	EA	7	1	1.00	$1,800.00	$1,800.00
		EA	8	1	2.00	$385.00	$770.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$856.67**	**$2,570.00**
	Item Code 705222 Total No. of Proj.			**2**		**Total Amount**	**$2,570.00**
705224	600 MM CONCRETE FLARED END SECTION	EA	7	1	4.00	$900.00	$3,600.00
		EA	8	1	2.00	$500.00	$1,000.00
		EA	11	1	1.00	$1,200.00	$1,200.00
	Unit Sub Total	**EA**		**3**	**7.00**	**$828.57**	**$5,800.00**
	Item Code 705224 Total No. of Proj.			**3**		**Total Amount**	**$5,800.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
705227	900 MM CONCRETE FLARED END SECTION	EA	7	1	2.00	$1,200.00	$2,400.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,200.00**	**$2,400.00**
	Item Code 705227 Total No. of Proj.			**1**		**Total Amount**	**$2,400.00**
705229	1200 MM CONCRETE FLARED END SECTION	EA	7	1	8.00	$2,000.00	$16,000.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$2,000.00**	**$16,000.00**
	Item Code 705229 Total No. of Proj.			**1**		**Total Amount**	**$16,000.00**
705230	1350 MM CONCRETE FLARED END SECTION	EA	8	1	1.00	$1,200.00	$1,200.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,200.00**	**$1,200.00**
	Item Code 705230 Total No. of Proj.			**1**		**Total Amount**	**$1,200.00**
705300	ALTERNATIVE FLARED END SECTION	EA	4	2	2.00	$1,450.00	$2,900.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$1,450.00**	**$2,900.00**
	Item Code 705300 Total No. of Proj.			**2**		**Total Amount**	**$2,900.00**
705307	12" ALTERNATIVE FLARED END SECTION	EA	1	2	3.00	$633.33	$1,900.00
		EA	4	3	5.00	$267.25	$1,336.25
		EA	10	1	94.00	$350.00	$32,900.00
	Unit Sub Total	**EA**		**6**	**102.00**	**$354.28**	**$36,136.25**
	Item Code 705307 Total No. of Proj.			**6**		**Total Amount**	**$36,136.25**
705309	15" ALTERNATIVE FLARED END SECTION	EA	8	1	1.00	$530.00	$530.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$530.00**	**$530.00**
	Item Code 705309 Total No. of Proj.			**1**		**Total Amount**	**$530.00**
705311	18" ALTERNATIVE FLARED END SECTION	EA	1	2	14.00	$517.86	$7,250.00
		EA	3	3	27.00	$249.70	$6,742.00
		EA	4	6	43.00	$323.93	$13,929.10
		EA	5	1	1.00	$300.00	$300.00
		EA	6	3	19.00	$306.32	$5,820.00
		EA	8	1	8.00	$590.00	$4,720.00
		EA	9	1	2.00	$300.00	$600.00
		EA	10	2	26.00	$726.92	$18,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
705311	18" ALTERNATIVE FLARED END SECTION	EA	12	2	9.00	$686.67	$6,180.00
	Unit Sub Total	**EA**		**21**	**149.00**	**$432.49**	**$64,441.10**
	Item Code 705311 Total No. of Proj.			**21**		**Total Amount**	**$64,441.10**
705315	24" ALTERNATIVE FLARED END SECTION	EA	1	2	22.00	$659.09	$14,500.00
		EA	3	2	9.00	$477.78	$4,300.00
		EA	4	3	5.00	$436.26	$2,181.30
		EA	5	1	7.00	$200.00	$1,400.00
		EA	6	3	207.00	$384.44	$79,580.00
		EA	8	1	2.00	$620.00	$1,240.00
		EA	9	1	18.00	$450.00	$8,100.00
		EA	10	1	25.00	$1,100.00	$27,500.00
		EA	12	1	2.00	$860.00	$1,720.00
	Unit Sub Total	**EA**		**15**	**297.00**	**$473.14**	**$140,521.30**
	Item Code 705315 Total No. of Proj.			**15**		**Total Amount**	**$140,521.30**
705319	30" ALTERNATIVE FLARED END SECTION	EA	1	1	4.00	$760.00	$3,040.00
		EA	4	1	3.00	$1,000.00	$3,000.00
		EA	6	1	13.00	$450.00	$5,850.00
	Unit Sub Total	**EA**		**3**	**20.00**	**$594.50**	**$11,890.00**
	Item Code 705319 Total No. of Proj.			**3**		**Total Amount**	**$11,890.00**
705321	36" ALTERNATIVE FLARED END SECTION	EA	1	1	3.00	$870.00	$2,610.00
		EA	4	2	3.00	$694.67	$2,084.00
		EA	6	2	20.00	$628.80	$12,576.00
		EA	9	1	10.00	$1,044.00	$10,440.00
		EA	10	1	9.00	$1,500.00	$13,500.00
	Unit Sub Total	**EA**		**7**	**45.00**	**$915.78**	**$41,210.00**
	Item Code 705321 Total No. of Proj.			**7**		**Total Amount**	**$41,210.00**
705323	42" ALTERNATIVE FLARED END SECTION	EA	1	1	2.00	$1,075.00	$2,150.00
		EA	6	1	4.00	$950.00	$3,800.00
	Unit Sub Total	**EA**		**2**	**6.00**	**$991.67**	**$5,950.00**
	Item Code 705323 Total No. of Proj.			**2**		**Total Amount**	**$5,950.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
705325	48" ALTERNATIVE FLARED END SECTION	EA	6	2	8.00	$1,191.25	$9,530.00
		EA	10	1	3.00	$2,300.00	$6,900.00
	Unit Sub Total	**EA**		**3**	**11.00**	**$1,493.64**	**$16,430.00**
	Item Code 705325 Total No. of Proj.			**3**		**Total Amount**	**$16,430.00**
705329	60" ALTERNATIVE FLARED END SECTION	EA	6	1	2.00	$1,600.00	$3,200.00
		EA	10	1	6.00	$2,800.00	$16,800.00
	Unit Sub Total	**EA**		**2**	**8.00**	**$2,500.00**	**$20,000.00**
	Item Code 705329 Total No. of Proj.			**2**		**Total Amount**	**$20,000.00**
705336	450 MM ALTERNATIVE FLARED END SECTION	EA	4	1	8.00	$200.00	$1,600.00
		EA	5	1	20.00	$400.00	$8,000.00
		EA	10	1	34.00	$750.00	$25,500.00
		EA	11	1	2.00	$620.00	$1,240.00
	Unit Sub Total	**EA**		**4**	**64.00**	**$567.81**	**$36,340.00**
	Item Code 705336 Total No. of Proj.			**4**		**Total Amount**	**$36,340.00**
705337	600 MM ALTERNATIVE FLARED END SECTION	EA	5	1	120.00	$500.00	$60,000.00
		EA	8	1	1.00	$400.00	$400.00
		EA	10	1	25.00	$650.00	$16,250.00
	Unit Sub Total	**EA**		**3**	**146.00**	**$525.00**	**$76,650.00**
	Item Code 705337 Total No. of Proj.			**3**		**Total Amount**	**$76,650.00**
705338	750 MM ALTERNATIVE FLARED END SECTION	EA	5	1	8.00	$600.00	$4,800.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$600.00**	**$4,800.00**
	Item Code 705338 Total No. of Proj.			**1**		**Total Amount**	**$4,800.00**
705339	900 MM ALTERNATIVE FLARED END SECTION	EA	5	1	10.00	$750.00	$7,500.00
	Unit Sub Total	**EA**		**1**	**10.00**	**$750.00**	**$7,500.00**
	Item Code 705339 Total No. of Proj.			**1**		**Total Amount**	**$7,500.00**
705341	1200 MM ALTERNATIVE FLARED END SECTION	EA	5	1	2.00	$1,600.00	$3,200.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,600.00**	**$3,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 705341 Total No. of Proj.			**1**		**Total Amount**	**$3,200.00**
705517	18" AUTOMATIC DRAINAGE GATE	EA	12	1	2.00	$2,000.00	$4,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$2,000.00**	**$4,000.00**
	Item Code 705517 Total No. of Proj.			**1**		**Total Amount**	**$4,000.00**
705527	36" AUTOMATIC DRAINAGE GATE	EA	4	1	1.00	$4,500.00	$4,500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$4,500.00**	**$4,500.00**
	Item Code 705527 Total No. of Proj.			**1**		**Total Amount**	**$4,500.00**
705529	42" AUTOMATIC DRAINAGE GATE	EA	4	1	2.00	$6,000.00	$12,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$6,000.00**	**$12,000.00**
	Item Code 705529 Total No. of Proj.			**1**		**Total Amount**	**$12,000.00**
705569	900 MM AUTOMATIC DRAINAGE GATE	EA	4	1	1.00	$3,500.00	$3,500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$3,500.00**	**$3,500.00**
	Item Code 705569 Total No. of Proj.			**1**		**Total Amount**	**$3,500.00**
706584	DEBRIS RACK CAGE	EA	4	1	2.00	$1,033.00	$2,066.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,033.00**	**$2,066.00**
	Item Code 706584 Total No. of Proj.			**1**		**Total Amount**	**$2,066.00**
706607	48" DEBRIS RACK CAGE (H=4')	EA	2	1	1.00	$2,500.00	$2,500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$2,500.00**	**$2,500.00**
	Item Code 706607 Total No. of Proj.			**1**		**Total Amount**	**$2,500.00**
707050	DRAINAGE INLET	EA	6	1	5.00	$1,200.00	$6,000.00
	Unit Sub Total	**EA**		**1**	**5.00**	**$1,200.00**	**$6,000.00**
	Item Code 707050 Total No. of Proj.			**1**		**Total Amount**	**$6,000.00**
707051	DRAINAGE MANHOLE	EA	7	1	12.00	$20,000.00	$240,000.00
	Unit Sub Total	**EA**		**1**	**12.00**	**$20,000.00**	**$240,000.00**
	Item Code 707051 Total No. of Proj.			**1**		**Total Amount**	**$240,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
707117	36" PRECAST CONCRETE PIPE INLET	LF	1	1	58.00	$350.00	$20,300.00
		LF	2	3	27.00	$765.56	$20,670.00
		LF	4	1	120.00	$190.00	$22,800.00
		LF	11	1	0.70	$2,000.00	$1,400.00
	Unit Sub Total	**LF**		**6**	**205.70**	**$316.82**	**$65,170.00**
	Item Code 707117 Total No. of Proj.			**6**		**Total Amount**	**$65,170.00**
707133	900 MM PRECAST CONCRETE PIPE INLET	M	8	1	16.00	$520.00	$8,320.00
		M	11	1	10.00	$750.00	$7,500.00
	Unit Sub Total	**M**		**2**	**26.00**	**$608.46**	**$15,820.00**
	Item Code 707133 Total No. of Proj.			**2**		**Total Amount**	**$15,820.00**
707210	24" PRECAST CONCRETE PIPE MANHOLE	LF	3	1	7.00	$600.00	$4,200.00
		LF	7	1	2.00	$500.00	$1,000.00
		LF	12	1	6.00	$200.00	$1,200.00
	Unit Sub Total	**LF**		**3**	**15.00**	**$426.67**	**$6,400.00**
	Item Code 707210 Total No. of Proj.			**3**		**Total Amount**	**$6,400.00**
707217	36" PRECAST CONCRETE PIPE MANHOLE	LF	12	2	11.00	$1,189.09	$13,080.00
	Unit Sub Total	**LF**		**2**	**11.00**	**$1,189.09**	**$13,080.00**
	Item Code 707217 Total No. of Proj.			**2**		**Total Amount**	**$13,080.00**
707218	36" PRECAST CONCRETE PIPE MANHOLE (EXTRA STRENGTH)	LF	7	1	13.00	$450.00	$5,850.00
	Unit Sub Total	**LF**		**1**	**13.00**	**$450.00**	**$5,850.00**
	Item Code 707218 Total No. of Proj.			**1**		**Total Amount**	**$5,850.00**
707225	48" PRECAST CONCRETE PIPE MANHOLE	EA	3	1	3.00	$2,500.00	$7,500.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$2,500.00**	**$7,500.00**
	Item Code 707225 Total No. of Proj.			**1**		**Total Amount**	**$7,500.00**
707241	72" PRECAST CONCRETE PIPE MANHOLE	LF	7	1	10.00	$600.00	$6,000.00
	Unit Sub Total	**LF**		**1**	**10.00**	**$600.00**	**$6,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 707241 Total No. of Proj.			**1**		**Total Amount**	**$6,000.00**
707244	900 MM PRECAST CONCRETE PIPE MANHOLE	M	7	3	67.20	$926.85	$62,284.00
		M	8	1	9.00	$1,300.00	$11,700.00
	Unit Sub Total	**M**		**4**	**76.20**	**$970.92**	**$73,984.00**
	Item Code 707244 Total No. of Proj.			**4**		**Total Amount**	**$73,984.00**
707252	1800 MM PRECAST CONCRETE PIPE MANHOLE	M	8	1	2.40	$1,500.00	$3,600.00
	Unit Sub Total	**M**		**1**	**2.40**	**$1,500.00**	**$3,600.00**
	Item Code 707252 Total No. of Proj.			**1**		**Total Amount**	**$3,600.00**
707417	36" PRECAST CONCRETE PIPE RISER	LF	5	1	4.40	$1,100.00	$4,840.00
	Unit Sub Total	**LF**		**1**	**4.40**	**$1,100.00**	**$4,840.00**
	Item Code 707417 Total No. of Proj.			**1**		**Total Amount**	**$4,840.00**
707467	36" REINFORCED CONCRETE PIPE RISER	LF	5	1	2.00	$1,000.00	$2,000.00
		LF	6	1	13.00	$350.00	$4,550.00
		LF	11	1	10.00	$286.00	$2,860.00
	Unit Sub Total	**LF**		**3**	**25.00**	**$376.40**	**$9,410.00**
	Item Code 707467 Total No. of Proj.			**3**		**Total Amount**	**$9,410.00**
707471	900 MM PRECAST CONCRETE PIPE RISER	M	11	1	12.00	$300.00	$3,600.00
	Unit Sub Total	**M**		**1**	**12.00**	**$300.00**	**$3,600.00**
	Item Code 707471 Total No. of Proj.			**1**		**Total Amount**	**$3,600.00**
708058	900 MM ALTERNATIVE PIPE INLET	M	10	1	4.00	$1,650.00	$6,600.00
	Unit Sub Total	**M**		**1**	**4.00**	**$1,650.00**	**$6,600.00**
	Item Code 708058 Total No. of Proj.			**1**		**Total Amount**	**$6,600.00**
717074	150 MM SEWER PIPE (LATERAL)	M	7	1	280.00	$210.00	$58,800.00
	Unit Sub Total	**M**		**1**	**280.00**	**$210.00**	**$58,800.00**
	Item Code 717074 Total No. of Proj.			**1**		**Total Amount**	**$58,800.00**
719110	SEWER TERMINAL CLEANOUT	EA	7	1	1.00	$1,350.00	$1,350.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,350.00**	**$1,350.00**
	Item Code 719110 Total No. of Proj.			**1**		**Total Amount**	**$1,350.00**
719190	SEWER MANHOLE FRAME AND COVER	EA	7	1	37.00	$650.00	$24,050.00
	Unit Sub Total	**EA**		**1**	**37.00**	**$650.00**	**$24,050.00**
	Item Code 719190 Total No. of Proj.			**1**		**Total Amount**	**$24,050.00**
719210	CONCRETE SEWER MANHOLE	EA	7	1	34.00	$5,300.00	$180,200.00
	Unit Sub Total	**EA**		**1**	**34.00**	**$5,300.00**	**$180,200.00**
	Item Code 719210 Total No. of Proj.			**1**		**Total Amount**	**$180,200.00**
719300	MANHOLE	EA	6	1	1.00	$3,000.00	$3,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$3,000.00**	**$3,000.00**
	Item Code 719300 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
719305	MANHOLE (TYPE A)	EA	5	1	10.00	$3,000.00	$30,000.00
		EA	6	1	6.00	$3,000.00	$18,000.00
		EA	10	2	4.00	$5,250.00	$21,000.00
	Unit Sub Total	**EA**		**4**	**20.00**	**$3,450.00**	**$69,000.00**
	Item Code 719305 Total No. of Proj.			**4**		**Total Amount**	**$69,000.00**
719306	MANHOLE (TYPE B)	EA	5	1	20.00	$6,000.00	$120,000.00
	Unit Sub Total	**EA**		**1**	**20.00**	**$6,000.00**	**$120,000.00**
	Item Code 719306 Total No. of Proj.			**1**		**Total Amount**	**$120,000.00**
719530	CURB DRAIN	EA	7	1	5.00	$630.00	$3,150.00
	Unit Sub Total	**EA**		**1**	**5.00**	**$630.00**	**$3,150.00**
	Item Code 719530 Total No. of Proj.			**1**		**Total Amount**	**$3,150.00**
719589	MINOR CONCRETE (BACKFILL)	CY	1	3	1,222.00	$125.17	$152,960.00
		CY	4	2	2,040.00	$115.03	$234,653.00
		CY	6	1	670.00	$90.00	$60,300.00
	Unit Sub Total	**CY**		**6**	**3,932.00**	**$113.91**	**$447,913.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
719589	MINOR CONCRETE (BACKFILL)	M3	5	1	39.00	$200.00	$7,800.00
		M3	11	1	28.00	$120.00	$3,360.00
	Unit Sub Total	**M3**		**2**	**67.00**	**$166.57**	**$11,160.00**
	Item Code 719589 Total No. of Proj.			**8**		**Total Amount**	**$459,073.00**
719598	CLASS 4 CONCRETE (BACKFILL)	CY	3	1	470.00	$90.00	$42,300.00
	Unit Sub Total	**CY**		**1**	**470.00**	**$90.00**	**$42,300.00**
	Item Code 719598 Total No. of Proj.			**1**		**Total Amount**	**$42,300.00**
720002	ROCK SLOPE PROTECTION (DRAINAGE OUTLET)	CY	7	1	4.00	$600.00	$2,400.00
	Unit Sub Total	**CY**		**1**	**4.00**	**$600.00**	**$2,400.00**
	Item Code 720002 Total No. of Proj.			**1**		**Total Amount**	**$2,400.00**
720104	ROCK SLOPE PROTECTION (1 TON, METHOD A)	CY	2	1	857.00	$115.00	$98,555.00
		CY	5	1	96.00	$125.00	$12,000.00
	Unit Sub Total	**CY**		**2**	**953.00**	**$116.01**	**$110,555.00**
	Item Code 720104 Total No. of Proj.			**2**		**Total Amount**	**$110,555.00**
720106	ROCK SLOPE PROTECTION (1/2 TON, METHOD A)	CY	1	2	83.00	$216.59	$17,977.00
		CY	2	1	70.00	$97.50	$6,825.00
		CY	4	1	1,780.00	$75.00	$133,500.00
	Unit Sub Total	**CY**		**4**	**1,933.00**	**$81.89**	**$158,302.00**
	Item Code 720106 Total No. of Proj.			**4**		**Total Amount**	**$158,302.00**
720107	ROCK SLOPE PROTECTION(GRANULAR MATERIAL)	CY	1	1	55.00	$133.00	$7,315.00
		CY	2	1	9.00	$200.00	$1,800.00
		CY	7	1	27.00	$330.00	$8,910.00
	Unit Sub Total	**CY**		**3**	**91.00**	**$198.08**	**$18,025.00**
	Item Code 720107 Total No. of Proj.			**3**		**Total Amount**	**$18,025.00**
720120	ROCK SLOPE PROTECTION (1/2T, METHOD A)	CY	6	1	550.00	$76.00	$41,800.00
	Unit Sub Total	**CY**		**1**	**550.00**	**$76.00**	**$41,800.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 720120 Total No. of Proj.			**1**		**Total Amount**	**$41,800.00**
721006	ROCK SLOPE PROTECTION (1/2 TON, METHOD B)	CY	1	1	57.00	$148.00	$8,436.00
		CY	2	1	220.00	$130.00	$28,600.00
		CY	10	1	8.00	$125.00	$1,000.00
	Unit Sub Total	**CY**		**3**	**285.00**	**$133.46**	**$38,036.00**
721006	ROCK SLOPE PROTECTION (1/2 TON, METHOD B)	M3	8	1	34.00	$90.00	$3,060.00
	Unit Sub Total	**M3**		**1**	**34.00**	**$90.00**	**$3,060.00**
	Item Code 721006 Total No. of Proj.			**4**		**Total Amount**	**$41,096.00**
721007	ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	CY	1	4	2,691.20	$90.70	$244,095.00
		CY	2	2	308.00	$75.00	$23,100.00
		CY	4	1	1.00	$1,000.00	$1,000.00
		CY	10	1	70.00	$185.00	$12,950.00
		CY	11	1	37.00	$200.00	$7,400.00
	Unit Sub Total	**CY**		**9**	**3,107.20**	**$92.86**	**$288,545.00**
	Item Code 721007 Total No. of Proj.			**9**		**Total Amount**	**$288,545.00**
721008	ROCK SLOPE PROTECTION (LIGHT, METHOD B)	CY	1	5	231.00	$172.43	$39,832.00
		CY	2	3	444.00	$118.18	$52,470.00
		CY	3	4	1,120.00	$131.07	$146,800.00
		CY	4	4	3,495.00	$106.52	$372,270.00
		CY	5	1	52.00	$150.00	$7,800.00
		CY	8	1	52.00	$365.00	$18,980.00
		CY	9	1	35.00	$140.00	$4,900.00
		CY	10	1	9,150.00	$35.00	$320,250.00
	Unit Sub Total	**CY**		**20**	**14,579.00**	**$66.07**	**$963,302.00**
721008	ROCK SLOPE PROTECTION (LIGHT, METHOD B)	M3	4	1	6.00	$300.00	$1,800.00
		M3	10	1	680.00	$57.00	$38,760.00
		M3	11	2	167.00	$397.96	$66,460.00
	Unit Sub Total	**M3**		**4**	**853.00**	**$125.46**	**$107,020.00**
721008	ROCK SLOPE PROTECTION (LIGHT, METHOD B)	TON	3	1	17.00	$380.00	$6,460.00
	Unit Sub Total	**TON**		**1**	**17.00**	**$380.00**	**$6,460.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 721008 Total No. of Proj.			**25**		**Total Amount**	**$1,076,782.00**
721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	CY	1	3	651.00	$152.42	$99,225.00
		CY	2	3	593.00	$96.75	$57,375.00
		CY	3	1	170.00	$156.00	$26,520.00
		CY	4	4	1,554.00	$241.98	$376,040.00
		CY	5	1	1.20	$500.00	$600.00
		CY	6	3	2,742.00	$114.71	$314,530.00
		CY	7	2	12.00	$320.83	$3,850.00
		CY	8	1	70.00	$120.00	$8,400.00
		CY	9	3	17.70	$292.20	$5,172.00
		CY	12	4	48.00	$290.52	$13,945.00
	Unit Sub Total	**CY**		**25**	**5,858.90**	**$154.58**	**$905,657.00**
721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	M3	5	1	8,120.00	$80.00	$649,600.00
		M3	8	1	6.00	$180.00	$1,080.00
	Unit Sub Total	**M3**		**2**	**8,126.00**	**$80.07**	**$650,680.00**
	Item Code 721009 Total No. of Proj.			**27**		**Total Amount**	**$1,556,337.00**
721010	ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B)	CY	1	1	240.00	$105.00	$25,200.00
		CY	2	3	268.00	$103.06	$27,620.00
		CY	3	1	430.00	$150.00	$64,500.00
		CY	4	3	317.00	$126.26	$40,025.00
	ROCK SLOPE PROTECTION (NO. 1, METHOD B)	CY	4	2	722.00	$97.92	$70,700.00
		CY	7	1	100.00	$235.00	$23,500.00
	ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B)	CY	11	1	20.00	$200.00	$4,000.00
	Unit Sub Total	**CY**		**12**	**2,097.00**	**$121.86**	**$255,545.00**
721010	ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B)	M3	8	1	450.00	$85.00	$38,250.00
	Unit Sub Total	**M3**		**1**	**450.00**	**$85.00**	**$38,250.00**
721010	ROCK SLOPE PROTECTION (NO. 1, METHOD B)	TON	1	1	11.00	$65.00	$715.00
	Unit Sub Total	**TON**		**1**	**11.00**	**$65.00**	**$715.00**
	Item Code 721010 Total No. of Proj.			**14**		**Total Amount**	**$294,510.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	CY	1	3	535.00	$83.21	$44,520.00
		CY	2	4	3,033.00	$61.74	$187,260.00
	ROCK SLOPE PROTECTION (NO. 2, METHOD B)	CY	2	1	12.00	$40.00	$480.00
		CY	3	1	4.00	$500.00	$2,000.00
	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	CY	4	4	86.00	$237.40	$20,416.00
	ROCK SLOPE PROTECTION (NO. 2, METHOD B)	CY	4	3	449.00	$171.92	$77,191.80
	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	CY	5	1	26.00	$150.00	$3,900.00
		CY	6	1	900.00	$120.00	$108,000.00
		CY	8	2	23.00	$360.61	$8,294.00
		CY	10	2	747.00	$127.05	$94,905.00
	Unit Sub Total	**CY**		**22**	**5,815.00**	**$94.06**	**$546,966.80**
721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	M3	7	1	2.00	$820.00	$1,640.00
	ROCK SLOPE PROTECTION (NO. 2, METHOD B)	M3	7	1	70.00	$150.00	$10,500.00
	Unit Sub Total	**M3**		**2**	**72.00**	**$168.61**	**$12,140.00**
721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	TON	4	1	30.00	$125.00	$3,750.00
		TON	5	1	38.00	$85.00	$3,230.00
	Unit Sub Total	**TON**		**2**	**68.00**	**$102.65**	**$6,980.00**
	Item Code 721011 Total No. of Proj.			**26**		**Total Amount**	**$566,086.80**
721012	ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B)	CY	2	2	106.00	$119.58	$12,675.00
		CY	4	1	19.00	$430.00	$8,170.00
	Unit Sub Total	**CY**		**3**	**125.00**	**$166.76**	**$20,845.00**
	Item Code 721012 Total No. of Proj.			**3**		**Total Amount**	**$20,845.00**
721023	ROCK SLOPE PROTECTION (1/2T, METHOD B)	CY	7	1	260.00	$84.00	$21,840.00
	Unit Sub Total	**CY**		**1**	**260.00**	**$84.00**	**$21,840.00**
	Item Code 721023 Total No. of Proj.			**1**		**Total Amount**	**$21,840.00**
721024	ROCK SLOPE PROTECTION (1/4T, METHOD B)	CY	8	1	7.00	$450.00	$3,150.00
	Unit Sub Total	**CY**		**1**	**7.00**	**$450.00**	**$3,150.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
721024	ROCK SLOPE PROTECTION (1/4T, METHOD B)	M3	5	1	1,410.00	$100.00	$141,000.00
		M3	11	1	30.00	$150.00	$4,500.00
	Unit Sub Total	**M3**		**2**	**1,440.00**	**$101.04**	**$145,500.00**
	Item Code 721024 Total No. of Proj.			**3**		**Total Amount**	**$148,650.00**
721400	CONCRETE (SLOPE PROTECTION)	CY	11	1	4.90	$1,680.00	$8,232.00
	Unit Sub Total	**CY**		**1**	**4.90**	**$1,680.00**	**$8,232.00**
	Item Code 721400 Total No. of Proj.			**1**		**Total Amount**	**$8,232.00**
721420	CONCRETE (DITCH LINING)	CY	4	1	5.00	$950.00	$4,750.00
		CY	7	1	18.00	$400.00	$7,200.00
	Unit Sub Total	**CY**		**2**	**23.00**	**$519.57**	**$11,950.00**
	Item Code 721420 Total No. of Proj.			**2**		**Total Amount**	**$11,950.00**
721430	CONCRETE (CHANNEL LINING)	CY	4	1	77.00	$860.00	$66,220.00
		CY	7	1	4.00	$540.00	$2,160.00
	Unit Sub Total	**CY**		**2**	**81.00**	**$844.20**	**$68,380.00**
721430	CONCRETE (CHANNEL LINING)	M3	11	1	24.00	$400.00	$9,600.00
	Unit Sub Total	**M3**		**1**	**24.00**	**$400.00**	**$9,600.00**
	Item Code 721430 Total No. of Proj.			**3**		**Total Amount**	**$77,980.00**
721431	CONCRETE (CONCRETE APRON)	M3	11	2	28.00	$388.21	$10,870.00
	Unit Sub Total	**M3**		**2**	**28.00**	**$388.21**	**$10,870.00**
	Item Code 721431 Total No. of Proj.			**2**		**Total Amount**	**$10,870.00**
721501	CONCRETE (CONCRETED-ROCK SLOPE PROTECTION)	CY	3	1	10.00	$1,007.00	$10,070.00
		CY	8	1	13.00	$390.00	$5,070.00
	Unit Sub Total	**CY**		**2**	**23.00**	**$658.26**	**$15,140.00**
	Item Code 721501 Total No. of Proj.			**2**		**Total Amount**	**$15,140.00**
721607	CONCRETED-ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	CY	8	1	72.00	$390.00	$28,080.00
	Unit Sub Total	**CY**		**1**	**72.00**	**$390.00**	**$28,080.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 721607 Total No. of Proj.			**1**		**Total Amount**	**$28,080.00**
721608	CONCRETED-ROCK SLOPE PROTECTION (LIGHT, METHOD B)	CY	8	1	27.00	$390.00	$10,530.00
	Unit Sub Total	**CY**		**1**	**27.00**	**$390.00**	**$10,530.00**
	Item Code 721608 Total No. of Proj.			**1**		**Total Amount**	**$10,530.00**
721810	SLOPE PAVING (CONCRETE)	CY	1	1	8.20	$5,600.00	$45,920.00
		CY	2	1	106.00	$696.00	$73,776.00
		CY	3	3	637.00	$315.66	$201,075.00
		CY	4	1	96.00	$865.00	$83,040.00
		CY	6	1	29.00	$950.00	$27,550.00
		CY	7	1	39.00	$500.00	$19,500.00
		CY	8	1	61.00	$590.00	$35,990.00
		CY	12	2	159.00	$364.15	$57,900.00
	Unit Sub Total	**CY**		**11**	**1,135.20**	**$479.87**	**$544,751.00**
721810	SLOPE PAVING (CONCRETE)	M2	7	1	8,330.00	$46.00	$383,180.00
	Unit Sub Total	**M2**		**1**	**8,330.00**	**$46.00**	**$383,180.00**
721810	SLOPE PAVING (CONCRETE)	M3	8	1	269.00	$470.00	$126,430.00
		M3	11	1	49.00	$690.00	$33,810.00
	Unit Sub Total	**M3**		**2**	**318.00**	**$503.90**	**$160,240.00**
	Item Code 721810 Total No. of Proj.			**14**		**Total Amount**	**$1,088,171.00**
721811	SLOPE PAVING (MASONRY BLOCK)	SQFT	12	1	2,635.00	$27.00	$71,145.00
	Unit Sub Total	**SQFT**		**1**	**2,635.00**	**$27.00**	**$71,145.00**
	Item Code 721811 Total No. of Proj.			**1**		**Total Amount**	**$71,145.00**
722009	COBBLESTONE PAVING	SQYD	4	1	1,290.00	$82.62	$106,579.80
	Unit Sub Total	**SQYD**		**1**	**1,290.00**	**$82.62**	**$106,579.80**
	Item Code 722009 Total No. of Proj.			**1**		**Total Amount**	**$106,579.80**
722020	GABION	CY	2	2	4,250.00	$160.96	$684,100.00
		CY	7	1	60.00	$220.00	$13,200.00
	Unit Sub Total	**CY**		**3**	**4,310.00**	**$161.79**	**$697,300.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
722020	GABION	M3	7	1	9.00	$620.00	$5,580.00
	Unit Sub Total	**M3**		**1**	**9.00**	**$620.00**	**$5,580.00**
	Item Code 722020 Total No. of Proj.			**4**		**Total Amount**	**$702,880.00**
727901	MINOR CONCRETE (DITCH LINING)	CY	3	1	29.00	$446.25	$12,941.25
		CY	4	2	250.00	$386.00	$96,500.00
		CY	7	1	170.00	$350.00	$59,500.00
		CY	11	2	241.00	$307.05	$74,000.00
		CY	12	1	390.00	$245.00	$95,550.00
	Unit Sub Total	**CY**		**7**	**1,080.00**	**$313.42**	**$338,491.25**
727901	MINOR CONCRETE (DITCH LINING)	M3	7	1	41.00	$325.00	$13,325.00
		M3	11	1	130.00	$200.00	$26,000.00
	Unit Sub Total	**M3**		**2**	**171.00**	**$229.97**	**$39,325.00**
	Item Code 727901 Total No. of Proj.			**9**		**Total Amount**	**$377,816.25**
727902	MINOR CONCRETE (SLOPE PROTECTION)	CY	8	1	8.00	$1,230.00	$9,840.00
	Unit Sub Total	**CY**		**1**	**8.00**	**$1,230.00**	**$9,840.00**
	Item Code 727902 Total No. of Proj.			**1**		**Total Amount**	**$9,840.00**
727905	MINOR CONCRETE (CHANNEL LINING)	CY	5	1	55.00	$500.00	$27,500.00
		CY	7	1	261.00	$350.00	$91,350.00
		CY	12	2	200.80	$234.06	$47,000.00
	Unit Sub Total	**CY**		**4**	**516.80**	**$320.92**	**$165,850.00**
	Item Code 727905 Total No. of Proj.			**4**		**Total Amount**	**$165,850.00**
727906	MINOR CONCRETE (GUTTER LINING)	M3	7	1	4.00	$600.00	$2,400.00
	Unit Sub Total	**M3**		**1**	**4.00**	**$600.00**	**$2,400.00**
	Item Code 727906 Total No. of Proj.			**1**		**Total Amount**	**$2,400.00**
729000	FILTER FABRIC	M2	4	1	3,220.00	$1.00	$3,220.00
	Unit Sub Total	**M2**		**1**	**3,220.00**	**$1.00**	**$3,220.00**
729000	FILTER FABRIC	SQYD	2	2	3,440.00	$5.03	$17,310.00
		SQYD	6	1	300.00	$7.00	$2,100.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**SQYD**		**3**	**3,740.00**	**$5.19**	**$19,410.00**
	Item Code 729000	**Total No. of Proj.**			**4**		**Total Amount**	**$22,630.00**
729010	ROCK SLOPE PROTECTION FABRIC		M2	4	1	16.00	$1.00	$16.00
			M2	5	1	19,300.00	$1.00	$19,300.00
			M2	7	2	119.00	$16.28	$1,937.00
			M2	8	1	860.00	$5.00	$4,300.00
			M2	10	1	1,380.00	$2.50	$3,450.00
			M2	11	2	322.00	$10.19	$3,282.00
		Unit Sub Total	**M2**		**8**	**21,997.00**	**$1.47**	**$32,285.00**
729010	ROCK SLOPE PROTECTION FABRIC		SQFT	3	1	15.00	$10.00	$150.00
			SQFT	4	2	1,900.00	$1.00	$1,900.00
			SQFT	8	1	210.00	$7.00	$1,470.00
		Unit Sub Total	**SQFT**		**4**	**2,125.00**	**$1.66**	**$3,520.00**
729010	ROCK SLOPE PROTECTION FABRIC		SQYD	1	10	11,818.20	$1.45	$17,137.00
			SQYD	2	9	38,836.00	$1.31	$50,750.00
			SQYD	3	8	4,153.00	$2.54	$10,550.00
			SQYD	4	13	17,525.00	$3.21	$56,254.50
			SQYD	5	2	151.00	$6.17	$932.00
			SQYD	6	4	9,635.00	$0.97	$9,365.00
			SQYD	7	5	789.00	$5.28	$4,165.00
			SQYD	8	4	496.00	$6.30	$3,127.00
			SQYD	9	3	169.00	$8.81	$1,489.00
			SQYD	10	3	18,342.00	$1.97	$36,142.00
			SQYD	11	1	120.00	$4.60	$552.00
			SQYD	12	4	140.00	$30.18	$4,225.00
		Unit Sub Total	**SQYD**		**66**	**102,174.20**	**$1.91**	**$194,688.50**
	Item Code 729010	**Total No. of Proj.**			**78**		**Total Amount**	**$230,493.50**
731501	MINOR CONCRETE (CURB)		CY	1	2	131.30	$657.18	$86,287.50
			CY	3	2	45.00	$871.11	$39,200.00
			CY	4	2	88.00	$906.48	$79,770.00
			CY	6	2	38.00	$621.05	$23,600.00
			CY	7	1	20.00	$500.00	$10,000.00
			CY	9	1	16.00	$450.00	$7,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
731501	MINOR CONCRETE (CURB)		CY	12	1	50.00	$330.00	$16,500.00
		Unit Sub Total	**CY**		**11**	**388.30**	**$676.17**	**$262,557.50**
731501	MINOR CONCRETE (CURB)		LF	2	1	10.00	$100.00	$1,000.00
			LF	3	1	1,320.00	$22.00	$29,040.00
			LF	4	1	160.00	$20.00	$3,200.00
			LF	8	1	9,100.00	$13.00	$118,300.00
			LF	12	1	600.00	$32.00	$19,200.00
		Unit Sub Total	**LF**		**5**	**11,190.00**	**$15.26**	**$170,740.00**
731501	MINOR CONCRETE (CURB)		M	11	1	537.00	$60.00	$32,220.00
		Unit Sub Total	**M**		**1**	**537.00**	**$60.00**	**$32,220.00**
731501	MINOR CONCRETE (CURB)		M3	7	1	18.00	$350.00	$6,300.00
		Unit Sub Total	**M3**		**1**	**18.00**	**$350.00**	**$6,300.00**
	Item Code 731501	**Total No. of Proj.**			**18**		**Total Amount**	**$471,817.50**
731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)		CY	1	2	13.10	$721.76	$9,455.00
			CY	2	4	205.00	$977.66	$200,420.00
			CY	3	6	762.90	$404.32	$308,452.50
			CY	4	12	2,940.60	$350.34	$1,030,222.40
			CY	5	2	274.00	$761.31	$208,600.00
			CY	6	7	849.20	$563.98	$478,929.54
			CY	8	3	117.00	$529.41	$61,941.00
			CY	10	5	940.00	$515.99	$485,030.00
			CY	11	4	503.60	$478.95	$241,200.00
			CY	12	7	634.00	$351.88	$223,090.00
		Unit Sub Total	**CY**		**52**	**7,239.40**	**$448.56**	**$3,247,340.44**
731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)		M3	4	1	55.00	$870.00	$47,850.00
			M3	5	1	2,080.00	$550.00	$1,144,000.00
			M3	7	2	4.80	$1,037.50	$4,980.00
			M3	8	1	230.00	$350.00	$80,500.00
			M3	11	2	559.00	$311.14	$173,930.00
		Unit Sub Total	**M3**		**7**	**2,928.80**	**$495.51**	**$1,451,260.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 731502 Total No. of Proj.			**59**		**Total Amount**	**$4,698,600.44**
731504	MINOR CONCRETE (CURB AND GUTTER)	CY	1	1	120.00	$550.00	$66,000.00
		CY	2	1	24.00	$400.00	$9,600.00
		CY	3	2	1,309.00	$402.64	$527,050.00
		CY	4	1	60.00	$402.90	$24,174.00
		CY	5	1	40.00	$350.00	$14,000.00
		CY	6	2	47.00	$457.45	$21,500.00
		CY	7	3	156.00	$451.09	$70,370.00
		CY	8	1	31.00	$515.00	$15,965.00
	Unit Sub Total	**CY**		**12**	**1,787.00**	**$418.95**	**$748,659.00**
731504	MINOR CONCRETE (CURB AND GUTTER)	LF	12	1	36.00	$60.00	$2,160.00
	Unit Sub Total	**LF**		**1**	**36.00**	**$60.00**	**$2,160.00**
	Item Code 731504 Total No. of Proj.			**13**		**Total Amount**	**$750,819.00**
731505	MINOR CONCRETE (CURB AND SIDEWALK)	CY	3	1	10.00	$650.00	$6,500.00
	Unit Sub Total	**CY**		**1**	**10.00**	**$650.00**	**$6,500.00**
	Item Code 731505 Total No. of Proj.			**1**		**Total Amount**	**$6,500.00**
731507	MINOR CONCRETE (GUTTER DEPRESSION)	CY	4	1	200.00	$370.00	$74,000.00
		CY	7	1	1.00	$2,000.00	$2,000.00
	Unit Sub Total	**CY**		**2**	**201.00**	**$378.11**	**$76,000.00**
731507	MINOR CONCRETE (GUTTER DEPRESSION)	M3	7	1	11.00	$600.00	$6,600.00
	Unit Sub Total	**M3**		**1**	**11.00**	**$600.00**	**$6,600.00**
	Item Code 731507 Total No. of Proj.			**3**		**Total Amount**	**$82,600.00**
731508	MINOR CONCRETE (EXPOSED AGGREGATE CONCRETE)	M2	5	1	1,670.00	$50.00	$83,500.00
	Unit Sub Total	**M2**		**1**	**1,670.00**	**$50.00**	**$83,500.00**
	Item Code 731508 Total No. of Proj.			**1**		**Total Amount**	**$83,500.00**
731509	MINOR CONCRETE (CONCRETE MOW STRIP)	CY	7	1	36.00	$580.00	$20,880.00
	Unit Sub Total	**CY**		**1**	**36.00**	**$580.00**	**$20,880.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 731509 Total No. of Proj.			**1**		**Total Amount**	**$20,880.00**
731510	MINOR CONCRETE (CURB, GUTTER, SIDEWALK AND DRIVEWAY)	CY	7	1	16.00	$330.00	$5,280.00
	Unit Sub Total	**CY**		**1**	**16.00**	**$330.00**	**$5,280.00**
731510	MINOR CONCRETE (CURB, GUTTER, SIDEWALK AND DRIVEWAY)	M3	7	1	35.00	$650.00	$22,750.00
	Unit Sub Total	**M3**		**1**	**35.00**	**$650.00**	**$22,750.00**
	Item Code 731510 Total No. of Proj.			**2**		**Total Amount**	**$28,030.00**
731511	MINOR CONCRETE (ISLAND PAVING)	CY	1	1	0.30	$265.00	$79.50
		CY	4	1	2.00	$668.10	$1,336.20
		CY	7	1	60.00	$720.00	$43,200.00
	Unit Sub Total	**CY**		**3**	**62.30**	**$716.14**	**$44,615.70**
	Item Code 731511 Total No. of Proj.			**3**		**Total Amount**	**$44,615.70**
731516	MINOR CONCRETE (DRIVEWAY)	CY	3	1	11.00	$550.00	$6,050.00
		CY	4	1	20.00	$283.56	$5,671.20
		CY	5	1	70.00	$280.00	$19,600.00
		CY	8	1	19.00	$415.00	$7,885.00
	Unit Sub Total	**CY**		**4**	**120.00**	**$326.72**	**$39,206.20**
	Item Code 731516 Total No. of Proj.			**4**		**Total Amount**	**$39,206.20**
731517	MINOR CONCRETE (GUTTER)	CY	1	1	42.00	$350.00	$14,700.00
		CY	3	1	7.60	$550.00	$4,180.00
		CY	9	1	21.00	$450.00	$9,450.00
	Unit Sub Total	**CY**		**3**	**70.60**	**$401.27**	**$28,330.00**
731517	MINOR CONCRETE (GUTTER)	LF	1	1	25.00	$200.00	$5,000.00
		LF	3	2	307.00	$33.77	$10,366.25
		LF	4	3	3,724.00	$25.47	$94,844.00
		LF	5	1	880.00	$15.00	$13,200.00
		LF	12	3	5,171.00	$21.67	$112,038.00
	Unit Sub Total	**LF**		**10**	**10,107.00**	**$23.30**	**$235,448.25**
731517	MINOR CONCRETE (GUTTER)	M	5	1	458.00	$75.00	$34,350.00
		M	8	1	202.00	$120.00	$24,240.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
731517	MINOR CONCRETE (GUTTER)	M	11	2	174.00	$133.74	$23,270.00
	Unit Sub Total	**M**		**4**	**834.00**	**$98.15**	**$81,860.00**
	Item Code 731517 Total No. of Proj.			**17**		**Total Amount**	**$345,638.25**
731519	MINOR CONCRETE (STAMPED CONCRETE)	CY	3	1	230.00	$551.25	$126,787.50
		CY	10	1	2.90	$1,025.00	$2,972.50
	Unit Sub Total	**CY**		**2**	**232.90**	**$557.15**	**$129,760.00**
731519	MINOR CONCRETE (STAMPED CONCRETE)	M2	7	1	450.00	$148.00	$66,600.00
		M2	11	1	2,930.00	$75.00	$219,750.00
	Unit Sub Total	**M2**		**2**	**3,380.00**	**$84.72**	**$286,350.00**
731519	MINOR CONCRETE (STAMPED CONCRETE)	SQFT	7	1	7,000.00	$6.15	$43,050.00
	Unit Sub Total	**SQFT**		**1**	**7,000.00**	**$6.15**	**$43,050.00**
731519	MINOR CONCRETE (STAMPED CONCRETE)	SQYD	1	1	670.00	$63.00	$42,210.00
		SQYD	3	1	130.00	$150.00	$19,500.00
	Unit Sub Total	**SQYD**		**2**	**800.00**	**$77.14**	**$61,710.00**
	Item Code 731519 Total No. of Proj.			**7**		**Total Amount**	**$520,870.00**
731521	MINOR CONCRETE (SIDEWALK)	CY	1	1	130.00	$770.00	$100,100.00
		CY	2	2	95.70	$382.71	$36,625.00
		CY	3	3	130.10	$456.68	$59,414.00
		CY	4	1	78.00	$334.60	$26,098.80
		CY	5	1	28.00	$350.00	$9,800.00
		CY	6	2	390.30	$275.63	$107,580.00
		CY	7	1	16.00	$320.00	$5,120.00
		CY	8	1	62.00	$540.00	$33,480.00
		CY	12	2	31.00	$436.32	$13,526.00
	Unit Sub Total	**CY**		**14**	**961.10**	**$407.60**	**$391,743.80**
	Item Code 731521 Total No. of Proj.			**14**		**Total Amount**	**$391,743.80**
731530	MINOR CONCRETE (TEXTURED PAVING)	CY	11	1	76.00	$584.00	$44,384.00
	Unit Sub Total	**CY**		**1**	**76.00**	**$584.00**	**$44,384.00**
731530	MINOR CONCRETE (TEXTURED PAVING)	M2	7	1	1,600.00	$95.00	$152,000.00
		M2	11	1	1,550.00	$64.00	$99,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M2**		**2**	**3,150.00**	**$79.75**	**$251,200.00**
731530	MINOR CONCRETE (TEXTURED PAVING)	SQFT	2	1	10,700.00	$10.00	$107,000.00
		SQFT	3	1	55,624.00	$7.00	$389,368.00
		SQFT	5	2	10,620.00	$8.00	$84,965.00
		SQFT	6	5	126,390.00	$6.41	$810,138.00
		SQFT	7	1	13,200.00	$8.15	$107,580.00
		SQFT	10	3	51,160.00	$8.26	$422,460.00
		SQFT	11	1	7,780.00	$4.00	$31,120.00
		SQFT	12	2	308.00	$20.36	$6,272.00
	Unit Sub Total	**SQFT**		**16**	**275,782.00**	**$7.10**	**$1,958,903.00**
731530	MINOR CONCRETE (TEXTURED PAVING)	SQYD	2	2	1,000.00	$76.10	$76,100.00
		SQYD	11	1	410.00	$50.00	$20,500.00
	Unit Sub Total	**SQYD**		**3**	**1,410.00**	**$68.51**	**$96,600.00**
	Item Code 731530 Total No. of Proj.			**22**		**Total Amount**	**$2,351,087.00**
731623	MINOR CONCRETE (CURB RAMP)	CY	1	1	24.00	$1,800.00	$43,200.00
		CY	3	1	1.00	$3,000.00	$3,000.00
		CY	4	1	7.00	$591.60	$4,141.20
		CY	5	1	3.00	$390.00	$1,170.00
		CY	6	2	4.50	$1,328.33	$5,977.50
		CY	7	3	35.00	$619.43	$21,680.00
		CY	12	2	21.00	$278.57	$5,850.00
	Unit Sub Total	**CY**		**11**	**95.50**	**$890.25**	**$85,018.70**
731623	MINOR CONCRETE (CURB RAMP)	LF	12	1	6.00	$500.00	$3,000.00
	Unit Sub Total	**LF**		**1**	**6.00**	**$500.00**	**$3,000.00**
731623	MINOR CONCRETE (CURB RAMP)	M3	7	1	2.30	$1,550.00	$3,565.00
	Unit Sub Total	**M3**		**1**	**2.30**	**$1,550.00**	**$3,565.00**
	Item Code 731623 Total No. of Proj.			**13**		**Total Amount**	**$91,583.70**
731626	MINOR CONCRETE (CURB AND CURB RAMP)	CY	5	1	150.00	$370.00	$55,500.00
	Unit Sub Total	**CY**		**1**	**150.00**	**$370.00**	**$55,500.00**
	Item Code 731626 Total No. of Proj.			**1**		**Total Amount**	**$55,500.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
731627	MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP)	CY	1	1	200.00	$640.00	$128,000.00
		CY	3	3	40.70	$796.95	$32,436.00
		CY	4	1	20.00	$925.00	$18,500.00
		CY	6	1	51.00	$440.00	$22,440.00
		CY	8	2	69.00	$295.65	$20,400.00
		CY	12	3	114.00	$243.49	$27,758.00
	Unit Sub Total	**CY**		**11**	**494.70**	**$504.41**	**$249,534.00**
	Item Code 731627 Total No. of Proj.			**11**		**Total Amount**	**$249,534.00**
731656	CURB RAMP DETECTABLE WARNING SURFACE	M2	8	1	1.10	$150.00	$165.00
	Unit Sub Total	**M2**		**1**	**1.10**	**$150.00**	**$165.00**
731656	CURB RAMP DETECTABLE WARNING SURFACE	SQFT	2	1	170.00	$30.00	$5,100.00
		SQFT	3	2	188.00	$31.38	$5,900.00
		SQFT	4	1	90.00	$25.00	$2,250.00
		SQFT	5	1	48.00	$59.00	$2,832.00
		SQFT	6	1	15.00	$33.00	$495.00
		SQFT	11	1	150.00	$28.00	$4,200.00
		SQFT	12	2	84.00	$39.52	$3,320.00
	Unit Sub Total	**SQFT**		**9**	**745.00**	**$32.34**	**$24,097.00**
731656	CURB RAMP DETECTABLE WARNING SURFACE	SQYD	1	1	26.00	$300.00	$7,800.00
	Unit Sub Total	**SQYD**		**1**	**26.00**	**$300.00**	**$7,800.00**
	Item Code 731656 Total No. of Proj.			**11**		**Total Amount**	**$32,062.00**
740500	DRAINAGE PUMPING EQUIPMENT	LS	5	1	1.00	$123,000.00	$123,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$123,000.00**	**$123,000.00**
	Item Code 740500 Total No. of Proj.			**1**		**Total Amount**	**$123,000.00**
741001	PUMPING PLANT ELECTRICAL EQUIPMENT	LS	5	1	1.00	$160,000.00	$160,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$160,000.00**	**$160,000.00**
	Item Code 741001 Total No. of Proj.			**1**		**Total Amount**	**$160,000.00**
750001	MISCELLANEOUS IRON AND STEEL	KG	4	1	5,120.00	$2.50	$12,800.00
		KG	5	1	47,663.00	$3.00	$142,989.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
750001	MISCELLANEOUS IRON AND STEEL	KG	7	6	45,251.00	$3.51	$158,809.30
		KG	8	1	12,341.00	$3.00	$37,023.00
		KG	10	1	970.00	$4.50	$4,365.00
		KG	11	2	19,932.00	$1.24	$24,633.00
	Unit Sub Total	**KG**		**12**	**131,277.00**	**$2.90**	**$380,619.30**
750001	MISCELLANEOUS IRON AND STEEL	LB	1	11	18,753.00	$2.07	$38,839.34
		LB	2	10	96,252.00	$1.98	$190,367.15
		LB	3	11	121,545.00	$1.70	$206,707.10
		LB	4	17	382,821.00	$1.34	$512,663.50
		LB	5	6	12,993.00	$1.93	$25,135.30
		LB	6	8	72,062.00	$1.62	$116,451.90
		LB	7	11	418,089.00	$1.29	$539,698.90
		LB	8	3	1,930.00	$3.50	$6,761.00
		LB	9	1	239.00	$5.00	$1,195.00
		LB	10	4	82,853.00	$1.96	$162,523.00
		LB	11	6	14,607.00	$1.95	$28,453.60
		LB	12	7	75,028.00	$1.56	$116,859.60
	Unit Sub Total	**LB**		**95**	**1,297,172.00**	**$1.50**	**$1,945,655.39**
	Item Code 750001 Total No. of Proj.			**107**		**Total Amount**	**$2,326,274.69**
750007	FRAME AND GRATE	EA	6	1	1.00	$450.00	$450.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$450.00**	**$450.00**
	Item Code 750007 Total No. of Proj.			**1**		**Total Amount**	**$450.00**
750010	MANHOLE FRAME AND COVER	EA	3	1	20.00	$500.00	$10,000.00
		EA	5	1	23.00	$1,000.00	$23,000.00
		EA	10	1	3.00	$800.00	$2,400.00
	Unit Sub Total	**EA**		**3**	**46.00**	**$769.57**	**$35,400.00**
	Item Code 750010 Total No. of Proj.			**3**		**Total Amount**	**$35,400.00**
750011	MANHOLE FRAME AND GRATE	EA	5	1	9.00	$1,000.00	$9,000.00
	Unit Sub Total	**EA**		**1**	**9.00**	**$1,000.00**	**$9,000.00**
	Item Code 750011 Total No. of Proj.			**1**		**Total Amount**	**$9,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
750030	INLET FRAME AND GRATE	EA	5	1	7.00	$300.00	$2,100.00
	Unit Sub Total	**EA**		**1**	**7.00**	**$300.00**	**$2,100.00**
	Item Code 750030 Total No. of Proj.			**1**		**Total Amount**	**$2,100.00**
750041	ISOLATION CASING	KG	7	1	71,069.00	$10.00	$710,690.00
		KG	8	1	900.00	$6.00	$5,400.00
	Unit Sub Total	**KG**		**2**	**71,969.00**	**$9.95**	**$716,090.00**
	Item Code 750041 Total No. of Proj.			**2**		**Total Amount**	**$716,090.00**
750049	INLET GRATE (TYPE 36R)	KG	11	1	321.00	$5.00	$1,605.00
	Unit Sub Total	**KG**		**1**	**321.00**	**$5.00**	**$1,605.00**
	Item Code 750049 Total No. of Proj.			**1**		**Total Amount**	**$1,605.00**
750496	MISCELLANEOUS METAL (RESTRAINER - PIPE TYPE)	LB	3	1	6,765.00	$5.00	$33,825.00
		LB	10	1	18,000.00	$5.00	$90,000.00
	Unit Sub Total	**LB**		**2**	**24,765.00**	**$5.00**	**$123,825.00**
	Item Code 750496 Total No. of Proj.			**2**		**Total Amount**	**$123,825.00**
750497	MISCELLANEOUS METAL (RESTRAINER - BAR TYPE)	LB	3	1	3,214.00	$5.00	$16,070.00
	Unit Sub Total	**LB**		**1**	**3,214.00**	**$5.00**	**$16,070.00**
	Item Code 750497 Total No. of Proj.			**1**		**Total Amount**	**$16,070.00**
750498	MISCELLANEOUS METAL (RESTRAINER - CABLE TYPE)	KG	7	1	4,020.00	$10.00	$40,200.00
	Unit Sub Total	**KG**		**1**	**4,020.00**	**$10.00**	**$40,200.00**
750498	MISCELLANEOUS METAL (RESTRAINER - CABLE TYPE)	LB	3	3	51,274.00	$3.81	$195,405.00
		LB	5	1	28,506.00	$3.00	$85,518.00
		LB	10	1	3,160.00	$10.00	$31,600.00
	Unit Sub Total	**LB**		**5**	**82,940.00**	**$3.77**	**$312,523.00**
	Item Code 750498 Total No. of Proj.			**6**		**Total Amount**	**$352,723.00**
750500	MISCELLANEOUS METAL	KG	7	1	1,330.00	$9.00	$11,970.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**KG**		**1**	**1,330.00**	**$9.00**	**$11,970.00**
	Item Code 750500	**Total No. of Proj.**			**1**		**Total Amount**	**$11,970.00**
750501	MISCELLANEOUS METAL (BRIDGE)		KG	7	2	14,066.00	$13.76	$193,618.00
			KG	11	1	32,500.00	$1.00	$32,500.00
		Unit Sub Total	**KG**		**3**	**46,566.00**	**$4.86**	**$226,118.00**
750501	MISCELLANEOUS METAL (BRIDGE)		LB	1	1	1,292.00	$5.00	$6,460.00
			LB	3	5	6,152.00	$7.45	$45,857.00
			LB	4	2	6,616.00	$5.89	$38,970.00
			LB	6	1	1,740.00	$4.00	$6,960.00
			LB	7	5	479,536.00	$2.06	$986,855.90
			LB	8	1	14,032.00	$7.00	$98,224.00
			LB	10	2	380.00	$30.26	$11,500.00
			LB	12	1	2,000.00	$9.00	$18,000.00
		Unit Sub Total	**LB**		**18**	**511,748.00**	**$2.37**	**$1,212,826.90**
	Item Code 750501	**Total No. of Proj.**			**21**		**Total Amount**	**$1,438,944.90**
750505	BRIDGE DECK DRAINAGE SYSTEM		KG	5	1	2,474.00	$20.00	$49,480.00
			KG	7	2	37,996.00	$11.43	$434,117.00
			KG	8	1	4,875.00	$6.00	$29,250.00
			KG	11	2	16,300.00	$3.83	$62,400.00
		Unit Sub Total	**KG**		**6**	**61,645.00**	**$9.33**	**$575,247.00**
750505	BRIDGE DECK DRAINAGE SYSTEM		LB	3	3	117,438.00	$3.28	$384,963.00
			LB	4	2	104,610.00	$3.15	$329,656.00
			LB	6	1	7,883.00	$6.00	$47,298.00
			LB	7	2	299,150.00	$2.09	$624,040.00
			LB	8	1	35,600.00	$5.00	$178,000.00
			LB	10	1	32,270.00	$7.50	$242,025.00
			LB	12	1	8,200.00	$4.40	$36,080.00
		Unit Sub Total	**LB**		**11**	**605,151.00**	**$3.04**	**$1,842,062.00**
	Item Code 750505	**Total No. of Proj.**			**17**		**Total Amount**	**$2,417,309.00**
760011	WELL DEVELOPMENT		LS	5	1	1.00	$5,000.00	$5,000.00
			LS	10	1	1.00	$8,100.00	$8,100.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LS**		**2**	**2.00**	**$6,550.00**	**$13,100.00**
	Item Code 760011	**Total No. of Proj.**			**2**		**Total Amount**	**$13,100.00**
760012	TESTING WELL		HR	5	1	10.00	$200.00	$2,000.00
			HR	10	1	8.00	$154.00	$1,232.00
		Unit Sub Total	**HR**		**2**	**18.00**	**$179.56**	**$3,232.00**
	Item Code 760012	**Total No. of Proj.**			**2**		**Total Amount**	**$3,232.00**
760021	DRILL PILOT HOLE		LF	10	1	260.00	$33.00	$8,580.00
		Unit Sub Total	**LF**		**1**	**260.00**	**$33.00**	**$8,580.00**
760021	DRILL PILOT HOLE		M	5	1	100.00	$150.00	$15,000.00
		Unit Sub Total	**M**		**1**	**100.00**	**$150.00**	**$15,000.00**
	Item Code 760021	**Total No. of Proj.**			**2**		**Total Amount**	**$23,580.00**
760022	REAMING WATER WELL		LF	10	1	260.00	$47.50	$12,350.00
		Unit Sub Total	**LF**		**1**	**260.00**	**$47.50**	**$12,350.00**
760022	REAMING WATER WELL		M	5	1	100.00	$325.00	$32,500.00
		Unit Sub Total	**M**		**1**	**100.00**	**$325.00**	**$32,500.00**
	Item Code 760022	**Total No. of Proj.**			**2**		**Total Amount**	**$44,850.00**
760025	CONDUCTOR CASING		LF	10	1	50.00	$63.00	$3,150.00
		Unit Sub Total	**LF**		**1**	**50.00**	**$63.00**	**$3,150.00**
760025	CONDUCTOR CASING		M	5	1	16.00	$315.00	$5,040.00
		Unit Sub Total	**M**		**1**	**16.00**	**$315.00**	**$5,040.00**
	Item Code 760025	**Total No. of Proj.**			**2**		**Total Amount**	**$8,190.00**
760030	BLANK WELL CASING		LF	10	1	210.00	$12.50	$2,625.00
		Unit Sub Total	**LF**		**1**	**210.00**	**$12.50**	**$2,625.00**
760030	BLANK WELL CASING		M	5	1	98.00	$120.00	$11,760.00
		Unit Sub Total	**M**		**1**	**98.00**	**$120.00**	**$11,760.00**
	Item Code 760030	**Total No. of Proj.**			**2**		**Total Amount**	**$14,385.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
760035	WELL SCREEN		LF	10	1	50.00	$17.00	$850.00
		Unit Sub Total	**LF**		**1**	**50.00**	**$17.00**	**$850.00**
760035	WELL SCREEN		M	5	1	12.00	$430.00	$5,160.00
		Unit Sub Total	**M**		**1**	**12.00**	**$430.00**	**$5,160.00**
	Item Code 760035	**Total No. of Proj.**			**2**		**Total Amount**	**$6,010.00**
760080	WATER SUPPLY SYSTEM		LS	5	1	1.00	$20,000.00	$20,000.00
			LS	10	1	1.00	$13,850.00	$13,850.00
		Unit Sub Total	**LS**		**2**	**2.00**	**$16,925.00**	**$33,850.00**
	Item Code 760080	**Total No. of Proj.**			**2**		**Total Amount**	**$33,850.00**
760090	MOBILIZATION, DEMOBILIZATION, AND FINAL CLEANUP		LS	5	1	1.00	$6,000.00	$6,000.00
			LS	10	1	1.00	$2,000.00	$2,000.00
		Unit Sub Total	**LS**		**2**	**2.00**	**$4,000.00**	**$8,000.00**
	Item Code 760090	**Total No. of Proj.**			**2**		**Total Amount**	**$8,000.00**
800001	FENCE (TYPE BW, METAL POST)		LF	1	1	1,210.00	$16.00	$19,360.00
			LF	2	1	40.00	$50.00	$2,000.00
			LF	3	1	190.00	$25.00	$4,750.00
		Unit Sub Total	**LF**		**3**	**1,440.00**	**$18.13**	**$26,110.00**
800001	FENCE (TYPE BW, METAL POST)		M	5	1	5,550.00	$15.50	$86,025.00
		Unit Sub Total	**M**		**1**	**5,550.00**	**$15.50**	**$86,025.00**
	Item Code 800001	**Total No. of Proj.**			**4**		**Total Amount**	**$112,135.00**
800007	FENCE (TYPE BW, 5 STRAND, METAL POST)		LF	1	1	640.00	$11.00	$7,040.00
			LF	4	1	8,070.00	$5.90	$47,613.00
			LF	5	1	850.00	$10.00	$8,500.00
			LF	8	1	3,990.00	$6.00	$23,940.00
		Unit Sub Total	**LF**		**4**	**13,550.00**	**$6.43**	**$87,093.00**
	Item Code 800007	**Total No. of Proj.**			**4**		**Total Amount**	**$87,093.00**
800008	FENCE (TYPE BW, 4-STRAND, METAL POST)		LF	6	2	170,500.00	$3.87	$659,000.00
			LF	11	1	2,890.00	$5.00	$14,450.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**3**	**173,390.00**	**$3.88**	**$673,450.00**
800008	FENCE (TYPE BW, 4-STRAND, METAL POST)	M	7	1	11.00	$80.00	$880.00
	Unit Sub Total	**M**		**1**	**11.00**	**$80.00**	**$880.00**
	Item Code 800008 Total No. of Proj.			**4**		**Total Amount**	**$674,330.00**
800010	FENCE (TYPE BW, 4-STRAND, WOOD POST)	LF	10	1	680.00	$10.00	$6,800.00
	Unit Sub Total	**LF**		**1**	**680.00**	**$10.00**	**$6,800.00**
	Item Code 800010 Total No. of Proj.			**1**		**Total Amount**	**$6,800.00**
800051	FENCE (TYPE WM, METAL POST)	LF	1	2	715.00	$12.71	$9,090.00
		LF	3	1	850.00	$12.00	$10,200.00
		LF	4	1	2,340.00	$9.00	$21,060.00
		LF	6	1	17,900.00	$5.00	$89,500.00
		LF	10	1	15,200.00	$9.00	$136,800.00
	Unit Sub Total	**LF**		**6**	**37,005.00**	**$7.21**	**$266,650.00**
800051	FENCE (TYPE WM, METAL POST)	M	10	1	6,460.00	$15.00	$96,900.00
	Unit Sub Total	**M**		**1**	**6,460.00**	**$15.00**	**$96,900.00**
	Item Code 800051 Total No. of Proj.			**7**		**Total Amount**	**$363,550.00**
800052	FENCE (TYPE WM, WOOD POST)	LF	1	1	2,000.00	$12.50	$25,000.00
	Unit Sub Total	**LF**		**1**	**2,000.00**	**$12.50**	**$25,000.00**
	Item Code 800052 Total No. of Proj.			**1**		**Total Amount**	**$25,000.00**
800060	FENCE (TYPE WM AND BW)	LF	3	1	1,400.00	$10.00	$14,000.00
	Unit Sub Total	**LF**		**1**	**1,400.00**	**$10.00**	**$14,000.00**
	Item Code 800060 Total No. of Proj.			**1**		**Total Amount**	**$14,000.00**
800300	CHAIN LINK FENCE	LF	3	1	45.00	$40.00	$1,800.00
		LF	8	1	28.00	$94.00	$2,632.00
	Unit Sub Total	**LF**		**2**	**73.00**	**$60.71**	**$4,432.00**
	Item Code 800300 Total No. of Proj.			**2**		**Total Amount**	**$4,432.00**
800302	CHAIN LINK FENCE (TYPE CL-3, VINYL-CLAD)	LF	4	1	140.00	$19.00	$2,660.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**1**	**140.00**	**$19.00**	**$2,660.00**
	Item Code 800302	**Total No. of Proj.**			**1**		**Total Amount**	**$2,660.00**
800320	CHAIN LINK FENCE (TYPE CL-4)		LF	2	1	35.00	$112.64	$3,942.26
			LF	3	1	150.00	$30.80	$4,620.00
			LF	4	4	16,544.00	$12.22	$202,241.20
			LF	5	1	1,630.00	$15.00	$24,450.00
		Unit Sub Total	**LF**		**7**	**18,359.00**	**$12.81**	**$235,253.46**
	Item Code 800320	**Total No. of Proj.**			**7**		**Total Amount**	**$235,253.46**
800321	CHAIN LINK FENCE (TYPE CL-4, VINYL-CLAD)		LF	4	3	8,183.00	$10.53	$86,151.00
			LF	11	1	4,720.00	$17.00	$80,240.00
		Unit Sub Total	**LF**		**4**	**12,903.00**	**$12.90**	**$166,391.00**
	Item Code 800321	**Total No. of Proj.**			**4**		**Total Amount**	**$166,391.00**
800360	CHAIN LINK FENCE (TYPE CL-6)		LF	1	1	610.00	$20.00	$12,200.00
			LF	2	1	380.00	$23.00	$8,740.00
			LF	3	2	840.00	$17.62	$14,800.00
			LF	4	7	12,884.00	$15.91	$204,980.30
			LF	5	4	33,390.00	$14.46	$482,700.00
			LF	6	4	3,011.00	$17.13	$51,584.00
			LF	7	3	3,328.00	$15.48	$51,508.98
			LF	8	2	410.00	$22.07	$9,050.00
			LF	9	1	1,490.00	$35.00	$52,150.00
			LF	10	2	73.00	$77.66	$5,669.50
			LF	11	3	4,415.00	$20.24	$89,350.00
			LF	12	2	2,045.00	$20.31	$41,530.00
		Unit Sub Total	**LF**		**32**	**62,876.00**	**$16.29**	**$1,024,262.78**
	Item Code 800360	**Total No. of Proj.**			**32**		**Total Amount**	**$1,024,262.78**
800361	CHAIN LINK FENCE (TYPE CL-6, VINYL-CLAD)		LF	4	1	5,080.00	$13.00	$66,040.00
			LF	7	1	1,430.00	$20.00	$28,600.00
		Unit Sub Total	**LF**		**2**	**6,510.00**	**$14.54**	**$94,640.00**
	Item Code 800361	**Total No. of Proj.**			**2**		**Total Amount**	**$94,640.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
800365	CHAIN LINK FENCE (TYPE CL-6, SLATTED)	LF	4	1	140.00	$34.00	$4,760.00
	Unit Sub Total	**LF**		**1**	**140.00**	**$34.00**	**$4,760.00**
	Item Code 800365 Total No. of Proj.			**1**		**Total Amount**	**$4,760.00**
800381	CHAIN LINK FENCE (TYPE CL-0.9)	M	8	1	130.00	$40.00	$5,200.00
	Unit Sub Total	**M**		**1**	**130.00**	**$40.00**	**$5,200.00**
	Item Code 800381 Total No. of Proj.			**1**		**Total Amount**	**$5,200.00**
800385	CHAIN LINK FENCE (TYPE CL-1.2)	M	7	1	83.00	$51.00	$4,233.00
	Unit Sub Total	**M**		**1**	**83.00**	**$51.00**	**$4,233.00**
	Item Code 800385 Total No. of Proj.			**1**		**Total Amount**	**$4,233.00**
800391	CHAIN LINK FENCE (TYPE CL-1.8)	LF	1	1	240.00	$20.00	$4,800.00
	Unit Sub Total	**LF**		**1**	**240.00**	**$20.00**	**$4,800.00**
800391	CHAIN LINK FENCE (TYPE CL-1.8)	M	4	1	830.00	$40.00	$33,200.00
		M	5	1	8,390.00	$32.50	$272,675.00
		M	7	1	960.00	$45.00	$43,200.00
		M	8	1	500.00	$48.00	$24,000.00
		M	11	1	600.00	$50.00	$30,000.00
	Unit Sub Total	**M**		**5**	**11,280.00**	**$35.73**	**$403,075.00**
	Item Code 800391 Total No. of Proj.			**6**		**Total Amount**	**$407,875.00**
800400	CHAIN LINK FENCE (TYPE CL-8)	LF	10	1	920.00	$35.00	$32,200.00
		LF	11	1	60.00	$30.00	$1,800.00
	Unit Sub Total	**LF**		**2**	**980.00**	**$34.69**	**$34,000.00**
	Item Code 800400 Total No. of Proj.			**2**		**Total Amount**	**$34,000.00**
800701	WOOD FENCE	LF	3	1	79.00	$100.00	$7,900.00
		LF	4	1	390.00	$90.00	$35,100.00
	Unit Sub Total	**LF**		**2**	**469.00**	**$91.68**	**$43,000.00**
	Item Code 800701 Total No. of Proj.			**2**		**Total Amount**	**$43,000.00**
801120	5' WIRE MESH GATE	EA	3	1	1.00	$1,200.00	$1,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**1.00**	**$1,200.00**	**$1,200.00**
	Item Code 801120	**Total No. of Proj.**			**1**		**Total Amount**	**$1,200.00**
801130	6' WIRE MESH GATE		EA	4	1	7.00	$604.00	$4,228.00
		Unit Sub Total	**EA**		**1**	**7.00**	**$604.00**	**$4,228.00**
	Item Code 801130	**Total No. of Proj.**			**1**		**Total Amount**	**$4,228.00**
801230	16' WIRE MESH GATE		EA	8	1	2.00	$1,000.00	$2,000.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$1,000.00**	**$2,000.00**
	Item Code 801230	**Total No. of Proj.**			**1**		**Total Amount**	**$2,000.00**
801272	4.3 M WIRE MESH GATE		EA	10	1	1.00	$1,475.00	$1,475.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$1,475.00**	**$1,475.00**
	Item Code 801272	**Total No. of Proj.**			**1**		**Total Amount**	**$1,475.00**
801273	4.6 M WIRE MESH GATE		EA	10	1	1.00	$1,575.00	$1,575.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$1,575.00**	**$1,575.00**
	Item Code 801273	**Total No. of Proj.**			**1**		**Total Amount**	**$1,575.00**
801274	4.9 M WIRE MESH GATE		EA	10	1	5.00	$1,600.00	$8,000.00
		Unit Sub Total	**EA**		**1**	**5.00**	**$1,600.00**	**$8,000.00**
	Item Code 801274	**Total No. of Proj.**			**1**		**Total Amount**	**$8,000.00**
801277	6.4 M WIRE MESH GATE		EA	10	1	1.00	$2,500.00	$2,500.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$2,500.00**	**$2,500.00**
	Item Code 801277	**Total No. of Proj.**			**1**		**Total Amount**	**$2,500.00**
801364	16' METAL GATE		EA	1	1	1.00	$7,625.00	$7,625.00
			EA	10	1	9.00	$5,000.00	$45,000.00
		Unit Sub Total	**EA**		**2**	**10.00**	**$5,262.50**	**$52,625.00**
	Item Code 801364	**Total No. of Proj.**			**2**		**Total Amount**	**$52,625.00**
801900	CHAIN LINK GATE		EA	4	1	2.00	$969.00	$1,938.00
			EA	5	2	12.00	$1,100.00	$13,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
801900	CHAIN LINK GATE	EA	7	2	11.00	$1,936.36	$21,300.00
		EA	8	1	4.00	$845.00	$3,380.00
	Unit Sub Total	**EA**		**6**	**29.00**	**$1,373.03**	**$39,818.00**
	Item Code 801900 Total No. of Proj.			**6**		**Total Amount**	**$39,818.00**
802180	12' CHAIN LINK GATE (TYPE CL-4)	EA	10	1	2.00	$1,500.00	$3,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,500.00**	**$3,000.00**
	Item Code 802180 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
802501	4' CHAIN LINK GATE (TYPE CL-6)	EA	5	1	3.00	$1,000.00	$3,000.00
		EA	7	1	2.00	$1,780.00	$3,560.00
		EA	10	1	3.00	$1,600.00	$4,800.00
		EA	11	1	2.00	$1,300.00	$2,600.00
	Unit Sub Total	**EA**		**4**	**10.00**	**$1,396.00**	**$13,960.00**
	Item Code 802501 Total No. of Proj.			**4**		**Total Amount**	**$13,960.00**
802510	5' CHAIN LINK GATE (TYPE CL-6)	EA	4	1	1.00	$1,500.00	$1,500.00
		EA	12	1	3.00	$1,000.00	$3,000.00
	Unit Sub Total	**EA**		**2**	**4.00**	**$1,125.00**	**$4,500.00**
	Item Code 802510 Total No. of Proj.			**2**		**Total Amount**	**$4,500.00**
802520	6' CHAIN LINK GATE (TYPE CL-6)	EA	4	3	7.00	$1,371.43	$9,600.00
		EA	5	1	1.00	$1,650.00	$1,650.00
		EA	6	1	2.00	$950.00	$1,900.00
		EA	10	1	18.00	$1,000.00	$18,000.00
		EA	12	1	1.00	$1,050.00	$1,050.00
	Unit Sub Total	**EA**		**7**	**29.00**	**$1,110.34**	**$32,200.00**
	Item Code 802520 Total No. of Proj.			**7**		**Total Amount**	**$32,200.00**
802540	8' CHAIN LINK GATE (TYPE CL-6)	EA	6	1	2.00	$1,407.00	$2,814.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,407.00**	**$2,814.00**
	Item Code 802540 Total No. of Proj.			**1**		**Total Amount**	**$2,814.00**
802560	10' CHAIN LINK GATE (TYPE CL-6)	EA	4	1	3.00	$1,750.00	$5,250.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**1**	**3.00**	**$1,750.00**	**$5,250.00**
	Item Code 802560 Total No. of Proj.			**1**		**Total Amount**	**$5,250.00**
802580	12' CHAIN LINK GATE (TYPE CL-6)	EA	3	1	2.00	$2,000.00	$4,000.00
		EA	4	3	4.00	$2,423.00	$9,692.00
		EA	5	1	1.00	$2,000.00	$2,000.00
		EA	8	1	1.00	$2,050.00	$2,050.00
		EA	11	1	2.00	$1,250.00	$2,500.00
	Unit Sub Total	**EA**		**7**	**10.00**	**$2,024.20**	**$20,242.00**
	Item Code 802580 Total No. of Proj.			**7**		**Total Amount**	**$20,242.00**
802585	1.2 M CHAIN LINK GATE (TYPE CL-1.8)	EA	11	1	3.00	$850.00	$2,550.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$850.00**	**$2,550.00**
	Item Code 802585 Total No. of Proj.			**1**		**Total Amount**	**$2,550.00**
802590	1.8 M CHAIN LINK GATE (TYPE CL-1.8)	EA	5	1	1.00	$600.00	$600.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$600.00**	**$600.00**
	Item Code 802590 Total No. of Proj.			**1**		**Total Amount**	**$600.00**
802592	2.4 M CHAIN LINK GATE (TYPE CL-1.8)	EA	4	1	3.00	$1,000.00	$3,000.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$1,000.00**	**$3,000.00**
	Item Code 802592 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
802595	3.0 M CHAIN LINK GATE (TYPE CL-1.8)	EA	5	1	96.00	$835.00	$80,160.00
	Unit Sub Total	**EA**		**1**	**96.00**	**$835.00**	**$80,160.00**
	Item Code 802595 Total No. of Proj.			**1**		**Total Amount**	**$80,160.00**
802596	3.7 M CHAIN LINK GATE (TYPE CL-1.8)	EA	7	1	8.00	$1,120.00	$8,960.00
		EA	8	1	1.00	$1,300.00	$1,300.00
	Unit Sub Total	**EA**		**2**	**9.00**	**$1,140.00**	**$10,260.00**
	Item Code 802596 Total No. of Proj.			**2**		**Total Amount**	**$10,260.00**
802620	16' CHAIN LINK GATE (TYPE CL-6)	EA	6	1	1.00	$2,100.00	$2,100.00
		EA	12	1	7.00	$1,500.00	$10,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**2**	**8.00**	**$1,575.00**	**$12,600.00**
	Item Code 802620 Total No. of Proj.			**2**		**Total Amount**	**$12,600.00**
802660	20' CHAIN LINK GATE (TYPE CL-6)	EA	7	1	3.00	$1,500.00	$4,500.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$1,500.00**	**$4,500.00**
	Item Code 802660 Total No. of Proj.			**1**		**Total Amount**	**$4,500.00**
802670	24' CHAIN LINK GATE (TYPE CL-6)	EA	2	1	2.00	$2,100.00	$4,200.00
		EA	9	1	1.00	$5,000.00	$5,000.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$3,066.67**	**$9,200.00**
	Item Code 802670 Total No. of Proj.			**2**		**Total Amount**	**$9,200.00**
802671	4.3 M CHAIN LINK GATE (TYPE CL-1.8)	EA	7	1	1.00	$1,600.00	$1,600.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,600.00**	**$1,600.00**
	Item Code 802671 Total No. of Proj.			**1**		**Total Amount**	**$1,600.00**
802672	4.9 M CHAIN LINK GATE (TYPE CL-1.8)	EA	11	1	2.00	$1,600.00	$3,200.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,600.00**	**$3,200.00**
	Item Code 802672 Total No. of Proj.			**1**		**Total Amount**	**$3,200.00**
802676	7.3 M CHAIN LINK GATE (TYPE CL-1.8)	EA	7	1	1.00	$2,700.00	$2,700.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$2,700.00**	**$2,700.00**
	Item Code 802676 Total No. of Proj.			**1**		**Total Amount**	**$2,700.00**
804201	ROLLING CHAIN LINK GATE	EA	7	1	1.00	$3,350.00	$3,350.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$3,350.00**	**$3,350.00**
	Item Code 804201 Total No. of Proj.			**1**		**Total Amount**	**$3,350.00**
810110	SURVEY MONUMENT	EA	4	1	13.00	$800.00	$10,400.00
		EA	5	2	23.00	$500.00	$11,500.00
		EA	7	1	10.00	$1,500.00	$15,000.00
	Unit Sub Total	**EA**		**4**	**46.00**	**$802.17**	**$36,900.00**
	Item Code 810110 Total No. of Proj.			**4**		**Total Amount**	**$36,900.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
810111	SURVEY MONUMENT (TYPE A)	EA	2	2	27.00	$527.78	$14,250.00
		EA	5	1	1.00	$1,652.00	$1,652.00
		EA	6	1	31.00	$400.00	$12,400.00
		EA	10	2	4.00	$781.25	$3,125.00
	Unit Sub Total	**EA**		**6**	**63.00**	**$498.84**	**$31,427.00**
	Item Code 810111 Total No. of Proj.			**6**		**Total Amount**	**$31,427.00**
810112	SURVEY MONUMENT (TYPE B)	EA	6	1	4.00	$600.00	$2,400.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$600.00**	**$2,400.00**
	Item Code 810112 Total No. of Proj.			**1**		**Total Amount**	**$2,400.00**
810116	SURVEY MONUMENT (TYPE D)	EA	4	1	9.00	$550.00	$4,950.00
		EA	8	3	30.00	$700.00	$21,000.00
	Unit Sub Total	**EA**		**4**	**39.00**	**$665.38**	**$25,950.00**
	Item Code 810116 Total No. of Proj.			**4**		**Total Amount**	**$25,950.00**
820101	MARKER	EA	2	1	3.00	$60.00	$180.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$60.00**	**$180.00**
	Item Code 820101 Total No. of Proj.			**1**		**Total Amount**	**$180.00**
820107	DELINEATOR (CLASS 1)	EA	1	6	1,640.00	$33.94	$55,654.00
		EA	2	2	29.00	$49.31	$1,430.00
		EA	3	19	2,753.00	$33.30	$91,685.00
		EA	4	10	856.00	$39.44	$33,761.00
		EA	5	4	505.00	$23.13	$11,680.00
		EA	6	7	553.00	$45.01	$24,890.00
		EA	7	3	600.00	$28.65	$17,190.00
		EA	8	6	416.00	$35.96	$14,960.00
		EA	10	8	423.00	$38.51	$16,290.00
		EA	11	8	966.00	$51.34	$49,590.00
		EA	12	8	611.00	$40.92	$25,005.00
	Unit Sub Total	**EA**		**81**	**9,352.00**	**$36.58**	**$342,135.00**
	Item Code 820107 Total No. of Proj.			**81**		**Total Amount**	**$342,135.00**
820108	DELINEATOR (CLASS 2)	EA	1	2	268.00	$41.01	$10,990.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
820108	DELINEATOR (CLASS 2)	EA	2	10	1,881.00	$47.15	$88,690.00
		EA	3	6	655.00	$36.61	$23,982.00
		EA	7	1	39.00	$45.00	$1,755.00
		EA	8	1	720.00	$22.00	$15,840.00
		EA	9	4	1,163.00	$61.96	$72,060.00
		EA	10	1	18.00	$49.00	$882.00
	Unit Sub Total	**EA**		**25**	**4,744.00**	**$45.15**	**$214,199.00**
	Item Code 820108 Total No. of Proj.			**25**		**Total Amount**	**$214,199.00**
820110	MILEPOST MARKER	EA	1	3	23.00	$50.22	$1,155.00
		EA	2	7	94.00	$78.77	$7,404.00
		EA	3	1	6.00	$50.00	$300.00
		EA	4	2	174.00	$70.69	$12,300.00
		EA	6	1	26.00	$75.00	$1,950.00
		EA	9	2	21.00	$69.05	$1,450.00
		EA	10	2	6.00	$49.67	$298.00
		EA	11	12	166.00	$66.50	$11,039.00
		EA	12	1	48.00	$77.00	$3,696.00
	Unit Sub Total	**EA**		**31**	**564.00**	**$70.20**	**$39,592.00**
	Item Code 820110 Total No. of Proj.			**31**		**Total Amount**	**$39,592.00**
820111	UNDERDRAIN MARKER	EA	1	1	1.00	$50.00	$50.00
		EA	3	1	3.00	$40.00	$120.00
	Unit Sub Total	**EA**		**2**	**4.00**	**$42.50**	**$170.00**
	Item Code 820111 Total No. of Proj.			**2**		**Total Amount**	**$170.00**
820112	MARKER (CULVERT)	EA	1	11	225.00	$43.49	$9,785.00
		EA	2	9	271.00	$49.89	$13,519.00
		EA	3	8	158.00	$54.14	$8,554.00
		EA	4	1	93.00	$38.00	$3,534.00
		EA	7	1	4.00	$100.00	$400.00
		EA	9	5	168.00	$63.44	$10,658.00
		EA	10	1	62.00	$32.00	$1,984.00
	Unit Sub Total	**EA**		**36**	**981.00**	**$49.37**	**$48,434.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 820112 Total No. of Proj.			**36**		**Total Amount**	**$48,434.00**
820118	GUARD RAILING DELINEATOR	EA	1	6	433.00	$29.89	$12,942.00
		EA	2	5	140.00	$23.66	$3,313.00
		EA	3	2	8.00	$31.25	$250.00
		EA	4	5	178.00	$22.22	$3,955.00
		EA	5	4	163.00	$24.41	$3,978.40
		EA	7	1	270.00	$11.00	$2,970.00
		EA	8	3	319.00	$13.19	$4,209.00
		EA	10	3	104.00	$35.59	$3,701.00
		EA	11	9	501.00	$22.55	$11,300.00
		EA	12	8	6,149.00	$12.80	$78,727.00
	Unit Sub Total	**EA**		**46**	**8,265.00**	**$15.17**	**$125,345.40**
	Item Code 820118 Total No. of Proj.			**46**		**Total Amount**	**$125,345.40**
820130	OBJECT MARKER	EA	1	2	11.00	$50.00	$550.00
		EA	4	1	4.00	$10.00	$40.00
		EA	5	2	55.00	$28.45	$1,565.00
		EA	6	4	16.00	$107.50	$1,720.00
		EA	10	1	19.00	$50.00	$950.00
		EA	11	1	10.00	$25.00	$250.00
		EA	12	1	40.00	$36.00	$1,440.00
	Unit Sub Total	**EA**		**12**	**155.00**	**$42.03**	**$6,515.00**
	Item Code 820130 Total No. of Proj.			**12**		**Total Amount**	**$6,515.00**
820131	OBJECT MARKER (TYPE K)	EA	4	1	2.00	$60.00	$120.00
		EA	6	2	6.00	$49.17	$295.00
		EA	10	1	2.00	$33.00	$66.00
	Unit Sub Total	**EA**		**4**	**10.00**	**$48.10**	**$481.00**
	Item Code 820131 Total No. of Proj.			**4**		**Total Amount**	**$481.00**
820132	OBJECT MARKER (TYPE L)	EA	4	1	9.00	$35.00	$315.00
		EA	5	2	8.00	$46.13	$369.00
		EA	8	1	2.00	$100.00	$200.00
		EA	10	5	30.00	$47.20	$1,416.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**9**	**49.00**	**$46.94**	**$2,300.00**
	Item Code 820132	**Total No. of Proj.**			**9**		**Total Amount**	**$2,300.00**
820133	OBJECT MARKER (TYPE N)		EA	4	1	1.00	$45.90	$45.90
			EA	12	1	1.00	$100.00	$100.00
		Unit Sub Total	**EA**		**2**	**2.00**	**$72.95**	**$145.90**
	Item Code 820133	**Total No. of Proj.**			**2**		**Total Amount**	**$145.90**
820134	OBJECT MARKER (TYPE P)		EA	1	1	2.00	$95.00	$190.00
			EA	2	2	10.00	$160.00	$1,600.00
			EA	3	3	14.00	$60.71	$850.00
			EA	4	5	56.00	$58.75	$3,290.00
			EA	5	2	6.00	$56.67	$340.00
			EA	6	2	6.00	$59.00	$354.00
			EA	10	1	8.00	$80.00	$640.00
			EA	12	2	31.00	$51.13	$1,585.00
		Unit Sub Total	**EA**		**18**	**133.00**	**$66.53**	**$8,849.00**
	Item Code 820134	**Total No. of Proj.**			**18**		**Total Amount**	**$8,849.00**
820135	OBJECT MARKER (TYPE R)		EA	4	3	10.00	$40.50	$405.00
			EA	6	1	1.00	$55.00	$55.00
			EA	12	1	1.00	$55.00	$55.00
		Unit Sub Total	**EA**		**5**	**12.00**	**$42.92**	**$515.00**
	Item Code 820135	**Total No. of Proj.**			**5**		**Total Amount**	**$515.00**
820141	OBJECT MARKER (TYPE K-1)		EA	1	2	12.00	$67.67	$812.00
			EA	3	4	17.00	$38.09	$647.50
			EA	4	1	1.00	$50.00	$50.00
			EA	8	1	51.00	$13.00	$663.00
			EA	10	2	4.00	$41.25	$165.00
			EA	12	1	2.00	$91.00	$182.00
		Unit Sub Total	**EA**		**11**	**87.00**	**$28.96**	**$2,519.50**
	Item Code 820141	**Total No. of Proj.**			**11**		**Total Amount**	**$2,519.50**
820151	OBJECT MARKER (TYPE L-1)		EA	1	4	71.00	$40.77	$2,895.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
820151	OBJECT MARKER (TYPE L-1)	EA	2	2	21.00	$169.05	$3,550.00
		EA	3	24	279.00	$55.37	$15,448.45
		EA	4	5	50.00	$51.90	$2,595.00
		EA	5	1	1.00	$90.00	$90.00
		EA	6	2	39.00	$53.33	$2,080.00
		EA	8	1	8.00	$50.00	$400.00
		EA	9	2	13.00	$78.08	$1,015.00
		EA	10	2	12.00	$29.50	$354.00
	Unit Sub Total	**EA**		**43**	**494.00**	**$57.55**	**$28,427.45**
	Item Code 820151 Total No. of Proj.			**43**		**Total Amount**	**$28,427.45**
820152	OBJECT MARKER (TYPE L-2)	EA	2	2	22.00	$52.73	$1,160.00
		EA	5	1	6.00	$100.00	$600.00
		EA	9	1	70.00	$67.00	$4,690.00
	Unit Sub Total	**EA**		**4**	**98.00**	**$65.82**	**$6,450.00**
	Item Code 820152 Total No. of Proj.			**4**		**Total Amount**	**$6,450.00**
820180	INSTALL MEDIAN MILEAGE PANEL	EA	7	2	36.00	$119.44	$4,300.00
	Unit Sub Total	**EA**		**2**	**36.00**	**$119.44**	**$4,300.00**
	Item Code 820180 Total No. of Proj.			**2**		**Total Amount**	**$4,300.00**
820190	SPECIAL MARKER	EA	7	1	4.00	$100.00	$400.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$100.00**	**$400.00**
	Item Code 820190 Total No. of Proj.			**1**		**Total Amount**	**$400.00**
832001	METAL BEAM GUARD RAILING	LF	1	6	4,050.00	$30.12	$122,000.00
		LF	2	7	1,495.00	$41.66	$62,280.00
		LF	3	9	26,593.00	$16.10	$428,176.40
		LF	4	4	11,800.00	$17.85	$210,680.00
		LF	6	1	19.00	$35.00	$665.00
		LF	7	1	4,230.00	$19.25	$81,427.50
		LF	8	1	730.00	$23.00	$16,790.00
		LF	10	1	640.00	$21.50	$13,760.00
		LF	11	6	6,760.00	$22.80	$154,110.00
		LF	12	1	5,830.00	$19.00	$110,770.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**37**	**62,147.00**	**$19.32**	**$1,200,658.90**
832001	METAL BEAM GUARD RAILING		M	7	2	266.00	$107.37	$28,560.00
			M	11	2	176.00	$99.43	$17,500.00
		Unit Sub Total	**M**		**4**	**442.00**	**$104.21**	**$46,060.00**
	Item Code 832001	**Total No. of Proj.**			**41**		**Total Amount**	**$1,246,718.90**
832002	METAL BEAM GUARD RAILING (STEEL POST)		LF	1	2	425.00	$37.53	$15,950.00
			LF	2	4	6,350.00	$26.64	$169,160.00
			LF	3	5	20,000.00	$20.86	$417,210.00
			LF	4	2	6,850.00	$19.13	$131,050.00
			LF	5	5	3,795.00	$28.43	$107,890.00
			LF	6	8	4,263.00	$26.40	$112,531.00
			LF	7	1	7,540.00	$21.40	$161,356.00
			LF	8	4	15,440.00	$22.42	$346,219.00
			LF	10	1	560.00	$29.00	$16,240.00
			LF	11	2	2,910.00	$29.35	$85,410.00
		Unit Sub Total	**LF**		**34**	**68,133.00**	**$22.94**	**$1,563,016.00**
832002	METAL BEAM GUARD RAILING (STEEL POST)		M	5	1	6,630.00	$58.00	$384,540.00
		Unit Sub Total	**M**		**1**	**6,630.00**	**$58.00**	**$384,540.00**
	Item Code 832002	**Total No. of Proj.**			**35**		**Total Amount**	**$1,947,556.00**
832003	METAL BEAM GUARD RAILING (WOOD POST)		LF	1	4	3,725.00	$17.93	$66,800.00
			LF	2	2	680.00	$24.48	$16,645.00
			LF	3	5	20,300.00	$17.01	$345,340.00
			LF	4	10	19,105.00	$22.62	$432,221.70
			LF	6	1	1,510.00	$24.40	$36,844.00
			LF	7	8	4,285.00	$24.53	$105,130.50
			LF	8	9	73,210.00	$18.24	$1,335,506.50
			LF	10	3	2,810.00	$20.46	$57,490.00
			LF	11	1	390.00	$28.00	$10,920.00
			LF	12	11	42,282.00	$17.77	$751,473.88
		Unit Sub Total	**LF**		**54**	**168,297.00**	**$18.77**	**$3,158,371.58**
832003	METAL BEAM GUARD RAILING (WOOD POST)		M	7	1	46.00	$86.45	$3,976.70
			M	8	1	660.00	$75.00	$49,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**2**	**706.00**	**$75.75**	**$53,476.70**
	Item Code 832003 Total No. of Proj.			**56**		**Total Amount**	**$3,211,848.28**
832004	METAL BEAM GUARD RAILING (SPECIAL)	LF	5	1	75.00	$125.00	$9,375.00
	Unit Sub Total	**LF**		**1**	**75.00**	**$125.00**	**$9,375.00**
	Item Code 832004 Total No. of Proj.			**1**		**Total Amount**	**$9,375.00**
832012	METAL BEAM GUARD RAILING (7' WOOD POST)	LF	1	2	665.00	$28.50	$18,950.00
		LF	3	1	300.00	$22.00	$6,600.00
	Unit Sub Total	**LF**		**3**	**965.00**	**$26.48**	**$25,550.00**
	Item Code 832012 Total No. of Proj.			**3**		**Total Amount**	**$25,550.00**
832013	METAL BEAM GUARD RAILING (7' POST)	LF	1	1	38.00	$30.00	$1,140.00
		LF	2	1	250.00	$27.00	$6,750.00
	Unit Sub Total	**LF**		**2**	**288.00**	**$27.40**	**$7,890.00**
	Item Code 832013 Total No. of Proj.			**2**		**Total Amount**	**$7,890.00**
832014	METAL BEAM GUARD RAILING (8' POST)	LF	7	1	120.00	$30.00	$3,600.00
	Unit Sub Total	**LF**		**1**	**120.00**	**$30.00**	**$3,600.00**
	Item Code 832014 Total No. of Proj.			**1**		**Total Amount**	**$3,600.00**
832070	VEGETATION CONTROL (MINOR CONCRETE)	M2	5	1	11,200.00	$45.00	$504,000.00
	Unit Sub Total	**M2**		**1**	**11,200.00**	**$45.00**	**$504,000.00**
832070	VEGETATION CONTROL (MINOR CONCRETE)	SQYD	1	2	490.00	$66.53	$32,600.00
		SQYD	2	10	31,130.00	$41.00	$1,276,280.00
		SQYD	3	11	22,200.00	$54.43	$1,208,304.50
		SQYD	4	10	21,288.00	$52.18	$1,110,875.00
		SQYD	5	1	860.00	$78.00	$67,080.00
		SQYD	7	4	2,862.00	$27.59	$78,970.00
		SQYD	8	4	8,390.00	$15.80	$132,530.00
		SQYD	10	2	3,450.00	$36.59	$126,250.00
		SQYD	11	2	1,630.00	$44.25	$72,120.00
		SQYD	12	2	1,150.00	$52.27	$60,110.00
	Unit Sub Total	**SQYD**		**48**	**93,450.00**	**$44.57**	**$4,165,119.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 832070	**Total No. of Proj.**			**49**		**Total Amount**	**$4,669,119.50**
833020	CHAIN LINK RAILING		LF	4	1	2,458.00	$45.00	$110,610.00
		Unit Sub Total	**LF**		**1**	**2,458.00**	**$45.00**	**$110,610.00**
	Item Code 833020	**Total No. of Proj.**			**1**		**Total Amount**	**$110,610.00**
833024	CHAIN LINK RAILING (TYPE 4)		LF	5	1	30.00	$270.00	$8,100.00
		Unit Sub Total	**LF**		**1**	**30.00**	**$270.00**	**$8,100.00**
	Item Code 833024	**Total No. of Proj.**			**1**		**Total Amount**	**$8,100.00**
833032	CHAIN LINK RAILING (TYPE 7)		LF	3	1	1,340.00	$50.00	$67,000.00
			LF	4	3	3,136.00	$58.34	$182,945.00
			LF	6	1	235.00	$97.00	$22,795.00
			LF	7	1	420.00	$75.00	$31,500.00
			LF	8	1	332.00	$57.00	$18,924.00
			LF	12	1	388.00	$67.00	$25,996.00
		Unit Sub Total	**LF**		**8**	**5,851.00**	**$59.68**	**$349,160.00**
833032	CHAIN LINK RAILING (TYPE 7)		M	8	1	82.00	$200.00	$16,400.00
		Unit Sub Total	**M**		**1**	**82.00**	**$200.00**	**$16,400.00**
	Item Code 833032	**Total No. of Proj.**			**9**		**Total Amount**	**$365,560.00**
833033	CHAIN LINK RAILING (TYPE 7 MODIFIED)		LF	3	1	1,479.00	$50.00	$73,950.00
			LF	4	2	326.00	$87.33	$28,468.00
			LF	11	1	8,140.00	$38.00	$309,320.00
		Unit Sub Total	**LF**		**4**	**9,945.00**	**$41.40**	**$411,738.00**
833033	CHAIN LINK RAILING (TYPE 7 MODIFIED)		M	7	1	692.00	$340.00	$235,280.00
			M	11	1	95.00	$160.00	$15,200.00
		Unit Sub Total	**M**		**2**	**787.00**	**$318.27**	**$250,480.00**
	Item Code 833033	**Total No. of Proj.**			**6**		**Total Amount**	**$662,218.00**
833034	CHAIN LINK RAILING (TYPE 7L)		LF	4	1	1,548.00	$79.75	$123,453.00
		Unit Sub Total	**LF**		**1**	**1,548.00**	**$79.75**	**$123,453.00**
	Item Code 833034	**Total No. of Proj.**			**1**		**Total Amount**	**$123,453.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
833072	WILDLIFE PASSAGE WAY (TYPE S)	EA	4	1	49.00	$75.00	$3,675.00
		EA	5	1	380.00	$51.00	$19,380.00
		EA	6	1	640.00	$100.00	$64,000.00
	Unit Sub Total	**EA**		**3**	**1,069.00**	**$81.44**	**$87,055.00**
	Item Code 833072 Total No. of Proj.			**3**		**Total Amount**	**$87,055.00**
833073	WILDLIFE PASSAGE WAY (TYPE M)	EA	6	1	25.00	$400.00	$10,000.00
		EA	11	1	4.00	$2,000.00	$8,000.00
	Unit Sub Total	**EA**		**2**	**29.00**	**$620.69**	**$18,000.00**
	Item Code 833073 Total No. of Proj.			**2**		**Total Amount**	**$18,000.00**
833077	PEDESTRIAN BARRICADE	EA	5	2	3.00	$1,233.33	$3,700.00
		EA	6	1	1.00	$1,500.00	$1,500.00
	Unit Sub Total	**EA**		**3**	**4.00**	**$1,300.00**	**$5,200.00**
	Item Code 833077 Total No. of Proj.			**3**		**Total Amount**	**$5,200.00**
833080	CONCRETE BARRIER (TYPE K)	LF	3	1	6,230.00	$35.00	$218,050.00
		LF	4	2	2,020.00	$16.93	$34,190.00
		LF	12	1	5,350.00	$13.00	$69,550.00
	Unit Sub Total	**LF**		**4**	**13,600.00**	**$23.66**	**$321,790.00**
833080	CONCRETE BARRIER (TYPE K)	M	7	1	850.00	$100.00	$85,000.00
		M	11	1	51.00	$85.00	$4,335.00
	Unit Sub Total	**M**		**2**	**901.00**	**$99.15**	**$89,335.00**
	Item Code 833080 Total No. of Proj.			**6**		**Total Amount**	**$411,125.00**
833085	PIPE HANDRAILING	LF	4	1	60.00	$100.00	$6,000.00
	Unit Sub Total	**LF**		**1**	**60.00**	**$100.00**	**$6,000.00**
833085	PIPE HANDRAILING	M	11	1	27.00	$400.00	$10,800.00
	Unit Sub Total	**M**		**1**	**27.00**	**$400.00**	**$10,800.00**
	Item Code 833085 Total No. of Proj.			**2**		**Total Amount**	**$16,800.00**
833088	TUBULAR HANDRAILING	LF	2	1	253.00	$53.77	$13,603.05
		LF	4	1	77.00	$85.00	$6,545.00
		LF	5	1	2,127.00	$34.00	$72,318.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
833088	TUBULAR HANDRAILING	LF	7	1	1,800.00	$50.00	$90,000.00
		LF	8	1	1,392.00	$40.00	$55,680.00
		LF	11	1	150.00	$75.00	$11,250.00
	Unit Sub Total	**LF**		**6**	**5,799.00**	**$43.01**	**$249,396.05**
833088	TUBULAR HANDRAILING	M	7	1	461.00	$130.00	$59,930.00
		M	8	1	15.00	$335.00	$5,025.00
	Unit Sub Total	**M**		**2**	**476.00**	**$136.46**	**$64,955.00**
	Item Code 833088 Total No. of Proj.			**8**		**Total Amount**	**$314,351.05**
833092	METAL TUBE BRIDGE RAILING	LF	4	1	30.00	$255.00	$7,650.00
		LF	7	1	70.00	$150.00	$10,500.00
	Unit Sub Total	**LF**		**2**	**100.00**	**$181.50**	**$18,150.00**
	Item Code 833092 Total No. of Proj.			**2**		**Total Amount**	**$18,150.00**
833125	CONCRETE BARRIER (TYPE 25)	LF	4	1	110.00	$130.00	$14,300.00
		LF	5	1	11.00	$1,200.00	$13,200.00
	Unit Sub Total	**LF**		**2**	**121.00**	**$227.27**	**$27,500.00**
	Item Code 833125 Total No. of Proj.			**2**		**Total Amount**	**$27,500.00**
833127	CONCRETE BARRIER (TYPE 25B)	LF	4	1	80.00	$150.00	$12,000.00
	Unit Sub Total	**LF**		**1**	**80.00**	**$150.00**	**$12,000.00**
	Item Code 833127 Total No. of Proj.			**1**		**Total Amount**	**$12,000.00**
833128	CONCRETE BARRIER (TYPE 25 MODIFIED)	LF	5	1	11.00	$1,300.00	$14,300.00
	Unit Sub Total	**LF**		**1**	**11.00**	**$1,300.00**	**$14,300.00**
	Item Code 833128 Total No. of Proj.			**1**		**Total Amount**	**$14,300.00**
833129	CONCRETE BARRIER (TYPE 25A MODIFIED)	M	7	1	2.00	$450.00	$900.00
	Unit Sub Total	**M**		**1**	**2.00**	**$450.00**	**$900.00**
	Item Code 833129 Total No. of Proj.			**1**		**Total Amount**	**$900.00**
833136	CONCRETE BARRIER (TYPE 25R MODIFIED)	LF	4	1	282.50	$80.00	$22,600.00
	Unit Sub Total	**LF**		**1**	**282.50**	**$80.00**	**$22,600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 833136 Total No. of Proj.			**1**		**Total Amount**	**$22,600.00**
833140	CONCRETE BARRIER (TYPE 26)	LF	4	1	30.00	$100.00	$3,000.00
		LF	6	1	194.00	$125.00	$24,250.00
	Unit Sub Total	**LF**		**2**	**224.00**	**$121.65**	**$27,250.00**
	Item Code 833140 Total No. of Proj.			**2**		**Total Amount**	**$27,250.00**
833142	CONCRETE BARRIER (TYPE 26 MODIFIED)	LF	2	1	253.00	$350.59	$88,700.03
		LF	4	2	1,516.00	$175.77	$266,470.00
		LF	7	1	2,688.00	$155.00	$416,640.00
		LF	8	1	332.00	$75.00	$24,900.00
	Unit Sub Total	**LF**		**5**	**4,789.00**	**$166.36**	**$796,710.03**
833142	CONCRETE BARRIER (TYPE 26 MODIFIED)	M	5	1	590.00	$550.00	$324,500.00
		M	7	1	814.00	$575.00	$468,050.00
		M	8	1	91.00	$340.00	$30,940.00
		M	11	1	553.00	$400.00	$221,200.00
	Unit Sub Total	**M**		**4**	**2,048.00**	**$510.10**	**$1,044,690.00**
	Item Code 833142 Total No. of Proj.			**9**		**Total Amount**	**$1,841,400.03**
833143	CONCRETE BARRIER (TYPE 26A MODIFIED)	M	8	1	3.70	$1,100.00	$4,070.00
		M	11	1	160.00	$528.00	$84,480.00
	Unit Sub Total	**M**		**2**	**163.70**	**$540.93**	**$88,550.00**
	Item Code 833143 Total No. of Proj.			**2**		**Total Amount**	**$88,550.00**
833148	CONCRETE BARRIER (TYPE 26R MODIFIED)	LF	4	1	1,462.50	$125.00	$182,812.50
	Unit Sub Total	**LF**		**1**	**1,462.50**	**$125.00**	**$182,812.50**
	Item Code 833148 Total No. of Proj.			**1**		**Total Amount**	**$182,812.50**
833159	CONCRETE BARRIER (TYPE 27A MODIFIED)	M	5	1	141.00	$315.00	$44,415.00
	Unit Sub Total	**M**		**1**	**141.00**	**$315.00**	**$44,415.00**
	Item Code 833159 Total No. of Proj.			**1**		**Total Amount**	**$44,415.00**
833187	CONCRETE BARRIER (TYPE 27 MODIFIED)	M	5	1	67.00	$400.00	$26,800.00
	Unit Sub Total	**M**		**1**	**67.00**	**$400.00**	**$26,800.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 833187 Total No. of Proj.			**1**		**Total Amount**	**$26,800.00**
833190	CONCRETE BARRIER (TYPE 28)	LF	7	1	2.00	$593.54	$1,187.08
	Unit Sub Total	**LF**		**1**	**2.00**	**$593.54**	**$1,187.08**
	Item Code 833190 Total No. of Proj.			**1**		**Total Amount**	**$1,187.08**
839201	DOUBLE METAL BEAM BARRIER	M	11	1	16.00	$150.00	$2,400.00
	Unit Sub Total	**M**		**1**	**16.00**	**$150.00**	**$2,400.00**
	Item Code 839201 Total No. of Proj.			**1**		**Total Amount**	**$2,400.00**
839220	DOUBLE METAL BEAM GUARD RAILING (WOOD POST)	LF	1	1	50.00	$87.00	$4,350.00
		LF	2	2	770.00	$36.40	$28,030.00
		LF	3	3	3,440.00	$25.65	$88,250.00
		LF	8	1	250.00	$42.00	$10,500.00
		LF	12	1	4,530.00	$27.00	$122,310.00
	Unit Sub Total	**LF**		**8**	**9,040.00**	**$28.04**	**$253,440.00**
	Item Code 839220 Total No. of Proj.			**8**		**Total Amount**	**$253,440.00**
839301	SINGLE THRIE BEAM BARRIER	LF	4	1	1,130.00	$32.00	$36,160.00
		LF	7	1	116.00	$34.65	$4,019.40
		LF	12	1	450.00	$22.00	$9,900.00
	Unit Sub Total	**LF**		**3**	**1,696.00**	**$29.53**	**$50,079.40**
	Item Code 839301 Total No. of Proj.			**3**		**Total Amount**	**$50,079.40**
839302	SINGLE THRIE BEAM BARRIER (WOOD POST)	LF	4	1	200.00	$30.00	$6,000.00
		LF	8	1	150.00	$29.25	$4,387.50
		LF	10	1	220.00	$24.50	$5,390.00
	Unit Sub Total	**LF**		**3**	**570.00**	**$27.68**	**$15,777.50**
	Item Code 839302 Total No. of Proj.			**3**		**Total Amount**	**$15,777.50**
839310	DOUBLE THRIE BEAM BARRIER	LF	3	1	1,530.00	$50.00	$76,500.00
		LF	4	1	8,750.00	$30.00	$262,500.00
		LF	7	1	25.00	$73.50	$1,837.50
	Unit Sub Total	**LF**		**3**	**10,305.00**	**$33.07**	**$340,837.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 839310 Total No. of Proj.			**3**		**Total Amount**	**$340,837.50**
839311	DOUBLE THRIE BEAM BARRIER (WOOD POST)	LF	3	1	410.00	$40.00	$16,400.00
		LF	4	1	370.00	$51.77	$19,154.90
		LF	7	2	2,475.00	$37.43	$92,637.50
	Unit Sub Total	**LF**		**4**	**3,255.00**	**$39.38**	**$128,192.40**
	Item Code 839311 Total No. of Proj.			**4**		**Total Amount**	**$128,192.40**
839312	DOUBLE THRIE BEAM BARRIER (STEEL POST)	LF	3	1	1,530.00	$39.00	$59,670.00
		LF	4	2	6,160.00	$40.99	$252,520.00
		LF	5	1	390.00	$50.00	$19,500.00
	Unit Sub Total	**LF**		**4**	**8,080.00**	**$41.05**	**$331,690.00**
839312	DOUBLE THRIE BEAM BARRIER (STEEL POST)	M	5	1	60.00	$160.00	$9,600.00
	Unit Sub Total	**M**		**1**	**60.00**	**$160.00**	**$9,600.00**
	Item Code 839312 Total No. of Proj.			**5**		**Total Amount**	**$341,290.00**
839401	CONCRETE BARRIER	LF	4	1	25.00	$800.00	$20,000.00
		LF	9	1	56.00	$340.00	$19,040.00
	Unit Sub Total	**LF**		**2**	**81.00**	**$481.98**	**$39,040.00**
	Item Code 839401 Total No. of Proj.			**2**		**Total Amount**	**$39,040.00**
839483	CONCRETE BARRIER (TYPE 50A)	LF	3	1	283.00	$70.00	$19,810.00
	Unit Sub Total	**LF**		**1**	**283.00**	**$70.00**	**$19,810.00**
	Item Code 839483 Total No. of Proj.			**1**		**Total Amount**	**$19,810.00**
839514	HANDRAILING	LF	7	1	48.00	$87.40	$4,195.20
	Unit Sub Total	**LF**		**1**	**48.00**	**$87.40**	**$4,195.20**
839514	HANDRAILING	M	4	1	17.00	$580.00	$9,860.00
	Unit Sub Total	**M**		**1**	**17.00**	**$580.00**	**$9,860.00**
	Item Code 839514 Total No. of Proj.			**2**		**Total Amount**	**$14,055.20**
839521	CABLE RAILING	LF	1	6	1,012.00	$35.12	$35,546.00
		LF	2	4	930.00	$39.09	$36,350.00
		LF	3	3	420.00	$23.85	$10,018.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839521	CABLE RAILING		LF	4	7	3,056.00	$18.09	$55,287.00
			LF	5	1	880.00	$8.55	$7,524.00
			LF	6	1	110.00	$16.00	$1,760.00
			LF	7	4	18,849.00	$11.81	$222,660.00
			LF	10	1	250.00	$28.00	$7,000.00
			LF	11	1	46.00	$61.00	$2,806.00
			LF	12	4	5,402.00	$18.68	$100,936.00
		Unit Sub Total	**LF**		**32**	**30,955.00**	**$15.50**	**$479,887.00**
839521	CABLE RAILING		M	5	1	725.00	$30.00	$21,750.00
			M	7	2	147.00	$48.08	$7,068.00
			M	8	1	261.00	$45.00	$11,745.00
			M	11	2	113.00	$94.76	$10,708.00
		Unit Sub Total	**M**		**6**	**1,246.00**	**$41.15**	**$51,271.00**
	Item Code 839521	**Total No. of Proj.**			**38**		**Total Amount**	**$531,158.00**
839529	ANCHOR POST		EA	3	1	1.00	$1,550.00	$1,550.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$1,550.00**	**$1,550.00**
	Item Code 839529	**Total No. of Proj.**			**1**		**Total Amount**	**$1,550.00**
839540	TRANSITION RAILING (TYPE STB)		EA	4	1	2.00	$2,500.00	$5,000.00
			EA	6	1	8.00	$4,000.00	$32,000.00
			EA	12	1	2.00	$2,600.00	$5,200.00
		Unit Sub Total	**EA**		**3**	**12.00**	**$3,516.67**	**$42,200.00**
	Item Code 839540	**Total No. of Proj.**			**3**		**Total Amount**	**$42,200.00**
839541	TRANSITION RAILING (TYPE WB)		EA	1	6	57.00	$3,329.12	$189,760.00
			EA	2	10	59.00	$3,677.97	$217,000.00
			EA	3	18	213.00	$2,855.38	$608,196.50
			EA	4	12	85.00	$2,973.12	$252,715.00
			EA	5	5	38.00	$3,386.84	$128,700.00
			EA	6	10	109.00	$3,447.71	$375,800.00
			EA	7	5	15.00	$2,936.67	$44,050.00
			EA	8	12	472.00	$2,618.03	$1,235,710.00
			EA	9	1	16.00	$3,170.00	$50,720.00
			EA	10	6	44.00	$2,899.45	$127,576.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839541	TRANSITION RAILING (TYPE WB)	EA	11	9	67.00	$3,046.27	$204,100.00
		EA	12	9	128.00	$2,661.52	$340,675.00
	Unit Sub Total	**EA**		**103**	**1,303.00**	**$2,897.16**	**$3,775,002.50**
	Item Code 839541 Total No. of Proj.			**103**		**Total Amount**	**$3,775,002.50**
839542	TRANSITION RAILING (TYPE DTB)	EA	3	3	9.00	$3,688.89	$33,200.00
		EA	4	1	6.00	$3,400.00	$20,400.00
		EA	5	1	1.00	$4,000.00	$4,000.00
		EA	6	1	1.00	$4,000.00	$4,000.00
		EA	10	1	2.00	$4,500.00	$9,000.00
	Unit Sub Total	**EA**		**7**	**19.00**	**$3,715.79**	**$70,600.00**
	Item Code 839542 Total No. of Proj.			**7**		**Total Amount**	**$70,600.00**
839552	TERMINAL SECTION (TYPE C)	EA	7	1	1.00	$240.00	$240.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$240.00**	**$240.00**
	Item Code 839552 Total No. of Proj.			**1**		**Total Amount**	**$240.00**
839553	END SECTION	EA	3	1	10.00	$750.00	$7,500.00
		EA	4	1	2.00	$100.00	$200.00
	Unit Sub Total	**EA**		**2**	**12.00**	**$641.67**	**$7,700.00**
	Item Code 839553 Total No. of Proj.			**2**		**Total Amount**	**$7,700.00**
839555	END CAP	EA	3	1	7.00	$1,500.00	$10,500.00
		EA	4	1	8.00	$750.00	$6,000.00
		EA	11	1	16.00	$250.00	$4,000.00
	Unit Sub Total	**EA**		**3**	**31.00**	**$661.29**	**$20,500.00**
	Item Code 839555 Total No. of Proj.			**3**		**Total Amount**	**$20,500.00**
839559	TERMINAL SYSTEM (TYPE ET)	EA	4	1	2.00	$2,500.00	$5,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$2,500.00**	**$5,000.00**
	Item Code 839559 Total No. of Proj.			**1**		**Total Amount**	**$5,000.00**
839561	RAIL TENSIONING ASSEMBLY	EA	2	1	6.00	$475.00	$2,850.00
		EA	3	3	15.00	$580.00	$8,700.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839561	RAIL TENSIONING ASSEMBLY	EA	6	1	2.00	$292.00	$584.00
		EA	8	1	2.00	$470.00	$940.00
		EA	10	1	3.00	$500.00	$1,500.00
		EA	11	2	4.00	$550.00	$2,200.00
	Unit Sub Total	**EA**		**9**	**32.00**	**$524.19**	**$16,774.00**
	Item Code 839561 Total No. of Proj.			**9**		**Total Amount**	**$16,774.00**
839565	TERMINAL SYSTEM (TYPE SRT)	EA	4	1	13.00	$2,020.00	$26,260.00
		EA	5	1	2.00	$3,000.00	$6,000.00
	Unit Sub Total	**EA**		**2**	**15.00**	**$2,150.67**	**$32,260.00**
	Item Code 839565 Total No. of Proj.			**2**		**Total Amount**	**$32,260.00**
839566	TERMINAL SYSTEM (TYPE CAT)	EA	2	1	6.00	$5,500.00	$33,000.00
		EA	3	3	21.00	$4,290.48	$90,100.00
		EA	4	1	2.00	$4,000.00	$8,000.00
		EA	8	2	3.00	$5,600.00	$16,800.00
	Unit Sub Total	**EA**		**7**	**32.00**	**$4,621.88**	**$147,900.00**
	Item Code 839566 Total No. of Proj.			**7**		**Total Amount**	**$147,900.00**
839567	TERMINAL SYSTEM (TYPE CAT) BACKUP	EA	1	1	2.00	$2,850.00	$5,700.00
		EA	3	3	21.00	$304.76	$6,400.00
		EA	8	2	3.00	$613.33	$1,840.00
	Unit Sub Total	**EA**		**6**	**26.00**	**$536.15**	**$13,940.00**
	Item Code 839567 Total No. of Proj.			**6**		**Total Amount**	**$13,940.00**
839568	TERMINAL ANCHOR ASSEMBLY (TYPE SFT)	EA	1	2	6.00	$729.17	$4,375.00
		EA	2	3	13.00	$767.69	$9,980.00
		EA	3	2	20.00	$527.50	$10,550.00
		EA	7	2	3.00	$508.33	$1,525.00
		EA	8	4	221.00	$472.65	$104,455.00
		EA	12	1	2.00	$800.00	$1,600.00
	Unit Sub Total	**EA**		**14**	**265.00**	**$499.94**	**$132,485.00**
	Item Code 839568 Total No. of Proj.			**14**		**Total Amount**	**$132,485.00**
839569	TERMINAL ANCHOR ASSEMBLY (TYPE CA)	EA	8	1	1.00	$1,200.00	$1,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**1.00**	**$1,200.00**	**$1,200.00**
	Item Code 839569	**Total No. of Proj.**			**1**		**Total Amount**	**$1,200.00**
839572	RETURN CAP (TYPE TA)		EA	7	1	2.00	$100.00	$200.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$100.00**	**$200.00**
	Item Code 839572	**Total No. of Proj.**			**1**		**Total Amount**	**$200.00**
839576	END CAP (TYPE A)		EA	1	1	4.00	$250.00	$1,000.00
			EA	2	2	3.00	$233.33	$700.00
			EA	3	9	43.00	$185.65	$7,983.00
			EA	4	3	6.00	$130.00	$780.00
			EA	6	1	2.00	$50.00	$100.00
			EA	7	2	3.00	$90.00	$270.00
			EA	8	2	7.00	$405.43	$2,838.00
			EA	12	2	4.00	$145.00	$580.00
		Unit Sub Total	**EA**		**22**	**72.00**	**$197.93**	**$14,251.00**
	Item Code 839576	**Total No. of Proj.**			**22**		**Total Amount**	**$14,251.00**
839577	END CAP (TYPE TA)		EA	7	1	3.00	$410.00	$1,230.00
		Unit Sub Total	**EA**		**1**	**3.00**	**$410.00**	**$1,230.00**
	Item Code 839577	**Total No. of Proj.**			**1**		**Total Amount**	**$1,230.00**
839578	END CAP (TYPE TC)		EA	1	2	11.00	$959.09	$10,550.00
			EA	3	5	57.00	$228.95	$13,050.00
			EA	4	1	22.00	$90.00	$1,980.00
			EA	6	2	21.00	$133.33	$2,800.00
			EA	7	3	10.00	$244.50	$2,445.00
			EA	8	2	24.00	$76.67	$1,840.00
			EA	11	1	19.00	$167.00	$3,173.00
			EA	12	1	15.00	$80.00	$1,200.00
		Unit Sub Total	**EA**		**17**	**179.00**	**$206.92**	**$37,038.00**
	Item Code 839578	**Total No. of Proj.**			**17**		**Total Amount**	**$37,038.00**
839581	END ANCHOR ASSEMBLY (TYPE SFT)		EA	1	3	7.00	$1,478.57	$10,350.00
			EA	2	5	68.00	$629.41	$42,800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839581	END ANCHOR ASSEMBLY (TYPE SFT)	EA	3	16	113.00	$728.44	$82,313.20
		EA	4	15	100.00	$662.66	$66,266.00
		EA	5	3	33.00	$587.27	$19,380.00
		EA	6	8	42.00	$664.76	$27,920.00
		EA	7	9	39.00	$551.43	$21,505.80
		EA	8	6	25.00	$524.20	$13,105.00
		EA	10	2	9.00	$766.67	$6,900.00
		EA	11	6	25.00	$719.72	$17,993.00
		EA	12	10	165.00	$756.38	$124,802.00
	Unit Sub Total	**EA**		**83**	**626.00**	**$692.23**	**$433,335.00**
	Item Code 839581 Total No. of Proj.			**83**		**Total Amount**	**$433,335.00**
839582	END ANCHOR ASSEMBLY (TYPE CA)	EA	10	1	3.00	$1,600.00	$4,800.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$1,600.00**	**$4,800.00**
	Item Code 839582 Total No. of Proj.			**1**		**Total Amount**	**$4,800.00**
839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM	EA	1	6	26.00	$2,632.69	$68,450.00
		EA	2	6	16.00	$3,256.25	$52,100.00
		EA	3	11	115.00	$2,430.29	$279,482.85
		EA	4	10	50.00	$2,697.72	$134,886.00
		EA	5	6	21.00	$2,700.57	$56,712.00
		EA	6	4	24.00	$2,666.67	$64,000.00
		EA	7	9	20.00	$2,670.00	$53,400.00
		EA	8	6	166.00	$2,396.82	$397,872.00
		EA	10	1	2.00	$2,600.00	$5,200.00
		EA	11	3	10.00	$3,265.00	$32,650.00
		EA	12	8	34.00	$2,658.35	$90,384.00
	Unit Sub Total	**EA**		**70**	**484.00**	**$2,551.94**	**$1,235,136.85**
	Item Code 839584 Total No. of Proj.			**70**		**Total Amount**	**$1,235,136.85**
839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	1	10	144.00	$2,238.75	$322,380.00
		EA	2	14	116.00	$2,538.02	$294,410.00
		EA	3	18	190.00	$2,006.33	$381,203.64
		EA	4	16	110.00	$2,318.28	$255,011.00
		EA	5	6	46.00	$2,383.65	$109,648.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	6	11	100.00	$2,466.00	$246,600.00
		EA	7	6	37.00	$1,803.11	$66,715.05
		EA	8	11	542.00	$1,966.99	$1,066,110.00
		EA	9	1	16.00	$2,635.00	$42,160.00
		EA	10	7	73.00	$2,203.01	$160,820.00
		EA	11	6	31.00	$2,492.90	$77,280.00
		EA	12	11	258.00	$2,133.33	$550,398.00
	Unit Sub Total	**EA**		**117**	**1,663.00**	**$2,148.37**	**$3,572,735.69**
	Item Code 839585 Total No. of Proj.			**117**		**Total Amount**	**$3,572,735.69**
839591	CRASH CUSHION, SAND FILLED	EA	1	1	2.00	$5,200.00	$10,400.00
		EA	4	2	15.00	$706.67	$10,600.00
		EA	6	1	1.00	$8,000.00	$8,000.00
		EA	7	1	1.00	$3,000.00	$3,000.00
		EA	11	1	48.00	$380.00	$18,240.00
		EA	12	1	2.00	$180.00	$360.00
	Unit Sub Total	**EA**		**7**	**69.00**	**$733.33**	**$50,600.00**
	Item Code 839591 Total No. of Proj.			**7**		**Total Amount**	**$50,600.00**
839601	CRASH CUSHION (TYPE CAT)	EA	3	1	2.00	$5,050.00	$10,100.00
		EA	4	3	5.00	$4,634.00	$23,170.00
		EA	7	2	2.00	$9,050.00	$18,100.00
		EA	8	4	72.00	$4,112.92	$296,130.00
		EA	11	1	2.00	$6,000.00	$12,000.00
		EA	12	2	48.00	$4,464.06	$214,275.00
	Unit Sub Total	**EA**		**13**	**131.00**	**$4,379.96**	**$573,775.00**
	Item Code 839601 Total No. of Proj.			**13**		**Total Amount**	**$573,775.00**
839602	CRASH CUSHION (TYPE CAT) BACKUP	EA	3	1	2.00	$250.00	$500.00
		EA	4	3	5.00	$506.60	$2,533.00
		EA	7	1	1.00	$900.00	$900.00
		EA	8	1	2.00	$740.00	$1,480.00
		EA	11	1	2.00	$550.00	$1,100.00
		EA	12	1	23.00	$100.00	$2,300.00
	Unit Sub Total	**EA**		**8**	**35.00**	**$251.80**	**$8,813.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 839602 Total No. of Proj.			**8**		**Total Amount**	**$8,813.00**
839603	CRASH CUSHION (ADIEM)	EA	4	2	7.00	$19,142.86	$134,000.00
		EA	7	1	1.00	$20,000.00	$20,000.00
		EA	8	1	2.00	$20,000.00	$40,000.00
		EA	10	1	2.00	$20,000.00	$40,000.00
	Unit Sub Total	**EA**		**5**	**12.00**	**$19,500.00**	**$234,000.00**
	Item Code 839603 Total No. of Proj.			**5**		**Total Amount**	**$234,000.00**
839604	CRASH CUSHION (REACT 9CBB)	EA	7	1	2.00	$45,000.00	$90,000.00
		EA	8	1	1.00	$54,930.00	$54,930.00
		EA	11	1	3.00	$48,600.00	$145,800.00
	Unit Sub Total	**EA**		**3**	**6.00**	**$48,455.00**	**$290,730.00**
	Item Code 839604 Total No. of Proj.			**3**		**Total Amount**	**$290,730.00**
839605	CRASH CUSHION (REACT 9SCBS)	EA	4	3	4.00	$47,500.00	$190,000.00
		EA	7	1	1.00	$57,000.00	$57,000.00
	Unit Sub Total	**EA**		**4**	**5.00**	**$49,400.00**	**$247,000.00**
	Item Code 839605 Total No. of Proj.			**4**		**Total Amount**	**$247,000.00**
839631	CRASH CUSHION MODULE, SAND FILLED	EA	2	1	16.00	$375.00	$6,000.00
		EA	3	1	21.00	$300.00	$6,300.00
		EA	7	1	39.00	$580.00	$22,620.00
	Unit Sub Total	**EA**		**3**	**76.00**	**$459.47**	**$34,920.00**
	Item Code 839631 Total No. of Proj.			**3**		**Total Amount**	**$34,920.00**
839701	CONCRETE BARRIER (TYPE 60)	LF	2	1	1,160.00	$40.00	$46,400.00
		LF	3	5	53,634.00	$30.67	$1,645,080.00
		LF	4	12	27,780.00	$51.36	$1,426,915.20
		LF	5	2	2,140.00	$56.03	$119,900.00
		LF	6	2	19,740.00	$38.14	$752,840.00
		LF	7	3	675.00	$84.87	$57,290.00
		LF	10	3	19,080.00	$34.21	$652,800.00
		LF	11	2	5,560.00	$48.35	$268,850.00
		LF	12	4	4,680.00	$53.36	$249,730.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**34**	**134,449.00**	**$38.82**	**$5,219,805.20**
839701	CONCRETE BARRIER (TYPE 60)		M	5	1	2,920.00	$115.00	$335,800.00
			M	8	1	330.00	$300.00	$99,000.00
			M	11	1	1,180.00	$180.00	$212,400.00
		Unit Sub Total	**M**		**3**	**4,430.00**	**$146.09**	**$647,200.00**
	Item Code 839701	**Total No. of Proj.**			**37**		**Total Amount**	**$5,867,005.20**
839702	CONCRETE BARRIER (TYPE 60A)		LF	3	1	1,326.00	$30.00	$39,780.00
			LF	6	1	225.00	$80.00	$18,000.00
			LF	7	1	3,187.00	$55.00	$175,285.00
			LF	12	1	50.00	$59.00	$2,950.00
		Unit Sub Total	**LF**		**4**	**4,788.00**	**$49.29**	**$236,015.00**
839702	CONCRETE BARRIER (TYPE 60A)		M	8	1	49.00	$360.00	$17,640.00
			M	11	1	60.00	$175.00	$10,500.00
		Unit Sub Total	**M**		**2**	**109.00**	**$258.17**	**$28,140.00**
	Item Code 839702	**Total No. of Proj.**			**6**		**Total Amount**	**$264,155.00**
839703	CONCRETE BARRIER (TYPE 60C)		LF	2	1	4,790.00	$50.00	$239,500.00
			LF	3	3	13,100.00	$38.90	$509,580.00
			LF	4	7	62,800.00	$70.00	$4,395,930.40
			LF	5	2	5,290.00	$76.53	$404,850.00
			LF	6	1	69,300.00	$50.00	$3,465,000.00
			LF	7	3	6,260.00	$180.80	$1,131,830.00
			LF	11	1	1,750.00	$90.00	$157,500.00
			LF	12	2	2,140.00	$105.51	$225,800.00
		Unit Sub Total	**LF**		**20**	**165,430.00**	**$63.65**	**$10,529,990.40**
839703	CONCRETE BARRIER (TYPE 60C)		M	5	1	1,040.00	$142.00	$147,680.00
			M	7	1	26.00	$230.00	$5,980.00
			M	8	1	770.00	$300.00	$231,000.00
			M	11	1	1,680.00	$280.00	$470,400.00
		Unit Sub Total	**M**		**4**	**3,516.00**	**$243.19**	**$855,060.00**
	Item Code 839703	**Total No. of Proj.**			**24**		**Total Amount**	**$11,385,050.40**
839704	CONCRETE BARRIER (TYPE 60D)		LF	3	2	399.00	$47.34	$18,890.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839704	CONCRETE BARRIER (TYPE 60D)	LF	4	5	3,820.00	$36.58	$139,735.00
		LF	7	1	735.00	$56.00	$41,160.00
		LF	10	1	250.00	$50.00	$12,500.00
		LF	11	1	374.00	$38.00	$14,212.00
		LF	12	3	1,495.00	$44.22	$66,105.00
	Unit Sub Total	**LF**		**13**	**7,073.00**	**$41.37**	**$292,602.00**
839704	CONCRETE BARRIER (TYPE 60D)	M	5	1	296.00	$200.00	$59,200.00
		M	8	1	7.00	$600.00	$4,200.00
	Unit Sub Total	**M**		**2**	**303.00**	**$209.24**	**$63,400.00**
	Item Code 839704 Total No. of Proj.			**15**		**Total Amount**	**$356,002.00**
839705	CONCRETE BARRIER (TYPE 60E)	LF	3	5	1,685.00	$183.96	$309,975.00
		LF	4	3	920.00	$222.83	$205,000.00
		LF	5	1	130.00	$306.00	$39,780.00
		LF	10	1	240.00	$175.00	$42,000.00
		LF	12	1	74.00	$135.00	$9,990.00
	Unit Sub Total	**LF**		**11**	**3,049.00**	**$199.00**	**$606,745.00**
839705	CONCRETE BARRIER (TYPE 60E)	M	7	1	55.00	$124.00	$6,820.00
		M	11	1	230.00	$534.00	$122,820.00
	Unit Sub Total	**M**		**2**	**285.00**	**$454.88**	**$129,640.00**
	Item Code 839705 Total No. of Proj.			**13**		**Total Amount**	**$736,385.00**
839706	CONCRETE BARRIER (TYPE 60G)	LF	3	1	3,910.00	$35.00	$136,850.00
		LF	4	1	410.00	$112.00	$45,920.00
		LF	5	1	290.00	$90.00	$26,100.00
		LF	7	2	16,900.00	$100.27	$1,694,620.00
	Unit Sub Total	**LF**		**5**	**21,510.00**	**$88.49**	**$1,903,490.00**
839706	CONCRETE BARRIER (TYPE 60G)	M	7	1	730.00	$275.00	$200,750.00
		M	8	1	190.00	$400.00	$76,000.00
	Unit Sub Total	**M**		**2**	**920.00**	**$300.82**	**$276,750.00**
	Item Code 839706 Total No. of Proj.			**7**		**Total Amount**	**$2,180,240.00**
839708	CONCRETE BARRIER (TYPE 60GC)	LF	7	1	1,490.00	$69.00	$102,810.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**1**	**1,490.00**	**$69.00**	**$102,810.00**
839708	CONCRETE BARRIER (TYPE 60GC)	M	8	1	86.00	$450.00	$38,700.00
	Unit Sub Total	**M**		**1**	**86.00**	**$450.00**	**$38,700.00**
	Item Code 839708 Total No. of Proj.			**2**		**Total Amount**	**$141,510.00**
839709	CONCRETE BARRIER (TYPE 60GE)	LF	7	1	420.00	$130.00	$54,600.00
	Unit Sub Total	**LF**		**1**	**420.00**	**$130.00**	**$54,600.00**
839709	CONCRETE BARRIER (TYPE 60GE)	M	7	1	95.00	$690.00	$65,550.00
	Unit Sub Total	**M**		**1**	**95.00**	**$690.00**	**$65,550.00**
	Item Code 839709 Total No. of Proj.			**2**		**Total Amount**	**$120,150.00**
839710	CONCRETE BARRIER (TYPE 60S)	LF	5	1	15,500.00	$42.00	$651,000.00
		LF	7	3	445.00	$69.46	$30,909.00
	Unit Sub Total	**LF**		**4**	**15,945.00**	**$42.77**	**$681,909.00**
839710	CONCRETE BARRIER (TYPE 60S)	M	4	1	88.00	$350.00	$30,800.00
		M	5	1	270.00	$138.00	$37,260.00
	Unit Sub Total	**M**		**2**	**358.00**	**$190.11**	**$68,060.00**
	Item Code 839710 Total No. of Proj.			**6**		**Total Amount**	**$749,969.00**
839712	CONCRETE BARRIER (TYPE 60SC)	LF	7	1	5,720.00	$45.00	$257,400.00
	Unit Sub Total	**LF**		**1**	**5,720.00**	**$45.00**	**$257,400.00**
839712	CONCRETE BARRIER (TYPE 60SC)	M	4	1	470.00	$350.00	$164,500.00
		M	5	1	2,540.00	$140.00	$355,600.00
	Unit Sub Total	**M**		**2**	**3,010.00**	**$172.79**	**$520,100.00**
	Item Code 839712 Total No. of Proj.			**3**		**Total Amount**	**$777,500.00**
839713	CONCRETE BARRIER (TYPE 60SE)	M	5	1	42.00	$675.00	$28,350.00
	Unit Sub Total	**M**		**1**	**42.00**	**$675.00**	**$28,350.00**
	Item Code 839713 Total No. of Proj.			**1**		**Total Amount**	**$28,350.00**
839717	CONCRETE BARRIER (TYPE 732 MODIFIED)	LF	2	1	128.00	$240.00	$30,720.00
		LF	3	1	1,303.00	$160.00	$208,480.00
		LF	4	2	1,107.00	$130.81	$144,805.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839717	CONCRETE BARRIER (TYPE 732 MODIFIED)	LF	7	2	1,154.00	$110.18	$127,152.08
	Unit Sub Total	**LF**		**6**	**3,692.00**	**$138.45**	**$511,157.08**
	Item Code 839717 Total No. of Proj.			**6**		**Total Amount**	**$511,157.08**
839718	CONCRETE BARRIER (TYPE 732R)	LF	3	1	1,184.00	$85.00	$100,640.00
	Unit Sub Total	**LF**		**1**	**1,184.00**	**$85.00**	**$100,640.00**
	Item Code 839718 Total No. of Proj.			**1**		**Total Amount**	**$100,640.00**
839720	CONCRETE BARRIER (TYPE 732)	LF	3	1	210.00	$73.50	$15,435.00
		LF	4	3	593.00	$92.51	$54,860.00
		LF	5	1	4,268.00	$60.00	$256,080.00
		LF	6	1	194.00	$110.00	$21,340.00
		LF	7	1	2,394.00	$72.82	$174,331.08
		LF	10	2	3,541.00	$83.69	$296,340.00
	Unit Sub Total	**LF**		**9**	**11,200.00**	**$73.07**	**$818,386.08**
839720	CONCRETE BARRIER (TYPE 732)	M	4	1	658.00	$100.00	$65,800.00
		M	8	1	138.00	$260.00	$35,880.00
	Unit Sub Total	**M**		**2**	**796.00**	**$127.74**	**$101,680.00**
	Item Code 839720 Total No. of Proj.			**11**		**Total Amount**	**$920,066.08**
839721	CONCRETE BARRIER (TYPE 732A)	LF	4	2	8,538.00	$58.87	$502,650.00
		LF	6	1	42.00	$185.00	$7,770.00
	Unit Sub Total	**LF**		**3**	**8,580.00**	**$59.49**	**$510,420.00**
839721	CONCRETE BARRIER (TYPE 732A)	M	8	1	7.00	$600.00	$4,200.00
	Unit Sub Total	**M**		**1**	**7.00**	**$600.00**	**$4,200.00**
	Item Code 839721 Total No. of Proj.			**4**		**Total Amount**	**$514,620.00**
839723	CONCRETE BARRIER (TYPE 732B)	LF	4	1	480.00	$65.00	$31,200.00
	Unit Sub Total	**LF**		**1**	**480.00**	**$65.00**	**$31,200.00**
839723	CONCRETE BARRIER (TYPE 732B)	M	4	1	71.00	$100.00	$7,100.00
	Unit Sub Total	**M**		**1**	**71.00**	**$100.00**	**$7,100.00**
	Item Code 839723 Total No. of Proj.			**2**		**Total Amount**	**$38,300.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839725	CONCRETE BARRIER (TYPE 736)	LF	2	1	406.00	$90.00	$36,540.00
		LF	4	2	1,412.00	$83.76	$118,275.00
		LF	6	2	914.00	$94.58	$86,445.00
		LF	7	1	2,801.00	$85.00	$238,085.00
		LF	8	1	332.00	$63.00	$20,916.00
		LF	12	3	1,837.00	$63.42	$116,506.00
	Unit Sub Total	**LF**		**10**	**7,702.00**	**$80.08**	**$616,767.00**
839725	CONCRETE BARRIER (TYPE 736)	M	8	1	495.00	$160.00	$79,200.00
		M	11	2	326.00	$200.00	$65,200.00
	Unit Sub Total	**M**		**3**	**821.00**	**$175.88**	**$144,400.00**
	Item Code 839725 **Total No. of Proj.**			**13**		**Total Amount**	**$761,167.00**
839726	CONCRETE BARRIER (TYPE 736A)	LF	4	1	189.00	$50.00	$9,450.00
		LF	6	3	1,187.00	$84.75	$100,600.00
		LF	10	1	2,110.00	$65.00	$137,150.00
		LF	12	2	2,587.00	$85.79	$221,951.00
	Unit Sub Total	**LF**		**7**	**6,073.00**	**$77.25**	**$469,151.00**
839726	CONCRETE BARRIER (TYPE 736A)	M	5	1	34.00	$285.00	$9,690.00
		M	7	1	265.00	$270.00	$71,550.00
	Unit Sub Total	**M**		**2**	**299.00**	**$271.71**	**$81,240.00**
	Item Code 839726 **Total No. of Proj.**			**9**		**Total Amount**	**$550,391.00**
839727	CONCRETE BARRIER (TYPE 736 MODIFIED)	LF	3	2	7,907.00	$78.50	$620,665.00
		LF	4	2	2,093.00	$94.39	$197,555.00
		LF	5	1	1,476.00	$65.00	$95,940.00
		LF	6	2	4,539.00	$95.17	$431,980.00
		LF	7	2	18,841.00	$50.24	$946,645.00
		LF	10	1	954.00	$125.00	$119,250.00
		LF	12	1	176.00	$100.00	$17,600.00
	Unit Sub Total	**LF**		**11**	**35,986.00**	**$67.52**	**$2,429,635.00**
839727	CONCRETE BARRIER (TYPE 736 MODIFIED)	M	5	1	331.00	$270.00	$89,370.00
		M	7	2	1,847.00	$159.26	$294,160.00
		M	11	2	630.00	$202.14	$127,350.00
	Unit Sub Total	**M**		**5**	**2,808.00**	**$181.94**	**$510,880.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 839727 Total No. of Proj.			**16**		**Total Amount**	**$2,940,515.00**
839728	CONCRETE BARRIER (TYPE 736R)	LF	2	1	1,503.00	$90.00	$135,270.00
	Unit Sub Total	**LF**		**1**	**1,503.00**	**$90.00**	**$135,270.00**
839728	CONCRETE BARRIER (TYPE 736R)	M	11	1	71.00	$250.00	$17,750.00
	Unit Sub Total	**M**		**1**	**71.00**	**$250.00**	**$17,750.00**
	Item Code 839728 Total No. of Proj.			**2**		**Total Amount**	**$153,020.00**
839731	CONCRETE BARRIER (TYPE 736B)	LF	5	1	730.00	$115.00	$83,950.00
		LF	6	1	2,240.00	$75.00	$168,000.00
		LF	7	1	60.00	$50.00	$3,000.00
		LF	10	1	61.00	$180.00	$10,980.00
		LF	12	1	3,110.00	$105.00	$326,550.00
	Unit Sub Total	**LF**		**5**	**6,201.00**	**$95.55**	**$592,480.00**
839731	CONCRETE BARRIER (TYPE 736B)	M	5	1	180.00	$420.00	$75,600.00
		M	7	1	160.00	$135.00	$21,600.00
		M	11	1	7.00	$230.00	$1,610.00
	Unit Sub Total	**M**		**3**	**347.00**	**$284.76**	**$98,810.00**
	Item Code 839731 Total No. of Proj.			**8**		**Total Amount**	**$691,290.00**
839734	CONCRETE BARRIER (TYPE 736SV)	LF	4	3	4,569.00	$120.93	$552,510.00
		LF	6	1	11,000.00	$100.00	$1,100,000.00
		LF	7	1	552.00	$74.98	$41,388.96
		LF	10	1	4,030.00	$125.00	$503,750.00
	Unit Sub Total	**LF**		**6**	**20,151.00**	**$109.06**	**$2,197,648.96**
839734	CONCRETE BARRIER (TYPE 736SV)	M	5	1	720.00	$310.00	$223,200.00
		M	7	1	450.00	$280.00	$126,000.00
	Unit Sub Total	**M**		**2**	**1,170.00**	**$298.46**	**$349,200.00**
	Item Code 839734 Total No. of Proj.			**8**		**Total Amount**	**$2,546,848.96**
839735	CONCRETE BARRIER (TYPE 742)	LF	4	1	3,268.00	$75.00	$245,100.00
		LF	5	1	2,090.00	$64.00	$133,760.00
		LF	7	1	1,420.00	$85.38	$121,239.60

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**3**	**6,778.00**	**$73.78**	**$500,099.60**
839735	CONCRETE BARRIER (TYPE 742)	M	11	1	243.00	$300.00	$72,900.00
	Unit Sub Total	**M**		**1**	**243.00**	**$300.00**	**$72,900.00**
	Item Code 839735 Total No. of Proj.			**4**		**Total Amount**	**$572,999.60**
839736	CONCRETE BARRIER (TYPE 742A)	LF	4	1	70.00	$100.00	$7,000.00
	Unit Sub Total	**LF**		**1**	**70.00**	**$100.00**	**$7,000.00**
	Item Code 839736 Total No. of Proj.			**1**		**Total Amount**	**$7,000.00**
839737	CONCRETE BARRIER (TYPE 742B)	M	8	1	8.00	$1,200.00	$9,600.00
	Unit Sub Total	**M**		**1**	**8.00**	**$1,200.00**	**$9,600.00**
	Item Code 839737 Total No. of Proj.			**1**		**Total Amount**	**$9,600.00**
839740	CALIFORNIA ST-10 BRIDGE RAIL	LF	1	1	539.00	$225.00	$121,275.00
	Unit Sub Total	**LF**		**1**	**539.00**	**$225.00**	**$121,275.00**
	Item Code 839740 Total No. of Proj.			**1**		**Total Amount**	**$121,275.00**
840501	THERMOPLASTIC TRAFFIC STRIPE	LF	1	4	637,420.00	$0.64	$405,790.00
		LF	4	1	7,010.00	$0.57	$3,995.70
		LF	6	2	109,900.00	$0.51	$55,687.00
		LF	7	1	2,820.00	$0.62	$1,748.40
		LF	8	1	540.00	$1.25	$675.00
	Unit Sub Total	**LF**		**9**	**757,690.00**	**$0.62**	**$467,896.10**
	Item Code 840501 Total No. of Proj.			**9**		**Total Amount**	**$467,896.10**
840504	4" THERMOPLASTIC TRAFFIC STRIPE	LF	1	29	4,141,228.00	$0.39	$1,629,364.00
		LF	2	1	222,000.00	$0.25	$55,500.00
		LF	3	43	4,843,760.00	$0.38	$1,823,236.00
		LF	4	57	3,644,780.00	$0.41	$1,489,732.00
		LF	5	17	1,733,890.00	$0.39	$668,107.00
		LF	6	32	2,706,296.00	$0.40	$1,072,042.60
		LF	7	52	5,001,005.00	$0.35	$1,735,647.10
		LF	10	7	484,470.00	$0.36	$175,431.80
		LF	11	15	586,910.00	$0.43	$252,386.40

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840504	4" THERMOPLASTIC TRAFFIC STRIPE	LF	12	24	1,897,660.00	$0.40	$754,021.20
	Unit Sub Total	**LF**		**277**	**###########**	**$0.38**	**$9,655,468.10**
	Item Code 840504 Total No. of Proj.			**277**		**Total Amount**	**$9,655,468.10**
840505	6" THERMOPLASTIC TRAFFIC STRIPE	LF	2	1	9,400.00	$0.30	$2,820.00
		LF	3	3	3,170.00	$1.18	$3,727.00
		LF	4	7	12,791.00	$1.34	$17,164.30
		LF	5	3	24,620.00	$0.45	$11,189.50
		LF	6	2	160,000.00	$0.49	$78,800.00
		LF	7	2	1,200.00	$0.86	$1,032.00
		LF	11	3	306,240.00	$0.70	$214,416.00
		LF	12	2	33,530.00	$0.65	$21,938.00
	Unit Sub Total	**LF**		**23**	**550,951.00**	**$0.64**	**$351,086.80**
	Item Code 840505 Total No. of Proj.			**23**		**Total Amount**	**$351,086.80**
840506	8" THERMOPLASTIC TRAFFIC STRIPE	LF	1	11	36,520.00	$1.12	$40,724.00
		LF	2	1	2,490.00	$0.40	$996.00
		LF	3	33	194,190.00	$0.88	$171,459.10
		LF	4	42	178,574.00	$1.03	$184,639.30
		LF	5	16	93,810.00	$0.93	$87,419.00
		LF	6	26	147,480.00	$0.40	$59,204.50
		LF	7	42	331,398.00	$0.87	$286,674.40
		LF	8	3	4,440.00	$1.09	$4,832.00
		LF	10	5	22,220.00	$0.84	$18,774.00
		LF	11	18	121,150.00	$0.87	$105,452.70
		LF	12	22	187,045.00	$0.89	$166,944.70
	Unit Sub Total	**LF**		**219**	**1,319,317.00**	**$0.85**	**$1,127,119.70**
	Item Code 840506 Total No. of Proj.			**219**		**Total Amount**	**$1,127,119.70**
840508	8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	LF	1	1	430.00	$0.80	$344.00
		LF	3	15	76,690.00	$0.62	$47,600.60
		LF	4	16	57,810.00	$0.87	$50,442.80
		LF	5	5	2,960.00	$0.91	$2,689.00
		LF	6	2	2,950.00	$0.49	$1,454.00
		LF	7	21	173,910.00	$0.67	$116,941.20

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840508	8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	LF	10	2	9,240.00	$0.43	$3,972.00
		LF	11	6	73,030.00	$0.48	$35,175.00
		LF	12	14	141,460.00	$0.56	$79,918.80
	Unit Sub Total	**LF**		**82**	**538,480.00**	**$0.63**	**$338,537.40**
	Item Code 840508 Total No. of Proj.			**82**		**Total Amount**	**$338,537.40**
840515	THERMOPLASTIC PAVEMENT MARKING	LF	4	1	3,370.00	$2.00	$6,740.00
	Unit Sub Total	**LF**		**1**	**3,370.00**	**$2.00**	**$6,740.00**
840515	THERMOPLASTIC PAVEMENT MARKING	M2	4	1	200.00	$40.00	$8,000.00
		M2	5	1	1,140.00	$35.00	$39,900.00
		M2	7	5	2,460.00	$36.69	$90,247.50
		M2	10	2	141.00	$26.94	$3,798.00
		M2	11	2	526.00	$31.03	$16,320.00
	Unit Sub Total	**M2**		**11**	**4,467.00**	**$35.43**	**$158,265.50**
840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	1	18	37,569.00	$4.66	$175,059.00
		SQFT	2	21	20,258.00	$5.64	$114,195.52
		SQFT	3	39	72,097.00	$3.83	$276,358.20
		SQFT	4	41	69,390.00	$3.94	$273,631.90
		SQFT	5	25	67,611.00	$3.73	$252,481.90
		SQFT	6	32	70,524.00	$3.69	$259,998.70
		SQFT	7	41	126,830.00	$3.19	$405,023.00
		SQFT	8	19	18,964.00	$3.87	$73,394.10
		SQFT	9	3	1,200.00	$5.69	$6,824.00
		SQFT	10	23	43,231.00	$4.39	$189,665.90
		SQFT	11	18	53,800.00	$2.94	$158,034.80
		SQFT	12	20	86,876.00	$3.14	$272,526.20
	Unit Sub Total	**SQFT**		**300**	**668,350.00**	**$3.68**	**$2,457,193.22**
840515	THERMOPLASTIC PAVEMENT MARKING	SQYD	1	1	2,770.00	$6.30	$17,451.00
	Unit Sub Total	**SQYD**		**1**	**2,770.00**	**$6.30**	**$17,451.00**
	Item Code 840515 Total No. of Proj.			**313**		**Total Amount**	**$2,639,649.72**
840519	THERMOPLASTIC CROSSWALK AND PAVEMENT MARKING	M2	8	1	180.00	$32.00	$5,760.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M2**		**1**	**180.00**	**$32.00**	**$5,760.00**
	Item Code 840519 Total No. of Proj.			**1**		**Total Amount**	**$5,760.00**
840521	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 6-1)	LF	1	2	530.00	$0.47	$250.00
		LF	3	6	1,077.00	$0.60	$644.85
		LF	4	1	1,040.00	$1.22	$1,268.80
		LF	5	1	71.00	$1.00	$71.00
		LF	6	2	217.00	$1.50	$326.10
		LF	7	1	120.00	$2.00	$240.00
		LF	11	1	52.00	$0.51	$26.52
		LF	12	4	1,742.00	$0.49	$852.40
	Unit Sub Total	**LF**		**18**	**4,849.00**	**$0.76**	**$3,679.67**
	Item Code 840521 Total No. of Proj.			**18**		**Total Amount**	**$3,679.67**
840523	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	LF	1	11	29,560.00	$0.38	$11,321.60
		LF	2	1	3,740.00	$0.20	$748.00
		LF	3	8	15,459.00	$0.26	$4,092.40
		LF	4	4	12,060.00	$0.54	$6,458.40
		LF	5	1	220.00	$1.00	$220.00
		LF	6	9	18,230.00	$0.30	$5,546.70
		LF	7	1	420.00	$0.42	$176.40
		LF	10	1	3,520.00	$0.25	$880.00
	Unit Sub Total	**LF**		**36**	**83,209.00**	**$0.35**	**$29,443.50**
	Item Code 840523 Total No. of Proj.			**36**		**Total Amount**	**$29,443.50**
840525	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	LF	1	14	305,030.00	$0.23	$69,348.50
		LF	2	1	36,600.00	$0.20	$7,320.00
		LF	3	39	2,514,190.00	$0.25	$629,760.50
		LF	4	12	411,010.00	$0.22	$91,777.40
		LF	5	13	584,790.00	$0.27	$158,247.00
		LF	6	27	1,348,230.00	$0.33	$449,292.70
		LF	7	42	3,399,538.00	$0.26	$883,111.50
		LF	10	3	204,540.00	$0.21	$42,057.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840525	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	LF	11	8	170,850.00	$0.26	$44,010.50
		LF	12	19	1,245,120.00	$0.25	$312,118.50
	Unit Sub Total	**LF**		**178**	**############**	**$0.26**	**$2,687,043.60**
	Item Code 840525 Total No. of Proj.			**178**		**Total Amount**	**$2,687,043.60**
840526	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 17-7)	LF	1	2	420.00	$0.59	$246.00
		LF	3	21	72,600.00	$0.42	$30,422.00
		LF	4	17	50,370.00	$0.52	$26,341.50
		LF	5	12	33,980.00	$0.39	$13,285.20
		LF	6	14	113,500.00	$0.28	$32,065.90
		LF	7	23	98,060.00	$0.32	$31,199.40
		LF	10	3	2,770.00	$0.59	$1,645.00
		LF	11	10	12,970.00	$0.69	$8,955.50
		LF	12	17	110,580.00	$0.28	$30,568.80
	Unit Sub Total	**LF**		**119**	**495,250.00**	**$0.35**	**$174,729.30**
	Item Code 840526 Total No. of Proj.			**119**		**Total Amount**	**$174,729.30**
840539	4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED, 36-12)	LF	3	1	12,200.00	$1.35	$16,470.00
	Unit Sub Total	**LF**		**1**	**12,200.00**	**$1.35**	**$16,470.00**
	Item Code 840539 Total No. of Proj.			**1**		**Total Amount**	**$16,470.00**
840545	4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED, BROKEN 36-12)	LF	3	5	155,800.00	$1.32	$206,060.00
		LF	6	1	83,200.00	$1.20	$99,840.00
	Unit Sub Total	**LF**		**6**	**239,000.00**	**$1.28**	**$305,900.00**
	Item Code 840545 Total No. of Proj.			**6**		**Total Amount**	**$305,900.00**
840550	8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	LF	7	5	10,170.00	$0.58	$5,915.30
		LF	12	7	89,770.00	$0.73	$65,129.00
	Unit Sub Total	**LF**		**12**	**99,940.00**	**$0.71**	**$71,044.30**
	Item Code 840550 Total No. of Proj.			**12**		**Total Amount**	**$71,044.30**
840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	LF	2	26	2,565,980.00	$0.25	$636,096.20

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	LF	4	2	232,900.00	$0.64	$149,330.00
		LF	5	12	355,070.00	$0.56	$199,886.50
		LF	6	1	11,100.00	$0.35	$3,885.00
		LF	8	35	8,509,350.00	$0.18	$1,551,732.50
		LF	10	22	2,159,620.00	$0.25	$536,103.00
	Unit Sub Total	**LF**		**98**	**###########**	**$0.22**	**$3,077,033.20**
840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	M	5	1	52,500.00	$0.65	$34,125.00
		M	8	1	30,300.00	$0.75	$22,725.00
		M	10	2	19,750.00	$1.57	$30,995.00
	Unit Sub Total	**M**		**4**	**102,550.00**	**$0.86**	**$87,845.00**
	Item Code 840560 Total No. of Proj.			**102**		**Total Amount**	**$3,164,878.20**
840561	100 MM THERMOPLASTIC TRAFFIC STRIPE	M	4	1	5,280.00	$1.00	$5,280.00
		M	5	1	18,100.00	$1.20	$21,720.00
		M	7	5	60,670.00	$1.53	$92,923.50
		M	10	1	3,260.00	$2.00	$6,520.00
		M	11	1	33,100.00	$1.00	$33,100.00
	Unit Sub Total	**M**		**9**	**120,410.00**	**$1.33**	**$159,543.50**
	Item Code 840561 Total No. of Proj.			**9**		**Total Amount**	**$159,543.50**
840562	150 MM THERMOPLASTIC TRAFFIC STRIPE	M	4	1	480.00	$1.20	$576.00
	Unit Sub Total	**M**		**1**	**480.00**	**$1.20**	**$576.00**
	Item Code 840562 Total No. of Proj.			**1**		**Total Amount**	**$576.00**
840563	200 MM THERMOPLASTIC TRAFFIC STRIPE	M	4	1	1,500.00	$1.50	$2,250.00
		M	5	1	7,180.00	$3.00	$21,540.00
		M	7	5	6,000.00	$2.49	$14,918.00
		M	11	2	3,920.00	$3.00	$11,760.00
	Unit Sub Total	**M**		**9**	**18,600.00**	**$2.71**	**$50,468.00**
	Item Code 840563 Total No. of Proj.			**9**		**Total Amount**	**$50,468.00**
840564	200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M)	M	5	1	440.00	$4.00	$1,760.00
		M	7	3	2,460.00	$2.27	$5,590.00
		M	11	2	3,410.00	$1.30	$4,450.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**6**	**6,310.00**	**$1.87**	**$11,800.00**
	Item Code 840564 Total No. of Proj.			**6**		**Total Amount**	**$11,800.00**
840567	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 1.83 M - 0.30 M)	M	4	1	140.00	$1.00	$140.00
		M	5	1	220.00	$1.00	$220.00
		M	7	1	460.00	$1.20	$552.00
		M	11	1	250.00	$2.00	$500.00
	Unit Sub Total	**M**		**4**	**1,070.00**	**$1.32**	**$1,412.00**
	Item Code 840567 Total No. of Proj.			**4**		**Total Amount**	**$1,412.00**
840570	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M)	M	4	1	950.00	$1.00	$950.00
		M	5	1	20,100.00	$1.00	$20,100.00
		M	7	5	32,400.00	$1.18	$38,358.00
	Unit Sub Total	**M**		**7**	**53,450.00**	**$1.11**	**$59,408.00**
	Item Code 840570 Total No. of Proj.			**7**		**Total Amount**	**$59,408.00**
840571	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 5.18 M - 2.14 M)	M	4	1	1,030.00	$1.00	$1,030.00
		M	5	1	3,910.00	$1.00	$3,910.00
		M	7	4	9,700.00	$1.14	$11,057.30
		M	11	1	81.00	$1.00	$81.00
	Unit Sub Total	**M**		**7**	**14,721.00**	**$1.09**	**$16,078.30**
	Item Code 840571 Total No. of Proj.			**7**		**Total Amount**	**$16,078.30**
840580	4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED) (BROKEN 17-7)	LF	1	1	1,710.00	$0.10	$171.00
		LF	3	2	23,920.00	$1.16	$27,768.00
		LF	6	1	640.00	$1.10	$704.00
	Unit Sub Total	**LF**		**4**	**26,270.00**	**$1.09**	**$28,643.00**
	Item Code 840580 Total No. of Proj.			**4**		**Total Amount**	**$28,643.00**
840581	4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED)	LF	3	6	476,400.00	$2.34	$1,113,680.00
		LF	6	1	52,700.00	$1.20	$63,240.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**7**	**529,100.00**	**$2.22**	**$1,176,920.00**
	Item Code 840581 Total No. of Proj.			**7**		**Total Amount**	**$1,176,920.00**
840582	4" TWO-COMPONENT PAINT TRAFFIC STRIPE	LF	2	7	1,256,680.00	$0.75	$944,066.00
		LF	3	10	699,510.00	$0.43	$300,148.20
		LF	11	1	36,300.00	$0.78	$28,314.00
	Unit Sub Total	**LF**		**18**	**1,992,490.00**	**$0.64**	**$1,272,528.20**
	Item Code 840582 Total No. of Proj.			**18**		**Total Amount**	**$1,272,528.20**
840583	6" TWO-COMPONENT PAINT TRAFFIC STRIPE	LF	3	1	500.00	$9.50	$4,750.00
		LF	11	2	142,600.00	$0.83	$117,855.00
	Unit Sub Total	**LF**		**3**	**143,100.00**	**$0.86**	**$122,605.00**
	Item Code 840583 Total No. of Proj.			**3**		**Total Amount**	**$122,605.00**
840584	8" TWO-COMPONENT PAINT TRAFFIC STRIPE	LF	2	5	32,750.00	$1.99	$65,144.50
		LF	3	1	250.00	$3.00	$750.00
		LF	11	1	1,180.00	$3.00	$3,540.00
	Unit Sub Total	**LF**		**7**	**34,180.00**	**$2.03**	**$69,434.50**
	Item Code 840584 Total No. of Proj.			**7**		**Total Amount**	**$69,434.50**
840600	PAINTED TRAFFIC STRIPE	LF	7	1	2,910.00	$0.40	$1,164.00
	Unit Sub Total	**LF**		**1**	**2,910.00**	**$0.40**	**$1,164.00**
	Item Code 840600 Total No. of Proj.			**1**		**Total Amount**	**$1,164.00**
840608	4" TWO-COMPONENT PAINT TRAFFIC STRIPE (BROKEN 17-7)	LF	2	3	4,110.00	$1.20	$4,947.00
		LF	11	1	540.00	$0.30	$162.00
	Unit Sub Total	**LF**		**4**	**4,650.00**	**$1.10**	**$5,109.00**
	Item Code 840608 Total No. of Proj.			**4**		**Total Amount**	**$5,109.00**
840653	PAINT TRAFFIC STRIPE	LF	1	1	2,850.00	$2.00	$5,700.00
		LF	4	1	20,600.00	$0.50	$10,300.00
	Unit Sub Total	**LF**		**2**	**23,450.00**	**$0.68**	**$16,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 840653	**Total No. of Proj.**			**2**		**Total Amount**	**$16,000.00**
840655	PAINT TRAFFIC STRIPE (1-COAT)		LF	1	1	1,270.00	$0.13	$165.10
			LF	11	7	158,680.00	$0.15	$23,326.00
			LF	12	2	95,300.00	$0.08	$7,862.00
		Unit Sub Total	**LF**		**10**	**255,250.00**	**$0.12**	**$31,353.10**
	Item Code 840655	**Total No. of Proj.**			**10**		**Total Amount**	**$31,353.10**
840656	PAINT TRAFFIC STRIPE (2-COAT)		LF	1	1	820.00	$3.00	$2,460.00
			LF	2	1	423,000.00	$0.25	$105,750.00
			LF	4	2	119,380.00	$0.32	$37,766.80
			LF	5	1	22,100.00	$0.20	$4,420.00
			LF	6	6	1,625,880.00	$0.28	$460,912.00
			LF	7	10	1,983,160.00	$0.18	$349,948.40
			LF	9	13	1,662,910.00	$0.15	$252,035.60
			LF	10	2	1,052,500.00	$0.22	$227,190.00
			LF	11	11	3,111,420.00	$0.12	$369,198.00
			LF	12	11	1,512,100.00	$0.14	$214,819.00
		Unit Sub Total	**LF**		**58**	**############**	**$0.18**	**$2,024,499.80**
840656	PAINT TRAFFIC STRIPE (2-COAT)		M	4	1	590.00	$3.00	$1,770.00
			M	5	1	90,300.00	$0.55	$49,665.00
			M	7	1	8,590.00	$0.75	$6,442.50
			M	8	1	21,800.00	$0.40	$8,720.00
			M	11	2	109,000.00	$0.87	$95,260.00
		Unit Sub Total	**M**		**6**	**230,280.00**	**$0.70**	**$161,857.50**
	Item Code 840656	**Total No. of Proj.**			**64**		**Total Amount**	**$2,186,357.30**
840660	PAINT PAVEMENT MARKING		SQFT	3	1	740.00	$3.68	$2,723.20
			SQFT	4	1	530.00	$3.50	$1,855.00
			SQFT	7	1	830.00	$2.30	$1,909.00
			SQFT	10	1	5,520.00	$3.00	$16,560.00
			SQFT	11	1	150.00	$1.50	$225.00
			SQFT	12	1	1,490.00	$1.50	$2,235.00
		Unit Sub Total	**SQFT**		**6**	**9,260.00**	**$2.75**	**$25,507.20**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 840660 Total No. of Proj.			**6**		**Total Amount**	**$25,507.20**
840661	TWO-COMPONENT PAINT PAVEMENT MARKING	SQFT	2	3	11,600.00	$14.62	$169,560.00
		SQFT	3	8	8,604.00	$8.71	$74,899.40
	Unit Sub Total	**SQFT**		**11**	**20,204.00**	**$12.10**	**$244,459.40**
	Item Code 840661 Total No. of Proj.			**11**		**Total Amount**	**$244,459.40**
840666	PAINT PAVEMENT MARKING (2-COAT)	M2	5	1	360.00	$45.00	$16,200.00
		M2	7	1	500.00	$10.00	$5,000.00
		M2	8	1	19.00	$30.00	$570.00
	Unit Sub Total	**M2**		**3**	**879.00**	**$24.77**	**$21,770.00**
840666	PAINT PAVEMENT MARKING (2-COAT)	SQFT	1	1	75.00	$12.00	$900.00
		SQFT	3	1	1,900.00	$2.00	$3,800.00
		SQFT	4	1	60.00	$5.18	$310.80
		SQFT	6	3	3,230.00	$2.02	$6,519.00
		SQFT	7	5	5,210.00	$2.82	$14,694.00
		SQFT	9	6	9,850.00	$3.04	$29,959.70
		SQFT	11	1	780.00	$3.00	$2,340.00
		SQFT	12	5	3,540.00	$2.33	$8,262.00
	Unit Sub Total	**SQFT**		**23**	**24,645.00**	**$2.71**	**$66,785.50**
	Item Code 840666 Total No. of Proj.			**26**		**Total Amount**	**$88,555.50**
842000	PARKING BUMPER (PRECAST CONCRETE)	EA	3	2	38.00	$61.05	$2,320.00
		EA	4	1	13.00	$120.00	$1,560.00
		EA	7	2	43.00	$73.26	$3,150.00
	Unit Sub Total	**EA**		**5**	**94.00**	**$74.79**	**$7,030.00**
	Item Code 842000 Total No. of Proj.			**5**		**Total Amount**	**$7,030.00**
850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	1	3	1,420.00	$4.82	$6,846.00
		EA	3	10	7,735.00	$3.06	$23,700.20
		EA	4	37	112,409.00	$2.18	$244,894.00
		EA	5	22	73,145.00	$1.30	$95,312.00
		EA	6	3	742.00	$1.98	$1,469.60
		EA	7	45	341,598.00	$1.17	$401,052.00
		EA	8	21	104,716.00	$1.18	$123,355.60

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	10	3	710.00	$3.18	$2,257.00
		EA	11	17	131,265.00	$1.06	$139,264.10
		EA	12	19	138,540.00	$1.18	$163,150.80
	Unit Sub Total	**EA**		**180**	**912,280.00**	**$1.32**	**$1,201,301.30**
	Item Code 850101 Total No. of Proj.			**180**		**Total Amount**	**$1,201,301.30**
850102	PAVEMENT MARKER (REFLECTIVE)	EA	4	1	270.00	$5.50	$1,485.00
		EA	8	2	4,270.00	$2.19	$9,350.00
		EA	12	1	760.00	$4.00	$3,040.00
	Unit Sub Total	**EA**		**4**	**5,300.00**	**$2.62**	**$13,875.00**
	Item Code 850102 Total No. of Proj.			**4**		**Total Amount**	**$13,875.00**
850104	PAVEMENT MARKER (REFLECTIVE-SPECIAL TYPE H)	EA	4	1	23.00	$10.00	$230.00
	Unit Sub Total	**EA**		**1**	**23.00**	**$10.00**	**$230.00**
	Item Code 850104 Total No. of Proj.			**1**		**Total Amount**	**$230.00**
850110	PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE C)	EA	8	1	8.00	$4.50	$36.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$4.50**	**$36.00**
	Item Code 850110 Total No. of Proj.			**1**		**Total Amount**	**$36.00**
850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	1	23	50,071.00	$3.59	$179,775.00
		EA	2	11	46,182.00	$3.40	$157,180.00
		EA	3	38	117,625.00	$3.63	$426,484.00
		EA	4	57	108,189.00	$3.16	$341,437.70
		EA	5	30	71,496.00	$2.90	$207,092.40
		EA	6	36	68,481.00	$2.78	$190,716.00
		EA	7	57	251,072.00	$2.78	$696,976.21
		EA	8	29	104,281.00	$3.14	$327,455.00
		EA	10	29	62,009.00	$3.14	$194,998.30
		EA	11	24	86,918.00	$3.61	$313,544.80
		EA	12	23	119,521.00	$2.76	$329,480.80
	Unit Sub Total	**EA**		**357**	**1,085,845.00**	**$3.10**	**$3,365,140.21**
850111	PAVEMENT MARKER (RETROREFLECTIVE)	LF	6	1	1,200.00	$3.00	$3,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**1**	**1,200.00**	**$3.00**	**$3,600.00**
	Item Code 850111 Total No. of Proj.			**358**		**Total Amount**	**$3,368,740.21**
850112	PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE G)	EA	4	1	52.00	$7.00	$364.00
	Unit Sub Total	**EA**		**1**	**52.00**	**$7.00**	**$364.00**
	Item Code 850112 Total No. of Proj.			**1**		**Total Amount**	**$364.00**
850113	PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE H)	EA	4	1	190.00	$2.50	$475.00
	Unit Sub Total	**EA**		**1**	**190.00**	**$2.50**	**$475.00**
	Item Code 850113 Total No. of Proj.			**1**		**Total Amount**	**$475.00**
850120	PAVEMENT MARKER (REFLECTIVE-RECESSED)	EA	8	4	31,390.00	$4.57	$143,480.00
	Unit Sub Total	**EA**		**4**	**31,390.00**	**$4.57**	**$143,480.00**
	Item Code 850120 Total No. of Proj.			**4**		**Total Amount**	**$143,480.00**
850121	PAVEMENT MARKER (NON-REFLECTIVE-RECESSED)	EA	1	1	410.00	$6.00	$2,460.00
		EA	2	1	220.00	$23.00	$5,060.00
	Unit Sub Total	**EA**		**2**	**630.00**	**$11.94**	**$7,520.00**
	Item Code 850121 Total No. of Proj.			**2**		**Total Amount**	**$7,520.00**
850122	PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)	EA	1	14	29,978.00	$8.73	$261,641.00
		EA	2	18	59,289.00	$7.71	$456,888.00
		EA	3	6	16,110.00	$6.83	$110,096.00
		EA	4	2	5,920.00	$7.56	$44,780.00
		EA	6	3	7,492.00	$9.13	$68,436.00
		EA	7	7	24,220.00	$10.63	$257,458.50
		EA	8	7	27,470.00	$9.18	$252,145.00
		EA	10	1	2,350.00	$15.00	$35,250.00
		EA	11	2	12,040.00	$10.13	$121,940.00
		EA	12	1	4,250.00	$8.10	$34,425.00
	Unit Sub Total	**EA**		**61**	**189,119.00**	**$8.69**	**$1,643,059.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 850122 Total No. of Proj.			**61**		**Total Amount**	**$1,643,059.50**
860090	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	1	5	5.00	$2,400.00	$12,000.00
		LS	2	18	18.00	$1,494.44	$26,900.00
		LS	3	30	30.00	$2,339.40	$70,182.09
		LS	4	32	32.00	$2,932.03	$93,825.00
		LS	5	17	17.00	$1,427.06	$24,260.00
		LS	6	29	29.00	$2,006.91	$58,200.50
		LS	7	43	43.00	$1,721.19	$74,011.06
		LS	8	39	39.00	$2,018.23	$78,711.00
		LS	9	9	9.00	$7,877.89	$70,901.00
		LS	10	29	29.00	$1,386.84	$40,218.40
		LS	11	34	34.00	$2,784.71	$94,680.00
		LS	12	33	33.00	$1,556.61	$51,368.00
	Unit Sub Total	**LS**		**318**	**318.00**	**$2,186.34**	**$695,257.05**
	Item Code 860090 Total No. of Proj.			**318**		**Total Amount**	**$695,257.05**
860150	SIGNAL AND LIGHTING (TEMPORARY)	LS	3	2	2.00	$184,082.50	$368,165.00
		LS	7	1	1.00	$198,178.00	$198,178.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$188,781.00**	**$566,343.00**
	Item Code 860150 Total No. of Proj.			**3**		**Total Amount**	**$566,343.00**
860201	SIGNAL AND LIGHTING	LS	1	1	1.00	$152,000.00	$152,000.00
		LS	2	1	1.00	$200,000.00	$200,000.00
		LS	3	1	1.00	$208,931.00	$208,931.00
		LS	4	3	3.00	$126,500.00	$379,500.00
		LS	5	1	1.00	$120,000.00	$120,000.00
		LS	6	2	2.00	$106,500.00	$213,000.00
		LS	8	1	1.00	$148,564.00	$148,564.00
		LS	10	1	1.00	$174,000.00	$174,000.00
		LS	11	2	2.00	$44,250.00	$88,500.00
		LS	12	5	5.00	$134,698.80	$673,494.00
	Unit Sub Total	**LS**		**18**	**18.00**	**$130,999.39**	**$2,357,989.00**
	Item Code 860201 Total No. of Proj.			**18**		**Total Amount**	**$2,357,989.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860251	SIGNAL AND LIGHTING (LOCATION 1)	LS	3	1	1.00	$170,000.00	$170,000.00
		LS	4	5	5.00	$93,400.00	$467,000.00
		LS	7	1	1.00	$200,000.00	$200,000.00
		LS	8	1	1.00	$111,200.00	$111,200.00
		LS	10	1	1.00	$153,000.00	$153,000.00
		LS	11	3	3.00	$134,666.67	$404,000.00
		LS	12	2	2.00	$128,150.00	$256,300.00
	Unit Sub Total	**LS**		**14**	**14.00**	**$125,821.43**	**$1,761,500.00**
	Item Code 860251 Total No. of Proj.			**14**		**Total Amount**	**$1,761,500.00**
860252	SIGNAL AND LIGHTING (LOCATION 2)	LS	3	1	1.00	$120,000.00	$120,000.00
		LS	4	5	5.00	$129,600.00	$648,000.00
		LS	7	1	1.00	$100,000.00	$100,000.00
		LS	8	1	1.00	$80,600.00	$80,600.00
		LS	10	1	1.00	$150,000.00	$150,000.00
		LS	11	3	3.00	$76,000.00	$228,000.00
		LS	12	2	2.00	$78,050.00	$156,100.00
	Unit Sub Total	**LS**		**14**	**14.00**	**$105,907.14**	**$1,482,700.00**
	Item Code 860252 Total No. of Proj.			**14**		**Total Amount**	**$1,482,700.00**
860253	SIGNAL AND LIGHTING (LOCATION 3)	LS	4	1	1.00	$40,000.00	$40,000.00
		LS	11	2	2.00	$52,500.00	$105,000.00
		LS	12	1	1.00	$8,900.00	$8,900.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$38,475.00**	**$153,900.00**
	Item Code 860253 Total No. of Proj.			**4**		**Total Amount**	**$153,900.00**
860254	SIGNAL AND LIGHTING (LOCATION 4)	LS	4	1	1.00	$15,000.00	$15,000.00
		LS	7	1	1.00	$151,000.00	$151,000.00
		LS	11	2	2.00	$48,500.00	$97,000.00
		LS	12	1	1.00	$41,900.00	$41,900.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$60,980.00**	**$304,900.00**
	Item Code 860254 Total No. of Proj.			**5**		**Total Amount**	**$304,900.00**
860255	SIGNAL AND LIGHTING (LOCATION 5)	LS	7	1	1.00	$155,000.00	$155,000.00
		LS	11	2	2.00	$50,000.00	$100,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860255	SIGNAL AND LIGHTING (LOCATION 5)	LS	12	1	1.00	$45,500.00	$45,500.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$75,125.00**	**$300,500.00**
	Item Code 860255 Total No. of Proj.			**4**		**Total Amount**	**$300,500.00**
860256	SIGNAL AND LIGHTING (LOCATION 6)	LS	11	1	1.00	$75,000.00	$75,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$75,000.00**	**$75,000.00**
	Item Code 860256 Total No. of Proj.			**1**		**Total Amount**	**$75,000.00**
860257	SIGNAL AND LIGHTING (LOCATION 7)	LS	11	1	1.00	$80,000.00	$80,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$80,000.00**	**$80,000.00**
	Item Code 860257 Total No. of Proj.			**1**		**Total Amount**	**$80,000.00**
860258	SIGNAL AND LIGHTING (LOCATION 8)	LS	11	1	1.00	$63,000.00	$63,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$63,000.00**	**$63,000.00**
	Item Code 860258 Total No. of Proj.			**1**		**Total Amount**	**$63,000.00**
860297	SIGNAL AND LIGHTING (CITY)	LS	3	1	1.00	$25,000.00	$25,000.00
		LS	4	1	1.00	$15,000.00	$15,000.00
		LS	7	1	1.00	$170,855.00	$170,855.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$70,285.00**	**$210,855.00**
	Item Code 860297 Total No. of Proj.			**3**		**Total Amount**	**$210,855.00**
860298	SIGNAL AND LIGHTING (STAGE CONSTRUCTION)	LS	4	1	1.00	$100,000.00	$100,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$100,000.00**	**$100,000.00**
	Item Code 860298 Total No. of Proj.			**1**		**Total Amount**	**$100,000.00**
860300	SIGNAL AND LIGHTING (CITY STREET LOCATION 1)	LS	5	1	1.00	$215,000.00	$215,000.00
		LS	7	2	2.00	$155,000.00	$310,000.00
		LS	11	1	1.00	$142,000.00	$142,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$166,750.00**	**$667,000.00**
	Item Code 860300 Total No. of Proj.			**4**		**Total Amount**	**$667,000.00**
860301	SIGNAL AND LIGHTING	LS	4	1	1.00	$132,500.00	$132,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860301	SIGNAL AND LIGHTING	LS	6	1	1.00	$210,000.00	$210,000.00
		LS	7	1	1.00	$192,325.00	$192,325.00
		LS	11	2	2.00	$109,668.00	$219,336.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$150,832.20**	**$754,161.00**
	Item Code 860301 Total No. of Proj.			**5**		**Total Amount**	**$754,161.00**
860302	SIGNAL AND LIGHTING (CITY STREET LOCATION 2)	LS	5	1	1.00	$155,000.00	$155,000.00
		LS	7	2	2.00	$87,500.00	$175,000.00
		LS	11	1	1.00	$118,000.00	$118,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$112,000.00**	**$448,000.00**
	Item Code 860302 Total No. of Proj.			**4**		**Total Amount**	**$448,000.00**
860303	SIGNAL AND LIGHTING (CITY STREET LOCATION 3)	LS	4	1	1.00	$175,000.00	$175,000.00
		LS	5	1	1.00	$130,000.00	$130,000.00
		LS	7	1	1.00	$130,000.00	$130,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$145,000.00**	**$435,000.00**
	Item Code 860303 Total No. of Proj.			**3**		**Total Amount**	**$435,000.00**
860304	SIGNAL AND LIGHTING (CITY STREET LOCATION 4)	LS	4	1	1.00	$170,000.00	$170,000.00
		LS	5	1	1.00	$170,000.00	$170,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$170,000.00**	**$340,000.00**
	Item Code 860304 Total No. of Proj.			**2**		**Total Amount**	**$340,000.00**
860306	SIGNAL AND LIGHTING (CITY STREET LOCATION 6)	LS	7	1	1.00	$142,000.00	$142,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$142,000.00**	**$142,000.00**
	Item Code 860306 Total No. of Proj.			**1**		**Total Amount**	**$142,000.00**
860400	LIGHTING (TEMPORARY)	LS	3	1	1.00	$14,051.00	$14,051.00
		LS	7	5	5.00	$65,681.20	$328,406.00
		LS	12	3	3.00	$37,200.00	$111,600.00
	Unit Sub Total	**LS**		**9**	**9.00**	**$50,450.78**	**$454,057.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 860400 Total No. of Proj.			**9**		**Total Amount**	**$454,057.00**
860401	LIGHTING	LS	1	2	2.00	$76,500.00	$153,000.00
		LS	2	1	1.00	$450,000.00	$450,000.00
		LS	3	1	1.00	$14,175.00	$14,175.00
		LS	5	1	1.00	$36,000.00	$36,000.00
		LS	7	1	1.00	$20,000.00	$20,000.00
		LS	10	2	2.00	$46,800.00	$93,600.00
		LS	11	1	1.00	$124,450.00	$124,450.00
		LS	12	2	2.00	$29,500.00	$59,000.00
	Unit Sub Total	**LS**		**11**	**11.00**	**$86,384.09**	**$950,225.00**
	Item Code 860401 Total No. of Proj.			**11**		**Total Amount**	**$950,225.00**
860402	LIGHTING (CITY STREET)	LS	3	1	1.00	$100,000.00	$100,000.00
		LS	4	4	4.00	$78,250.00	$313,000.00
		LS	7	2	2.00	$132,500.00	$265,000.00
		LS	11	1	1.00	$144,000.00	$144,000.00
		LS	12	1	1.00	$38,200.00	$38,200.00
	Unit Sub Total	**LS**		**9**	**9.00**	**$95,577.78**	**$860,200.00**
	Item Code 860402 Total No. of Proj.			**9**		**Total Amount**	**$860,200.00**
860403	HIGHWAY LIGHTING	LS	1	1	1.00	$95,594.00	$95,594.00
		LS	8	1	1.00	$150,000.00	$150,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$122,797.00**	**$245,594.00**
	Item Code 860403 Total No. of Proj.			**2**		**Total Amount**	**$245,594.00**
860407	LIGHTING (PARKING LOT)	LS	4	1	1.00	$9,000.00	$9,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$9,000.00**	**$9,000.00**
	Item Code 860407 Total No. of Proj.			**1**		**Total Amount**	**$9,000.00**
860415	LIGHTING (STAGE CONSTRUCTION)	LS	4	3	3.00	$82,000.00	$246,000.00
		LS	10	1	1.00	$300,000.00	$300,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$136,500.00**	**$546,000.00**
	Item Code 860415 Total No. of Proj.			**4**		**Total Amount**	**$546,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860430	LIGHTING (NAVIGATION)	LS	7	1	1.00	$100,000.00	$100,000.00
		LS	8	1	1.00	$60,000.00	$60,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$80,000.00**	**$160,000.00**
	Item Code 860430 Total No. of Proj.			**2**		**Total Amount**	**$160,000.00**
860460	LIGHTING AND SIGN ILLUMINATION	LS	2	1	1.00	$50,000.00	$50,000.00
		LS	3	2	2.00	$241,500.00	$483,000.00
		LS	4	7	7.00	$184,285.71	$1,290,000.00
		LS	5	1	1.00	$245,000.00	$245,000.00
		LS	6	1	1.00	$200,000.00	$200,000.00
		LS	7	2	2.00	$500,000.00	$1,000,000.00
		LS	8	1	1.00	$152,100.00	$152,100.00
		LS	10	1	1.00	$500,000.00	$500,000.00
		LS	11	5	5.00	$190,400.00	$952,000.00
		LS	12	3	3.00	$660,810.11	$1,982,430.34
	Unit Sub Total	**LS**		**24**	**24.00**	**$285,605.43**	**$6,854,530.34**
	Item Code 860460 Total No. of Proj.			**24**		**Total Amount**	**$6,854,530.34**
860501	SIGN ILLUMINATION	LS	7	1	1.00	$9,200.00	$9,200.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$9,200.00**	**$9,200.00**
	Item Code 860501 Total No. of Proj.			**1**		**Total Amount**	**$9,200.00**
860503	EXTINGUISHABLE MESSAGE SIGN	EA	4	1	4.00	$15,000.00	$60,000.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$15,000.00**	**$60,000.00**
860503	EXTINGUISHABLE MESSAGE SIGN	LS	4	1	1.00	$50,000.00	$50,000.00
		LS	7	1	1.00	$60,000.00	$60,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$55,000.00**	**$110,000.00**
	Item Code 860503 Total No. of Proj.			**3**		**Total Amount**	**$170,000.00**
860504	EXTINGUISHABLE MESSAGE SIGN SYSTEM	LS	3	1	1.00	$87,059.50	$87,059.50
	Unit Sub Total	**LS**		**1**	**1.00**	**$87,059.50**	**$87,059.50**
	Item Code 860504 Total No. of Proj.			**1**		**Total Amount**	**$87,059.50**
860508	MODIFY SIGN ILLUMINATION	LS	3	2	2.00	$24,250.00	$48,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860508	MODIFY SIGN ILLUMINATION	LS	4	1	1.00	$27,000.00	$27,000.00
		LS	8	1	1.00	$15,000.00	$15,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$22,625.00**	**$90,500.00**
	Item Code 860508 Total No. of Proj.			**4**		**Total Amount**	**$90,500.00**
860520	HIGHWAY ADVISORY RADIO SYSTEM	LS	3	1	1.00	$148,588.13	$148,588.13
	Unit Sub Total	**LS**		**1**	**1.00**	**$148,588.13**	**$148,588.13**
	Item Code 860520 Total No. of Proj.			**1**		**Total Amount**	**$148,588.13**
860530	CHANGEABLE MESSAGE SIGN SYSTEM	LS	3	2	2.00	$25,909.18	$51,818.36
		LS	6	1	1.00	$19,950.00	$19,950.00
		LS	10	2	2.00	$62,500.00	$125,000.00
		LS	11	1	1.00	$13,000.00	$13,000.00
	Unit Sub Total	**LS**		**6**	**6.00**	**$34,961.39**	**$209,768.36**
	Item Code 860530 Total No. of Proj.			**6**		**Total Amount**	**$209,768.36**
860551	LIGHTING AND SIGN ILLUMINATION (LOCATION 1)	LS	4	2	2.00	$40,300.00	$80,600.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$40,300.00**	**$80,600.00**
	Item Code 860551 Total No. of Proj.			**2**		**Total Amount**	**$80,600.00**
860552	LIGHTING AND SIGN ILLUMINATION (LOCATION 2)	LS	4	2	2.00	$26,040.00	$52,080.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$26,040.00**	**$52,080.00**
	Item Code 860552 Total No. of Proj.			**2**		**Total Amount**	**$52,080.00**
860553	LIGHTING AND SIGN ILLUMINATION (LOCATION 3)	LS	4	1	1.00	$84,660.00	$84,660.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$84,660.00**	**$84,660.00**
	Item Code 860553 Total No. of Proj.			**1**		**Total Amount**	**$84,660.00**
860554	LIGHTING AND SIGN ILLUMINATION (LOCATION 4)	LS	4	1	1.00	$48,960.00	$48,960.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$48,960.00**	**$48,960.00**
	Item Code 860554 Total No. of Proj.			**1**		**Total Amount**	**$48,960.00**
860555	LIGHTING AND SIGN ILLUMINATION (LOCATION 5)	LS	4	1	1.00	$12,240.00	$12,240.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LS**		**1**	**1.00**	**$12,240.00**	**$12,240.00**
	Item Code 860555 Total No. of Proj.			**1**		**Total Amount**	**$12,240.00**
860556	LIGHTING AND SIGN ILLUMINATION (LOCATION 6)	LS	4	1	1.00	$43,860.00	$43,860.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$43,860.00**	**$43,860.00**
	Item Code 860556 Total No. of Proj.			**1**		**Total Amount**	**$43,860.00**
860615	MODIFY FLASHING BEACON	LS	7	2	2.00	$44,750.00	$89,500.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$44,750.00**	**$89,500.00**
	Item Code 860615 Total No. of Proj.			**2**		**Total Amount**	**$89,500.00**
860701	INTERCONNECTION CONDUIT AND CONDUCTOR	LS	7	1	1.00	$38,000.00	$38,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$38,000.00**	**$38,000.00**
	Item Code 860701 Total No. of Proj.			**1**		**Total Amount**	**$38,000.00**
860703	INTERCONNECTION CONDUIT AND CABLE	LS	4	2	2.00	$26,250.00	$52,500.00
		LS	8	1	1.00	$12,100.00	$12,100.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$21,533.33**	**$64,600.00**
	Item Code 860703 Total No. of Proj.			**3**		**Total Amount**	**$64,600.00**
860785	2" CONDUIT	LS	8	1	1.00	$16,800.00	$16,800.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$16,800.00**	**$16,800.00**
	Item Code 860785 Total No. of Proj.			**1**		**Total Amount**	**$16,800.00**
860792	COMMUNICATION CONDUIT (BRIDGE)	LS	4	1	1.00	$4,000.00	$4,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$4,000.00**	**$4,000.00**
	Item Code 860792 Total No. of Proj.			**1**		**Total Amount**	**$4,000.00**
860796	SPRINKLER CONTROL CONDUIT (BRIDGE)	LF	7	1	470.00	$25.00	$11,750.00
		LF	12	2	700.00	$28.36	$19,850.00
	Unit Sub Total	**LF**		**3**	**1,170.00**	**$27.01**	**$31,600.00**
860796	SPRINKLER CONTROL CONDUIT (BRIDGE)	M	5	1	913.00	$58.00	$52,954.00
		M	11	1	80.00	$45.00	$3,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M**		**2**	**993.00**	**$56.95**	**$56,554.00**
	Item Code 860796	**Total No. of Proj.**			**5**		**Total Amount**	**$88,154.00**
860797	ELECTRIC SERVICE (IRRIGATION)		LS	3	1	1.00	$10,000.00	$10,000.00
			LS	4	4	4.00	$19,462.50	$77,850.00
			LS	5	3	3.00	$9,900.00	$29,700.00
			LS	7	3	3.00	$6,433.33	$19,300.00
			LS	10	1	1.00	$58,058.00	$58,058.00
			LS	11	5	5.00	$12,088.60	$60,443.00
			LS	12	3	3.00	$6,402.33	$19,207.00
		Unit Sub Total	**LS**		**20**	**20.00**	**$13,727.90**	**$274,558.00**
	Item Code 860797	**Total No. of Proj.**			**20**		**Total Amount**	**$274,558.00**
860798	BOOSTER PUMP ELECTRICAL SYSTEM		LS	5	1	1.00	$39,000.00	$39,000.00
			LS	12	1	1.00	$18,000.00	$18,000.00
		Unit Sub Total	**LS**		**2**	**2.00**	**$28,500.00**	**$57,000.00**
	Item Code 860798	**Total No. of Proj.**			**2**		**Total Amount**	**$57,000.00**
860810	INDUCTIVE LOOP DETECTOR		EA	8	9	179.00	$480.98	$86,095.00
			EA	11	5	217.00	$559.45	$121,400.00
			EA	12	2	104.00	$274.81	$28,580.00
		Unit Sub Total	**EA**		**16**	**500.00**	**$472.15**	**$236,075.00**
860810	INDUCTIVE LOOP DETECTOR		LS	4	1	1.00	$10,000.00	$10,000.00
			LS	5	1	1.00	$35,000.00	$35,000.00
			LS	6	1	1.00	$6,000.00	$6,000.00
			LS	7	1	1.00	$100,000.00	$100,000.00
			LS	10	1	1.00	$11,200.00	$11,200.00
			LS	11	1	1.00	$2,000.00	$2,000.00
			LS	12	12	12.00	$36,521.25	$438,255.00
		Unit Sub Total	**LS**		**18**	**18.00**	**$33,469.72**	**$602,455.00**
	Item Code 860810	**Total No. of Proj.**			**34**		**Total Amount**	**$838,530.00**
860811	DETECTOR LOOP		EA	6	1	2.00	$3,600.00	$7,200.00
			EA	9	3	6.00	$1,366.67	$8,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**4**	**8.00**	**$1,925.00**	**$15,400.00**
860811	DETECTOR LOOP		LS	3	2	2.00	$71,650.00	$143,300.00
			LS	4	1	1.00	$58,375.00	$58,375.00
			LS	6	4	4.00	$8,025.00	$32,100.00
			LS	10	1	1.00	$18,500.00	$18,500.00
		Unit Sub Total	**LS**		**8**	**8.00**	**$31,534.38**	**$252,275.00**
	Item Code 860811	**Total No. of Proj.**			**12**		**Total Amount**	**$267,675.00**
860812	MICROWAVE VEHICLE DETECTION SYSTEM		LS	3	1	1.00	$125,000.00	$125,000.00
			LS	5	1	1.00	$65,000.00	$65,000.00
			LS	6	2	2.00	$160,495.00	$320,990.00
		Unit Sub Total	**LS**		**4**	**4.00**	**$127,747.50**	**$510,990.00**
	Item Code 860812	**Total No. of Proj.**			**4**		**Total Amount**	**$510,990.00**
860889	MODIFY TRAFFIC MONITORING STATION		EA	12	1	48.00	$600.00	$28,800.00
		Unit Sub Total	**EA**		**1**	**48.00**	**$600.00**	**$28,800.00**
860889	MODIFY TRAFFIC MONITORING STATION		LS	2	4	4.00	$29,625.00	$118,500.00
			LS	3	4	4.00	$69,812.50	$279,250.00
			LS	7	4	4.00	$41,750.00	$167,000.00
			LS	8	2	2.00	$22,074.00	$44,148.00
		Unit Sub Total	**LS**		**14**	**14.00**	**$43,492.71**	**$608,898.00**
	Item Code 860889	**Total No. of Proj.**			**15**		**Total Amount**	**$637,698.00**
860890	MODIFY TRAFFIC MONITORING STATION (COUNT)		LS	1	1	1.00	$16,000.00	$16,000.00
			LS	2	1	1.00	$4,000.00	$4,000.00
			LS	3	7	7.00	$16,915.71	$118,410.00
			LS	5	1	1.00	$17,525.00	$17,525.00
			LS	8	3	3.00	$47,000.00	$141,000.00
		Unit Sub Total	**LS**		**13**	**13.00**	**$22,841.15**	**$296,935.00**
	Item Code 860890	**Total No. of Proj.**			**13**		**Total Amount**	**$296,935.00**
860925	TRAFFIC MONITORING STATION (COUNT)		LS	3	1	1.00	$20,000.00	$20,000.00
			LS	6	1	1.00	$63,000.00	$63,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860925	TRAFFIC MONITORING STATION (COUNT)	LS	10	1	1.00	$9,000.00	$9,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$30,666.67**	**$92,000.00**
	Item Code 860925 Total No. of Proj.			**3**		**Total Amount**	**$92,000.00**
860930	TRAFFIC MONITORING STATION	LS	2	9	9.00	$14,761.11	$132,850.00
		LS	3	2	2.00	$23,256.18	$46,512.35
		LS	4	1	1.00	$125,000.00	$125,000.00
		LS	6	2	2.00	$9,750.00	$19,500.00
		LS	7	1	1.00	$18,000.00	$18,000.00
		LS	10	3	3.00	$91,333.33	$274,000.00
	Unit Sub Total	**LS**		**18**	**18.00**	**$34,214.58**	**$615,862.35**
	Item Code 860930 Total No. of Proj.			**18**		**Total Amount**	**$615,862.35**
860931	TRAFFIC MONITORING STATION (LOCATION 1)	LS	6	2	2.00	$29,400.00	$58,800.00
		LS	11	3	3.00	$24,500.00	$73,500.00
		LS	12	2	2.00	$20,150.00	$40,300.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$24,657.14**	**$172,600.00**
	Item Code 860931 Total No. of Proj.			**7**		**Total Amount**	**$172,600.00**
860932	TRAFFIC MONITORING STATION (LOCATION 2)	LS	6	2	2.00	$23,525.00	$47,050.00
		LS	11	3	3.00	$37,000.00	$111,000.00
		LS	12	2	2.00	$28,450.00	$56,900.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$30,707.14**	**$214,950.00**
	Item Code 860932 Total No. of Proj.			**7**		**Total Amount**	**$214,950.00**
860933	TRAFFIC MONITORING STATION (LOCATION 3)	LS	6	1	1.00	$20,900.00	$20,900.00
		LS	11	1	1.00	$8,000.00	$8,000.00
		LS	12	2	2.00	$29,300.00	$58,600.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$21,875.00**	**$87,500.00**
	Item Code 860933 Total No. of Proj.			**4**		**Total Amount**	**$87,500.00**
860934	TRAFFIC MONITORING STATION (LOCATION 4)	LS	12	1	1.00	$41,400.00	$41,400.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$41,400.00**	**$41,400.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 860934 Total No. of Proj.			**1**		**Total Amount**	**$41,400.00**
860937	TRAFFIC MONITORING STATION (LOCATION 7)	LS	6	1	1.00	$22,000.00	$22,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$22,000.00**	**$22,000.00**
	Item Code 860937 Total No. of Proj.			**1**		**Total Amount**	**$22,000.00**
860990	CLOSED CIRCUIT TELEVISION SYSTEM	LS	2	3	3.00	$168,333.33	$505,000.00
		LS	3	1	1.00	$127,430.52	$127,430.52
		LS	4	1	1.00	$75,000.00	$75,000.00
		LS	5	1	1.00	$100,000.00	$100,000.00
		LS	6	2	2.00	$40,750.00	$81,500.00
		LS	10	2	2.00	$48,500.00	$97,000.00
		LS	12	1	1.00	$32,000.00	$32,000.00
	Unit Sub Total	**LS**		**11**	**11.00**	**$92,539.14**	**$1,017,930.52**
	Item Code 860990 Total No. of Proj.			**11**		**Total Amount**	**$1,017,930.52**
861088	MODIFY RAMP METERING SYSTEM	LS	3	7	7.00	$69,060.57	$483,424.00
		LS	7	7	7.00	$81,685.09	$571,795.60
		LS	12	2	2.00	$22,250.00	$44,500.00
	Unit Sub Total	**LS**		**16**	**16.00**	**$68,732.48**	**$1,099,719.60**
	Item Code 861088 Total No. of Proj.			**16**		**Total Amount**	**$1,099,719.60**
861100	RAMP METERING SYSTEM	LS	3	3	3.00	$146,300.00	$438,900.00
		LS	4	1	1.00	$600,000.00	$600,000.00
		LS	6	1	1.00	$488,846.00	$488,846.00
		LS	7	2	2.00	$122,500.00	$245,000.00
		LS	11	1	1.00	$9,000.00	$9,000.00
	Unit Sub Total	**LS**		**8**	**8.00**	**$222,718.25**	**$1,781,746.00**
	Item Code 861100 Total No. of Proj.			**8**		**Total Amount**	**$1,781,746.00**
861101	RAMP METERING SYSTEM (LOCATION 1)	LS	7	1	1.00	$80,000.00	$80,000.00
		LS	11	1	1.00	$93,000.00	$93,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$86,500.00**	**$173,000.00**
	Item Code 861101 Total No. of Proj.			**2**		**Total Amount**	**$173,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
861102	RAMP METERING SYSTEM (LOCATION 2)	LS	7	1	1.00	$100,000.00	$100,000.00
		LS	11	1	1.00	$84,000.00	$84,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$92,000.00**	**$184,000.00**
	Item Code 861102 Total No. of Proj.			**2**		**Total Amount**	**$184,000.00**
861103	RAMP METERING SYSTEM (LOCATION 3)	LS	11	1	1.00	$38,000.00	$38,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$38,000.00**	**$38,000.00**
	Item Code 861103 Total No. of Proj.			**1**		**Total Amount**	**$38,000.00**
861107	RAMP METERING SYSTEM (LOCATION 7)	LS	12	1	1.00	$64,600.00	$64,600.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$64,600.00**	**$64,600.00**
	Item Code 861107 Total No. of Proj.			**1**		**Total Amount**	**$64,600.00**
861108	RAMP METERING SYSTEM (LOCATION 8)	LS	12	1	1.00	$75,800.00	$75,800.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$75,800.00**	**$75,800.00**
	Item Code 861108 Total No. of Proj.			**1**		**Total Amount**	**$75,800.00**
861109	RAMP METERING SYSTEM (LOCATION 9)	LS	12	1	1.00	$64,600.00	$64,600.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$64,600.00**	**$64,600.00**
	Item Code 861109 Total No. of Proj.			**1**		**Total Amount**	**$64,600.00**
861110	RAMP METERING SYSTEM (LOCATION 10)	LS	12	1	1.00	$71,700.00	$71,700.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$71,700.00**	**$71,700.00**
	Item Code 861110 Total No. of Proj.			**1**		**Total Amount**	**$71,700.00**
861200	WEIGH-IN-MOTION SYSTEM	LS	7	1	1.00	$90,000.00	$90,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$90,000.00**	**$90,000.00**
	Item Code 861200 Total No. of Proj.			**1**		**Total Amount**	**$90,000.00**
861204	WEIGH STATION BYPASS SYSTEM	LS	12	1	1.00	$1,008,585.36	$1,008,585.36
	Unit Sub Total	**LS**		**1**	**1.00**	**$1,008,585.36**	**$1,008,585.36**
	Item Code 861204 Total No. of Proj.			**1**		**Total Amount**	**$1,008,585.36**
861295	RELOCATE EXTINGUISHABLE MESSAGE SIGN	LS	4	1	1.00	$10,000.00	$10,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LS**		**1**	**1.00**	**$10,000.00**	**$10,000.00**
	Item Code 861295 Total No. of Proj.			**1**		**Total Amount**	**$10,000.00**
861349	REMOVE EXISTING SIGNAL SYSTEM	LS	8	1	1.00	$20,300.00	$20,300.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$20,300.00**	**$20,300.00**
	Item Code 861349 Total No. of Proj.			**1**		**Total Amount**	**$20,300.00**
861490	REMOVE FLASHING BEACON AND LIGHTING	LS	7	1	1.00	$10,000.00	$10,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$10,000.00**	**$10,000.00**
	Item Code 861490 Total No. of Proj.			**1**		**Total Amount**	**$10,000.00**
861491	MODIFY SIGNAL (LOCATION 1)	LS	3	1	1.00	$20,000.00	$20,000.00
		LS	6	3	3.00	$71,833.33	$215,500.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$58,875.00**	**$235,500.00**
	Item Code 861491 Total No. of Proj.			**4**		**Total Amount**	**$235,500.00**
861492	MODIFY SIGNAL (LOCATION 2)	LS	6	2	2.00	$84,750.00	$169,500.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$84,750.00**	**$169,500.00**
	Item Code 861492 Total No. of Proj.			**2**		**Total Amount**	**$169,500.00**
861493	MODIFY SIGNAL (LOCATION 3)	LS	6	2	2.00	$105,450.00	$210,900.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$105,450.00**	**$210,900.00**
	Item Code 861493 Total No. of Proj.			**2**		**Total Amount**	**$210,900.00**
861494	MODIFY SIGNAL (LOCATION 4)	LS	6	1	1.00	$13,000.00	$13,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$13,000.00**	**$13,000.00**
	Item Code 861494 Total No. of Proj.			**1**		**Total Amount**	**$13,000.00**
861495	MODIFY SIGNAL (LOCATION 5)	LS	6	1	1.00	$50,000.00	$50,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$50,000.00**	**$50,000.00**
	Item Code 861495 Total No. of Proj.			**1**		**Total Amount**	**$50,000.00**
861497	MODIFY SIGNAL AND LIGHTING (LOCATION 1)	LS	6	1	1.00	$18,000.00	$18,000.00
		LS	8	2	2.00	$39,000.00	$78,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
861497	MODIFY SIGNAL AND LIGHTING (LOCATION 1)	LS	10	1	1.00	$65,000.00	$65,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$40,250.00**	**$161,000.00**
	Item Code 861497 Total No. of Proj.			**4**		**Total Amount**	**$161,000.00**
861498	MODIFY SIGNAL AND LIGHTING (LOCATION 2)	LS	6	2	2.00	$78,000.00	$156,000.00
		LS	8	2	2.00	$70,000.00	$140,000.00
		LS	10	1	1.00	$35,000.00	$35,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$66,200.00**	**$331,000.00**
	Item Code 861498 Total No. of Proj.			**5**		**Total Amount**	**$331,000.00**
861501	MODIFY SIGNAL AND LIGHTING	LS	1	1	1.00	$48,000.00	$48,000.00
		LS	3	4	4.00	$368,250.00	$1,473,000.00
		LS	6	2	2.00	$90,191.75	$180,383.50
		LS	7	6	6.00	$89,750.00	$538,500.00
		LS	12	2	2.00	$38,500.00	$77,000.00
	Unit Sub Total	**LS**		**15**	**15.00**	**$154,458.90**	**$2,316,883.50**
	Item Code 861501 Total No. of Proj.			**15**		**Total Amount**	**$2,316,883.50**
861502	MODIFY SIGNAL	LS	2	1	1.00	$15,450.00	$15,450.00
		LS	3	2	2.00	$44,966.50	$89,933.00
		LS	4	1	1.00	$7,500.00	$7,500.00
		LS	5	6	6.00	$23,750.00	$142,500.00
		LS	6	1	1.00	$8,400.00	$8,400.00
		LS	8	1	1.00	$70,000.00	$70,000.00
		LS	10	3	3.00	$23,987.33	$71,962.00
	Unit Sub Total	**LS**		**15**	**15.00**	**$27,049.67**	**$405,745.00**
	Item Code 861502 Total No. of Proj.			**15**		**Total Amount**	**$405,745.00**
861503	MODIFY LIGHTING	LS	2	1	1.00	$110,000.00	$110,000.00
		LS	3	3	3.00	$76,271.67	$228,815.00
		LS	4	1	1.00	$55,000.00	$55,000.00
		LS	5	5	5.00	$25,092.60	$125,463.00
		LS	6	5	5.00	$25,815.40	$129,077.00
		LS	7	3	3.00	$50,267.88	$150,803.63
		LS	8	1	1.00	$15,000.00	$15,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
861503	MODIFY LIGHTING	LS	10	2	2.00	$25,350.00	$50,700.00
		LS	11	1	1.00	$6,500.00	$6,500.00
		LS	12	2	2.00	$28,050.00	$56,100.00
	Unit Sub Total	**LS**		**24**	**24.00**	**$38,644.11**	**$927,458.63**
	Item Code 861503 Total No. of Proj.			**24**		**Total Amount**	**$927,458.63**
861504	MODIFY LIGHTING AND SIGN ILLUMINATION	LS	3	3	3.00	$359,111.33	$1,077,334.00
		LS	4	1	1.00	$275,000.00	$275,000.00
		LS	5	1	1.00	$2,650.00	$2,650.00
		LS	6	2	2.00	$21,000.00	$42,000.00
		LS	7	7	7.00	$178,674.14	$1,250,719.00
		LS	8	1	1.00	$220,000.00	$220,000.00
		LS	10	1	1.00	$155,000.00	$155,000.00
		LS	12	1	1.00	$77,000.00	$77,000.00
	Unit Sub Total	**LS**		**17**	**17.00**	**$182,335.47**	**$3,099,703.00**
	Item Code 861504 Total No. of Proj.			**17**		**Total Amount**	**$3,099,703.00**
862026	LIGHTING (AREA)	LS	2	1	1.00	$41,000.00	$41,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$41,000.00**	**$41,000.00**
	Item Code 862026 Total No. of Proj.			**1**		**Total Amount**	**$41,000.00**
862031	SALVAGE FLASHING BEACON	LS	1	1	1.00	$1,550.00	$1,550.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$1,550.00**	**$1,550.00**
	Item Code 862031 Total No. of Proj.			**1**		**Total Amount**	**$1,550.00**
862065	REPLACE PULL BOX	LS	6	1	1.00	$24,000.00	$24,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$24,000.00**	**$24,000.00**
	Item Code 862065 Total No. of Proj.			**1**		**Total Amount**	**$24,000.00**
869001	MISCELLANEOUS ELECTRICAL	LS	11	1	1.00	$14,800.00	$14,800.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$14,800.00**	**$14,800.00**
	Item Code 869001 Total No. of Proj.			**1**		**Total Amount**	**$14,800.00**
869042	ADJUST PULL BOX	LS	6	1	1.00	$11,000.00	$11,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LS**		**1**	**1.00**	**$11,000.00**	**$11,000.00**
	Item Code 869042	**Total No. of Proj.**			**1**		**Total Amount**	**$11,000.00**
869050	GUARD POST		EA	7	1	5.00	$500.00	$2,500.00
		Unit Sub Total	**EA**		**1**	**5.00**	**$500.00**	**$2,500.00**
	Item Code 869050	**Total No. of Proj.**			**1**		**Total Amount**	**$2,500.00**
869072	SEISMIC MONITORING SYSTEM		LS	7	1	1.00	$80,000.00	$80,000.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$80,000.00**	**$80,000.00**
	Item Code 869072	**Total No. of Proj.**			**1**		**Total Amount**	**$80,000.00**
869075	SYSTEM TESTING AND DOCUMENTATION		LS	7	2	2.00	$24,450.00	$48,900.00
			LS	8	1	1.00	$35,000.00	$35,000.00
			LS	12	2	2.00	$40,350.00	$80,700.00
		Unit Sub Total	**LS**		**5**	**5.00**	**$32,920.00**	**$164,600.00**
	Item Code 869075	**Total No. of Proj.**			**5**		**Total Amount**	**$164,600.00**
869080	TRAINING		LS	8	1	1.00	$50,000.00	$50,000.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$50,000.00**	**$50,000.00**
	Item Code 869080	**Total No. of Proj.**			**1**		**Total Amount**	**$50,000.00**
991061	ELECTRICAL WORK		LS	3	2	2.00	$32,500.00	$65,000.00
		Unit Sub Total	**LS**		**2**	**2.00**	**$32,500.00**	**$65,000.00**
	Item Code 991061	**Total No. of Proj.**			**2**		**Total Amount**	**$65,000.00**
994420	PICNIC TABLE WITH BENCHES		EA	11	1	43.00	$722.00	$31,046.00
		Unit Sub Total	**EA**		**1**	**43.00**	**$722.00**	**$31,046.00**
	Item Code 994420	**Total No. of Proj.**			**1**		**Total Amount**	**$31,046.00**
994425	BENCH		EA	11	1	12.00	$412.00	$4,944.00
		Unit Sub Total	**EA**		**1**	**12.00**	**$412.00**	**$4,944.00**
	Item Code 994425	**Total No. of Proj.**			**1**		**Total Amount**	**$4,944.00**
994650	BUILDING WORK		LS	3	4	4.00	$616,857.25	$2,467,429.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
994650	BUILDING WORK	LS	4	3	3.00	$572,811.10	$1,718,433.31
		LS	5	1	1.00	$224,320.00	$224,320.00
		LS	6	2	2.00	$1,987,070.50	$3,974,141.00
		LS	8	2	2.00	$376,350.00	$752,700.00
		LS	9	1	1.00	$320,000.00	$320,000.00
		LS	11	2	2.00	$1,654,514.89	$3,309,029.78
	Unit Sub Total	**LS**		**15**	**15.00**	**$851,070.21**	**$12,766,053.09**
	Item Code 994650 Total No. of Proj.			**15**		**Total Amount**	**$12,766,053.09**
994901	TRASH RECEPTACLE	EA	8	1	6.00	$750.00	$4,500.00
		EA	11	1	31.00	$370.00	$11,470.00
	Unit Sub Total	**EA**		**2**	**37.00**	**$431.62**	**$15,970.00**
	Item Code 994901 Total No. of Proj.			**2**		**Total Amount**	**$15,970.00**
999990	MOBILIZATION	LS	1	22	22.00	$201,201.55	$4,426,434.00
		LS	2	22	22.00	$533,807.61	$11,743,767.41
		LS	3	41	41.00	$721,362.86	$29,575,877.38
		LS	4	65	65.00	$307,465.29	$19,985,244.17
		LS	5	20	20.00	$430,020.15	$8,600,402.95
		LS	6	20	20.00	$530,601.15	$10,612,023.03
		LS	7	76	76.00	$607,695.41	$46,184,850.92
		LS	8	38	38.00	$243,632.79	$9,258,046.00
		LS	9	1	1.00	$70,000.00	$70,000.00
		LS	10	13	13.00	$999,909.06	$12,998,817.82
		LS	11	32	32.00	$382,409.89	$12,237,116.55
		LS	12	27	27.00	$259,606.26	$7,009,368.99
	Unit Sub Total	**LS**		**377**	**377.00**	**$458,095.36**	**$172,701,949.22**
	Item Code 999990 Total No. of Proj.			**377**		**Total Amount**	**$172,701,949.22**

APPENDIX A

Conversion Factors From English Units to SI Units

Unit	Abbr.	Multiply:	Unit	Abbr.
Acre	ACRE	0.4046856	Hectare	HA
Calendar Day	CDAY	1	Calendar Day	CDAY
Cubic Foot	CF	0.02831685	Cubic Meter	M3
Cubic Yard	CY	0.7645549	Cubic Meter	M3
Each	EA	1	Each	EA
Gallon	GAL	3.785412	Liter	L
Hour	HR	1	Hour	H
Pound	LB	0.4535924	Kilogram	KG
Linear Foot	LF	0.3048	Meter	M
Lane Mile	LNMI	1.609344	Lane Kilometer	LNKM
Lump Sum	LS	1	Lump Sum	LS
Thousand Foot Board Measure	MFBM	2.359737	Cubic Meter	M3
Mile	MI	1.609344	Kilometer	KM
Square Foot	SQFT	0.09290304	Square Meter	M2
Square Yard	SQYD	0.8361274	Square Meter	M2
Station (100 Ft)	STA	0.3048	Station (100 m)	STA
Tablet	TAB	1	Tablet	TAB
Ton	TON	0.9071847	Tonne (1000 kg)	TONN
Track Foot	TF	1	Track Foot	TF
Working Day	WDAY	1	Working Day	WDAY

APPENDIX B

Conversion Factors From SI Units to English Units

Unit	Abbr.	Multiply:	Unit	Abbr.
Hectare	HA	2.471054	Acre	ACRE
Calendar Day	CDAY	1	Calendar Day	CDAY
Cubic Meter	M3	35.31467	Cubic Foot	CF
Cubic Meter	M3	1.307951	Cubic Yard	CY
Each	EA	1	Each	EA
Liter	L	0.2641720	Gallon	GAL
Hour	H	1	Hour	HR
Kilogram	KG	2.204623	Pound	LB
Meter	M	3.280840	Linear Foot	LF
Lane Kilometer	LNKM	0.6213712	Lane Mile	LNMI
Lump Sum	LS	1	Lump Sum	LS
Cubic Meter	M3	0.4237760	Thousand Foot Board Measure	MFBM
Kilometer	KM	0.6213712	Mile	MI
Square Meter	M2	10.76391	Square Foot	SQFT
Square Meter	M2	1.195990	Square Yard	SQYD
Station (100 m)	STA	3.280840	Station (100 Ft)	STA
Tablet	TAB	1	Tablet	TAB
Tonne (1000 kg)	TONN	1.102312	Ton	TON
Track Foot	TF	1	Track Foot	TF
Working Day	WDAY	1	Working Day	WDAY