

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

[www.dot.ca.gov/hq/esc/oe](http://www.dot.ca.gov/hq/esc/oe)

*Serious Drought.  
Help save water!*

October 29, 2015

01-DN-199-24.7

01-0B3204

Project ID 0112000116

ACSTP-ER-19B8(004)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN DEL NORTE COUNTY NEAR PATRICK CREEK AT 2.6 MILES NORTH OF PATRICK CREEK ROAD, to revise the project plans, the *Notice to Bidders and Special Provisions*, the *Bid* book and the Federal Minimum Wages with Modification Number 11 dated 10/16/2015.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Tuesday, November 10, 2015.

Project plan sheet 36 is replaced and attached for substitution for the like-numbered sheet.

In the Special Provisions, Section 39-4.02C, the first paragraph is replaced as follows:

"For HMA-O, the grade of asphalt binder must be PG 58-34 PM."

In the *Bid* book, in the "Bid Item List," Items 32, 33, 57, 61 and 66 are replaced.

Addendum No. 1  
Page 2  
October 29, 2015

01-DN-199-24.7  
01-0B3204  
Project ID 0112000116  
ACSTP-ER-19B8(004)E

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

**[http://www.dot.ca.gov/hq/esc/oe/electronic\\_bidding/electronic\\_bidding.html](http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html)**

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file, attachments and the modified wage rates are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/01/01-0B3204](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/01/01-0B3204)**

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



for

CHARLIE FIELDER  
District Director

Attachments

**BID ITEM LIST  
01-0B3204**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	141120	TREATED WOOD WASTE	LB	3,750		
22	146001	CONTRACTOR-SUPPLIED BIOLOGIST (DAY)	DAY	6		
23	150661	REMOVE GUARDRAIL	LF	260		
24	150711	REMOVE PAINTED TRAFFIC STRIPE	LF	210		
25	150712	REMOVE PAINTED PAVEMENT MARKING	SQFT	24		
26	150722	REMOVE PAVEMENT MARKER	EA	24		
27	152316	RESET ROADSIDE SIGN (ONE POST)	EA	1		
28	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	620		
29	160102	CLEARING AND GRUBBING (LS)	LS	LUMP SUM	LUMP SUM	
30	190101	ROADWAY EXCAVATION	CY	100		
31	190185	SHOULDER BACKING	TON	50		
32 (F)	192049	STRUCTURE EXCAVATION (SOLDIER PILE WALL)	CY	150		
33 (F)	193029	STRUCTURE BACKFILL (SOLDIER PILE WALL)	CY	52		
34 (F)	193116	CONCRETE BACKFILL (SOLDIER PILE WALL)	CY	56		
35 (F)	193119	LEAN CONCRETE BACKFILL	CY	54		
36	205035	WOOD MULCH	CY	6		
37	210270	ROLLED EROSION CONTROL PRODUCT (NETTING)	SQFT	1,750		
38	210300	HYDROMULCH	SQFT	3,850		
39	210350	FIBER ROLLS	LF	320		
40	210420	STRAW	SQFT	2,100		

**BID ITEM LIST  
01-0B3204**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41	210430	HYDROSEED	SQFT	3,850		
42	260203	CLASS 2 AGGREGATE BASE (CY)	CY	100		
43	390132	HOT MIX ASPHALT (TYPE A)	TON	180		
44	390135	HOT MIX ASPHALT (LEVELING)	TON	20		
45	390401	HOT MIX ASPHALT-OPEN GRADED (OPEN GRADED FRICTION COURSE)	TON	130		
46	393004	GEOSYNTHETIC PAVEMENT INTERLAYER (PAVING FABRIC)	SQYD	200		
47	029900	CENTERLINE RUMBLE STRIP	STA	4.1		
48	397005	TACK COAT	TON	0.3		
49	460210	GROUND ANCHOR (SUBHORIZONTAL)	EA	17		
50	045078	STEEL SOLDIER PILE (W 16 X 67)	LF	210		
51	045079	STEEL SOLDIER PILE (2-C 15 X 50)	LF	570		
52	490400	24" DRILLED HOLE	LF	208		
53	490403	30" DRILLED HOLE	LF	394		
54 (F)	510060	STRUCTURAL CONCRETE, RETAINING WALL	CY	120		
55 (F)	510072	STRUCTURAL CONCRETE, BARRIER SLAB	CY	64		
56 (F)	045080	RANDOM ROCK TEXTURE	SQFT	3,130		
57 (F)	520103	BAR REINFORCING STEEL (RETAINING WALL)	LB	11,200		
58 (F)	575004	TIMBER LAGGING	MFBM	17		
59	590120	CLEAN AND PAINT STEEL SOLDIER PILING	LS	LUMP SUM	LUMP SUM	
60	597601	PREPARE AND STAIN CONCRETE	SQFT	3,130		

**BID ITEM LIST  
01-0B3204**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	681132	GEOCOMPOSITE DRAIN	SQFT	534		
62	045081	DRILL HOLE (CRIB WALL)	EA	34		
63	045082	CLASS 1 PERMEABLE MATERIAL, TYPE B	CY	144		
64	839543	TRANSITION RAILING (TYPE WB-31)	EA	2		
65	839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM	EA	2		
66 (F)	045083	CONCRETE BARRIER (TYPE 80 MODIFIED)	LF	178		
67	846001	4" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY)	LF	1,230		
68	850122	PAVEMENT MARKER (RETROREFLECTIVE- RECESSED)	EA	38		
69	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

**TOTAL BID:**

**\$**

---