

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.
Help save water!*

October 16, 2015

01-Men-128-2.8/11.1

01-378174

Project ID 0100000137

ACSTP-P128(056)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN MENDOCINO COUNTY NEAR NAVARRO AT VARIOUS LOCATIONS FROM 2.8 MILES EAST OF ROUTE 1 TO 0.5 MILE WEST OF FLYNN CREEK BRIDGE to revise the project plans, the *Notice to Bidders and Special Provisions*, the *Bid* book, EBS file and the Federal Minimum Wages with Modification Number 11 dated 10/16/2015.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, October 29, 2015.

The table below identifies project plan sheet number and a corresponding numbered note. The numbered note is revised to read as "EXPECT EXISTING CULVERT TO BE ENCASED IN CONCRETE BACKFILL THROUGHOUT TRENCH LENGTH."

Project Sheet No./ Note	Project Sheet No./ Note	Project Sheet No./ Note
5, 5	23, 3	36, 3
6, 5	24, 4	39, 3
8, 5	25, 3	40, 4
10, 5	26, 3	42, 4
12, 7& 8	27, 4	43, 4
14, 4	28, 5	44, 3
15, 4	29, 3	45, 4
18, 4	31, 3	49, 5
19, 4	32, 3	50, 4
20, 4	33, 4	52, 4
21, 3	34, 4	54, 3
22, 4	35, 5	

Addendum No. 1
Page 2
October 16, 2015

01-Men-128-2.8/11.1
01-378174
Project ID 0100000137
ACSTP-P128(056)E

In the Special Provisions, Section 12-4.02A the eleventh paragraph is replaced as follows:

"At each location where a culvert is to be installed across existing pavement, temporary or permanent pavement must be constructed and the full width of the roadway is opened to public traffic at the end of each work day. Temporary pavement must be 6 inches in thickness and must consist of slow curing asphalt concrete or other approved methods which will produce a smooth and even surface suitable for use by public traffic. Locations where temporary pavement is used must be permanently paved within 10 working days. Full compensation for furnishing, placing, and removing temporary pavement is considered as included in the contract price paid per foot for the various sizes and types of pipe involved and no separate payment is made therefor."

In the *Bid* book, in the "Bid Item List," Item 55 is deleted.

In the *Bid* book, in the "Bid Item List," Items 56 and 57 are added.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html


Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file, attachment and the modified wage rates are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/01/01-378174

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



FOR CHARLIE FIELDER
District Director

Attachments

BID ITEM LIST

01-378174

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41 (F)	620800	CONCRETE BACKFILL (PIPE TRENCH)	CY	230		
42	667010	24" X 18" CORRUGATED STEEL PIPE ARCH (.109" THICK)	LF	320		
43	705321	36" ALTERNATIVE FLARED END SECTION	EA	1		
44	705405	24" X 18" STEEL FLARED END PIPE ARCH SECTION	EA	2		
45 (F)	721013	ROCK SLOPE PROTECTION (1/4 T, METHOD B) (CY)	CY	15		
46 (F)	721015	ROCK SLOPE PROTECTION (LIGHT, METHOD B) (CY)	CY	94		
47 (F)	721030	ROCK SLOPE PROTECTION (1/2 T, METHOD B) (CY)	CY	36		
48	729011	ROCK SLOPE PROTECTION FABRIC (CLASS 8)	SQYD	270		
49 (F)	750001	MISCELLANEOUS IRON AND STEEL	LB	6,301		
50	820112	MARKER (CULVERT)	EA	110		
51	820130	OBJECT MARKER	EA	3		
52 (F)	839521	CABLE RAILING	LF	96		
53	840655	PAINT TRAFFIC STRIPE (1-COAT)	LF	1,260		
54	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	110		
55	BLANK					
56	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
57	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID:

\$
