

**DEPARTMENT OF TRANSPORTATION**

ESC/OE MS #43  
1727 30TH Street, 2ND Floor  
Sacramento, CA 95816



November 15, 2000

05-Mon-1-2.4  
05-0E9504  
ACSTP-P001(549)E

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in NEAR GORDA 2.4 km NORTH OF THE MONTEREY COUNTY LINE.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on November 16, 2000 at 10:00 a.m.

This addendum is being issued to revise the Project Plans, the Notice to Contractors and Special Provisions, and the Proposal and Contract.

Project Plan Sheet 16 is revised as follows:

The quantity for "STRUCTURAL CONCRETE, BRIDGE" is changed from 2031 m<sup>3</sup> to 1260 m<sup>3</sup>

Project Plan Sheet 17 is revised as follows:

In the legend for the CONCRETE STRENGTH AND TYPE LIMITS diagram, "Structural Concrete, Bridge ( $f_c = 35$  Mpa @ 28 days)" is changed to "900 mm CIDH Concrete Piling ( $f_c = 35$  Mpa @ 28 days)"

Project Plan Sheet 24 is revised as follows:

On DETAIL "X" the callout "Spiral shall be "Ultimate" butt spliced" is changed to "Splices are not allowed"

In the Special Provisions, Section 10-1.33, "REINFORCEMENT," a new subsection "ULTIMATE BUTT SPLICES" is added after the last paragraph as attached.

In the Proposal and Contract, the Engineer's Estimate Item 36 is revised as attached.

Addendum No. 2  
Page 2  
November 15, 2000

05-Mon-1-2.4  
05-0E9504  
ACSTP-P001(549)E

To Proposal and Contract book holders:

Replace page 4 of the Engineer's Estimate in the Proposal with the attached revised page 4 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by confirmed facsimile to Proposal and Contract book holders to ensure that each receives it.

Sincerely,

ORIGINAL SIGNED BY

NICK YAMBAO, Chief  
Office of Plans, Specifications & Estimates  
Division of Office Engineer

Attachment

## ULTIMATE BUTT SPLICES

Ultimate butt splices shall be either welded or mechanical splices, shall be used at the locations shown on the plans, and shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications and these special provisions.

## GENERAL REQUIREMENTS

The Contractor shall designate in writing an ultimate butt splicing Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for 1) the quality of all ultimate butt splicing including the inspection of materials and workmanship performed by the Contractor and all subcontractors; and 2) submitting, receiving, and approving all correspondence, required submittals, and reports regarding ultimate butt splicing to and from the Engineer.

The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

The length of any type of ultimate mechanical butt splice shall not exceed 10 times the bar diameter of the larger bar to be spliced.

All ultimate prejob, production, and job control sample splices shall be 1) a minimum length of 1.5 meters for reinforcing bars No. 25 or smaller and 2 meters for reinforcing bars No. 29 or larger, with the splice located at mid-point, and 2) suitably identified prior to shipment with weatherproof markings that do not interfere with the Engineer's tamper-proof markings or seals. Any splice that shows signs of tampering will be rejected.

A minimum of one control bar shall be removed from the same bar as, and adjacent to, all ultimate prejob, production, and job control sample splices. Control bars shall be 1) a minimum length of one meter for reinforcing bars No. 25 or smaller and 1.5 meters for reinforcing bars No. 29 or larger, and 2) suitably identified prior to shipment with weatherproof markings that do not interfere with the Engineer's tamper-proof markings or seals. The portion of adjacent bar remaining in the work shall also be identified with weatherproof markings that correspond to its adjacent control bar.

Shorter length sample splice and control bars may be furnished if approved in writing by the Engineer.

Each sample splice and its associated control bar shall be identified and marked as a set. Each set shall be identified as representing a prejob, production, or job control sample splice.

The portion of hoop reinforcing bar, removed to obtain a sample splice and control bar, shall be replaced using a prequalified ultimate mechanical butt splice, or the hoop shall be replaced in kind.

Reinforcing bars, other than hoops, from which sample splices are removed, shall be repaired using ultimate mechanical butt splices conforming to the provisions in "Prejob Test Requirements for Ultimate Butt Splices" specified herein, or the bars shall be replaced in kind. These bars shall be repaired or replaced such that no splices are located in the "No Splice Zone" shown on the plans.

Section 52-1.08E, "Job Control Tests," of the Standard Specifications shall not apply.

The provisions for total slip shall not apply to any ultimate splices that are welded or that are used on hoops.

The independent qualified testing laboratory used to perform the testing of all ultimate butt sample splices and control bars shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors who will provide other services or materials for the project, and shall have the following:

- A. Proper facilities, including a tensile testing machine capable of breaking the largest size of reinforcing bar to be tested.
- B. A device for measuring the total slip of the reinforcing bars across the splice to the nearest 25  $\mu\text{m}$ , that, when placed parallel to the longitudinal axis of the bar is able to simultaneously measure movement across the splice, at 2 locations, 180 degrees apart.
- C. Operators who have received formal training for performing the testing requirements of ASTM Designation: A 370/A 370M and California Test 670.
- D. A record of annual calibration of testing equipment performed by an independent third party that has 1) standards that are traceable to the National Institute of Standards and Technology, and 2) a formal reporting procedure, including published test forms.

## **ULTIMATE BUTT SPLICE TEST CRITERIA**

Ultimate prejob, production, and job control sample splices shall be tensile tested in conformance with the requirements described in ASTM Designation: A 370/A 370M and California Test 670.

Ultimate prejob and production sample splices shall rupture in the reinforcing bar either: 1) outside of the affected zone or 2) within the affected zone, provided that the sample has achieved at least 95 percent of the ultimate tensile strength of the control bar associated with the sample. In addition, necking of the bar shall be visibly evident at rupture regardless of whether the bar breaks inside or outside the affected zone.

The affected zone is the portion of the reinforcing bar where any properties of the bar, including the physical, metallurgical, or material characteristics, have been altered by fabrication or installation of the splice.

The ultimate tensile strength of each control bar shall be determined by tensile testing the bar to rupture and shall be determined for all control bars, regardless of where each sample splice ruptures. If 2 control bars are tested for one sample splice, the bar with the lower ultimate tensile strength shall be considered the control bar.

Testing to determine the minimum tensile strength, in conformance with the provisions in the ninth paragraph of Section 52-1.08, "Splicing," of the Standard Specifications, will not be required.

## **PREJOB TEST REQUIREMENTS FOR ULTIMATE BUTT SPLICES**

Prior to use in the work, all ultimate butt splices shall conform to the following prejob test requirements:

- A. Eight prejob sample splices for each bar size of each splice type including ultimate mechanical butt splices, ultimate complete joint penetration butt welded splices, and ultimate resistance butt welded splices, that will be used in the work, shall be fabricated by the Contractor. For deformation-dependent types of couplers, 8 sample prejob splices shall also be fabricated for each reinforcing bar size and deformation pattern that will be used in the work.
- B. The sample splices shall be fabricated using the same splice materials, position, operators, location, and equipment, and following the same procedures as will be used to make the splices in the work. In addition, for resistance butt welded splices, the sample splices shall have the weld flash removed and be epoxy-coated as specified elsewhere in these special provisions.
- C. At the option of the Contractor, operator qualification tests may be performed simultaneously with the preparation of prejob sample splices.
- D. If different diameters of hoops are shown on the plans, prejob sample splices, as described above, will only be required for the smallest hoop diameter. In addition, these splices shall be fabricated using the same radius as shown on the plans for these hoops.
- E. Unless otherwise directed in writing by the Engineer, 4 prejob sample splices and control bar sets shall be shipped to the Transportation Laboratory and the remaining 4 sets shall be tested by the Contractor's independent qualified testing laboratory.
- F. Each group of 4 sets from a prejob test shall be securely bundled together and identified by location and contract number with weatherproof markings prior to shipment. Bundles containing fewer than 4 sets will not be tested by the Transportation Laboratory, nor shall they be tested by the independent laboratory.
- G. All 8 sample splices from each prejob test shall conform to the provisions in "Ultimate Butt Splice Test Criteria" specified herein.
- H. Prior to performing any tensile tests on prejob test sample splices, one of the 4 samples shall be tested for, and shall conform to, the provisions for total slip. Should this sample not meet these requirements, one retest, in which the 3 remaining samples are tested for total slip, will be allowed. All 3 of these remaining samples tested shall conform to the aforementioned slip requirements.
- I. For each bundle of 4 sets, a Prejob Test Report shall be prepared by the independent testing laboratory performing the testing. The report shall 1) be signed by an engineer who represents the laboratory and is registered as a Civil Engineer in the State of California; 2) include, as a minimum, the following information for each set: contract number, bridge number, bar size, type of splice, length of mechanical splice, physical condition of test sample splice and control bar, any notable defects, limits of affected zone, total measured slip, location of visible necking area, ultimate strength of each splice, ultimate strength and 95 percent of this ultimate strength for each control bar, and a comparison between 95 percent of the ultimate strength of each control bar and the ultimate strength of its associated splice; and 3) be submitted to the QCM for review and approval, and then to the Engineer.
- J. Test results for each bundle of 4 sets will be reported in writing to the Contractor within 10 working days after receipt of the bundle by the Transportation Laboratory. In the event that more than one bundle is received on the same day, 2 additional working days shall be allowed for providing test results for each additional bundle received. A test report will be made for each bundle received.

- K. Should the Engineer fail to provide the test results within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in providing the test results, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

### **PRODUCTION TEST REQUIREMENTS FOR ULTIMATE BUTT SPLICES**

Production tests shall be performed for all ultimate butt splices used in the work. A production test shall consist of 4 sets of sample splices and control bars removed from each lot of completed splices, except when quality assurance tests are performed.

A lot of ultimate butt splices is defined as 1) 150, or fraction thereof, of the same type of ultimate mechanical butt splices used for each bar size and each bar deformation pattern that is used in the work or 2) 150, or fraction thereof, of ultimate complete joint penetration butt welded splices, or ultimate resistance butt welded splices for each bar size used in the work. If different diameters of hoop reinforcement are shown on the plans, separate lots shall be used for each different hoop diameter.

After all splices in a lot have been completed, the QCM shall notify the Engineer in writing that all couplers in this lot conform to the specifications and are ready for testing. The sample splices will either be selected by the Engineer at the job site or a fabrication facility, provided the facility is located within an 80-km radius of the jobsite.

After notification has been received, the Engineer will randomly select the 4 sample splices to be removed from the lot and place tamper-proof markings or seals on them. The Contractor or QCM shall select the adjacent control bar for each sample splice bar, and the Engineer will place tamper-proof markings or seals on them. These ultimate production sample splices and control bars shall be removed by the Contractor, and tested by an independent qualified testing laboratory, in the presence of either the Engineer or the Engineer's authorized representative.

The Engineer or the Engineer's authorized representative will be at the independent qualified testing laboratory within a maximum of 5 working days after receiving written notification that the samples are at the laboratory and ready for testing. Should the Engineer or the Engineer's authorized representative fail to be at the laboratory within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of this action, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

A sample splice or control bar from any set will be rejected if any tamper-proof marking or seal is disturbed prior to testing.

The 4 sets from each production test shall be securely bundled together and identified with a completed sample identification card prior to shipment to the independent laboratory. The card will be furnished by the Engineer. Bundles of samples containing fewer than 4 sets of splices shall not be tested.

A Production Test Report for all testing performed on each lot shall be prepared by the independent testing laboratory performing the testing and submitted to the QCM for review and approval. The report shall be signed by an engineer who represents the laboratory and is registered as a Civil Engineer in the State of California. The report shall include, as a minimum, the following information for each set: contract number, bridge number, lot number and location, bar size, type of splice, length of mechanical splice, physical condition of test sample splice and control bar, any notable defects, limits of affected zone, total measured slip, location of visible necking area, ultimate strength of each splice, ultimate strength and 95 percent of this ultimate strength for each control bar, and a comparison between 95 percent of the ultimate strength of each control bar and the ultimate strength of its associated splice.

The QCM must review, approve, and forward each Production Test Report to the Engineer for review before any splices represented by the report are encased in concrete. The Engineer shall have 3 working days to review each Production Test Report and respond in writing after a complete report has been received. Should the Contractor elect to encase any splices prior to receiving notification from the Engineer, it is expressly understood that the Contractor will not be relieved of the Contractor's responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Any material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase any splices pending notification by the Engineer, and should the Engineer fail to complete the review and provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in notification, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Prior to performing any tensile tests on production test sample splices, one of the 4 samples shall be tested for, and shall conform to, the provisions for total slip. Should this sample not meet these requirements, one retest, in which the 3 remaining samples are tested for total slip, will be allowed. Should any of the 3 remaining samples not conform to these requirements, all splices in the lot represented by this production test will be rejected.

If 3 or more sample splices from any production test conform to the provisions in "Ultimate Butt Splice Test Criteria" specified herein, all splices in the lot represented by this production test will be considered acceptable.

Should only 2 sample splices from any production test conform to the provisions in "Ultimate Butt Splice Test Criteria" specified herein, one additional production test shall be performed on the same lot of splices. Should any of the 4 sample splices from this additional test fail to conform to these provisions, all splices in the lot represented by these production tests will be rejected.

If only one sample splice from any production test conforms to the provisions in "Ultimate Butt Splice Test Criteria" specified herein, all splices in the lot represented by this production test will be rejected.

If a production test for any lot fails, the Contractor will be required to repair or replace all reinforcing bars from which sample splices were removed, complete in place, before the Engineer selects any additional splices from this lot for further testing.

Whenever any lot of ultimate butt splices is rejected, additional ultimate butt splices shall not be used in the work until 1) the QCM performs a complete review of the Contractor's quality control process for these splices, 2) a written report is submitted to the Engineer describing the cause of failure for the splices in this lot and provisions for correcting these failures in future lots, and 3) the Engineer has provided the Contractor with written notification that the report is acceptable. The Engineer shall have 3 working days after receipt of the report to provide notification to the Contractor. Should the Engineer not provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of this action, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Production tests will not be required on any repaired splice from a lot, regardless of the type of prequalified ultimate mechanical butt splice used to make the repair.

Should an additional production test be required, the Engineer may select any repaired splice for use in the additional production test.

### **QUALITY ASSURANCE TEST REQUIREMENTS FOR ULTIMATE BUTT SPLICES**

For the first production test performed, and for at least one, randomly selected by the Engineer, of every 5 additional production tests, or portion thereof, performed thereafter, the Contractor shall concurrently prepare 4 additional ultimate job control sample splices along with associated control bars. These ultimate job control samples shall be prepared in the same manner as specified herein for ultimate prejob sample splices and control bars.

Each time 4 additional ultimate job control sample splices are prepared, 2 of these job control sample splice and associated control bar sets and 2 of the production sample splice and associated control bar sets, together, shall conform to the requirements for ultimate production sample splices in "Production Test Requirements for Ultimate Butt Splices" specified herein.

The 2 remaining job control sample splice and associated control bar sets, along with the 2 remaining production sample splice and associated control bar sets shall be shipped, unless otherwise directed in writing by the Engineer, to the Transportation Laboratory for quality assurance testing. The 4 sets shall be securely bundled together and identified by location and contract number with weatherproof markings prior to shipment. Bundles containing fewer than 4 sets will not be tested.

Quality assurance testing will be performed in conformance with the requirements for ultimate production sample splices in "Production Test Requirements for Ultimate Butt Splices" specified herein.

Test results for each bundle of 4 sets will be reported in writing to the Contractor within 3 working days after receipt of the bundle by Transportation Laboratory. In the event that more than one bundle is received on the same day, 2 additional working days shall be allowed for providing test results for each additional bundle received. A test report will be made for each bundle received. Should the Contractor elect to encase any splices prior to receiving notification from the Engineer, it is expressly understood that the Contractor will not be relieved of the Contractor's responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Any material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase any splices pending notification by the Engineer, and should the Engineer fail to complete the review and provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in notification, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

### **MEASUREMENT AND PAYMENT**

Measurement and payment for reinforcement in structures shall conform to the provisions in Section 52-1.10, "Measurement," and Section 52-1.11, "Payment," of the Standard Specifications and these special provisions.

Full compensation for conforming to the provisions of "Ultimate Butt Splices," of these special provisions shall be considered as included in the contract prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

**ENGINEER'S ESTIMATE**  
**05-0E9504**

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21 (S)	203001	EROSION CONTROL (BLANKET)	M2	10 000		
22 (S)	203014	FIBER (EROSION CONTROL)	KG	1600		
23 (S)	203021	FIBER ROLLS	M	1200		
24 (S)	203024	COMPOST (EROSION CONTROL)	KG	3200		
25 (S)	203040	SEED (EROSION CONTROL)	KG	40		
26 (S)	203056	COMMERCIAL FERTILIZER (EROSION CONTROL)	KG	240		
27 (S)	203061	STABILIZING EMULSION (EROSION CONTROL)	KG	150		
28 (S)	204013	PLANT (GROUP M)	EA	1000		
29 (S)	020143	TRANSPLANT PLANT	EA	50		
30 (S)	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM	LUMP SUM	
31 (S)	020144	TEMPORARY IRRIGATION SYSTEM	LS	LUMP SUM	LUMP SUM	
32	390103	ASPHALT CONCRETE (TYPE B)	TONN	840		
33	394044	PLACE ASPHALT CONCRETE DIKE (TYPE C)	M	55		
34	397001	ASPHALTIC EMULSION (PAINT BINDER)	TONN	2		
35 (S)	490675	900 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	760		
36 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	M3	1260		
37 (F)	510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	M3	58		
38 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	1.9		
39 (S)	519144	JOINT SEAL (MR 50 MM)	M	22		
40 (S-F)	520102	BAR REINFORCING STEEL (BRIDGE)	KG	329 590		