

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.
Help save water!*

June 19, 2015

05-SCr-129-9.5/10.0

05-OT5404

Project ID 0500000857

ACHSSTPG-P129(016)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN SANTA CRUZ COUNTY NEAR CHITTENDEN FROM 0.4 MILE WEST TO 0.1 MILE EAST OF CHITTENDEN UNDERPASS.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, July 1, 2015.

This addendum is being issued to revise the project plans, the *Notice to Bidders and Special Provisions*, the *Bid* book, and the Federal Minimum Wages with Modification Number 16 dated 06/19/15.

Project plan sheets 57 and 129 are replaced and attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 83, "Railings and Barriers," replace 83-2.02D(1) as follows:

Replace the paragraph in the RSS for section 83-2.02D(1) with:

For concrete barrier transition,

1. Remove portions of the existing concrete barrier where shown under section 15-3
2. Roughen the contact surface of the existing concrete barrier
3. Drill and bond dowels into the existing concrete barrier under section 51-1
4. Install pipes to extend the existing weep holes through the concrete barrier transition.
5. Where shown, use 1/4 inch expansion joint filler under section 51-2.01B.
6. Install steel plates with the hardware and anchorage shown. Steel, hardware, and anchorage must comply with section 55 and be galvanized under section 75-1.05. Steel plate must be grade 50.

Addendum No. 1
Page 2
June 19, 2015

05-SCr-129-9.5/10.0
05-0T5404
Project ID 0500000857
ACHSSTPG-P129(016)E

In the *Bid* book, in the "Bid Item List," Items 20, 76 and 102 are replaced.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file, attachments and the modified wage rates are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/05/05-0T5404

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



SHARRI BENDER EHLERT
District Director
District 6 Central Region

Attachments

BID ITEM LIST**05-0T5404**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
2	080050	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM	LUMP SUM	
3	090100	TIME-RELATED OVERHEAD (WDAY)	WDAY	175		
4	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
5	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
6	120120	TYPE III BARRICADE	EA	13		
7	120149	TEMPORARY PAVEMENT MARKING (PAINT)	SQFT	36		
8	120159	TEMPORARY TRAFFIC STRIPE (PAINT)	LF	8,660		
9	120165	CHANNELIZER (SURFACE MOUNTED)	EA	37		
10	128601	TEMPORARY SIGNAL SYSTEM	LS	LUMP SUM	LUMP SUM	
11	128652	PORTABLE CHANGEABLE MESSAGE SIGN (LS)	LS	LUMP SUM	LUMP SUM	
12	129000	TEMPORARY RAILING (TYPE K)	LF	3,900		
13	129100	TEMPORARY CRASH CUSHION MODULE	EA	44		
14	130100	JOB SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
15	130300	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM	LUMP SUM	
16	130310	RAIN EVENT ACTION PLAN	EA	15	500.00	7,500.00
17	130320	STORM WATER SAMPLING AND ANALYSIS DAY	EA	15		
18	130330	STORM WATER ANNUAL REPORT	EA	1	2,000.00	2,000.00
19	130505	MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL)	EA	6		
20	130530	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	SQYD	35,300		

BID ITEM LIST

05-0T5404

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	029100	COMPOST BERM	LF	4,010		
62	210600	COMPOST	SQFT	16,400		
63	029101	COMPOST (WITH SEED)	SQFT	212,000		
64	210630	INCORPORATE MATERIALS	SQFT	16,400		
65	260203	CLASS 2 AGGREGATE BASE (CY)	CY	4,600		
66	390011	PREPAVING INERTIAL PROFILER	LS	LUMP SUM	LUMP SUM	
67	390020	PREPAVING GRINDING DAY	EA	3		
68	390132	HOT MIX ASPHALT (TYPE A)	TON	4,900		
69	029102	CENTERLINE RUMBLE STRIP (HMA, GROUND-IN INDENTATIONS)	STA	22		
70	394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	LF	1,560		
71	394074	PLACE HOT MIX ASPHALT DIKE (TYPE C)	LF	170		
72	394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	LF	1,000		
73	394077	PLACE HOT MIX ASPHALT DIKE (TYPE F)	LF	190		
74	394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	650		
75	397005	TACK COAT	TON	4		
76 (F)	510072	STRUCTURAL CONCRETE, BARRIER SLAB	CY	38		
77 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	CY	30		
78	566011	ROADSIDE SIGN - ONE POST	EA	4		
79	029103	FURNISH SINGLE SHEET ALUMINIUM SIGN (0.080-UNFRAMED) FOR RETROREFLECTIVE SHEETING (TYPE XI)	SQFT	44		
80	029104	RETROREFLECTIVE SHEETING (TYPE XI)	SQFT	44		

BID ITEM LIST**05-0T5404**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
101	832070	VEGETATION CONTROL (MINOR CONCRETE)	SQYD	180		
102 (F)	044906	CONCRETE BARRIER (TRANSITION)	LF	226		
103	839543	TRANSITION RAILING (TYPE WB-31)	EA	4		
104	839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	4		
105	029105	ALTERNATIVE CRASH CUSHION SYSTEM	EA	2		
106	840504	4" THERMOPLASTIC TRAFFIC STRIPE	LF	9,040		
107	840523	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	LF	90		
108	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	36		
109	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	740		
110	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID:**\$**
