

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER
1727 30th Street MS-43
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
www.dot.ca.gov/hq/esc/oe



*Serious Drought.
Help save water!*

April 15, 2016

07-LA,Ora-5-0.0/1.5, 44.3/44.4
07-2159U4
Project ID 0715000160
ACNHPI-005-2(981)N
DEMO06-6207(062)N

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN LOS ANGELES AND ORANGE COUNTIES IN BUENA PARK, LA MIRADA, CERRITOS AND SANTA FE SPRINGS FROM ARTESIA BOULEVARD UNDERCROSSING TO NORTH FORK COYOTE CREEK to revise the project plans, the *Notice to Bidders and Special Provisions*, the *Bid book*, and *Information Handout*.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, April 27, 2016.

Project plan sheets 16, 190, 198, 200, 201, 204, 205, 206, 218, 251, 252, 264, 265, 306, 307, 308, 309, 315, 318, 319, 320, 321, 328, 329, 330, 332, 333, 399, 407, 408, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 561, 562, 563, 565, 585, 586, 1028, 1068, 1072, 1106, 1259, 1308, and 1460 are replaced and attached for substitution for the like-numbered sheets.

In the *Notice to Bidders*, the twelfth and thirteenth paragraphs are replaced as follows:

"Complete the work, excluding plant establishment work, within 1080 working days."

"Complete the work, including plant establishment work, within 1330 working days."

In the *Special Notices*, attached special notice is added as attached.

Addendum No. 3
Page 2
April 15, 2016

07-LA,Ora-5-0.0/1.5, 44.3/44.4
07-2159U4
Project ID 0715000160
ACNHPI-005-2(981)N
DEMO06-6207(062)N

In the Special Provisions, Section 2-1.09 is added as attached.

In the Special Provisions, Section 5-1.36D, the table titled, "Utility Relocation and Contractor-Arranged Time for the Relocation," is replaced as attached.

In the Special Provisions, Sections 7-1.02K(1), and 7-1.02K(3) are added as attached.

The *Information Handout* "Site Investigation Reports" for parcels and local street area are available in the same location as the Information Handout, as described in Section 2-1.06B.

In the Supplemental Project Information, additional project information for XML, KCM and DGN are made available in the same location as the as-built drawings, as described in Section 2-1.06B.

In the *Bid* book, in the "Bid Item List," Items 3, 62, 112, 113, 160, 174, 183, 209, and 242 are replaced.

In the *Bid* book, in the "Bid Item List," Items 336, 337, 338, and 339 are added.

In the *Bid* book, in the "Bid Item List," Items 215, 216, 217 and 335 are deleted.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/07/07-2159U4

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,


for CARRIE BOWEN
District Director

Attachments

SPECIAL NOTICES

- Because Labor Code § 1720.9 will affect the cost of hauling and delivering ready-mixed concrete and because Labor Code § 1720.9 applies to public works contracts that are awarded on or after July 1, 2016, the Department has included specifications regarding the new code provisions, including the method the Department will use to manage the cost impacts of the new provisions. See sections 2-1.09, 7-1.02K(1), and 7-1.02K(3) for the specifications.

Add to the end of section 2-1.09:

For bid items requiring delivery of ready-mix concrete, base your bid on the award period specified in section 3-1.04. If the Department extends the award period and the cost of any bid item increases as a result of the new prevailing wage provisions in Labor Code § 1720.9, Department makes a payment adjustment under section 9-1.04 except markups are not added.

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SWS 12" PVC, CL-350 pipe To be relocated	Suburban Water System 1325 N Grand Ave Suite 100 Covina, CA 91724-4044	City of La Mirada, North side of freeway on Firestone Blvd from Knott Ave STA 47+00 to 71+17 (U-15, U-16 and U-17)	30 days of Notice to Owner. 61 Working days of construction
SWS 12" PVC, CL-350 pipe To be relocated	Suburban Water System 1325 N Grand Ave Suite 100 Covina, CA 91724-4044	North side of freeway along Valley View Ave. from STA "VAL" 114+00 to 104+00 (U-23)	30 days of Notice to Owner. 25 Working days of construction
SWS 12" PVC, CL-350 pipe To be relocated	Suburban Water System 1325 N Grand Ave Suite 100 Covina, CA 91724-4044	City of La Mirada South side of freeway on Valley View Ave, from STA "VAL" 84+85 to 91+18 (U-22)	30 days of Notice to Owner. 14 Working days of construction
SWS 12" PVC, CL-350 pipe To be relocated	Suburban Water System 1325 N Grand Ave Suite 100 Covina, CA 91724-4044	City of La Mirada Southeast of Valley View Ave and rail road from STA "VAL" 91+18 to Firestone Blvd STA "SFIR1" 57+14.15 (U-22 & U-20)	30 days of Notice to Owner. 11 Working days of construction
SWS 12" PVC, CL-350 pipe To be relocated	Suburban Water System 1325 N Grand Ave Suite 100 Covina, CA 91724-4044	City of La Mirada South side of freeway on Firestone Blvd from STA 57+14.15 to 19+30 (U-17, U-18, U-19, & U-20)	30 days of Notice to Owner. 85 Working days of construction
SWS 16" PVC CL-350 pipe and 20" Steel Casing To be relocated	Suburban Water System 1325 N Grand Ave Suite 100 Covina, CA 91724-4044	City of La Mirada Freeway crossing extend the 20" Steel casing to New Firestone Blvd and replace existing 16" steel pipe to 16" PVC CL-350 to STA "SFIR1" 55+22 (U-20)	30 days of Notice to Owner. 10 Working days of construction

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SWS 12" PVC CL-350 pipe and 16" Steel Casing To be relocated	Suburban Water System 1325 N Grand Ave Suite 100 Covina, CA 91724-4044	City of La Mirada Freeway crossing extend the 16" Steel casing to New Firestone Blvd , and replace existing 12" steel pipe to 12" PVC CL-350 to STA "SFIR1" 30+42 (U-17)	30 days of Notice to Owner. 11 Working days of construction
City of Cerritos 12" Ductile Iron Pipe (DIP) CL-350 CC To be relocated	City of Cerritos 18125 Bloomfield Ave. P.O.Box 3130 Cerritos, CA 90703	City of Cerritos West Side of Valley View (U-22, U-22)	30 days of Notice to Owner. 30 Working days of construction
SCE pole #, PP2275985E, PP4679784E, PP2216044E, PP2276168E, PP1541694E, PP2276169E, PP2275890E, PP4679785E, PP2276170E, PP4578995E, PP2275554E, PP2062305E, PP1040322H TP1949714E, TP1402784E	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd to be relocated (U-14)	30 days of Notice to Owner. 40 Working days of construction
SCE 66KV 6-5"conduit from V-TM4434 to New Transmission Pole is proposed	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	Knott Ave and North Firestone Blvd (U-14)	
SCE 66KV 6-5"conduit crossing Freeway at Knott Ave, Caltrans provide utility opening at RW-No-2 to protect in place	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	Knott Ave and North Firestone Blvd (U-14)	
SCE New Transmission Pole is proposed at island of South Firestone Blvd off ramp to Artesia Blvd .	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	Knott Ave and Artesia Blvd at South Firestone Blvd exit (U-14)	

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SCE 66KV 6-5" conduit from New Transmission Pole to existing 66KV, 6-5" conduit is proposed	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	Knott Ave and Artesia Blvd at South Firestone Blvd exit (U-14)	30 days of Notice to Owner. 40 Working days of construction
SCE 12KV, 4-5" & 1-5" conduit 172', 5' North of "NFIR1", SCE M5642345 (6'X12"X7)' MH, SCE 12KV 2-5" & 6-5", 118' Conduit, 6' W of "KNO", to V5636366 Vault SCE 12KV 1-5", 27' conduit from V5636366 Vault at Sta 14+20 "KNO", SCE 12KV 1-5" & 4-5", 57' conduit, 5' W of "KNO" From V5636366 Vault SCE 12KV 1-5" & 4-5", 91' conduit at Sta 14+91 "KNO" and SCE 12KV 2-5", 194' conduit from M5642345 Manhole to PP2275554E Proposed	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	Knott Ave and North Firestone Blvd (U-14)	30 days of Notice to Owner. 10 Working days of construction

CONTRACT NO. 07-2159U4
REPLACED PER ADDENDUM NO. 3 DATED APRIL 15, 2016

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
Paramount Petroleum Oil, 6" in 12" casing and 12" in 20" casing crossing I-5 at Knott Ave, contractor to provide utility opening for RW No 2 per structural design	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	Knott Ave and North Firestone Blvd (U-14).	5 days of Notice to Owner prior to commencement of construction.
SCE pole #, PP4422376E, PP1994089E, PP2062308E, PP2062309E, PP625515H PP1353090E, PP4453080E, PP625517H PP4805003E, PP2218789, PP4401918E, PP4401922E, PP1994089E, PP1353090E, PP4221487E	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd ,(U-15)	30 days of Notice to Owner. 20 Working days of construction
SCE 12KV, 1-4", 201' conduit from Sta 6+54 to Sta 8+15 of I-5 Centerline to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd (U-15)	
SCE 12KV, 153' 1-4" conduit from PP 1353090E along Osmond Way to P5179057 Slab Box to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd (U-15)	

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SCE 12KV, 400', 4-4" from P5179057 Slab Box to HO57A Concrete to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd (U-15)	30 days of Notice to Owner. 20 Working days of construction
SCE pole #, PP4221487E, PP2062559E, PP2062560E, PP4248402E, PP5127295E, PP4085091E, PP1075734E, PP1004984H PP4437137, PP4437138E, PP4437139, PP4437140E, PP4437135E, PP4437133E, PP4437131, PP4437129E, PP4437127E, PP4437125E	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd (U-16),	30 days of Notice to Owner. 120 Working days of construction
SCE 12KV, 1-5" conduit 134' from PP 4221487E to V5420573 Vault to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd (U-16)	
SCE 12KV, 1-4" conduit 164' from V5420573 Vault to P5127295 Slab Box to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd (U-16)	
P5127295 Slab Box 12KV to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd (U-16)	
SCE 12KV, 1-3", 225' conduit from V5420573 Vault to SCE HH to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd (U-16)	

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SCE 12KV, 2-5", 1-4", 516' conduit from V5420573 to V5420569 Vault (U-16) to be removed	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd (U-16)	30 days of Notice to Owner. 120 Working days of construction
SCE 12KV, 2-5" conduit 166' from PP 4221487E to V5628178 Vault (U-16) Proposed	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd U-16)	
SCE 12KV, 4-5", 569' conduit from V5628178 Vault to V5640055 Vault (U-16) Proposed	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North & South side of freeway on Firestone Blvd (U-16)	
SCE 12KV, 2-4", 4-5", 37' conduit from V5640055 Vault to V5420569 Vault (U-16) Proposed	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North & South side of freeway on Firestone Blvd (U-16)	
SCE 12KV, 1-5", 658' conduit from V5420569 Vault to V5502479 Vault to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North & South side of freeway on Firestone Blvd (U-16)	
SCE 12KV, 1-5" conduit, 69' from V5420570 Vault to X5420571 Vault (U-16) to remain	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U-16)	

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SCE 12KV, 4-5" conduit, 342' from V5420570 Vault to V5420569 Vault crossing Freeway (U-16) to remain	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	Crossing I-5 at Coyote Creek (U-16)	30 days of Notice to Owner. 120 Working days of construction
SCE #, PP4085091E, 2062559, 4085091E, PP1004983H, PP1004984H, PP4085091E, PP1075731E, PP2062560E, PP833010E, PP823983H, PP2314775E, PP398196E, PP1398195E, PP1752354E, PP4007118E, PP1352609E, PP4745464E, PP1021312H, PP833007E, PP2275537E, PP4805006E, PP1398196E, PP2062561E, PP4745464E, PP4401925E, PP4445620E, PP1752354E	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U-17)	30 days of Notice to Owner. 30 Working days of construction
SCE 12KV, 1-4" conduit 57' from PP 833010E to X5628177 Pull Box (U-17) to be removed by others	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U-17)	
PP4437135E, PP4437133E, PP4437131E, PP4437129E, PP44237127, PP447125E	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd (U-17)	

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SCE 12KV V5502477, Vault at Sta 76+57 North Firestone centerline (U-17) to remain	SCE 1444 E McFadden Ave. Santa Ana, CA.92705	South side of freeway on Firestone Blvd (U- 17)	30 days of Notice to Owner. 30 Working days of construction
SCE pole #, PP4053569E, PP833006E, PP2275551E, PP231477E, PP833005E, PP231777E, PP4284749E, PP1263087E, PP231776E, PP4126154E, PP4126159, PP1021332H	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U- 18)	30 days of Notice to Owner 30 Working days of construction
P5125974 Slab Box 12KV (U-18) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U- 18)	
SCE 12KV, 1-4" conduit 133' from PP 833006E to P5125974 Slab Box (U-18) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U- 18)	
SCE pole #, PP1263087E, PP833002E, PP454866E, PP1227240E, PP1752766E, PP2317795E, PP4745463, PP1153942E, PP5399425, PP4023978E, PP1752400E, PP4401927E		South side of freeway on Firestone Blvd (U- 19)	30 days of Notice to Owner 30 Working days of construction
SCE X5399424 Pull Box 12KV (U-20) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U- 20)	

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SCE 12KV 4-4" conduit 50' from X5399424 Pull Box to Slab Box (U-20) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U-20)	30 days of Notice to Owner 30 Working days of construction
SCE P5399423 Slab Box 12KV (U-20) to be removed by others	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U-20)	
SCE 12KV 1-4" conduit 726' from P5399423 Slab Box to P539945 Slab Box (U-19, U-20) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U-19, U-20)	
SCE pole #, PP1466481E, PP4556394E, PP1153938E, PP4468903E, PP1994206E, PP1300937E, PP1300936, PP1300935E, PP1300934E, PP1300933E, PP4401929E, PP4468903E, PP4402697, PP4556394E, PP4832058E, PP4832060E, PP4528092E, PP4528092E, PP4832059E	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U-20)	30 days of Notice to Owner 30 Working days of construction
SCE 12KV, 1-4" conduit 162' from PP 1300936E to P5127281 Slab Box (U-20) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U-20)	
SCE P5127281 Slab Box & P5127283 12KV (U-20) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U-20)	

CONTRACT NO. 07-2159U4
REPLACED PER ADDENDUM NO. 3 DATED APRIL 15, 2016

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SCE 12KV, 1-4" conduit 204' from P5127281 Slab Box to P5127283 Slab Box (U-20) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Firestone Blvd (U-20)	30 days of Notice to Owner 30 Working days of construction
SCE pole #, PP1752346E, PP1752347E PP4814903E (U-21)	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Freeway Drive (U-21)	10 Working days of construction
SCE 12KV, 1-4" conduit 487' from PP 1752346E to P5058512 Slab Box (U-21) to be removed by others	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Freeway Drive (U-21))	
SCE P5058512 Slab Box 12KV (U-21) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Freeway Drive (U-21))	
SCE P5127284, P5127285, P5127286, & P5127287 utility boxes 12KV (U-21) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Freeway Drive (U-21)	
SCE 12KV, 1-4" conduit 1074' from P5127283 Slab Box to P5127287 Slab Box (U-21) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway on Firestone Blvd (U-21)	

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SCE pole #, PP1915769E, PP1915770E, PP4832061E, PP2167939E, PP1915771E, PP1915772E, PP1915775E, PP1915774E, PP1915773E, PP2276303E, PP4658051E, PP1852689E, PP2276301E, PP1982887E (U-22)	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Valley View Ave.(U-22)	30 days of Notice to Owner 20 Working days of construction
SCE 12KV, 1-4" conduit 150' from PP 1915775E to P5203777 Slab Box (U-22) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Valley View Ave.(U-22)	

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SCE P5203777 Slab Box & X5399420 Pull Box 12KV (U-22) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Valley View Ave.(U-22)	30 days of Notice to Owner 20 Working days of construction
SCE 12KV, 1-4" conduit 22' from X5399420 Pull Box to New X5636097 Pull Box (U-22) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Valley View Ave.(U-22)	
SCE 12KV, 1-4" conduit 116' from P5165046 Slab Box to Split" Y" at Sta 86+65 "VAL" (U-22) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Valley View Ave.(U-22)	
SCE 12 KV, 1-4" conduit, 4'from PP 1915770E to New X5636388 Pull Box at Sta 83+23 "VAL" (U-22) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Valley View Ave.(U-22)	

CONTRACT NO. 07-2159U4
REPLACED PER ADDENDUM NO. 3 DATED APRIL 15, 2016

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SCE 12 KV, 1-4" conduit, 8' from PP 1915769E to New X5636095 Pull Box at Sta 81+35 "VAL" (U-22) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	South side of freeway on Valley View Ave.(U-22)	30 days of Notice to Owner 20 Working days of construction
SCE pole #, PP1300932E, PP1300931E, PP1300929E, PP4456681E, PP1300927E, PP1300926E, PP1320907E, PP1113691E, PP1113690E, PP1113689E, PP1655054E, PP4832056E, PP4832055E, PP4456681E, PP4274029E, PP4274028E, PP4274019E, PP4274018E, PP4832054E, PP4832053E, PP4832052E, 4832051E	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway along Valley View and Firestone to Valley View Avenue (U-23)	30 days of Notice to Owner 20 Working days of construction
SCE 12KV, 1-4" conduit 170' from PP 1300929E to P5411759 Slab Box (U-23) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway along Valley View Ave. and Firestone Blvd. to Valley View Avenue (U-23)	
SCE 12KV, 1-4" conduit 136' from PP 1300931E to P5411759 Slab Box (U-23) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway along Valley View and Firestone Blvd. to Valley View Avenue (U-23)	

CONTRACT NO. 07-2159U4
REPLACED PER ADDENDUM NO. 3 DATED APRIL 15, 2016

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SCE 12KV, 1-5" conduit 50' from PP 1113691E to M5194771 Manhole (U-23) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway along Valley View Ave. and Firestone Blvd. to Valley View Avenue (U-23)	30 days of Notice to Owner 20 Working days of construction
SCE 12KV, 1-4" conduit 502' from M5194771 Manhole to V5194770 Vault (U-23) to be abandoned	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	North side of freeway along Valley View Ave. and Firestone Blvd to Valley View Avenue (U-23)	
City of Buena Park , Street Lights	SCE 1444 E McFadden Ave. Santa Ana, CA 92705	City of Buena Park, on Firestone Blvd, from Artesia to Knott Ave	30 day of Notice to Owner 30 Working days of construction
City of La Mirada, Street Lights, (LA County Department of Public Work, Street lighting and Traffic Signals)	City of La Mirada 15515 Phoebe Ave. LA Mirada, CA 90638	North & South side of freeway on Firestone Blvd	30 day of Notice to Owner 60 Working days of construction
City of Cerritos, Street Lights	City of Cerritos 18125 Bloomfield Ave. P.O.Box 3130 Cerritos, CA 90703	City of Cerritos West Side of Valley View	30 day of Notice to Owner 30 Working days of construction
SCG, 4" P-M, 6" P-M, 2" P-M to be relocated	SCG 1919 S State College Blvd. Anaheim, CA 92806	North side of freeway along East of Valley View STA "VAL" 109+45 to "NFIR1" 65+33, A-230' of 6" P-M, A-395' of 4" P-M, I-641' of 6" P-M, West of Valley View I-159' of 2" P-M (U-10, U-23)	30 day of Notice to Owner 35 Working days of construction

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
SCG, 2" M, 3" M, 4" M, 6" M to be relocated	SCG 1919 S State College Blvd. Anaheim, CA 92806	South side of freeway along Firestone Blvd I-3210' 3"P-M, A-970' 6"M, A1060', A-1630' 3"M, A-169' 2" PEM (U-4 to U-7, U-17 to U-20), Freeway Crossing at STA 51+59 A-80' 6"M	30 day of Notice to Owner 45 Working days of construction
SCG, 2" M, 3" M, 4" M to be relocated	SCG 1919 S State College Blvd. Anaheim, CA 92806	South side of freeway Rail Road crossing to Valley View and along Valley View I-1168' 4" P-M A-653' 4"M, Along Arbor Pl, I-434' 2" PEM A-186' 3"M, A-207' 2" M (U-7, U-9, U-20 to U22)	30 day of Notice to Owner 20 Working days of construction
SCG, 3" P-M to be relocated	SCG 1919 S State College Blvd. Anaheim, CA 92806	South side of freeway along Firestone Blvd I-1820' of 3" P-M (U-7,U-8)	30 day of Notice to Owner 30 Working days of construction

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
AT&T California, Install - 470' 6-4" DU, 11' 2-4" DU, 304' 4-4" DU, 25' 8-4" DU, 21' 8-4" DU, 11' 4-4" DU, 16' 4-4" DU, 137' 4-4" DU, 3'X5'X4' pullbox, 12'x6'x7' MH, Abandon - 281' 1-4" DU, 95' 2-4" DU, 7' 1-4" DU	AT&T 600 E Green Street Pasadena, CA 91101	North side of freeway on Firestone Blvd, and West Corner of Knott Ave (U-1, U-14)	30 day of Notice to Owner 60 Working days of construction
ATT&T California, Install - 26' 8-4" DU, 33' 4-4" DU, 66' 4-4" DU, 46' 4-4" DU, 165' 5-4" DU, 279' 6- 4" DU, 30' 11-4" DU, 46' 15-4" DU, 162' 3- 4" DU, 21' 1-4" DU, 20' 4-4" DU, 32' 4-4" DU, 72' 9-4" DU, 160' 8-4" DU, 3'X5'X4' pullbox, 3- 12'x6'x7' MH, Abandon - 115' 7-4" du, 115' 10-4"DU, 109' 8-4" DU, 19' 1- 4" DU, 143' 7-4" DU, 98' 9-4" DU, 42' 1-4" DU, 22' 2-4" DU, 34' 6-4" DU	AT&T 600 E Green Street Pasadena, CA 91101	North side of freeway on Firestone Blvd, and connections on South side of freeway (U-3, U-16)	30 day of Notice to Owner 60 working days of Construction
ATT&T California, Install-290' 3-4" DU, 268' 1-4" DU, 94' 4- 4" DU, 25' 3-4" DU, 82' 7-4" DU, 43' 7-4" DU, 11' 4-4" DU, 17' 3-4" DU, 12'X6'X7' MH, Abandon - 17' 1-4" DU, 19' 1-4" DU, 15' 1-4" DU, 181' 2-4" DU, 370' 1- 4" DU	AT&T 600 E Green Street Pasadena, CA 91101	South side of freeway on Firestone Blvd (U- 6, U-7, U-19, U-20)	30 day of Notice to Owner 60 working days of Construction

Utility Relocation and Contractor-Arranged Time for the Relocation

Utility	Utility address	Location	Days
Verizon California, 1164' 4-4" Sch-40 PVC, Two Manholes 4'-6"X8'-6"X6'-6" and 5'X10'X6'-6" Relocate	12905 E. Los Nietos Rd. Santa Fe Springs, CA 90670	South side of I-5 Freeway, along S Firestone Blvd (U-7,U-8, U-20, U-21)	30 days of Notice to Owner 15 working days on Construction
Verizon California, Crossing RR 120' 12" Steel Casing; 635' 4-4" Sch-40 PVC; 5' 8-4" Sch-40 PVC; Place MH 5'X10'X6'6";	12905 E. Los Nietos Rd. Santa Fe Springs, CA 90670	South side of I-5 Freeway, Crossing RR and to Valley View Blvd (U-7,U-9, U-20, U-22)	15 working days on Construction
Verizon California 625' 4-4" Sch-40 PVC, 96' 2-4" Sch-40 PVC; MH 5'x10.5'x6.5', 3'x5'x4'; Relocate	12905 E. Los Nietos Rd. Santa Fe Springs, CA 90670	South side of I-5 Freeway, along Valley View Ave	30 day of Notice to Owner 10 working days on Construction
Verizon California; 109' 1-4" Sch-80 PVC, 684' 2-4" Sch-40 PVC;3-3'X5"X4 PB' 255' 2-4" Sch-40;2'x3' HH Relocate	12905 E. Los Nietos Rd. Santa Fe Springs, CA 90670	North side of I-5 Freeway along East side of Valley View Ave	30 day of Notice to Owner 10 working days on Construction
Time Warner Cable Underground	Time Warner Cable 14338 Lakewood Blvd. Bellflower, CA 90706	North side of I-5 Freeway along North Firestone Blvd STA "NFIR1" 44+80 to STA "NFIR1" 69+77 (U-1 to U-4, U-14 to U-17)	30 day of Notice to Owner 10 working days on Construction
Time Warner Cable underground	Time Warner Cable 14338 Lakewood Blvd. Bellflower, CA 90706	North side of I-5 Freeway along Valley View Ave (U-7, U-10, U-20, U-23)	30 day of Notice to Owner 10 working days on Construction
Time Warner Cable underground	Time Warner Cable 14338 Lakewood Blvd. Bellflower, CA 90706	South side of I-5 Freeway along south Firestone Blvd (U-3 to U-6, U-16 to U-19)	30 day of Notice to Owner 10 working days on Construction
Chevron, 8" Crude Oil line, Active	2600 Homestead P. Rancho Dominguez, CA 90220	Cross the Freeway from Trojan Way to Firestone Blvd. on south side of freeway (U-3, U-16)	45 days of Notice to Owner 221 Working days of construction On stage 2 phase 1, 45 day Notice to Owner and 30 working days on construction.
Crimson, 8" Crude Oil line, Active and 6" Dry Gas line, idle	Crimson CA Pipeline, LP 2459 Redondo Ave. Long Beach, CA 90755	Cross the Freeway from Trojan Way to Firestone Blvd. on the south side of freeway (U-3, U-16)	45 days of Notice to Owner 221 Working days of construction On stage 2 phase 1, 45 day Notice to Owner and 30 working days on construction

Add to the end of the 2nd sentence of the 1st paragraph of section 7-1.02K(1):
, and hauling and delivery of ready-mixed concrete.

CONTRACT NO. 07-2159U4
REPLACED PER ADDENDUM NO. 3 DATED APRIL 15, 2016

Add between the 4th and 5th paragraphs of section 7-1.02K(3):

Submitted certified payrolls for hauling and delivering ready-mixed concrete must be accompanied by a written time record. The time record must include:

1. Truck driver's full name
2. Name and location of the batch plant
3. Time the concrete was loaded
4. Time the truck returned to the batch plant
5. Truck driver's signature certifying under penalty of perjury that the information contained in it is true and correct

**BID ITEM LIST
07-2159U4**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
2	080050	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM	LUMP SUM	
3	090100	TIME-RELATED OVERHEAD (WDAY)	WDAY	1080		
4	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
5	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
6	120120	TYPE III BARRICADE	EA	310		
7	120165	CHANNELIZER (SURFACE MOUNTED)	EA	800		
8	121161	TEMPORARY TERMINAL SECTION (TYPE K)	EA	1		
9	128605	TEMPORARY SIGNAL AND LIGHTING	LS	LUMP SUM	LUMP SUM	
10	129000	TEMPORARY RAILING (TYPE K)	LF	87,800		
11	129100	TEMPORARY CRASH CUSHION MODULE	EA	460		
12	130100	JOB SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
13	130300	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM	LUMP SUM	
14	130310	RAIN EVENT ACTION PLAN	EA	83	500.00	41,500.00
15	130320	STORM WATER SAMPLING AND ANALYSIS DAY	EA	47		
16	130330	STORM WATER ANNUAL REPORT	EA	4	2,000.00	8,000.00
17	130500	TEMPORARY EROSION CONTROL BLANKET	SQYD	61,100		
18	029576	IMPERMEABLE MEMBRANE	SQYD	6,050		
19	130505	MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL)	EA	18		
20	130510	TEMPORARY MULCH	SQYD	3,400		

BID ITEM LIST
07-2159U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	152440	ADJUST MANHOLE TO GRADE	EA	10		
62	153121	REMOVE CONCRETE (CY)	CY	930		
63	153140	REMOVE CONCRETE SIDEWALK (SQYD)	SQYD	4,910		
64	153211	REMOVE CONCRETE SIDEWALK AND DRIVEWAY	CY	370		
65	153215	REMOVE CONCRETE (CURB AND GUTTER)	LF	34,200		
66	153221	REMOVE CONCRETE BARRIER	LF	2,910		
67	153229	REMOVE CONCRETE BARRIER (TYPE K)	LF	2,200		
68	153248	REMOVE CONCRETE (MISCELLANEOUS) (SQFT)	SQFT	5,990		
69	029580	REMOVE CONCRETE MASONRY BLOCK WALL	SQFT	200		
70	156572	REMOVE RAILING	LS	LUMP SUM	LUMP SUM	
71	157551	BRIDGE REMOVAL, LOCATION A	LS	LUMP SUM	LUMP SUM	
72	157552	BRIDGE REMOVAL, LOCATION B	LS	LUMP SUM	LUMP SUM	
73	157561	BRIDGE REMOVAL (PORTION), LOCATION A	LS	LUMP SUM	LUMP SUM	
74	157562	BRIDGE REMOVAL (PORTION), LOCATION B	LS	LUMP SUM	LUMP SUM	
75	157563	BRIDGE REMOVAL (PORTION), LOCATION C	LS	LUMP SUM	LUMP SUM	
76	160102	CLEARING AND GRUBBING (LS)	LS	LUMP SUM	LUMP SUM	
77	190101	ROADWAY EXCAVATION	CY	317,000		
78	190107	ROADWAY EXCAVATION (TYPE Y-1) (AERIALY DEPOSITED LEAD)	CY	3,380		
79	190108	ROADWAY EXCAVATION (TYPE Y-2) (AERIALY DEPOSITED LEAD)	CY	3,430		
80 (F)	192001	STRUCTURE EXCAVATION	CY	2,402		

BID ITEM LIST
07-2159U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
101	204038	PLANT (GROUP U)	EA	65		
102	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM	LUMP SUM	
103	205035	WOOD MULCH	CY	250		
104	206400	CHECK AND TEST EXISTING IRRIGATION FACILITIES	LS	LUMP SUM	LUMP SUM	
105	206402	OPERATE EXISTING IRRIGATION FACILITIES	LS	LUMP SUM	LUMP SUM	
106	206560	CONTROL AND NEUTRAL CONDUCTORS	LS	LUMP SUM	LUMP SUM	
107	206562	1" REMOTE CONTROL VALVE	EA	21		
108	206564	1 1/2" REMOTE CONTROL VALVE	EA	9		
109	206565	2" REMOTE CONTROL VALVE	EA	2		
110	206749	8 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	1		
111	206757	16-18 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	2		
112 (F)	208003	1" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	20		
113 (F)	208006	2" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	40		
114	208301	IRRIGATION CONTROLLER ENCLOSURE CABINET	EA	3		
115	208423	1" BACKFLOW PREVENTER ASSEMBLY	EA	1		
116	208426	2" BACKFLOW PREVENTER ASSEMBLY	EA	2		
117	208442	FLOW SENSOR	EA	3		
118	208446	RISER SPRINKLER ASSEMBLY (GEAR DRIVEN)	EA	120		
119	208448	RISER SPRINKLER ASSEMBLY	EA	220		
120	208449	POP-UP SPRINKLER ASSEMBLY	EA	220		

BID ITEM LIST
07-2159U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
141	414242	ISOLATION JOINT SEAL (PREFORMED COMPRESSION)	LF	5,910		
142	490550	FURNISH 24" STEEL PIPE PILING	LF	93,841		
143	490555	DRIVE 24" STEEL PIPE PILE	EA	1,807		
144	490606	42" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	5,913		
145	490742	FURNISH PILING (CLASS 90) (ALTERNATIVE W)	LF	34,314		
146	490743	DRIVE PILE (CLASS 90) (ALTERNATIVE W)	EA	669		
147	490746	FURNISH PILING (CLASS 140) (ALTERNATIVE W)	LF	28,001		
148	490747	DRIVE PILE (CLASS 140) (ALTERNATIVE W)	EA	476		
149	495115	FURNISH 24" CAST-IN-STEEL SHELL CONCRETE PILING	LF	9,387		
150	495116	DRIVE 24" CAST-IN-STEEL SHELL CONCRETE PILE	EA	242		
151	498044	36" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	15		
152	498052	60" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	240		
153	500001	PRESTRESSING CAST-IN-PLACE CONCRETE	LS	LUMP SUM	LUMP SUM	
154 (F)	510050	STRUCTURAL CONCRETE	CY	509		
155 (F)	510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	CY	6,964		
156 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	CY	32,419		
157 (F)	510060	STRUCTURAL CONCRETE, RETAINING WALL	CY	8,787		
158 (F)	510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	CY	884		
159 (F)	510088	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N MODIFIED)	CY	420		
160 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	CY	753		

BID ITEM LIST
07-2159U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
161 (F)	045033	ARCHITECTURAL TREATMENT (SPLIT SLATE)	SQFT	50,108		
162 (F)	045034	ARCHITECTURAL TREATMENT (WALL 8 MOTIF)	SQFT	930		
163 (F)	045035	ARCHITECTURAL TREATMENT (SUNRAY-SPLIT SLATE)	SQFT	5,100		
164 (F)	045036	ARCHITECTURAL TREATMENT (WALL 2 MOTIF)	SQFT	10,525		
165 (F)	511064	FRACTURED RIB TEXTURE	SQFT	2,600		
166	511106	DRILL AND BOND DOWEL	LF	2,366		
167	511110	DRILL AND BOND DOWEL (CHEMICAL ADHESIVE)	EA	1,398		
168	512281	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (120'-130')	EA	14		
169	512350	FURNISH PRECAST PRESTRESSED CONCRETE SLAB	SQFT	4,703		
170	045037	FURNISH PRECAST PRESTRESSED CONCRETE SLAB (TYPE SIII MODIFIED)	SQFT	22,400		
171 (F)	512500	ERECT PRECAST PRESTRESSED CONCRETE GIRDER	EA	14		
172 (F)	512510	ERECT PRECAST PRESTRESSED CONCRETE DECK UNIT	EA	198		
173 (F)	513501	CONCRETE CLOSURE WALL	SQFT	8,033		
174	518051	PTFE SPHERICAL BEARING	EA	86		
175	519081	JOINT SEAL (MR 1/2")	LF	751		
176	519088	JOINT SEAL (MR 1")	LF	178		
177	519091	JOINT SEAL (MR 1 1/2")	LF	135		
178	519093	JOINT SEAL ASSEMBLY (MR 3")	LF	237		
179	519094	JOINT SEAL ASSEMBLY (MR 3 1/2")	LF	135		
180	519099	JOINT SEAL ASSEMBLY (MR 6")	LF	122		

BID ITEM LIST
07-2159U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
181	519100	JOINT SEAL (MR 2")	LF	143		
182	519102	JOINT SEAL (TYPE AL)	LF	73		
183	519109	JOINT SEAL ASSEMBLY (MR 6 1/2")	LF	131		
184	519118	JOINT SEAL ASSEMBLY (MR 9")	LF	135		
185 (F)	520101	BAR REINFORCING STEEL	LB	120,587		
186 (F)	520102	BAR REINFORCING STEEL (BRIDGE)	LB	11,433,950		
187 (F)	520103	BAR REINFORCING STEEL (RETAINING WALL)	LB	1,618,868		
188 (F)	520110	BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	LB	45,920		
189 (F)	520115	BAR REINFORCING STEEL (GALVANIZED)	LB	6,837		
190 (F)	520120	HEADED BAR REINFORCEMENT	EA	4,766		
191 (F)	560213	FURNISH SIGN STRUCTURE (LIGHTWEIGHT)	LB	26,400		
192 (F)	560214	INSTALL SIGN STRUCTURE (LIGHTWEIGHT)	LB	26,400		
193 (F)	560218	FURNISH SIGN STRUCTURE (TRUSS)	LB	206,000		
194 (F)	560219	INSTALL SIGN STRUCTURE (TRUSS)	LB	206,000		
195	560233	FURNISH FORMED PANEL SIGN (OVERHEAD)	SQFT	2,400		
196	560244	FURNISH LAMINATED PANEL SIGN (1"-TYPE A)	SQFT	820		
197	560245	FURNISH LAMINATED PANEL SIGN (1"-TYPE B)	SQFT	96		
198	560248	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	SQFT	990		
199	560249	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED)	SQFT	580		
200	560251	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-FRAMED)	SQFT	44		

BID ITEM LIST
07-2159U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
201	560252	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED)	SQFT	310		
202	562001	METAL (ROADSIDE SIGN)	LB	7,900		
203	029582	METAL (MEDIAN BARRIER MOUNTED SIGN)	LB	1,130		
204	562004	METAL (RAIL MOUNTED SIGN)	LB	1,020		
205	566011	ROADSIDE SIGN - ONE POST	EA	35		
206	566012	ROADSIDE SIGN - TWO POST	EA	10		
207	568001	INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	16		
208 (F)	620800	CONCRETE BACKFILL (PIPE TRENCH)	CY	340		
209	029583	REINFORCED CONCRETE PIPE (12"-30")	LF	23,300		
210	650026	36" REINFORCED CONCRETE PIPE	LF	1,170		
211	650030	42" REINFORCED CONCRETE PIPE	LF	1,670		
212	650034	48" REINFORCED CONCRETE PIPE	LF	300		
213	650038	54" REINFORCED CONCRETE PIPE	LF	230		
214	650042	60" REINFORCED CONCRETE PIPE	LF	240		
215	BLANK					
216	BLANK					
217	BLANK					
218	665717	18" SLOTTED CORRUGATED STEEL PIPE (.079" THICK)	LF	2,590		
219	680902	6" PERFORATED PLASTIC PIPE UNDERDRAIN	LF	850		
220	680903	6" NON-PERFORATED PLASTIC PIPE UNDERDRAIN	LF	600		

BID ITEM LIST
07-2159U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
241	029590	MINOR CONCRETE (SIDEWALK AND CURB RAMP)	CY	1,830		
242 (F)	750001	MISCELLANEOUS IRON AND STEEL	LB	113,707		
243 (F)	750496	MISCELLANEOUS METAL (RESTRAINER - PIPE TYPE)	LB	16,229		
244 (F)	750500	MISCELLANEOUS METAL	LB	230		
245 (F)	750501	MISCELLANEOUS METAL (BRIDGE)	LB	626		
246 (F)	750505	BRIDGE DECK DRAINAGE SYSTEM	LB	96,240		
247	029591	8" VITRIFIED CLAY SEWER PIPE	LF	710		
248	029592	10" VITRIFIED CLAY SEWER PIPE	LF	3,160		
249	029593	VITRIFIED CLAY SEWER PIPE (15"-24")	LF	840		
250	029594	18" DUCTILE IRON PIPE	LF	170		
251	029595	SEWER MANHOLE FRAME AND COVER	EA	21		
252	029596	CONCRETE SEWER MANHOLE	EA	21		
253	029597	ABANDON SEWER PIPE	LF	4,060		
254	029598	ABANDON SEWER MANHOLE	EA	15		
255	770070	REMOVE SEWER MANHOLE	EA	5		
256	770075	REMOVE SEWER PIPE	LF	1,020		
257	029599	FURNISH AND INSTALL 8" CEMENT LINED DUCTILE IRON PIPE (CL 52) (DOUBLE CEMENT LINED)	LF	310		
258	029600	FURNISH AND INSTALL 12" CEMENT LINED DUCTILE IRON PIPE (CL 52) (DOUBLE CEMENT LINED)	LF	2,920		
259	029601	FURNISH AND INSTALL PIPELINE CONNECTIONS	EA	4		
260	029602	FURNISH AND INSTALL 16" STEEL CASING	LF	20		

BID ITEM LIST
07-2159U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
321	029620	TEMPORARY TRAFFIC MONITORING STATION (LOCATION 1)	LS	LUMP SUM	LUMP SUM	
322	860930	TRAFFIC MONITORING STATION	LS	LUMP SUM	LUMP SUM	
323	029621	MODIFY COMMUNICATION SYSTEM	LS	LUMP SUM	LUMP SUM	
324	029622	TEMPORARY WIRELESS CLOSED CIRCUIT TELEVISION SYSTEM	LS	LUMP SUM	LUMP SUM	
325	029623	WORK AT NORWALK HUB AND LOS ANGELES REGIONAL TRAFFIC MANAGEMENT CENTER	LS	LUMP SUM	LUMP SUM	
326	029624	WORK AT LOS ANGELES REGIONAL TRANSPORTATION MANAGEMENT CENTER	LS	LUMP SUM	LUMP SUM	
327	861088	MODIFY RAMP METERING SYSTEM	LS	LUMP SUM	LUMP SUM	
328	029625	TEMPORARY RAMP METERING SYSTEM	LS	LUMP SUM	LUMP SUM	
329	861100	RAMP METERING SYSTEM	LS	LUMP SUM	LUMP SUM	
330	029626	MODIFY SIGNAL AND LIGHTING (CITY)	LS	LUMP SUM	LUMP SUM	
331	861504	MODIFY LIGHTING AND SIGN ILLUMINATION	LS	LUMP SUM	LUMP SUM	
332	030829	SYSTEM TESTING AND DOCUMENTATION	LS	LUMP SUM	LUMP SUM	
333	029627	CLASS D FILTER FABRIC	SQYD	940		
334	995100	WATER METER CHARGES	LS	LUMP SUM	LUMP SUM	
335	BLANK					
336	650046	66" REINFORCED CONCRETE PIPE	LF	720		
337	650050	72" REINFORCED CONCRETE PIPE	LF	620		
338	650058	84" REINFORCED CONCRETE PIPE	LF	590		
339	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID:

\$