



Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	101	119

  
 REGISTERED CIVIL ENGINEER  
 April 19, 2013  
 PLANS APPROVAL DATE



THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 6-15-15



**TYPICAL LANE CLOSURE**

**NOTES:**

- See Revised Standard Plan RSP T9 for tables.
- Use cone spacing X for taper segment, Y for tangent segment or Z for conflict situations, as appropriate, per Table 1, unless X, Y, or Z cone spacing is shown on this sheet.
- Unless otherwise specified in the special provisions, all temporary warning signs shall have black legend on fluorescent orange background.
- California codes are designated by (CA). Otherwise, Federal (MUTCD) codes are shown.

**NOTES:**

- Each advance warning sign shall be equipped with at least two flags for daytime closure. Each flag shall be at least 16" x 16" in size and shall be orange or fluorescent red-orange in color. Flashing beacons shall be placed at the locations indicated for lane closure during hours of darkness.
- A G20-2 "END ROAD WORK" sign, as appropriate, shall be placed at the end of the lane closure unless the end of work area is obvious, or ends within a larger project's limits.
- If the W20-1 sign would follow within 2000' of a stationary W20-1 or G20-1 "ROAD WORK NEXT \_\_\_\_\_ MILES", use a C20(CA) sign for the first advance warning sign.
- All cones used for lane closures during the hours of darkness shall be fitted with retroreflective bands (or sleeves) as specified in the specifications.
- Portable delineators, placed at one-half the spacing indicated for traffic cones, may be used instead of cones for daytime closures only.
- Flashing arrow sign shall be either Type I or Type II.
- For approach speeds over 50 mph, use the "Traffic Control System for Lane Closure On Freeways And Expressways" plan for lane closure details and requirements.
- A minimum 1500' of sight distance shall be provided where possible for vehicles approaching the first flashing arrow sign. Lane closures shall not begin at the top of crest vertical curve or on a horizontal curve.
- Place a C30(CA) sign every 2000' throughout length of lane closure.
- Median lane closures shall conform to the details as shown except that C20(CA)L and W4-2L signs shall be used.
- At least one person shall be assigned to provide full time maintenance of traffic control devices for lane closure unless, otherwise directed by the Engineer.

**LEGEND**

- TRAFFIC CONE
- TRAFFIC CONE (OPTIONAL TAPER)
- ⌋ TEMPORARY TRAFFIC CONTROL SIGN
-  FLASHING ARROW SIGN (FAS)
-  FAS SUPPORT OR TRAILER
-  PORTABLE FLASHING BEACON

**SIGN PANEL SIZE (Min)**

- A 48" x 48"
- B 36" x 18"
- C 30" x 30"

STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION  
**TRAFFIC CONTROL SYSTEM  
 FOR LANE CLOSURE ON  
 MULTILANE CONVENTIONAL  
 HIGHWAYS**

NO SCALE

RSP T11 DATED APRIL 19, 2013 SUPERSEDES STANDARD PLAN T11 DATED MAY 20, 2011 - PAGE 239 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP T11**

2010 REVISED STANDARD PLAN RSP T11

# TYPICAL RAMP CLOSURES

## SIGN PANEL SIZE (Min)

- A 48" x 48"
- B 48" x 30"
- C 36" x 36"
- D 48" x 36"

## LEGEND

- TRAFFIC CONE
- † TEMPORARY TRAFFIC CONTROL SIGN
- ‡ BARRICADES
- ⚡ PORTABLE FLASHING BEACON

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	102	119

*Gurinderpal Bhullar*  
 REGISTERED CIVIL ENGINEER  
 April 19, 2013  
 PLANS APPROVAL DATE


THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER  
 Gurinderpal Bhullar  
 No. C48815  
 Exp. 9-30-14  
 CIVIL  
 STATE OF CALIFORNIA


TO ACCOMPANY PLANS DATED 6-15-15

## NOTES:


- Barricades shall be Type I, II, or III for closures lasting one week or less and Type III for closures lasting longer than one week.
- In addition to placing the C19(CA) "RAMP CLOSED AHEAD" and C30(CA) "RAMP CLOSED" signs, black on orange overlay plates with the word "CLOSED" may be mounted, as directed by the Engineer, on all guide signs that refer to the closed ramp. The letter size on the overlay shall be the same as the guide sign.
- Each advance C19(CA) "RAMP CLOSED AHEAD" sign shall be equipped with at least two flags for daytime closure. Each flag shall be at least 16" x 16" in size and shall be orange or fluorescent red-orange in color. A flashing beacon shall be placed on top of the first C19(CA) sign during hours of darkness.
- All cones used for ramp closures during the hours of darkness shall be fitted with retroreflective bands (or sleeves) as specified in the specifications.
- Portable delineators, placed at one-half the spacing indicated for traffic cones, may be used instead of cones for daytime ramp closures only.
- At least one person shall be assigned to provide full time maintenance of traffic control devices, unless otherwise directed by the Engineer.
- The existing "EXIT" signs shall be covered during ramp closures.
- A minimum of 3 cones shall be placed transversely across each closed lane and shoulder.




EXIT RAMP OR CONNECTOR



EXIT RAMP OR CONNECTOR WITH ADDITIONAL LANE



ENTRANCE RAMP WITH TURNING POCKETS



ENTRANCE RAMP WITHOUT TURNING POCKETS

## NOTES:

- See Revised Standard Plan RSP T9 for tables.
- Use cone spacing X for taper segment, Y for tangent segment or Z for conflict situations, as appropriate, per Table 1, unless X, Y, or Z cone spacing is shown on this sheet.
- Unless otherwise specified in the special provisions, all temporary warning signs shall have black legend on fluorescent orange background.
- California codes are designated by (CA). Otherwise, Federal (MUTCD) codes are shown.

STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION  
**TRAFFIC CONTROL SYSTEM  
 FOR RAMP CLOSURE**  
 NO SCALE

RSP T14 DATED APRIL 19, 2013 SUPERSEDES STANDARD PLAN T14  
 DATED MAY 20, 2011 - PAGE 242 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP T14**

2010 REVISED STANDARD PLAN RSP T14

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	103	119


REGISTERED CIVIL ENGINEER

October 21, 2011  
PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 6-15-15

REGISTERED PROFESSIONAL ENGINEER  
Tillett Satter  
No. C42892  
Exp. 3-31-12  
CIVIL  
STATE OF CALIFORNIA




**EXISTING WALL (WITHOUT GUTTER)** Existing  
**RETAINING WALL (WITH GUTTER)** Existing  
**RETAINING WALL (WITH GUTTER)** New construction


**ELEVATION**

**NOTES:**


1. Maximum distance between turnbuckles shall be 200'-0"±.
2. Intermediate turnbuckles to be placed in adjacent spans.
3. Cable shall not be spliced between intermediate turnbuckles and end posts.
4. Posts to be vertical.
5. Alignment of holes in posts may vary to conform to slope of top of retaining wall.
6. The Contractor shall verify all dependent dimensions in the field before ordering or fabricating any material.
7. Line posts shall be braced horizontally and trussed diagonally in both directions at intervals not to exceed 1000'.
8. Post pockets to be centered in top of wall.
9. Typical end spans, braced in both directions, shall be constructed at changes in line where the angle of deflection is 15° or more.
10. Provide thimbles at all cable loops.




**SECTION A-A** Existing  
**SECTION B-B** Existing  
**SECTION C-C** New construction



**ALTERNATIVE CABLE CONNECTION**



**ALTERNATIVE DEAD END ANCHORAGE**



**POST POCKET**

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION  
**CABLE RAILING**

NO SCALE

RSP B11-47 DATED OCTOBER 21, 2011 SUPERSEDES STANDARD PLAN B11-47  
DATED MAY 20, 2011 - PAGE 293 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP B11-47**

2010 REVISED STANDARD PLAN RSP B11-47



Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	104	119

REGISTERED CIVIL ENGINEER





November 15, 2013  
PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 6-15-15



- NOTES:**
1. Walls are to be backfilled before barrier is placed.
  2. Clearance to reinforcing steel in barrier to be 1", except as noted. Longitudinal reinforcement to stop at all expansion joints.
  3. Dimensions may vary with roadway cross slope and with certain thickness of surfacing. See Project Plans.
  4. For typical metal railing connection details not shown, see Revised Standard Plans RSP A77U1 and RSP A77U2.
  5. See Standard Plans ES-9A, ES-9B, ES-9C, ES-9D and ES-9E for electrical details. The maximum number of conduits in the barrier is limited to two 2" conduits along with one 3" conduit. When a 3" conduit is used, it is restricted to the base of the barrier.
  6. For electrolier mounting details, See Standard Plans ES-6A and ES-6B.
  7. Minimum concrete edge distance, to the reinforcing shown, shall be maintained. Edge distance may be adjusted to accommodate increase in concrete cover for architectural treatment.
  8. Taper the top of the end of the bridge railing at 4:1 to match the top elevation of the thrie beam rail element.



Details shown for barrier anchorage to Type 736A. Anchorage for barrier Types 736 and 736B are similar to their respective details.

RSP B11-56 DATED NOVEMBER 15, 2013 SUPERSEDES RSP B11-56 DATED JULY 19, 2013 AND STANDARD PLAN B11-56 DATED MAY 20, 2011 - PAGE 298 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP B11-56**

2010 REVISED STANDARD PLAN RSP B11-56

**LEGEND:**

<b>AB</b>	ABANDON. IF APPLIED TO CONDUIT, REMOVE CONDUCTORS
<b>BC</b>	INSTALL PULL BOX IN EXISTING CONDUIT RUN
<b>BP</b>	PEDESTRIAN BARRICADE, TYPE AS INDICATED ON PLAN
<b>CB</b>	INSTALL CONDUIT INTO EXISTING PULL BOX
<b>CC</b>	CONNECT NEW AND EXISTING CONDUIT. REMOVE EXISTING CONDUCTORS AND INSTALL CONDUCTORS AS INDICATED
<b>CF</b>	CONDUIT TO REMAIN FOR FUTURE USE. REMOVE CONDUCTORS. INSTALL PULL TAPE
<b>DH</b>	DETECTOR HANDHOLE
<b>FA</b>	FOUNDATION TO BE ABANDONED
<b>IS</b>	INSTALL SIGN ON SIGNAL MAST ARM
<b>NS</b>	NO SLIP BASE ON STANDARD
<b>PEC</b>	PHOTOELECTRIC CONTROL
<b>PEU</b>	PHOTOELECTRIC UNIT
<b>RC</b>	EQUIPMENT OR MATERIAL TO BE REMOVED AND BECOME THE PROPERTY OF THE CONTRACTOR
<b>RE</b>	REMOVE ELECTROLIER, FUSES AND BALLAST. TAPE ENDS OF CONDUCTORS
<b>RL</b>	RELOCATE EQUIPMENT
<b>RR</b>	REMOVE AND REUSE EQUIPMENT
<b>RS</b>	REMOVE AND SALVAGE EQUIPMENT
<b>SC</b>	SPLICE NEW TO EXISTING CONDUCTORS
<b>SD</b>	SERVICE DISCONNECT
<b>TSP</b>	TELEPHONE SERVICE POINT

**ABBREVIATIONS**

APS	ACCESSIBLE PEDESTRIAN SIGNAL	M/M	MULTIPLE TO MULTIPLE TRANSFORMER
BBS	BATTERY BACKUP SYSTEM	Mtg	MOUNTING
BC	BOLT CIRCLE	MV	MERCURY VAPOR LIGHTING FIXTURE
BPB	BICYCLE PUSH BUTTON	MVDS	MICROWAVE VEHICLE DETECTION SYSTEM
C	CONDUIT	N	NEUTRAL (GROUNDED CONDUCTOR)
CB	CIRCUIT BREAKER	NB	NEUTRAL BUS
CCTV	CLOSED CIRCUIT TELEVISION	NC	NORMALLY CLOSE
Ck+	CIRCUIT	NO	NORMALLY OPEN
CMS	CHANGEABLE MESSAGE SIGN	P	CIRCUIT BREAKER'S POLE
Ctid	CALTRANS IDENTIFICATION	PB	PULL BOX
Comm	COMMUNICATION	PBA	PUSH BUTTON ASSEMBLY
DLC	LOOP DETECTOR LEAD-IN CABLE	PEC	PHOTOELECTRIC CONTROL
EMS	EXTINGUISHABLE MESSAGE SIGN	Ped	PEDESTRIAN
EVUC	EMERGENCY VEHICLE UNIT CABLE	PEU	PHOTOELECTRIC UNIT
EVUD	EMERGENCY VEHICLE UNIT DETECTOR	PT	CONDUIT WITH PULL TAPE
FB	FLASHING BEACON	RE	RELOCATED EQUIPMENT
FBCA	FLASHING BEACON CONTROL ASSEMBLY	RM	RAMP METERING
FBS	FLASHING BEACON WITH SLIP BASE	RWIS	ROADSIDE WEATHER INFORMATION SYSTEM
FO	FIBER OPTIC	SB	SLIP BASE
G	EQUIPMENT GROUNDING CONDUCTOR	SIC	SIGNAL INTERCONNECT CABLE
GB	GROUND BUS	Sig	SIGNAL
GFCI	GROUND FAULT CIRCUIT INTERRUPTER	SMA	SIGNAL MAST ARM
HAR	HIGHWAY ADVISORY RADIO	SNS	STREET NAME SIGN
Hex	HEXAGONAL	SP	SERVICE POINT
HPS	HIGH PRESSURE SODIUM	TDC	TELEPHONE DEMARCATION CABINET
IISNS	INTERNALLY ILLUMINATED STREET NAME SIGN	TMS	TRAFFIC MONITORING STATION
ISL	INDUCTION SIGN LIGHTING	TOS	TRAFFIC OPERATIONS SYSTEM
LED	LIGHT EMITTING DIODE	Veh	VEHICLE
LMA	LUMINAIRE MAST ARM	VIVDS	VIDEO IMAGE VEHICLE DETECTION SYSTEM
LPS	LOW PRESSURE SODIUM	WIM	WEIGH-IN-MOTION
Ltg	LIGHTING	Xfmr	TRANSFORMER
Lum	LUMINAIRE		
M	METERED		
MAT	MAST ARM MOUNTING TOP ATTACHMENT		
MAS	MAST ARM MOUNTING SIDE ATTACHMENT		

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	105	119

*Theresa Gabriel*  
REGISTERED ELECTRICAL ENGINEER

July 19, 2013  
PLANS APPROVAL DATE

Theresa  
Aziz Gabriel  
No. E15129  
Exp. 6-30-14  
ELECTRICAL  
STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 6-15-15

**SOFFIT AND WALL MOUNTED LUMINAIRES**

- PENDANT, 70 W HPS UNLESS OTHERWISE SPECIFIED
- FLUSH, 70 W HPS UNLESS OTHERWISE SPECIFIED
- WALL SURFACE, 70 W HPS UNLESS OTHERWISE SPECIFIED
- EXISTING SOFFIT OR WALL LUMINAIRE TO REMAIN UNMODIFIED
- EXISTING SOFFIT OR WALL LUMINAIRE TO BE MODIFIED AS SPECIFIED

**NOTE:**  
Arrow indicates "street side" of luminaire.

COMMONLY USED SYMBOLS FOR UNITED STATES CUSTOMARY UNITS OF MEASUREMENT:

SYMBOL USED	DEFINITIONS
$\Omega$	OHMS
min	MINUTE
s	SECOND
bps	BITS PER SECOND
Bps	BYTES PER SECOND
A	AMPERE
V	VOLT
V(dc)	VOLT (DIRECT CURRENT)
V(ac)	VOLT (ALTERNATING CURRENT)
FC	FOOT - CANDLE
W	WATTS
VA	VOLT-AMPERE
M	MEGA
k	KILO
m	MILLI
$\mu$	MICRO
P	PICO
HZ	HERTZ

**MISCELLANEOUS ELECTROLIERS**

NEW	EXISTING	
		LUMINAIRE ON WOOD POLE
		NON-STANDARD ELECTROLIER (SEE PROJECT NOTES OR PROJECT PLANS)
		CITY ELECTROLIER
		ELECTROLIER FOUNDATION (FUTURE INSTALLATION)

**NOTES:**

- HPS luminaires shall be 310 W HPS when installed on Type 21, 21D, 30, 31 and 32 Standards, unless otherwise specified. HPS luminaires shall be 200 W when installed on other type standards or poles, unless otherwise specified.
- LED luminaires shall be 235 W when installed on Type 21, 21D, 30, 31 and 32 Standards, unless otherwise specified. LED luminaires shall be 165 W when installed on other type standards or poles, unless otherwise specified.
- Luminaires shall be the cutoff type, ANSI Type III medium cutoff lighting distribution, unless otherwise specified.

**STANDARD ELECTROLIER**

NEW	EXISTING	STANDARD TYPE
		15
		15D
		15 STRUCTURE
		15D STRUCTURE
		21
		21D
		21 STRUCTURE
		21D STRUCTURE
		30
		31
		32

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

**ELECTRICAL SYSTEMS (LEGEND AND ABBREVIATIONS)**

NO SCALE

RSP ES-1A DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-1A DATED MAY 20, 2011 - PAGE 425 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP ES-1A**

2010 REVISED STANDARD PLAN RSP ES-1A

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	106	119

*Theresa Gabriel*  
REGISTERED ELECTRICAL ENGINEER

July 19, 2013  
PLANS APPROVAL DATE

Theresa Aziz Gabriel  
No. E15129  
Exp. 6-30-14  
ELECTRICAL  
STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 6-15-15

**CONDUIT**

**SIGNAL EQUIPMENT**

NEW	EXISTING	
---	---	LIGHTING CONDUIT, UNLESS OTHERWISE INDICATED OR NOTED
---	---	TRAFFIC SIGNAL CONDUIT
---C---	---c---	COMMUNICATION CONDUIT
---T---	---t---	TELEPHONE CONDUIT
---F---	---f---	FIRE ALARM CONDUIT
---FO---	---fo---	FIBER OPTIC CONDUIT
---	---	CONDUIT TERMINATION
		CONDUIT RISER ATTACHED TO THE STRUCTURE OR SERVICE POLE

NEW	EXISTING	
		PEDESTRIAN SIGNAL HEAD "C" INDICATES COUNTDOWN PEDESTRIAN HEAD
		PUSH BUTTON ASSEMBLY POST
		PEDESTRIAN BARRICADE
		VEHICLE SIGNAL HEAD (WITH BACKPLATE AND 3-SECTIONS: RED, YELLOW AND GREEN)
		VEHICLE SIGNAL HEAD WITH ANGLE VISOR
		MODIFICATIONS OF BASIC SYMBOL: "L" INDICATES ALL NON-ARROW SECTIONS LOUVERED "LG" INDICATES LOUVERED GREEN SECTION ONLY "PV" INDICATES ALL 12" SECTIONS PROGRAMMED VISIBILITY "8" INDICATES ALL 8" SECTIONS (ONLY WHEN SPECIFIED)

**SIGNAL EQUIPMENT Cont**

NEW	EXISTING	
		GUARD POST
		TYPE 1 STANDARD WITH RAMP METERING SIGN
		OPTICAL DETECTOR FOR THE EMERGENCY VEHICLE DETECTION SYSTEM

**SERVICE EQUIPMENT**


NEW	EXISTING	
---OH---	---oh---	OVERHEAD LINES
		WOOD POLE, "U" INDICATES UTILITY OWNED
		POLE GUY WITH ANCHOR
		UTILITY TRANSFORMER - GROUND MOUNTED
		SERVICE EQUIPMENT ENCLOSURE TYPE. DOOR INDICATES FRONT OF ENCLOSURE
		TELEPHONE DEMARCATION CABINET

NEW	EXISTING	
		VEHICLE SIGNAL HEAD CONSISTING OF RED, YELLOW AND GREEN LEFT ARROW SECTIONS
		VEHICLE SIGNAL HEAD CONSISTING OF RED AND YELLOW SECTIONS WITH AN UP GREEN ARROW SECTION
		VEHICLE SIGNAL HEAD (5 SECTION) CONSISTING OF RED, YELLOW AND GREEN SECTIONS WITH YELLOW AND GREEN RIGHT ARROW SECTIONS
		TYPE 15TS STANDARD WITH VEHICLE SIGNAL HEAD AND LUMINAIRE
		TYPE 21TS STANDARD WITH VEHICLE SIGNAL HEAD AND LUMINAIRE
		STANDARD WITH LUMINAIRE AND SIGNAL MAST ARMS AND ATTACHED VEHICLE SIGNAL HEADS
		TYPE 1 STANDARD WITH ATTACHED VEHICLE SIGNAL HEADS
		STANDARD WITH A SIGNAL MAST ARM, ATTACHED VEHICLE SIGNAL HEADS AND INTERNALLY ILLUMINATED STREET NAME SIGN
		CONTROLLER ASSEMBLY. DOOR INDICATES FRONT OF CABINET

**NOTES:**

- All signal sections shall be 12" unless shown otherwise.
- Signal heads shall be provided with backplates unless shown otherwise.

**POLE-MOUNTED SERVICE DESIGNATION**



**FLASHING BEACON**

NEW	EXISTING	
		FLASHING BEACON (ONE VEHICLE SIGNAL HEAD WITH BACKPLATE AND VISOR) "R" INDICATES RED INDICATION, "Y" INDICATES YELLOW INDICATION
		FLASHING BEACON WITH TYPE 15-FBS STANDARD AND A SIGN.
		FLASHING BEACON WITH TYPES 9, 9A OR 9B SIGN UNLESS OTHERWISE SPECIFIED OR INDICATED

**ILLUMINATED OVERHEAD SIGN**

NEW	EXISTING	
		SINGLE POST, SINGLE ILLUMINATED SIGN, BALANCED BUTTERFLY
		SINGLE POST, DOUBLE ILLUMINATED SIGN, BALANCED BUTTERFLY
		SINGLE POST, SINGLE ILLUMINATED SIGN, FULL CANTILEVER
		DOUBLE POST, SINGLE ILLUMINATED SIGN
		SINGLE ILLUMINATED SIGN MOUNTED ON STRUCTURE
		DOUBLE POST, SINGLE ILLUMINATED SIGN WITH ELECTROLIER

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS  
(LEGEND AND ABBREVIATIONS)**

NO SCALE  
RSP ES-1B DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-1B DATED MAY 20, 2011 - PAGE 426 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP ES-1B**


2010 REVISED STANDARD PLAN RSP ES-1B




TO ACCOMPANY PLANS DATED 6-15-15

### EQUIPMENT IDENTIFICATION


#### ILLUMINATED SIGN IDENTIFICATION NUMBER:




#### ELECTROLIER OR EQUIPMENT IDENTIFICATION NUMBER:




#### CONDUIT AND CONDUCTOR IDENTIFICATION:




#### SIGNAL AND LIGHTING STANDARD (TYPICAL DESIGNATION):




### MISCELLANEOUS EQUIPMENT





### WIRING DIAGRAM LEGEND



### PULL BOXES



### VEHICLE DETECTORS



STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION

## ELECTRICAL SYSTEMS (LEGEND AND ABBREVIATIONS)

NO SCALE

RSP ES-1C DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-1C DATED MAY 20, 2011 - PAGE 427 OF THE STANDARD PLANS BOOK DATED 2010.

2010 REVISED STANDARD PLAN RSP ES-1C

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	108	119

*Theresa Gabriel*  
 REGISTERED ELECTRICAL ENGINEER  
 July 19, 2013  
 PLANS APPROVAL DATE  
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 6-15-15

PLAN VIEW OF OTHER  
SIDE MOUNTINGS


**ABBREVIATIONS:**

- SV SIDE MOUNTED VEHICLE SIGNALS
- T TERMINAL COMPARTMENT
- TV TOP MOUNTED VEHICLE SIGNALS
- 1, 2, 3, 4 NUMBER OF SIGNAL FACES  
(3 - SECTION, UNLESS OTHERWISE INDICATED)
- A, B, C, D CONFIGURATION OF SIGNALS

**NOTES:**

1. Mountings shall be oriented to provide maximum horizontal clearance to adjacent roadway.
2. Bracket arms shall be long enough to permit proper alignment of signals and backplate installation.
3. See Standard Plans ES-4D and ES-4E for attachment fitting details.

PLAN VIEW OF  
TOP MOUNTINGS



SIDE MOUNTINGS

TOP MOUNTINGS

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS  
(VEHICULAR SIGNAL HEADS  
AND MOUNTINGS)**

NO SCALE

RSP ES-4A DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-4A  
DATED MAY 20, 2011 - PAGE 443 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP ES-4A**





2010 REVISED STANDARD PLAN RSP ES-4A

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	109	119

Theresa Gabriel  
 REGISTERED ELECTRICAL ENGINEER  
 July 19, 2013  
 PLANS APPROVAL DATE  
 Theresa Aziz Gabriel  
 No. E15129  
 Exp. 6-30-14  
 ELECTRICAL  
 STATE OF CALIFORNIA


THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TO ACCOMPANY PLANS DATED 6-15-15



- NOTES:**
1. Typical signal pole placement unless dimensioned on plans.
  2. For A and B dimensions, see Pole Schedule, or as directed by the Engineer.

**VISORS**



**8" AND 12" SECTIONS**


**BACKPLATE**

1/16" minimum thickness  
 3001-14 aluminum or plastic when specified

**DIRECTIONAL LOUVER**

Directional louvers shall be oriented as directed by the Engineer and secured in place with one plated brass machine screw and nut.

**SIGNAL STANDARD PLACEMENT DIMENSIONS AND EQUIPMENT LOCATIONS**



**TOP MOUNTED SIGNALS (TV)**



Type 1-A, 1-B, 1-C and 1-D standard as indicated on the plans

**SIDE MOUNTED SIGNALS (SV AND SP)**

Normally used on standards with luminaire or signal mast arm

**LEFT TURN LANE SIGNAL**

Type 1-A, 1-B, 1-C and 1-D standard as indicated on plans



**SIGNAL FACES**

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

**ELECTRICAL SYSTEMS (VEHICULAR SIGNAL HEADS AND MOUNTINGS)**

NO SCALE

RSP ES-4C DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-04C DATED MAY 20, 2011 - PAGE 445 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP ES-4C**

2010 REVISED STANDARD PLAN RSP ES-4C


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	110	119

*Theresa Gabriel*  
 REGISTERED ELECTRICAL ENGINEER  
 July 19, 2013  
 PLANS APPROVAL DATE


REGISTERED PROFESSIONAL ENGINEER  
 Theresa  
 Aziz Gabriel  
 No. E15129  
 Exp. 6-30-14  
 ELECTRICAL  
 STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS  
 OR AGENTS SHALL NOT BE RESPONSIBLE FOR  
 THE ACCURACY OR COMPLETENESS OF SCANNED  
 COPIES OF THIS PLAN SHEET.


TO ACCOMPANY PLANS DATED 6-15-15



**MAST ARM MOUNTINGS**



**DETAIL A**



**DETAIL B**

**OPTICAL DETECTOR MOUNTING FOR EMERGENCY VEHICLE DETECTION SYSTEM**

STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS  
 (VEHICULAR SIGNAL HEADS AND  
 OPTICAL DETECTOR MOUNTING)**

NO SCALE

RSP ES-4E DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-4E DATED MAY 20, 2011 - 447 OF THE STANDARD PLANS BOOK DATED 2010.


**REVISED STANDARD PLAN RSP ES-4E**

2010 REVISED STANDARD PLAN RSP ES-4E


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	111	119

*Theresa Gabriel*  
 REGISTERED ELECTRICAL ENGINEER  
 July 19, 2013  
 PLANS APPROVAL DATE  
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


TO ACCOMPANY PLANS DATED 6-15-15




WINDING DETAIL  
SAWCUT DETAIL  
**TYPE A LOOP DETECTOR CONFIGURATION**




WINDING DETAIL  
SAWCUT DETAIL  
**TYPE B LOOP DETECTOR CONFIGURATION**




WINDING DETAIL  
SAWCUT DETAIL  
**TYPE C LOOP DETECTOR CONFIGURATION**




WINDING DETAIL  
SAWCUT DETAIL  
**TYPE D LOOP DETECTOR CONFIGURATION**



WINDING DETAIL  
SAWCUT DETAIL  
**TYPE E LOOP DETECTOR CONFIGURATION**



WINDING DETAIL  
SAWCUT DETAIL  
**TYPE Q LOOP DETECTOR CONFIGURATION**



**PLAN VIEW OF  
DIAGONAL SLOT  
AT CORNERS**

- NOTES:**
1. Round corners of acute angle sawcuts to prevent damage to conductors.
  2. Typical distance separating loops from edge to edge is 10' for Type A, B, D and E installation in single lane.

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

**ELECTRICAL SYSTEMS  
(DETECTORS)**

NO SCALE

RSP ES-5B DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-5B  
DATED MAY 20, 2011 - PAGE 449 OF THE STANDARD PLANS BOOK DATED 2010.


2010 REVISED STANDARD PLAN RSP ES-5B

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	112	119


Theresa Gabriel  
 REGISTERED ELECTRICAL ENGINEER  
 July 19, 2013  
 PLANS APPROVAL DATE  
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER  
 Theresa Aziz Gabriel  
 No. E15129  
 Exp. 6-30-14  
 ELECTRICAL  
 STATE OF CALIFORNIA


TO ACCOMPANY PLANS DATED 6-15-15




**TYPE A  
CURB TERMINATION DETAIL**




**"T" TRENCH  
DETAIL T**



**CROSS SECTION**




**DETECTOR HANDHOLE DETAIL**




**PLAN VIEW**

**SECTION C-C**

**TYPE B  
CURB TERMINATION DETAIL**




**SECTION A-A**




**PLAN VIEW**


**TYPICAL LOOP LEAD-IN DETAIL  
AT PAVEMENT JOINT**



**LOCKING GRADE RING**



**CROSS SECTION**



**PLAN VIEW**

**SHOULDER TERMINATION DETAILS**

**NOTES:**


- Bushing shall be used at end of conduit.
- Tape detector conductors or cables 3" each side of bushings.
- Install duct seal compound to each end of termination conduit before installing sealant.
- Round all sharp edges where detector conductors or cables have to pass.
- End of conduit shall be 3/8" below roadway surface.
- Conduit size      Loop conductors  
 1"C minimum      1 to 2 pairs  
 1 1/2"C minimum    3 to 4 pairs  
 2"C minimum      5 or more pairs
- Splice detector conductors or cables to detector lead-in-cable.
- Location of detector handhole when shown on plans.
- When the shoulder and traveled way are paved with the same material and there is no joint between them, the conduit shall extend only 2'-0" into the shoulder pavement.
- 3/4"C, Type 3 conduit 6" long minimum, plug both ends with duct compound to keep out sealant.
- 1/2" Minimum between top of conduit and pavement surface.
- Sawcut shall not exceed 1" in width and 1/8" longer than conduit to be installed.
- Conductors with 1/2" minimum slack inside conduit.
- Inductive loop detector saw slot.

STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS  
 (CURB TERMINATION  
 AND HANDHOLE)**  
 NO SCALE


RSP ES-5D DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-5D  
 DATED MAY 20, 2011 - PAGE 451 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP ES-5D**


2010 REVISED STANDARD PLAN RSP ES-5D




**TYPE 16-3-100, 18-3-100,  
23-3-100, 27-3-100**  
ELEVATION A



**SIGNAL MAST ARM CONNECTION**  
ELEVATION C  
VIEW A-A  
DETAIL A



**BASE PLATE**  
DETAIL B



**TYPE 17-3-100, 24A-3-100,  
19-3-100, 26-3-100,  
19A-3-100, 26A-3-100, 24-3-100**  
ELEVATION B

E PROJECTED LENGTH	F Min SPACING	G MOUNTING HEIGHT	H	Min OD AT POLE	THICKNESS	I BOLT CIRCLE	HS CAP SCREWS	J PLATE SIZE	K MAST ARM THICKNESS	L POLE THICKNESS	theta	X Max
15'-0"	8'-0"	21'-8"±	17'-6"	7 3/8"	0.1793"							-
20'-0"		21'-8"±		7 3/8"		12"		1'-0"	1 1/4"	1 1/2"	23°	
25'-0"		22'-8"±		7 3/8"								
30'-0"	12'-0"			8"								10'-6"
35'-0"	14'-0"	23'-0"±	16'-0"	8 3/4"	0.2391"						21°	
40'-0"				9 3/8"		13"		1'-1"	1 1/2"	1 3/4"	15°	13'-0"
45'-0"	15'-0"	23'-8"±		10 1/16"								

M PROJECTED LENGTH	N RISE	Min OD AT POLE	THICKNESS	P MOUNTING HEIGHT
6'-0"	2'-0"±	3 1/4"		30'-0" POLE 35'-0" POLE
8'-0"	2'-6"±	3 1/2"		31'-6"± 32'-0"± 36'-6"±
10'-0"	3'-3"±	3 3/8"	0.1196"	32'-0"± 32'-9"± 37'-9"±
12'-0"	4'-3"±			33'-9"± 38'-9"±
15'-0"	4'-9"±	4 1/4"		34'-3"± 39'-3"±

POLE TYPE	LOAD CASE	WIND VELOCITY (mph)	POLE DATA						BASE PLATE DATA				CIDH PILE FOUNDATION					
			A HEIGHT	Min OD		THICKNESS	ALTERNATIVE SECTION			C	BC = BOLT CIRCLE	THICKNESS	ANCHOR BOLT SIZE	LUMINAIRE MAST ARM	SIGNAL MAST ARM	DIAMETER	DEPTH	REINFORCED
				BASE	TOP		B LENGTH	BOTTOM	TOP									
16-3-100			18'-6"		8 1/16"	0.1793"	NONE							NONE	15'-0"		8'-6"	
17-3-100			30'-0"	10 3/4"	6 7/16"		10'-0"	7 7/8"	6 7/16"	1'-5 1/2"				6'-15' 12'-0"	20'-0"			
18-3-100			17'-0"		8 9/16"		NONE							NONE			9'-6"	
19-3-100			30'-0"		7 1/16"		10'-0"	9 1/8"	7 1/16"					6'-15' 12'-0"	25'-0"			
19A-3-100			35'-0"		6 15/16"		15'-0"		6 15/16"					6'-15' 15'-0"	30'-0"			
23-3-100	3	100	17'-0"	1'-0"	9 9/16"	0.2391"	NONE			1'-7"	1'-5 1/2"	3"		NONE				
24-3-100			30'-0"		7 1/16"		10'-0"	9 1/8"	7 1/16"					6'-15' 12'-0"	35'-0"			
24A-3-100			35'-0"		6 15/16"		15'-0"	9 1/8"	6 15/16"					6'-15' 15'-0"				
26-3-100			30'-0"		7 13/16"		10'-0"	9 1/4"	7 13/16"					6'-15' 12'-0"	40'-0"			
26A-3-100			35'-0"	1'-2"	7 1/16"	0.3125"	15'-0"		7 1/16"	1'-11"	1'-9"			6'-15' 15'-0"	45'-0"			
27-3-100			17'-0"		9 1/16"		NONE							NONE				

INDICATES MAST ARM LENGTH TO BE USED UNLESS OTHERWISE NOTED ON PLANS.

2010 REVISED STANDARD PLAN RSP ES-7E

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS**  
**(SIGNAL AND LIGHTING STANDARD,**  
**CASE 3 SIGNAL MAST ARM LOADING,**  
**WIND VELOCITY=100 MPH AND SIGNAL**  
**MAST ARM LENGTHS 15' TO 45')**  
NO SCALE  
RSP 7E DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN 7E  
DATED MAY 20, 2011 - PAGE 466 OF THE STANDARD PLANS BOOK DATED 2010.

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	114	119

Stanley P. Johnson  
 REGISTERED CIVIL ENGINEER  
 No. C57793  
 Exp. 3-31-14  
 CIVIL  
 STATE OF CALIFORNIA


July 19, 2013  
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS  
 OR AGENTS SHALL NOT BE RESPONSIBLE FOR  
 THE ACCURACY OR COMPLETENESS OF SCANNED  
 COPIES OF THIS PLAN SHEET.


TO ACCOMPANY PLANS DATED 6-15-15

**NOTES:**


1. See Revised Standard Plan RSP ES-4A and Standard Plan ES-4D for attachment fitting details.
2. For wiring diagram, see Standard Plan ES-14B.
3. For additional notes and details, see Standard Plans ES-7M and ES-7N.
4. Handhole shall be located on the downstream side of traffic.
5. See project plans for type of standard to be installed.




FRONT VIEW  
 SIDE VIEW  
**TYPE 15-FBS**  
**ADVANCE FLASHING BEACON WITH SLIP BASE INSTALLATION**  
**DETAIL A**




**ELEVATION B**




VIEW A-A  
**FLASHING BEACON MAST ARM CONNECTION DETAIL**  
**DETAIL B**



**TYPE 1-A, 1-B, 1-C AND 1-D**  
**ADVANCE FLASHING BEACON INSTALLATION**  
**DETAIL D**  
 See Note 5



**TYPE 40-0-100**  
**ELEVATION A**



**BASE PLATE**  
**DETAIL C**

**ELECTRICAL SYSTEMS**  
**(FLASHING BEACON ON A TYPE 1, TYPE 15-FBS AND TYPE 40 STANDARD)**  
 NO SCALE

RSP ES-7J DATED JULY 19, 2013 SUPERSEDES STANDARD PLAN ES-7J DATED MAY 20, 2011 - PAGE 471 OF THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP ES-7J**

2010 REVISED STANDARD PLAN RSP ES-7J

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
07	LA	5	25.2/25.9	115	119


Theresa Gabriel  
REGISTERED ELECTRICAL ENGINEER

July 19, 2013  
PLANS APPROVAL DATE


Theresa Aziz Gabriel  
No. E15129  
Exp. 6-30-14  
ELECTRICAL  
STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


TO ACCOMPANY PLANS DATED 6-15-15




**INSTALLATION DETAILS**  
**DETAIL A**



**COVER TOP VIEW**



**TYPICAL COVER CAPTIVE BOLT**  
**OR SIMILAR**



**TYPICAL THREADED INSERT**  
**OR SIMILAR**

**NOTES:**

- Pull box covers shall be marked as follows: "SERVICE" Service circuits between service point and service disconnect; "SPRINKLER-CONTROL" sprinkler control circuits, 50 V or less; "CALTRANS" on all pull boxes, except pull boxes marked "SPRINKLER-CONTROL"; and "TELEPHONE" Telephone service;
  - No. 3 1/2 pull box.
    - "SIGNAL" - Traffic signal circuits with or without lighting or sign lighting circuits.
    - "LIGHTING" - Lighting or sign lighting circuits where voltage is under 600 V.
  - No. 5, 6, 9 or 9A pull box.
    - "TRAFFIC SIGNAL" - Traffic signal circuits with or without lighting or sign lighting circuits.
    - "LIGHTING" - Lighting or sign lighting circuits where voltage is under 600 V.
    - "LIGHTING-HIGH VOLTAGE" - Lighting or sign lighting circuits where voltage is above 600 V.
    - "IRRIGATION" - Circuits to irrigation controller 120 V or more.
    - "RAMP METER" - Ramp meter circuits.
    - "COUNT STATION" - Count or speed monitor circuits.
    - "COMMUNICATIONS" - Communication circuits.
    - "TOS COMMUNICATIONS" - TOS communication line.
    - "TOS POWER" - TOS power.
    - "TDC POWER" - Telephone demarcation cabinet power.
    - "CCTV" - Closed circuit television circuits.
    - "TMS" - Traffic monitoring station circuits.
    - "CMS" - Changeable message sign circuits.
    - "HAR" - Highway advisory radio circuits.
    - "BOOSTER PUMP" - Booster pump circuit.
- The nominal dimensions of the opening in which the cover sets shall be the same as the cover dimensions except the length and width dimensions shall be 1/8" greater.
- Covers and boxes shall be interchangeable with California standard male and female gages. When interchanged with a standard male or female gage, the top surfaces shall be flush within 1/8". Top outside radius of covers and pull boxes shall have a 1/8" radius.
- Pull box extension may be another pull box as long as the bottom edge of the pull box can fit into the cover opening.
- All dimensions for the cover for non-traffic pull box are nominal values.

DIMENSION TABLE										
PULL BOX	PULL BOX			COVER						
	MINIMUM DEPTH BOX	MINIMUM DEPTH EXTENSION	MAXIMUM WEIGHT	L	W	R	TE	TA	D	MAXIMUM WEIGHT
No. 3 1/2	12"	N/A	40 lb	1' - 3 3/8"	10 1/8"	1 3/8"	2"	1/8"	1 3/4"	30 lb
No. 5	12"	10"	55 lb	1' - 11 1/4"	1' - 1 3/4"	1 3/8"	2"	1/8"	1 3/4"	60 lb
No. 6	12"	10"	70 lb	2' - 6 1/2"	1' - 5 1/2"	1 3/8"	2"	1/8"	2"	85 lb

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS**  
**(NON-TRAFFIC PULL BOX)**  
NO SCALE

RSP ES-8A DATED JULY 19, 2013 SUPERSEDES RSP ES-8A DATED JANUARY 20, 2012 THAT SUPPLEMENTS THE STANDARD PLANS BOOK DATED 2010.

**REVISED STANDARD PLAN RSP ES-8A**

2010 REVISED STANDARD PLAN RSP ES-8A


DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
07	LA	5	25.2/25.9	116	119

*Theresa Gabriel*  
 REGISTERED ELECTRICAL ENGINEER  
 July 19, 2013  
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



TO ACCOMPANY PLANS DATED 6-15-15



**SECTION A-A**  
**No. 3 1/2(T), No. 5(T) AND**  
**No. 6(T) TRAFFIC PULL BOX**

**NOTES:**

- Traffic pull box shall be provided with steel cover and special concrete footing. Steel cover shall have embossed non-skid pattern.
- Steel reinforcing shall be as regularly used in the standard products of the respective manufacturer.
- Pull box covers shall be marked as follows: "SERVICE" Service circuits between service point and service disconnect; "SPRINKLER-CONTROL" Sprinkler control circuits, 50 V or less; "CALTRANS" On all pull boxes, except pull boxes marked "SPRINKLER-CONTROL"; and "TELEPHONE" Telephone service.
  - No. 3 1/2(T) pull box.
    - "SIGNAL" - Traffic signal circuits with or without lighting or sign lighting circuits.
    - "LIGHTING" - Lighting or sign lighting circuits where voltage is under 600 V.
  - No. 5(T) or 6(T) pull box.
    - "TRAFFIC SIGNAL" - Traffic signal circuits with or without lighting or sign lighting circuits.
    - "LIGHTING" - Lighting or sign lighting circuits where voltage is under 600 V.
    - "LIGHTING-HIGH VOLTAGE" - Lighting or sign lighting circuits where voltage is above 600 V.
    - "IRRIGATION" - Circuits to irrigation controller 120 V or more.
    - "RAMP METER" - Ramp meter circuits.
    - "COUNT STATION" - Count or speed monitor circuits.
    - "COMMUNICATION" - Communication circuits.
    - "TOS COMMUNICATIONS" - TOS communications line.
    - "TOS POWER" - TOS power.
    - "TDC POWER" - Telephone demarcation cabinet power.
    - "CCTV" - Closed circuit television circuits.
    - "TMS" - Traffic monitoring station circuits.
    - "CMS" - Changeable message sign circuits.
    - "HAR" - Highway advisory radio circuits.
    - "BOOSTER PUMP" - Booster pump circuit.
- Bonding jumper for metal covers shall be 3' long, minimum.
- The nominal dimensions of the opening in which the cover sets shall be the same as the cover dimensions except the length and width dimensions shall be 1/8" greater.
- Covers and boxes shall be interchangeable with California standard male and female gages. When interchanged with a standard male or female gage, the top surfaces shall be flush within 1/8".

PULL BOX	PULL BOX						COVER				
	MINIMUM * THICKNESS	MINIMUM DEPTH BOX AND EXTENSION	W0	L0	L1	W1	L **	W **	R	EDGE THICKNESS	EDGE TAPER
No. 3 1/2(T)	1 1/2"	1'-0"	1'-5"± 1"	1'-8 3/8"±	1'-2 1/2"±	10 5/8"± 1"	1'-8"±	1'-1 3/4"±	0"	1/2"	NONE
No. 5(T)	1 3/4"	1'-0"	1'-11 1/2"± 1"	2'-5 1/2"±	1'-7"±	1'-1"± 1"	2'-3"±	1'-4"±	0"	1/2"	NONE
No. 6(T)	2"	1'-0"	2'-6"± 1"	2'-11 1/2"±	1'-11 1/2"±	1'-5"± 1"	2'-9"±	1'-8"±	0"	1/2"	NONE

\* EXCLUDING CONDUIT WEB      \*\* TOP DIMENSION


STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION  
**ELECTRICAL SYSTEMS**  
**(TRAFFIC PULL BOX)**  
 NO SCALE

RSP ES-8B DATED JULY 19, 2013 SUPERSEDES RSP ES-8B DATED JANUARY 20, 2012 THAT SUPPLEMENTS THE STANDARD PLANS BOOK DATED 2010.

2010 REVISED STANDARD PLAN RSP ES-8B

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	117	119

David P. Murray  
 REGISTERED CIVIL ENGINEER 05-19-15  
 DATE  
 6-15-15  
 PLANS APPROVAL DATE  
 DAVID P. MURRAY  
 No. C71259  
 Exp. 12-31-15  
 CIVIL  
 STATE OF CALIFORNIA  
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.



**QUANTITIES**


PUBLIC SAFETY PLAN	LUMP	SUM
REMOVE CONCRETE DECK SURFACE	2,051	SOFT
PREPARE CONCRETE BRIDGE DECK SURFACE	2,051	SOFT
FURNISH POLYESTER CONCRETE OVERLAY	154	CF
PLACE POLYESTER CONCRETE OVERLAY	2,051	SOFT
BRIDGE REMOVAL (PORTION), LOCATION A	LUMP	SUM
CONCRETE BARRIER (TYPE 60A MODIFIED)	342	LF

**INDEX TO PLANS**

- | SHEET NO. | SHEET TITLE        |
|-----------|--------------------|
| 1.        | GENERAL PLAN NO. 1 |
| 2.        | GENERAL PLAN NO. 2 |
| 3.        | BARRIER DETAILS    |

**LEGEND:**

- Indicates New Structure
- - - - - Indicates Existing Structure
- Bridge Removal (Portion)
- STANDARD PLAN SHEET No.
- DETAIL No.



**NEW CONSTRUCTION**


**EXISTING**

**SECTION A-A**

1/2" = 1'


**STANDARD PLANS 2010**

- A10A ACRONYMS AND ABBREVIATIONS (SHEET 1 OF 2)
- RSP A10B ACRONYMS AND ABBREVIATIONS (SHEET 2 OF 2)
- A10C LINES AND SYMBOLS (SHEET 1 OF 3)
- A10D LINES AND SYMBOLS (SHEET 2 OF 3)
- A10E LINES AND SYMBOLS (SHEET 3 OF 3)
- A76A CONCRETE BARRIER TYPE 60
- A76B CONCRETE BARRIER TYPE 60



**QUANTITIES**

PUBLIC SAFETY PLAN	LUMP	SUM
REMOVE CONCRETE DECK SURFACE	397	SOFT
PREPARE CONCRETE BRIDGE DECK SURFACE	397	SOFT
FURNISH POLYESTER CONCRETE OVERLAY	30	CF
PLACE POLYESTER CONCRETE OVERLAY	397	SOFT
BRIDGE REMOVAL (PORTION), LOCATION B	LUMP	SUM
CONCRETE BARRIER (TYPE 60A MODIFIED)	66	LF



**NEW CONSTRUCTION**

**SECTION B-B**

1/2" = 1'

**EXISTING**

**NOTES:**




- FOR CURVE/BEARING DATA, SEE LAYOUT PLANS.
- THE CONTRACTOR SHALL VERIFY ALL DEPENDENT DIMENSIONS IN THE FIELD.
- FOR LOCATION OF "MODIFIED TYPE 60A" TYP SECTION, SEE "GENERAL PLAN NO. 2"

X DESIGN ENGINEER	DESIGN	BY DAVID P MURRAY	CHECKED MATTHEW SCHOTT	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY"; PERMIT DESIGN VEHICLE	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN <b>DESIGN BRANCH 18</b>	BRIDGE NO.	<b>ROUTE 5 BRIDGES - ADD MEDIAN BARRIER</b> <b>GENERAL PLAN NO. 1</b>	
	DETAILS	BY JINLI GUO	CHECKED DAVID P MURRAY	LAYOUT	BY JINLI GUO			CHECKED DAVID MURRAY		Varies
	QUANTITIES	BY DAVID P MURRAY	CHECKED MATTHEW SCHOTT	SPECIFICATIONS	BY KAREN DOLL			PLANS AND SPECS COMPARED KAREN DOLL		25.2/25.9




UNIT: 3603  
 PROJECT NUMBER & PHASE: 0712000216-1 CONTRACT NO.: 07-293404  
 DISREGARD PRINTS BEARING EARLIER REVISION DATES  
 REVISION DATES: 11/14/14, 2/27/15, 4/28/15, 5/19/15  
 SHEET 1 OF 3

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	118	119

David P. Murray  
 REGISTERED CIVIL ENGINEER  
 05-19-15  
 DATE  
 6-15-15  
 PLANS APPROVAL DATE  
 No. C71259  
 Exp. 12-31-15  
 CIVIL  
 STATE OF CALIFORNIA  
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.



- NOTES:**
1. DEPTH OF DRILL HOLE EQUALS DEPTH OF SLAB MINUS 1 1/2", UP TO 6" MAXIMUM.
  2. MINOR ADJUSTMENTS MAY BE MADE IN DOWEL SPACING TO CLEAR MAIN REINFORCEMENT.
  3. THE CONTRACTOR SHALL VERIFY ALL DEPENDENT DIMENSIONS IN THE FIELD.
  4. FOR CURVE/BEARING DATA, SEE LAYOUT PLANS.



**QUANTITIES**

PUBLIC SAFETY PLAN	LUMP	SUM
REMOVE CONCRETE DECK SURFACE	939	SOFT
PREPARE CONCRETE BRIDGE DECK SURFACE	939	SOFT
FURNISH POLYESTER CONCRETE OVERLAY	70	CF
PLACE POLYESTER CONCRETE OVERLAY	939	SOFT
BRIDGE REMOVAL (PORTION), LOCATION C	LUMP	SUM
CONCRETE BARRIER (TYPE 60P MODIFIED-2)	24	LF
CONCRETE BARRIER (TYPE 60C MODIFIED)	133	LF

**SECTION A-A**  
1/2" = 1'


- LEGEND:**
- Indicates New Structure
  - - - - - Indicates Existing Structure
  - ▨ Bridge Removal (Portion)

X DESIGN ENGINEER	DESIGN	BY DAVID P MURRAY	CHECKED MATTHEW SCHOTT	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY"; PERMIT DESIGN VEHICLE	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN DESIGN BRANCH 18	BRIDGE No.	Varies	ROUTE 5 BRIDGES - ADD MEDIAN BARRIER GENERAL PLAN NO. 2	
	DETAILS	BY JINLI GUO	CHECKED DAVID P MURRAY	LAYOUT	BY JINLI GUO			CHECKED DAVID P MURRAY	POST MILE		25.2/25.9
	QUANTITIES	BY DAVID P MURRAY	CHECKED MATTHEW SCHOTT	SPECIFICATIONS	BY KAREN DOLL			CHECKED KAREN DOLL	PLANS AND SPECS COMPARED		
ORIGINAL SCALE IN INCHES FOR REDUCED PLANS						UNIT: 3603 PROJECT NUMBER & PHASE: 0712000216-1	CONTRACT NO.: 07-293404	DISREGARD PRINTS BEARING EARLIER REVISION DATES		REVISION DATES	SHEET 2 OF 3

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	25.2/25.9	119	119


David P. Murray  
 REGISTERED CIVIL ENGINEER 05-19-15 DATE  
 6-15-15 PLANS APPROVAL DATE  
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of scanned copies of this plan sheet.

- NOTES:
1. DEPTH OF DRILLED HOLE EQUALS DEPTH OF SLAB MINUS 1/2", UP TO 6" MAXIMUM.
  2. FOR LOCATION OF PLAN VIEW, SEE ROAD PLAN SHEET C-4.
  3. FOR DETAILS NOT SHOWN IN ELEVATION 1, SEE ELEVATION 2 VIEW.
  4. SEE LANDSCAPE DETAILS SHEETS FOR ADDITIONAL ARCHITECTURAL TREATMENT DETAILS.




**ELEVATION 1 (Sta 102+58.91 TO 102+70.91 COLORADO St Fwy EXTENSION LINE)**  
NO SCALE

MATCH EXPANSION JOINT IF EXISTING IN DECK AT BB. FOR DETAILS OF CONCRETE BARRIER TYPE 60 CONNECTION TO STRUCTURE, SEE A76B



**ELEVATION 2 (Sta 103+36.00 TO 103+48.00 COLORADO St Fwy EXTENSION LINE)**  
NO SCALE



**SECTION A-A**  
**CONCRETE BARRIER (TYPE 60P Mod-2)**  
NO SCALE

**ROUTE 134/5 SEPARATION**

STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10)	DESIGN	BY DAVID P MURRAY	CHECKED MATTHEW SCHOTT	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN <b>DESIGN BRANCH 18</b>	BRIDGE NO.	ROUTE 5 BRIDGES - ADD MEDIAN BARRIER		
	DETAILS	BY JINLI GUO	CHECKED DAVID P MURRAY			Varies			
	QUANTITIES	BY DAVID P MURRAY	CHECKED MATTHEW SCHOTT			POST MILE 25.2/25.9			
ORIGINAL SCALE IN INCHES FOR REDUCED PLANS					UNIT: 3603 PROJECT NUMBER & PHASE: 0712000216-1	CONTRACT NO.: 07-293404	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 3 OF 3