

**** WARNING ** WARNING ** WARNING ** WARNING ****

This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.



STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

**NOTICE TO CONTRACTORS
INSTRUCTIONS TO BIDDERS
GENERAL CONDITIONS**

AND

SPECIAL PROVISIONS

**FOR BUILDING CONSTRUCTION ADJACENT TO STATE
HIGHWAY IN**

MONO COUNTY NEAR TOM'S PLACE AT THE MCGEE CREEK MAINTENANCE STATION

CONTRACT NO. 09-307904

09-Mno-395-29.4

**Bids Open: May 8, 2007
Dated: April 9, 2007**

OSD

IMPORTANT SPECIAL NOTICES

- Attention is directed to Division 0.3, "Award and Execution of Contract," of these Special Provisions regarding submittal of insurance documents.

TABLE OF CONTENTS

NOTICE TO CONTRACTORS	1
GENERAL CONDITIONS	8
SPECIAL PROVISIONS	46
DIVISION 0 BIDDING AND CONTRACT REQUIREMENTS	46
0.1 INSTRUCTIONS TO BIDDERS AND GENERAL CONDITIONS	46
0.15 DEFINITIONS AND TERMS	46
0.2 PROPOSAL REQUIREMENTS AND CONDITIONS	47
0.21 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)	48
0.215 DVBE GOAL FOR THIS PROJECT	49
0.22 SUBMISSION OF DVBE INFORMATION	49
0.23 SMALL BUSINESS AND NON-SMALL BUSINESS SUBCONTRACTOR PREFERENCES	49
0.231 SMALL BUSINESS PREFERENCE	50
0.232 NON-SMALL BUSINESS SUBCONTRACTOR PREFERENCE	50
0.24 CALIFORNIA COMPANY PREFERENCE	50
0.3 AWARD AND EXECUTION OF CONTRACT	50
0.4 BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES	52
0.551 LINES AND GRADES	52
0.552 COST REDUCTION INCENTIVE	52
0.553 ARCHAEOLOGICAL DISCOVERIES	53
0.561 SAMPLING AND TESTING OF MATERIALS	53
0.562 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES	54
0.563 SOLID WASTE DISPOSAL AND RECYCLING REPORT	54
0.571 WORKERS' COMPENSATION	54
0.572 INDEMNIFICATION AND INSURANCE	54
0.573 INDEMNIFICATION AND INSURANCE	58
0.581 SUBCONTRACTING	58
0.5811 NON-SMALL BUSINESS SUBCONTRACTING	58
0.591 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS	59
0.592 PAYMENT OF WITHHELD FUNDS	59
0.593 INTEREST ON PAYMENTS	59
0.597 FINAL PAYMENT AND CLAIMS	61
0.599 GUARANTEE	64
DIVISION 1. GENERAL REQUIREMENTS	64
1.01 SCOPE	64
1.02 STATE-FURNISHED MATERIALS	64
1.03 AREAS FOR CONTRACTOR'S USE	65
1.04 COOPERATION	65
1.05 MEASUREMENT AND PAYMENT	65
1.06 PROJECT INFORMATION	65
1.07 SUBMITTALS	65
1.08 SCHEDULE OF VALUES	65
1.09 OBSTRUCTIONS	66
1.10 PRESERVATION OF PROPERTY	66
1.11 WATER POLLUTION CONTROL	66
RETENTION OF FUNDS	67
STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND AMENDMENTS	68
COST BREAK-DOWN	69
SWPPP IMPLEMENTATION	73
MAINTENANCE	74
REPORTING REQUIREMENTS	74
PAYMENT	75

10-1.12 FIBER ROLLS.....	75
10-1.13 TEMPORARY SILT FENCE.....	76
1.14 UTILITY CONNECTION.....	78
1.15 TEMPORARY UTILITIES.....	78
1.16 SANITARY FACILITIES.....	78
1.17 REFERENCES.....	79
1.18 PROJECT RECORD DRAWINGS.....	79
1.19 FIELD ENGINEERING.....	79
1.20 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS.....	80
DIVISION 2. SITEWORK.....	90
2.01 CLEARING AND GRUBBING.....	90
2.02 EARTHWORK FOR BUILDING WORK.....	91
2.03 FREE DRAINING GRANULAR MATERIAL.....	93
2.04 ASPHALT CONCRETE.....	94
2.05 PAINTED PAVEMENT MARKINGS.....	96
2.06 GUARD POSTS.....	97
2.07 ACCESSIBLE PARKING AND AUTHORIZATION SIGNS.....	97
2.08 SALVAGE FENCE.....	98
2.09 AGGREGATE BASE.....	99
DIVISION 3. CONCRETE AND REINFORCEMENT.....	100
3.01 CAST-IN-PLACE CONCRETE.....	100
DIVISION 4. MASONRY (BLANK).....	105
DIVISION 5. METALS.....	105
5.01 BUILDING MISCELLANEOUS METAL.....	105
DIVISION 6. WOOD AND PLASTICS.....	107
6.01 ROUGH CARPENTRY.....	107
DIVISION 7. THERMAL AND MOISTURE PROTECTION.....	110
7.01 INSULATION (GENERAL).....	110
7.02 BATT AND BLANKET INSULATION.....	111
7.03 INSULATION FOR PRE-ENGINEERED STEEL BUILDING.....	112
7.04 SEALANTS AND CAULKING.....	114
DIVISION 8. DOORS AND WINDOWS.....	115
8.01 HINGED DOORS.....	115
8.02 SECTIONAL OVERHEAD DOORS.....	116
8.03 WINDOWS.....	119
8.04 FINISH HARDWARE.....	120
8.05 GLAZING.....	125
DIVISION 9. FINISHES.....	126
9.01 GYPSUM WALLBOARD.....	126
9.02 FIBERGLASS REINFORCED PLASTIC PANELS.....	128
9.03 RESILIENT SHEET FLOORING.....	129
9.04 PAINTING.....	130
DIVISION 10. SPECIALTIES.....	135
10.01 SIGNS.....	135
10.02 FIRE EXTINGUISHERS.....	136
10.03 FREE STANDING STEEL SHELVING.....	137
10.04 TOILET AND SHOWER ACCESSORIES.....	138
DIVISION 11. EQUIPMENT.....	139
11.01 LUBRICATION AND COMPRESSED AIR SYSTEMS.....	139
11.02 EXHAUST EVACUATION HOSE REEL AND FAN.....	143
11.03 WORKBENCH.....	144
DIVISION 12. FURNISHINGS (BLANK).....	145
DIVISION 13. SPECIAL CONSTRUCTION.....	145
13.01 PRE-ENGINEERED STEEL BUILDING.....	145
DIVISION 14. CONVEYING SYSTEMS (BLANK).....	148
DIVISION 15. MECHANICAL.....	148
15.01 MECHANICAL WORK.....	149
15.02 PIPE, FITTINGS AND VALVES.....	150
15.03 MECHANICAL INSULATION.....	160

15.04 PLUMBING FIXTURES	162
15.05 WHEELCHAIR ACCESSIBLE SHOWER UNIT.....	165
15.06 HEATING, VENTILATING AND AIR CONDITIONING EQUIPMENT AND SYSTEMS.....	166
15.07 LIQUEFIED PETROLEUM GAS (LPG) SYSTEM.....	169
15.08 CATHODIC PROTECTION.....	171
DIVISION 16. ELECTRICAL	172
16.01 ELECTRICAL WORK.....	172
16.02 BASIC MATERIALS AND METHODS.....	173
16.03 ELECTRICAL EQUIPMENT.....	180
16.04 LIGHTING	183

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

CONTRACT NO. 09-307904

09-Mno-395-29.4

Sealed proposals for the work shown on the plans entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR BUILDING CONSTRUCTION ADJACENT TO STATE HIGHWAY IN MONO COUNTY NEAR TOM'S PLACE AT THE MCGEE CREEK MAINTENANCE STATION

will be received at the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, CA 95814, until 2 o'clock p.m. on May 8, 2007, at which time they will be publicly opened and read in Room 0100 at the same address.

Proposal forms for this work are included in a separate book entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR BUILDING CONSTRUCTION ADJACENT TO STATE HIGHWAY IN MONO COUNTY NEAR TOM'S PLACE AT THE MCGEE CREEK MAINTENANCE STATION

General work description: Construct mechanics facility, including mechanical and electrical work

This project has a goal of 3 percent disabled veteran business enterprise (DVBE) participation.

No prebid meeting is scheduled for this project.

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A license or Class B license or a combination of Class C licenses which constitutes a majority of the work.

The Contractor must also be properly licensed at the time the bid is submitted, except that on a joint venture bid a joint venture license may be obtained by a combination of licenses after bid opening but before award in conformance with Business and Professions Code, Section 7029.1.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

This project is subject to the State Small Business Preference, Non-Small Business Subcontractor Preference, and California Company Reciprocal Preference.

Inquiries or questions based on alleged patent ambiguity of the plans, specifications or estimate must be communicated as a bidder inquiry prior to bid opening. Any such inquiries or questions, submitted after bid opening, will not be treated as a bid protest.

The Caltrans Central Region Construction Office is located at 855 M Street, Suite 200, Fresno, CA 93721. The District Duty Senior for this project can be reached at (760) 872-5251, or by fax at (760) 872-5201. The Department will consider bidder inquiries only when a completed "Bidder Inquiry" form is submitted. The "Bidder Inquiry" form is available on the Internet at:

<http://www.dot.ca.gov/dist6/construction>

Contract No. 09-307904

To the extent feasible and at the discretion of the Department, completed "Bidder Inquiry" forms submitted for consideration will be investigated, and responses will be posted on the Internet at:

<http://www.dot.ca.gov/dist6/construction>

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated.

The successful bidder shall furnish a payment bond and a performance bond.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the office of the District Director of Transportation for District 6, located at Fresno, and available from the California Department of Industrial Relations' Internet Web Site at: <http://www.dir.ca.gov>. Future effective general prevailing wage rates which have been predetermined and are on file with the Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated April 9, 2007

WIA

STATE OF CALIFORNIA

DEPARTMENT OF TRANSPORTATION

**INSTRUCTIONS TO BIDDERS
AND
GENERAL CONDITIONS
FOR
BUILDING CONSTRUCTION**

JANUARY 2002

Issued by

DEPARTMENT OF TRANSPORTATION



Contract No. 09-307904

INSTRUCTIONS TO BIDDERS
SECTION 1
PROPOSAL REQUIREMENTS AND CONDITIONS

1-1.01 GENERAL

The bidder shall carefully examine the instructions contained herein and shall be satisfied as to the conditions with which the bidder must comply prior to bid and to the conditions affecting the award of contract.

These instructions form a part of the contract documents.

Attention is directed to Section 1-1.01, "General," of the General Conditions regarding the use of masculine gender pronouns in these Instructions to Bidders.

1-1.02 CONTRACTOR'S LICENSING LAWS

Attention is directed to the provisions of Chapter 9 of Division 3 of the Business and Professions Code concerning the licensing of contractors.

All bidders and contractors shall be licensed in conformance with the laws of this State and any bidder or contractor not so licensed is subject to the penalties imposed by those laws.

Attention is also directed to the requirements in Public Contract Code Section 10164. In all projects where Federal funds are involved, the Contractor shall be properly licensed at the time the contract is awarded.

1-1.03 EXAMINATION OF PLANS, SPECIAL PROVISIONS AND SITE OF THE WORK

The bidder shall examine carefully the site of the work contemplated, the plans and special provisions and these Instructions to Bidders and contract forms therefor. The submission of a bid shall be conclusive evidence that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and scope of work to be performed, the quantities of materials to be furnished, and as to the requirements of these Instructions to Bidders, plans, special provisions, and the contract.

Where the Department has made investigations of site conditions, including subsurface conditions in areas where work is to be performed under the contract, bidders or Contractors may, upon written request, inspect the records of the Department as to those investigations subject to and upon the conditions hereinafter set forth.

Where there has been prior construction by the Department or other public agencies within the project limits, records of the prior construction that are currently in the possession of the Department and which have been used by, or are known to, the designers and administrators of the project will be made available for inspection by bidders or Contractors, upon written request, subject to the conditions hereinafter set forth. Those records may include, but are not limited to, as-built drawings, design calculations, foundation and site studies, project reports and other data assembled in connection with the investigation, design, construction and maintenance of those prior projects.

Inspection of those records of investigations and project records may be made at the office of the district in which the work is situated, or in the case of records of investigations related to structure work, at the Transportation Laboratory, Sacramento, California. The records of investigations and project records are not a part of the contract and are available solely for the convenience of the bidder or contractor. It is expressly understood and agreed that the Department assumes no responsibility whatsoever in respect to the sufficiency or accuracy of the investigations thus made, the records thereof, or of project records, or of the interpretations set forth therein or made by the Department in its use thereof and there is no warranty or guaranty, either express or implied, that the conditions indicated by the investigations or records are representative of those existing in or throughout those areas, or any part thereof, or that unlooked-for developments may not occur, or that materials other than, or in proportions different from those indicated, may not be encountered.

No information derived from the inspection of investigations or compilation thereof made by the Department or from the Engineer, or his assistants, will in any way relieve the bidder or contractor from any risk or from properly fulfilling the terms of the contract.

1-1.04 PROPOSAL FORMS

The Department will furnish to each bidder a standard proposal form, which, when filled out and executed may be submitted as that bidder's bid. Bids not presented on forms so furnished, and copies or facsimiles of the bidder's completed and executed proposal forms submitted as a bid will be rejected.

The proposal form is bound together with the contract in a book entitled "Proposal and Contract." The proposal shall set forth the bid price, in clearly legible figures, in the space provided, and shall be signed by the bidder, who shall fill out all blanks in the proposal form as therein required.

The proposal shall be submitted as directed in the "Notice to Contractors" under sealed cover plainly marked as a proposal, and identifying the project to which the proposal relates and the date of the bid opening therefor. Proposals which are not properly marked may be disregarded.

All proposal forms other than for "District Opening" projects shall be obtained from the Department of Transportation, Plans and Bid Documents, Room 0200, Transportation Building, 1120 N Street, California 95814, or as otherwise designated in the "Notice to Contractor."

Proposals for "District Opening" projects shall be made on forms obtained from the District Director of Transportation in whose district the work is to be performed, but in all other respects the provisions in this Section 1-1.04 shall apply.

1-1.05 REQUIRED LISTING OF PROPOSED SUBCONTRACTORS

Each proposal shall have listed therein the name and address of each subcontractor to whom the bidder proposes to subcontract portions of the work in an amount in excess of one-half of one percent of the total bid, in conformance with the Subletting and Subcontracting Fair Practices Act, commencing with Section 4100 of the Public Contract Code. The bidder's attention is invited to other provisions of the Act related to the imposition of penalties for a failure to observe its provisions by using unauthorized subcontractors or by making unauthorized substitutions.

A sheet for listing the subcontractors, as required herein, is included in the "Proposal and Contract" book.

1-1.055 STATE EMPLOYEES AND DESIGN ENGINEERS MAY NOT BID ON CONSTRUCTION CONTRACTS

No employee of the State shall be eligible to submit a proposal for, nor to subcontract for any portion of, nor to supply any materials for any contract administered by the Department.

No engineering or architectural firm which has provided design services for a project shall be eligible to submit a proposal for the contract to construct the project nor to subcontract for any portion of the work. The ineligible firms include the prime contractor for design, subcontractors of portions of the design, and affiliates of either. An affiliate is a firm which is subject to the control of the same persons, through joint ownership or otherwise.

1-1.06 PREVIOUS DISQUALIFICATION, REMOVAL OR OTHER PREVENTION OF BIDDING

Pursuant to Section 10162 of the Public Contract Code the bidder shall complete, under penalty of perjury, the questionnaire in the Proposal relating to previous disqualification, removal or other prevention of bidding of the bidder, or officers or employees of the bidder because of violation of law or a safety regulation.

A bid may be rejected on the basis of a bidder, any officer of the bidder, or any employee of the bidder who has a proprietary interest in the bidder, having been disqualified, removed, or otherwise prevented from bidding on, or completing a Federal, State, or local project because of a violation of law or a safety regulation.

1-1.07 PROPOSAL GUARANTY

All bids shall be presented under sealed cover and accompanied by one of the following forms of bidder's security:

Cash, a cashier's check, a certified check, or a bidder's bond executed by an admitted surety insurer, made payable to the Director of Transportation.

The security shall be in an amount equal to at least 10 percent of the amount bid. A bid will not be considered unless one of the forms of bidder's security is enclosed with it.

The bidder's bond shall conform to the bond form in the book entitled "Proposal and Contract" for the project and shall be properly filled out and executed. The bidder's bond form included in that book may be used. Upon request, "Bidder's Bond" forms may be obtained from the Department of Transportation.

1-1.08 COMPLIANCE WITH ORDERS OF THE NATIONAL LABOR RELATIONS BOARD

Pursuant to Public Contract Code Section 10232, the Contractor shall swear by a statement, under penalty of perjury, that no more than one final, unappealable finding of contempt of court by a Federal court has been issued against the Contractor within the immediately preceding 2-year period because of the Contractor's failure to comply with an order of a Federal court which orders the Contractor to comply with an order of the National Labor Relations Board. For purposes of Section 10232 a finding of contempt does not include any finding which has been vacated, dismissed, or otherwise removed by the court

because the Contractor has complied with the order which was the basis for the finding. The State may rescind any contract in which the Contractor falsely swears to the truth of the statement required by Section 10232.

The statement required by Public Contract Code Section 10232 is on the page preceding the signature page of the Proposal.

1-1.09 WITHDRAWAL OF PROPOSALS

Any bid may be withdrawn at any time prior to the date and time fixed for the opening of bids only by written request for the withdrawal of the bid filed at the location at which the bid was received by the Department. The request shall be executed by the bidder or the bidder's duly authorized representative. The withdrawal of a bid does not prejudice the right of the bidder to file a new bid. Whether or not bids are opened exactly at the time fixed for opening bids, a bid will not be received after that time, nor may any bid be withdrawn after the time fixed for the opening of bids.

1-1.10 PUBLIC OPENING OF PROPOSALS

Proposals will be opened and read publicly at the time and place indicated in the Notice to Contractors. Bidders or their authorized agents are invited to be present.

1-1.11 REJECTION OF PROPOSALS

Proposals may be rejected if they have been transferred to another bidder, or if they show any alterations of form, additions not called for, conditional bids, incomplete bids, erasures, or irregularities of any kind.

When proposals are signed by an agent, other than the officer or officers of a corporation authorized to sign contracts on its behalf or a member of a partnership, a "Power of Attorney" must be on file with the Department prior to opening bids or shall be submitted with the proposal; otherwise, the proposal may be rejected as irregular and unauthorized.

1-1.12 COMPETITIVE BIDDING

If more than one proposal be offered by any individual, firm, copartnership, corporation, association, or any combination thereof, under the same or different names, all of those proposals may be rejected. A party who has quoted prices on materials or work to a bidder is not thereby disqualified from quoting prices to other bidders, or from submitting a bid directly for the materials or work.

All bidders are put on notice that any collusive agreement to control or affect the awarding of this contract is in violation of the competitive bidding requirements of the State Contract Act and the Business and Professions Code and may render void any contract let under those circumstances.

1-1.13 RELIEF OF BIDDERS

Attention is directed to the provisions of Public Contract Code Sections 5100 to 5107, inclusive, concerning relief of bidders and in particular to the requirement therein, that if the bidder claims a mistake was made in the bid presented, the bidder shall give the Department written notice within 5 days after the opening of the bids of the alleged mistake, specifying in the notice in detail how the mistake occurred.

1-1.14 INELIGIBILITY TO CONTRACT

Public Contract Code Section 10285.1 provides as follows:

Any State agency may suspend, for a period of up to three years from the date of conviction, any person from bidding upon, or being awarded, a public works or services contract with the agency under this part or from being a subcontractor at any tier upon the contract, if that person, or any partner, member, officer, director, responsible managing officer, or responsible managing employee thereof, has been convicted by a court of competent jurisdiction of any charge of fraud, bribery, collusion, conspiracy, or any other act in violation of any State or Federal antitrust law in connection with the bidding upon, award of, or performance of, any public works contract, as defined in Section 1101, with any public entity, as defined in Section 1100, including, for the purposes of this article, the Regents of the University of California or the Trustees of the California State University. A State agency may determine the eligibility of any person to enter into a contract under this article by requiring the person to submit a statement under penalty of perjury declaring that neither the person nor any subcontractor to be engaged by the person has been convicted of any of the offenses referred to in this section within the preceding three years.

A form for the statement required by Section 10285.1 is included in the Proposal.

SECTION 2

AWARD AND EXECUTION OF CONTRACT

2-1.01 AWARD OF CONTRACT

The right is reserved to reject any and all proposals. The award of the contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed. The award, if made, will be made within 30 days after the opening of the proposals. This period will be subject to extension for any further period as may be agreed upon in writing between the Department and the bidder concerned.

2-1.02 RETURN OF PROPOSAL GUARANTIES

The proposal guaranties accompanying the proposals of the first, second and third lowest responsible bidders will be retained until the contract has been finally executed, after which all those proposal guaranties, except bidders' bonds and any guaranties which have been forfeited, will be returned to the respective bidders whose proposals they accompany. The proposal guaranties, other than bidder's bonds, submitted by all other unsuccessful bidders will be returned upon determination, by the Department, of the first, second and third lowest responsible bidders.

2-1.03 CONTRACT BONDS

The successful bidder shall furnish the 2 bonds required by the State Contract Act. One bond shall secure the payment of the claims of laborers, mechanics or materialmen employed on the work under the contract and the other bond shall guarantee the faithful performance of the contract. The bond forms will be furnished to the successful bidder by the Department.

Except as otherwise provided in Section 3248 of the Civil Code and Section 30154 of the Streets and Highways Code, the payment bond shall be in a sum equal to the contract price and the performance bond shall be in a sum equal to at least one-half of the contract price.

All alterations, extensions of time, extra and additional work, and other changes authorized by the General Conditions, the special provisions or any part of the contract may be made without securing the consent of the surety or sureties on the contract bonds.

2-1.04 EXECUTION OF CONTRACT

The contract shall be signed by the successful bidder and returned, together with the contract bonds, within 8 days, not including Saturdays, Sundays and legal holidays, after the bidder has received the contract for execution.

2-1.05 FAILURE TO EXECUTE CONTRACT

Failure of the lowest responsible bidder, the second lowest responsible bidder, or the third lowest responsible bidder to execute the contract and file acceptable bonds as provided herein within 8 days, not including Saturdays, Sundays and legal holidays, after that bidder has received the contract for execution shall be just cause for the forfeiture of the bidder's security. The successful bidder may file with the Department a written notice, signed by the bidder or the bidder's authorized representative, specifying that the bidder will refuse to execute the contract if it is presented. The filing of this notice shall have the same force and effect as the failure of the bidder to execute the contract and furnish acceptable bonds within the time hereinbefore prescribed.

GENERAL CONDITIONS
SECTION 1
DEFINITIONS AND TERMS

1-1.01 GENERAL

Unless the context otherwise requires, wherever in the specifications and other contract documents the following abbreviations and terms, or pronouns in place of them, appear in the contract documents, the intent and meaning shall be interpreted as provided in this Section 1.

Working titles having a masculine gender, such as "workman" and "journeyman" and pronouns, such as "he" and "himself", are utilized in these General Conditions, the Instructions to Bidders and the special provisions for the sake of brevity, and are intended to refer to persons of either gender.

1-1.02 ACCEPTANCE

The formal written acceptance by the Director of Transportation of an entire contract which has been completed in all respects in conformance with the contract documents and any modifications thereof previously approved.

1-1.03 ADDENDUM

A document or written communication issued by the Department during the bidding period which modifies, supersedes, or supplements the original contract documents.

1-1.04 BIDDER

Any individual, firm, partnership, corporation, or combination thereof, submitting a proposal for the work contemplated, acting directly, or through a duly authorized representative.

1-1.05 CONTRACT

The written agreement covering the performance of the work and the furnishing of labor, materials, tools and equipment in the construction of the work. The contract shall include the notice to contractors, Instructions to Bidders, proposal, plans, General Conditions, special provisions and contract bonds; also any and all supplemental agreements amending or extending the work contemplated and which may be required to complete the work in a substantial and acceptable manner. Supplementary agreements are written agreements covering alterations, amendments, or extensions to the contract and include contract change orders.

1-1.06 CONTRACTOR

The person or persons, firm, partnership, corporation, or combination thereof, private or municipal, who have entered into a contract with the Department of Transportation, as party or parties of the second part or their legal representatives.

1-1.07 DAYS

Unless otherwise designated, days as used in the contract documents will be understood to mean calendar days.

1-1.08 DEPARTMENT

The Department of Transportation of the State of California, as created by law.

1-1.09 DIRECTOR

The executive officer of the Department of Transportation, as created by law.

1-1.10 ENGINEER

The Chief Engineer, Department of Transportation, acting either directly or through properly authorized agents, the agents acting within the scope of the particular duties delegated to them.

1-1.11 GENERAL NOTES

The written instructions, provisions, conditions or other requirements appearing on the plans, and so identified thereon, which pertain to the performance of the work.

1-1.12 LABORATORY

The Division of Engineering Services - Materials Engineering and Testing Services and the Division of Engineering Services - Geotechnical Services of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean the Division of Engineering Services - Materials Engineering and Testing Services and the Division of Engineering Services - Geotechnical Services, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

1-1.13 LEGAL HOLIDAYS

Those days designated as State holidays in the Government Code.

1-1.14 LIQUIDATED DAMAGES

The amount prescribed in the special provisions, pursuant to the authority of Public Contract Code Section 10226, to be paid to the State or to be deducted from any payments due or to become due the Contractor for each day's delay in completing the whole or any specified portion of the work beyond the time allowed in the special provisions.

1-1.15 PLANS

The official drawings including plans, elevations, sections, detail drawings, diagrams, plates, general notes, information and schedules thereon, or exact reproductions thereof, approved by the Engineer, which show the location, character, dimensions and details of the work to be performed. The plans include any drawings or plates bound within the special provisions.

1-1.16 PREMISES

The area of State-owned property which surrounds the work site, limited by the property lines thereof. In some cases the premises may coincide with the work site.

1-1.17 PROPOSAL

The offer of the bidder for the work when made out and submitted on the prescribed proposal form, properly signed and guaranteed.

1-1.18 PROPOSAL FORM

The approved form upon which the Department of Transportation requires formal bids be prepared and submitted for the work.

1-1.19 PROPOSAL GUARANTY

The cash, cashier's check, certified check, or bidder's bond accompanying the proposal submitted by the bidder, as a guaranty that the bidder will enter into a contract with the Department of Transportation for the performance of the work if the contract is awarded to the bidder.

1-1.20 SPECIAL PROVISIONS

The special provisions are specific clauses setting forth conditions or requirements of the work and supplementary to these General Conditions and the Instructions to Bidders. The Department of Transportation publication entitled Labor Surcharge And Equipment Rental Rates is to be considered as a part of the special provisions.

1-1.21 STATE

The State of California.

1-1.22 STATE CONTRACT ACT

An act to regulate contracts for the erection, construction, alteration, repair or improvement of any state structure, building, road, or other State improvements of any kind, to be found in Chapter 1, Division 2 of the Public Contract Code.

1-1.23 WORK

The furnishing of all labor, and the furnishing and installing of all materials, articles, supplies and equipment as specified, designated, or required by the contract.

1-1.24 WORKING DAY

Every day except Saturdays, Sundays, legal holidays, and those days not charged as working days pursuant to Section 6-1.07, "Time of Completion," of these General Conditions.

1-1.25 WORK SITE

The area of actual construction and the areas immediately adjacent thereto.

1-1.26 ABBREVIATIONS

AAMA	Architectural Aluminum Manufacturers' Association
AAN	American Association of Nurserymen
AASHTO	American Association of State Highway and Transportation Officials
ACI	American Concrete Institute
AGA	American Gas Association
AISC	American Institute of Steel Construction
AISI	American Iron and Steel Institute
AITC	American Institute of Timber Construction
AMCA	Air Movement and Control Association
ANSI	American National Standards Institute
APA	American Plywood Association
APHA	American Public Health Association
API	American Petroleum Institute.
AREA	American Railway Engineering Association
ARI	American Refrigeration Institute
ASHRAE	American Society of Heating, Refrigeration and Air Conditioning Engineers
ASME	American Society of Mechanical Engineers
ASTM	American Society for Testing and Materials
AWG	American Wire Gage
AWPA	American Wood Preservers' Association
AWS	American Welding Society
AWWA	American Water Works Association
CBC	California Building Code
CEC	California Electrical Code
CS	Commercial Standards (US Department of Commerce)
EIA	Electronic Industries Association
ESO	Electrical Safety Orders
FGMA	Flat Glass Marketing Association
FM	Factory Mutual
FS	Federal Specification
IEEE	Institute of Electrical and Electronics Engineers
ICBO	International Conference of Building Officials
NAAMM	National Association of Architectural Metal Manufacturers
NBFU	National Board Fire Underwriters
NEC	National Electrical Code
NEMA	National Electrical Manufacturers' Association
NFPA	National Fire Protection Association
PEI	Porcelain Enamel Institute

PS	Product Standard (US Department of Commerce)
RIS	Redwood Inspection Service
SCPI	Structural Clay Products Institute
SMACNA	Sheet Metal and Air Conditioning Contractors' National Association
TCA	Tile Council of America
TPI	Truss Plate Institute
UBC	Uniform Building Code
UL	Underwriters' Laboratory
UPC	Uniform Plumbing Code
WCLB	Grade Stamp for WCLIB
WCLIB	West Coast Lumber Inspection Bureau (Grade Stamped WCLB)
WIC	Woodwork Institute of California
WWPA	Western Wood Products' Association

Units of Measurement

Some of the symbols for units of measurement used in the specifications are defined as follows. The symbols for other units of measurement used in the specifications are as defined in ASTM Designation: E-380, or in the various specifications and test referenced in the specifications.

Symbols as used in the Specifications	Definitions
A	amperes
g	gram
kg	kilogram
ha	hectare (10 000 m ²)
h	hour
J	joule
L	liter
m	meter
km	kilometer
mm	millimeter
μm	micrometer
nm	nanometer
m ²	square meter
m ³	cubic meter
N	newton
N·m	newton meter
Ω	ohm
Pa	pascal
kPa	kilopascal
MPa	megapascal
s	second
tonne	metric ton (1000 kg)
W	watt
V	volt

SECTION 2
CONTROL AND SCOPE OF THE WORK

2-1.01 AUTHORITY OF ENGINEER

The Engineer shall decide all questions which may arise as to the quality or acceptability of materials furnished and work performed and as to the manner of performance and rate of progress of the work; all questions which may arise as to the interpretation of the plans and special provisions; all questions as to the acceptable fulfillment of the contract on the part of the Contractor; and all questions as to compensation. The Engineer's decision shall be final, and the Engineer shall have authority to enforce and make effective those decisions and orders which the Contractor fails to carry out promptly.

2-1.02 INTENT OF PLANS AND SPECIAL PROVISIONS

The intent of the plans and special provisions is to prescribe the details for the construction and completion of the work which the Contractor undertakes to perform in conformance with the terms of the contract. Where the plans or special provisions describe portions of the work in general terms, but not in complete detail, it is understood that only the best general practice is to prevail and that only materials and workmanship of the first quality are to be used. Unless otherwise specified, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals, and do all the work involved in executing the contract in a satisfactory and workmanlike manner.

2-1.03 COORDINATION AND INTERPRETATION OF CONTRACT DOCUMENTS

These General Conditions, the plans, special provisions, contract change orders, and all supplementary documents are essential parts of the contract, and a requirement occurring in one is as binding as though occurring in all. They are intended to be complementary, and to describe and provide for a complete work.

Plans shall govern over these General Conditions; the special provisions shall govern over both these General Conditions and the plans.

Should it appear that the work to be done or any of the matters relative thereto are not sufficiently detailed or explained in these General Conditions, the special provisions, or the plans, the Contractor shall apply to the Engineer for further explanations as may be necessary and shall conform to them as part of the contract. In the event of any doubt or question arising respecting the true meaning of these General Conditions, the special provisions or the plans, reference shall be made to the Engineer, whose decision thereon shall be final.

In the event of any discrepancy, between any drawing and the figures written thereon, the figures shall be taken as correct. Detail drawings shall prevail over general drawings and general notes shall prevail over drawings.

2-1.04 SHOP DRAWINGS, DESCRIPTIVE DATA, SAMPLES, AND ALTERNATIVES

It shall be the Contractor's responsibility to submit, so as to cause no delay in the work, all shop drawings, descriptive data, samples for the various trades as required by the special provisions, and offers of alternatives, if any. The submittals shall be checked and coordinated by the Contractor with the work of other trades involved before they are submitted to the Engineer for examination.

Submittals shall be delivered to the locations indicated in the special provisions.

Work requiring the submittal of shop drawings, descriptive data or samples shall not begin prior to approval of that submittal by the Engineer. Fifteen working days shall be allowed for approval or return for correction of each submittal or resubmittal. Approval of submittals shall not operate to waive any of the requirements of the plans and specifications or relieve the Contractor of any obligation thereunder, and defective work, materials and equipment may be rejected notwithstanding the approval of that submittal. Should the Engineer fail to complete his review within the time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted pursuant to the provisions in Section 6-1.08, "Liquidated Damages," of these General Conditions, and no additional compensation will be allowed for the delay.

Submittals shall be made by a letter of transmittal which shall contain a list of all matter submitted and identification of all variations from the plans and special provisions contained in the submittal. The letter and all items accompanying the same shall be fully identified as to project name and location, Contractor's name, district, county, and contract number, with ample cross references to the contract documents, to facilitate identification of items and their location in the work. Additional specific requirements shall be as follows:

Shop Drawings

The Contractor shall submit at least 5 copies of all shop drawings required by the special provisions. Two copies will be returned to the Contractor either approved for use or returned for correction and resubmittal. Shop drawings include any drawing which requires execution by a draftsman as distinguished from printed matter. The size of shop drawings shall be 559 mm x 864 mm or 279 mm x 432 mm in size.

Descriptive Data

The Contractor shall submit 5 copies of each set of manufacturer's brochures or other data required by the special provisions. The State will examine the submittals and return 2 copies either approved for use or returned for correction and resubmittal.

Samples

The Contractor shall submit samples of articles, materials or equipment as required by the special provisions. The work shall be in conformance with the approved samples. Samples shall be removed from State property when directed or may be incorporated in the work if approved by the Engineer. Samples not removed by the Contractor will become the property of the State or, at the State's option, will be removed or disposed of by the State at the Contractor's expense.

Alternatives

For convenience in designation on the plans or in the special provisions, certain materials, articles, or equipment may be designated by a brand or a trade name or the name of the manufacturer together with catalog designation or other identifying information, hereinafter referred to generically as "designated by brand name". An alternative material, article, or equipment which is of equal quality and of the required characteristics for the purpose intended may be proposed for use provided the Contractor complies with the following requirements:

- 1 The Contractor shall submit his proposal for an alternative in writing. The request shall be made in ample time to permit approval without delaying the work, but need not be made in less than 35 days after award of the contract.
- 2 No proposal will be considered unless accompanied by complete information and descriptive data, necessary to determine the equality of the offered materials, articles, or equipment. Samples shall be provided when requested by the Engineer. The Contractor shall satisfy the Engineer as to the comparative quality, suitability, or performance of the offered materials, articles, or equipment. In the event that the Engineer rejects the use of the alternative materials, articles, or equipment, then one of the particular products designated by brand name shall be furnished.

Approval of submittals by the Engineer shall not relieve the Contractor from responsibility for the successful completion of the work, nor shall it relieve the Contractor from responsibility for errors in the submittals. A failure by the Contractor to identify in the letter of transmittal, material deviations from the plans or specifications shall void the submittal and any action taken thereon by the Engineer. When specifically requested by the Engineer, the Contractor shall resubmit the shop drawings, descriptive data and samples as may be required.

If any mechanical, electrical, structural, or other changes are required for the proper installation and fit of alternative materials, articles, or equipment, or because of deviations from the contract plans and special provisions, the changes shall not be made without the approval of the Engineer and shall be made without additional cost to the State.

2-1.045 DIFFERING SITE CONDITIONS

During the progress of the work, if subsurface or latent physical conditions are encountered at the site differing materially from those indicated in the contract or if unknown physical conditions of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in the work provided for in the contract, are encountered at the site, the party discovering those conditions shall promptly notify the other party in writing of the specific differing conditions before they are disturbed and before the affected work is performed.

Upon written notification, the Engineer will investigate the conditions, and if the Engineer determines that the conditions materially differ and cause an increase or decrease in the cost or time required for the performance of any work under the contract, an adjustment, excluding loss of anticipated profits, will be made and the contract modified in writing accordingly. The Engineer will notify the Contractor of his determination whether or not an adjustment of the contract is warranted.

No contract adjustment which results in a benefit to the Contractor will be allowed unless the Contractor has provided the required written notice.

No contract adjustment will be allowed under the provisions specified in this section for any effects caused on unchanged work.

Any contract adjustment warranted due to differing site conditions will be made in conformance with the provisions in Section 3-1.01, "Changes," of these General Conditions, except as otherwise provided.

2-1.05 PRESERVATION AND CLEANING

The Contractor shall clean up the work at frequent intervals and at other times when directed by the Engineer. While finish work is being accomplished, floors shall be kept clean, free of dust, construction debris and trash. Upon completion of the work, the Contractor shall remove from the premises the Contractor's construction equipment and any waste materials not previously disposed of, leaving the premises thoroughly clean and ready for final inspection.

2-1.06 LIMITATIONS ON WORK SITE AND PREMISES

The Contractor shall limit the Contractor's construction operations to the work site unless otherwise shown on the plans or specified. The Contractor shall perform no operations of any nature over or on the premises except those operations as are authorized by the plans or special provisions, or as authorized by the Engineer.

2-1.07 SUPERINTENDENCE

The Contractor shall designate in writing before starting work, an authorized representative who shall have the authority to represent and act for the Contractor.

When the Contractor is comprised of 2 or more persons, firms, partnerships, or corporations functioning on a joint venture basis, the Contractor shall designate in writing before starting work, the name of one authorized representative who shall have the authority to represent and act for the Contractor.

The authorized representative shall be present at the site of the work at all times while work is actually in progress on the contract. When work is not in progress and during periods when work is suspended, arrangements acceptable to the Engineer shall be made for any emergency work which may be required.

Whenever the Contractor or the Contractor's authorized representative is not present on any particular part of the work where it may be desired to give direction, orders will be given by the Engineer, which shall be received and obeyed by the superintendent or foreman who may have charge of the particular work in reference to which the orders are given.

Any order given by the Engineer, not otherwise required by the specifications to be in writing, will on request of the Contractor, be given or confirmed by the Engineer in writing.

2-1.08 CHARACTER OF WORKMEN

If any subcontractor or person employed by the Contractor shall appear to the Engineer to be incompetent or to act in a disorderly or improper manner, they shall be discharged immediately on the request of the Engineer, and that person shall not again be employed on the work.

2-1.09 INSPECTION

The Contractor shall at all times permit the Engineer and the Engineer's authorized agents to inspect the work or any part thereof. The Contractor shall maintain proper facilities and provide safe access for inspection by the Engineer to all parts of the work, and to the shops where the work is in preparation. Work shall not be covered up until authorized by the Engineer and the Contractor shall be solely responsible for notifying the Engineer where and when the work is in readiness for inspection and testing. Should any work be covered without authorization, it shall, if so ordered, be uncovered at the Contractor's expense.

Whenever the Contractor intends to perform work on Saturday, Sunday, or a legal holiday, the Contractor shall give notice to the Engineer of the Contractor's intention 48 hours prior to performing that work, or a longer period as may be specified so that the Engineer may make necessary arrangements.

2-1.10 REMOVAL OF REJECTED AND UNAUTHORIZED WORK

All work which has been rejected shall be remedied, or removed and replaced by the Contractor in a manner acceptable to the Engineer and no compensation will be allowed to the Contractor for the removal, replacement, or remedial work.

Any work done beyond the lines shown on the plans or established by the Engineer, or any work done without written authority will be considered as unauthorized work and will not be paid for. Upon order of the Engineer, unauthorized work shall be remedied, removed, or replaced at the Contractor's expense.

Upon failure of the Contractor to comply promptly with any order of the Engineer made under this Section 2-1.10, the Department may cause rejected or unauthorized work to be remedied, removed, or replaced, and the costs thereof will be deducted from any moneys due or to become due the Contractor.

2-1.11 COST REDUCTION INCENTIVE

The Contractor may submit to the Engineer, in writing, proposals for modifying the plans, special provisions or other requirements of the contract for the sole purpose of reducing the total cost of construction. The cost reduction proposal shall not impair, in any manner, the essential functions or characteristics of the project, including but not limited to service life, economy of operation, ease of maintenance, desired appearance, or design and safety standards.

Prior to preparing a cost reduction proposal, the Contractor shall request a meeting with the Engineer to discuss the proposal in concept and to determine the merit of the cost reduction proposal. Items of discussion will also include permit issues, impact on other projects, impact on the project schedule, peer reviews, and review times required by the Department and other agencies.

Cost reduction proposals shall contain the following information:

1. A description of both the existing contract requirements for performing the work and the proposed changes.
2. An itemization of the contract requirements that must be changed if the proposal is adopted.
3. A detailed estimate of the cost of performing the work under the existing contract and under the proposed change. The estimates of cost shall be determined in the same manner as if the work were to be paid for as a change in the work as provided in Section 3, "Changes in the Work," of these General Conditions.
4. A statement of the time within which the Engineer must make a decision thereon.
5. The contract work affected by the proposed changes, including any quantity variation attributable thereto.

The provisions of this Section 2-1.11 shall not be construed to require the Engineer to consider any cost reduction proposal which may be submitted hereunder; proposed changes in basic design will not be considered as an acceptable cost reduction proposal; and the Department will not be liable to the Contractor for failure to accept or act upon any cost reduction proposal submitted pursuant to this section nor for any delays to the work attributable to any cost reduction proposal. If a cost reduction proposal is similar to a change in the plans or special provisions, under consideration by the Department for the project, at the time the proposal is submitted or if the proposal is based upon or similar to standard special provisions adopted by the Department after the advertisement for the contract, the Engineer will not accept the proposal, and the Department reserves the right to make the changes without compensation to the Contractor under the provisions of this section.

The Contractor shall continue to perform the work in conformance with the requirements of the contract until an executed change order, incorporating the cost reduction proposal has been issued. If an executed change order has not been issued by the date upon which the Contractor's cost reduction proposal specifies that a decision thereon should be made, or such other date as the Contractor may subsequently have specified in writing, the cost reduction proposal shall be deemed rejected.

The Engineer shall be the sole judge of the acceptability of a cost reduction proposal and of the estimated net savings in construction costs from the adoption of all or any part of the proposal. In determining the estimated net savings, the right is reserved to disregard the schedules of values if, in the judgment of the Engineer, the schedule does not represent a fair measure of the value of work to be performed or to be deleted.

The Department reserves the right where it deems action is appropriate, to require the Contractor to share in the Department's costs of investigating a cost reduction proposal submitted by the Contractor as a condition of considering the proposal. Where this condition is imposed, the Contractor shall indicate acceptance thereof in writing, and that acceptance shall constitute full authority for the Department to deduct amounts payable to the Department from any moneys due or that may become due to the Contractor under the contract.

If the Contractor's cost reduction proposal is accepted in whole or in part the acceptance will be by a contract change order, which shall specifically state that it is executed pursuant to this Section 2-1.11. The change order shall incorporate the changes in the plans and special provisions which are necessary to permit the cost reduction proposal or that part of it as has been accepted to be put into effect, and shall include any conditions upon which the Department's approval thereof is based if the approval of the Department is conditional. The change order shall also set forth the estimated net savings in construction costs attributable to the cost reduction proposal effectuated by the change order, and shall further provide that the Contractor be paid 50 percent of that estimated net savings amount. The Contractor's cost of preparing the cost reduction incentive proposal and the Department's costs of investigating a cost reduction incentive proposal, including any portion thereof paid by the Contractor, shall be excluded from consideration in determining the estimated net savings in construction costs.

Acceptance of the cost reduction proposal and performance of the work thereunder shall not extend the time of completion of the contract unless specifically provided for in the contract change order authorizing the use of the cost reduction proposal.

The amount specified to be paid to the Contractor in the change order which effectuates a cost reduction proposal shall constitute full compensation to the Contractor for the cost reduction proposal and the performance of the work thereof pursuant to the change order.

The Department expressly reserves the right to adopt a cost reduction proposal for general use on contracts administered by the Department when it determines that the proposal is suitable for application to other contracts. When an accepted cost reduction proposal is adopted for general use, only the Contractor who first submitted that proposal will be eligible for compensation pursuant to this section, and in that case, only as to those contracts awarded to that Contractor prior to submission of the accepted cost reduction proposal and as to which the cost reduction proposal is also submitted and accepted. Cost reduction proposals identical or similar to previously submitted proposals will be eligible for consideration and compensation under the provisions of this Section 2-1.11 if the identical or similar previously submitted proposals were not adopted for general application to other contracts administered by the Department. Subject to the provisions contained herein, the State or any other public agency shall have the right to use all or any part of any submitted cost reduction proposal without obligation or compensation of any kind to the Contractor.

This Section 2-1.11 shall apply only to contracts awarded to the lowest bidder pursuant to competitive bidding.

SECTION 3 CHANGES IN THE WORK

3-1.01 CHANGES

The Department reserves the right to order changes in the contract at any time prior to the acceptance of the work by the Director, and the Contractor shall comply with the ordered changes. Changes or deviations from the contract shall not be made without authority in writing from the Engineer, and changes to the work without the Engineer's written approval will be considered unauthorized work and will not be paid for.

On the basis set forth in this Section 3, the contract lump sum price will be adjusted for any ordered change which results in a change in the cost of the work.

When ordered by the Engineer, the Contractor shall halt work in the area affected by a proposed change. Whenever it appears to the Contractor that a change is necessary, the Contractor shall immediately notify the Engineer of the reasons for that change; however, work in the area affected shall not be discontinued unless ordered by the Engineer.

For any approved change in the work, the Contractor shall be entitled to an adjustment in time equal to the number of working days which completion of the entire work is delayed due to the changed work, and the State will be entitled to an adjustment in time equal to the number of working days which completion of the entire work is advanced due to the changed work. For ordinary changes, the Contractor's cost estimate for the changed work shall state the amount of extra time, if any, that the Contractor considers should be allowed for making the requested change. Failure to request additional time when submitting the estimate, or failure to submit the estimate, shall constitute a waiver of the right to later claim any adjustment in time based upon changed work. For ordinary changes which decrease the amount of work and for indeterminate type changes, an adjustment in time commensurate with the changed work will be determined by the Engineer. Disagreement as to time adjustments shall not affect contract price adjustments, nor shall it be cause for not proceeding with the changed work when ordered by the Engineer. The Contractor shall have the right, however, to further pursue a time adjustment in the event agreement is not reached.

3-1.01A Ordinary Changes

The Engineer will notify the Contractor in writing of any proposed changes and describe the intended change. Within 15 days after receipt of a written request, the Contractor shall submit his proposed price to be added or deducted from the contract price due to the change. The Contractor's proposed price to be added to or deducted from the contract price shall be supported by detailed estimates of cost prepared by the Contractor. The Contractor shall also provide information to support any request for an adjustment in contract time which is directly attributable to the changed work. The Contractor shall, upon request by the Engineer, permit inspection of his original contract estimate, subcontract agreements or purchase orders relating to the change.

If agreement is reached on the adjustment in compensation as provided in Section 3-1.01C, "Agreed Cost for Changes," of these General Conditions, the Contractor shall proceed with the work at the agreed price.

If the Contractor and the Engineer fail to agree as to the adjustment in compensation for the performance of the changed work, the Contractor, upon written order from the Engineer, shall proceed immediately with the changed work and the contract price will be adjusted in conformance with the provisions in Section 3-1.01D, "Failure to Agree to the Cost of Changes," of these General Conditions.

If the Contractor fails to submit his cost estimate within the specified 15 day period, the specified period may be extended in writing by the Engineer. If the Engineer does not so extend the specified period, or if the Contractor fails to submit his cost estimate within the extended time period, the Contractor shall commence the work immediately upon receipt of written order from the Engineer and the contract price will be adjusted in conformance with the provisions in Section 3-1.01D, "Failure to Agree to the Cost of Changes," of these General Conditions.

3-1.01B Indeterminate Type Changes

Changes in the work of a kind where the cost of the work cannot be determined until completed, may be authorized by the Engineer in writing. The written order shall state that it is issued pursuant to this Section 3-1.01B. Upon receipt of a written order from the Engineer, the Contractor shall proceed with the ordered work and the contract price will be adjusted in conformance with the provisions in Section 3-1.01D, "Failure to Agree to the Cost of Changes," of these General Conditions.

3-1.01C Agreed Cost For Changes

If the Engineer and the Contractor agree as to the adjustment in compensation for the performance of changed work on the basis of the Contractor's proposed cost estimate of the work, the contract lump sum price will be adjusted accordingly. The adjustment in compensation shall be agreed to in writing and executed by both parties.

3-1.01D Failure To Agree To The Cost Of Changes

When a proposed change order decreases the cost of the work and the Engineer and the Contractor fail to agree upon the decreased cost thereof, the Engineer's estimated decrease in cost will be deducted from the contract price. The Contractor will be allowed 15 days after receipt of a contract change order approved by the Engineer, in which to file a written protest setting forth in what respects the Contractor differs from the Engineer's estimate of decreased cost, otherwise the decision of the Engineer to deduct the Engineer's estimate of decreased cost shall be deemed to have been accepted by the Contractor as correct.

In the event the Engineer and the Contractor fail to agree on the cost of a change order which increases the cost of the work, the Engineer will maintain a daily job record containing a detailed summary of all labor, materials and equipment required by the ordered change. At the end of each day's work, the Contractor shall review the Engineer's daily job record comparing with the Contractor's own records, and after agreement is reached, the daily job record shall be signed by both the Engineer and the Contractor and shall become the basis for payment for the changed work. Upon completion of the work under the change order, the Contractor shall submit an invoice listing only those items of labor, materials and equipment that were agreed to by both the Engineer and the Contractor to be in addition to the requirements of the contract, together with allowable markups.

When there is a failure to agree as to cost, no payment for the changed work will be made to the Contractor until all work called for in the change order has been completed, except that progress payments may be made on those portions of the changed work which the Contractor and the Engineer agree as to cost.

3-1.01E Allowable Costs For Changes

The only costs which will be allowed because of changed work and the manner in which these costs shall be computed are set forth in Sections 3-1.01E(1) through 3-1.01E(5) of these General Conditions. Where the term "actual cost" is used in the aforesaid sections, it shall be deemed to mean "estimated cost" where the adjustment in compensation is of a necessity based upon estimated costs.

3-1.01E(1) Labor

The Contractor will be paid an amount based on the actual cost for labor and supervision directly required for the performance of the changed work, including payments, assessment of benefits required by lawful labor union collective bargaining agreements; compensation insurance payments; contributions made to the State pursuant to the Unemployment Insurance Code, and for taxes paid to the Federal Government pursuant to the Social Security Act of August 14, 1935, as amended. No labor cost will be recognized at a rate in excess of the wages prevailing in the locality at the time the work is performed, nor will the use of a labor classification which would increase the cost be permitted unless the Contractor establishes to the complete satisfaction of the Engineer the necessity for payment at a higher rate.

3-1.01E(2) Materials

The Contractor will be paid an amount based on the actual cost of the materials directly required for the performance of the changed work. The cost of materials may include the costs of procurement, transportation and delivery if necessarily incurred. If a cash or trade discount by the actual supplier is available to the Contractor, it shall be credited to the State. If the materials are obtained from a supply or source owned wholly or in part by the Contractor, payment therefor will not exceed the current wholesale price for the materials. If, in the opinion of the Engineer, the cost of materials is excessive, or if the Contractor fails to furnish satisfactory evidence of the cost to the Engineer from the actual supplier, the cost of the materials shall be deemed to be the lowest current wholesale price at which similar materials are available in the quantities required. The Department reserves the right to furnish the materials required by the change order as it deems advisable, and the Contractor shall have no claim for cost or markups on material furnished by the Department.

3-1.01E(3) Equipment

The Contractor will be paid an amount based on the actual cost for the use of equipment directly required and approved by the Engineer in the performance of the changed work. No payment will be made for time while equipment is inoperative due to breakdowns or on days when no work is performed. In addition, the rental time shall include the time required to move the equipment to the work from the nearest available source of the required equipment, and to return it to the source. If the equipment is not moved by its own power, then loading and transportation costs will be paid. Moving time, loading and transportation costs will only be paid if the equipment is used exclusively on the changed work during the time between move in and move out. Individual pieces of equipment having a replacement value of \$500 or less shall be considered to be tools or small equipment, and no payment will be made therefor. For equipment owned, furnished, or rented by the Contractor, no cost therefor shall be recognized in excess of the rental rates established by distributors or equipment rental agencies in the locality where the work is performed.

3-1.01E(4) Markups

When a change order increases the cost of the work, the Contractor may add the following maximum markups to the actual costs of labor, materials, or equipment rental:

- 33 percent for labor;
- 15 percent for materials; and
- 15 percent for equipment rental.

The above markups include full compensation for bonds, profit and overhead.

When a change order decreases the cost of the work, the reduction in cost shall include a 5 percent markup on the estimated cost for furnishing the labor, materials and equipment which would have been used on the work had the change order not been issued.

When a change order involves both added work and deleted work, the markup or markups to be used shall be as follows:

The actual costs of labor, materials, and equipment rental for added and deleted work shall be calculated separately without adding markups. If the difference between the calculated costs for labor results in an increased cost, a markup of 33 percent shall be applied to the increased cost. If the difference between the calculated costs of materials or equipment rental results in an increased cost, a markup of 15 percent shall be applied to the increased costs of materials or equipment rental, as the case may be. If the difference between the calculated costs for labor, materials or equipment rental results in a decreased cost, a markup of 5 percent shall be applied to the decreased costs of labor, materials or equipment rental, as the case may be.

When added or deleted work is performed by an authorized subcontractor, approved in conformance with the provisions in Section 1-1.05, "Required Listing of Proposed Subcontractors," of the Instructions to Bidders, an additional 5 percent will be added to the total cost of the work including all markups specified in this Section 3-1.01E(4). The additional 5 percent markup shall reimburse the Contractor for additional administrative costs, and no other additional payment will be made by reason of performance of the work by a subcontractor.

3-1.01E(5) General Limitation

In no event shall any actual cost for added work be recognized in excess of market values prevailing at the time of the change, unless the Contractor can establish to the satisfaction of the Engineer that the Contractor investigated all possible means of obtaining the added work at prevailing market values and that the excess cost could not be avoided by the Contractor. The Engineer will determine the necessity for incurring the costs enumerated above, and as to whether they are directly required for the performance of the changed work. Lump sum quotations may be accepted at the option of the Engineer. When a change order deletes work from the contract, the computation of the cost thereof shall be the values which prevailed at the time bids for the work were opened.

When work under this Section 3 is performed by forces other than the Contractor's organization, no additional payment will be made by the State by reason of the performance of the work by a subcontractor or other forces, except as provided elsewhere in this Section 3.

SECTION 4 CONTROL OF MATERIALS

4-1.01 MATERIALS

The Contractor shall furnish all materials required to complete the work, except materials that are designated in the special provisions to be furnished by the State and materials furnished by the State in conformance with Section 3, "Changes in the Work," of these General Conditions.

Unless otherwise specified in the special provisions, materials furnished by the Contractor for incorporation into the work shall be new. When the quality or kind of materials, articles, or equipment is not specifically indicated, then the quality or kind thereof shall be similar to those which are indicated.

Articles or materials to be incorporated in the work shall be stored in such a manner as to insure the preservation of their quality and fitness for the work, and to facilitate inspection.

All materials which do not conform to the requirements of the plans and special provisions, as determined by the Engineer, will be rejected whether in place or not. Rejected material shall be removed immediately from the site of the work, unless otherwise permitted by the Engineer. No rejected material, the defects of which have been subsequently corrected, shall be used in the work, unless approval in writing has been given by the Engineer. Upon failure of the Contractor to comply promptly with any order of the Engineer made under these provisions, the Engineer shall have authority to cause the removal and replacement of rejected material and to deduct the cost thereof from any moneys due or to become due the Contractor.

Manufacturers' warranties, guaranties, instruction sheets and parts lists, which are furnished with certain materials incorporated in the work, shall be delivered to the Engineer before acceptance of the contract.

Unless otherwise designated in the special provisions, materials furnished by the State will be delivered to the job site. Materials furnished by the State that are designated in the special provisions as available at locations other than the job site shall be hauled to the site of the work by the Contractor at his expense, including any necessary loading and unloading that may be involved.

The Contractor will be held responsible for all materials furnished to him, and he shall pay all demurrage and storage charges. State-furnished materials lost or damaged from any cause whatsoever shall be replaced by the Contractor. The Contractor will be liable to the Department for the cost of replacing State-furnished material and those costs may be deducted from any moneys due or to become due the Contractor.

4-1.02 PRODUCT AND REFERENCE STANDARDS

When descriptive catalog designations, including manufacturer's name, product brand name, or model number are referred to in the contract documents, those designations shall be considered as being those found in industry publications in effect on the day the Notice to Contractors for the work is dated.

When standards or test designations are referred to in the contract documents by specific date of issue, they shall be considered a part of the contract. When those references do not bear a date of issue, the edition in effect on the day the Notice to Contractors for the work is dated shall be considered as part of the contract.

4-1.03 SAMPLING AND TESTING OF MATERIALS

Unless otherwise specified, all tests shall be performed in conformance with the methods used by the Department of Transportation and shall be made by the Engineer or his designated representative.

The Department has developed methods for testing the quality of materials and work. These methods are identified by number and are referred to as California Test. Up to five copies of individual California Tests are available at the Division of New Technology, Materials and Research, located at 5900 Folsom Boulevard, (P.O. Box 19128), Sacramento, CA 95819, and will be furnished to interested persons upon request. If a complete set of California Test Methods is desired, it can be purchased from the Department's Office of Business Management, Materiel Operations Branch, 1900 Royal Oaks Drive, Sacramento, CA 95815.

Whenever a reference is made in the special provisions to a California Test by number, it shall mean the California Test in effect on the day the Notice to Contractors for the work is dated.

Whenever the special provisions provide an option between 2 or more tests, the Engineer will determine the test method to be used.

Whenever a specification, manual, or test designation provides for test reports (such as certified mill test reports) from the manufacturer, copies of those reports, identified as to the lot of material, shall be furnished to the Engineer. The manufacturer's test reports shall supplement the inspection, sampling and testing provisions of this Section 4-1.03 and shall not constitute a waiver of the State's right to inspect. When material which cannot be identified with specific test reports is proposed for use, the Engineer may, at his discretion, select random samples from the lot for testing. Testing specimens from the random samples, including those required for retest, shall be prepared in conformance with the referenced specification and furnished by the Contractor at his expense. The number of samples and test specimens shall be entirely at the discretion of the Engineer.

When requested by the Engineer, the Contractor shall furnish, without charge, samples of all materials entering into the work, and no material shall be used prior to approval by the Engineer, except as provided in Section 4-1.04, "Certificates of Compliance," of these General Conditions.

4-1.035 TESTING BY CONTRACTOR

The Contractor shall be responsible for controlling the quality of the material entering the work and of the work performed, and shall perform testing as necessary to ensure quality control. The test methods used for quality control testing by the Contractor shall be as determined by the Contractor. The results of those quality control tests shall be made available to the Engineer upon request. Contractor performed quality control tests are for the Contractor's use in controlling the work and will not be accepted for use as acceptance tests.

4-1.04 CERTIFICATES OF COMPLIANCE

A Certificate of Compliance shall be furnished prior to the use of any materials for which the special provisions require that a Certificate of Compliance be furnished. In addition, the Engineer may permit the use of certain materials or assemblies prior to sampling and testing if accompanied by a Certificate of Compliance. The certificate shall be signed by the manufacturer of the material or the manufacturer of assembled materials and shall state that the materials involved comply in all respects with the requirements of the special provisions. A Certificate of Compliance shall be furnished with each lot of such materials delivered to the work and the lot so certified shall be clearly identified in the certificate.

Materials used on the basis of a Certificate of Compliance may be sampled and tested at any time. The fact that material is used on the basis of a Certificate of Compliance shall not relieve the Contractor of responsibility for incorporating material in the work which conforms to the requirements of the plans and special provisions and any material not conforming to those requirements will be subject to rejection whether in place or not.

The Department reserves the right to refuse to permit the use of material on the basis of a Certificate of Compliance.

The form of the Certificate of Compliance and its disposition shall be as directed by the Engineer.

SECTION 5

LEGAL RELATIONS AND RESPONSIBILITIES

5-1.01 LAWS TO BE OBSERVED

The Contractor shall keep informed of and observe, and comply with and cause all of his agents and employees to observe and comply with all prevailing Federal and State laws, and rules and regulations made pursuant to the Federal and State laws, and county and municipal ordinances, and regulations, which in any way affect the conduct of the work of the contract. If any conflict arises between provisions of the contract and any laws above referred to, the Contractor shall notify the Engineer at once in writing. The Contractor shall protect and indemnify the State or any of its officers, agents, and servants against any claim or liability arising from or based on the violation of any law, rule, or regulation, whether by the Contractor or the Contractor's agents or employees.

5-1.01A Hours of Labor

Eight hours labor constitutes a legal day's work. The Contractor or any subcontractor under the Contractor shall forfeit, as a penalty to the State of California, \$25 for each worker employed in the execution of the contract by the respective Contractor or subcontractor for each calendar day during which that worker is required or permitted to work more than 8 hours in any one calendar day and 40 hours in any one calendar week in violation of the provisions of the Labor Code, and in particular, Section 1810 to Section 1815, thereof, inclusive, except that work performed by employees of Contractors in excess of 8 hours per day, and 40 hours during any one week, shall be permitted upon compensation for all hours worked in excess of 8 hours per day at not less than one and one-half times the basic rate of pay, as provided in Section 1815 thereof.

5-1.01B Labor Nondiscrimination

Attention is directed to Section 1735 of the Labor Code, which reads as follows:

"No discrimination shall be made in the employment of persons upon public works because of the race, religious creed, color, national origin, ancestry, physical handicap, medical condition, marital status, or sex of such persons, except as provided in Section 12940 of the Government Code and every contractor for public works violating this section is subject to all the penalties imposed for a violation of this chapter."

Attention is directed to the following "Nondiscrimination Clause" that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations:

NONDISCRIMINATION CLAUSE

1. During the performance of this contract, contractor and its subcontractors shall not unlawfully discriminate against any employee or applicant for employment because of race, religion, color, national origin, ancestry, physical handicap, medical condition, marital status, age (over 40) or sex. Contractors and subcontractors shall ensure that the evaluation and treatment of their employees and applicants for employment are free of such discrimination. Contractors and subcontractors shall comply with the provisions of the Fair Employment and Housing Act (Gov. Code, Section 12990 et seq.) and the applicable regulations promulgated thereunder (California Code of Regulations, Title 2, Section 7285.0 et seq.). The applicable regulations of the Fair Employment and Housing Commission implementing Government Code, Section 12990, set forth in Chapter 5 of Division 4 of Title 2 of the California Code of Regulations are incorporated into this contract by reference and made a part hereof as if set forth in full. Contractor and its subcontractors shall give written notice of their obligations under this clause to labor organizations with which they have a collective bargaining or other agreement.
2. This Contractor shall include the nondiscrimination and compliance provisions of this clause in all subcontracts to perform work under the contract.

**STANDARD CALIFORNIA NONDISCRIMINATION CONSTRUCTION
CONTRACT SPECIFICATIONS (GOVERNMENT CODE, SECTION 12990)**

These specifications are applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth herein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of \$5,000 or more.

1. As used in the specifications:

- a. "Administrator" means Administrator, Office of Compliance Programs, California Department of Fair Employment and Housing, or any person to whom the Administrator delegates authority;
 - b. "Minority" includes:
 - (i) Black (all persons having primary origins in any of the black racial groups of Africa, but not of Hispanic origin);
 - (ii) Hispanic (all persons of primary culture or origin in Mexico, Puerto Rico, Cuba, Central or South America or other Spanish derived culture or origin regardless of race);
 - (iii) Asian/Pacific Islander (all persons having primary origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent or the Pacific Islands); and
 - (iv) American Indian/Alaskan Native (all persons having primary origins in any of the original peoples of North America and who maintain culture identification through tribal affiliation or community recognition).
2. Whenever the contractor or any subcontractor subcontracts a portion of the work, it shall physically include in each subcontract of \$5,000 or more the nondiscrimination clause in this contract directly or through incorporation by reference. Any subcontract for work involving a construction trade shall also include the Standard California Construction Contract Specifications, either directly or through incorporation by reference.
 3. The contractor shall implement the specific nondiscrimination standards provided in paragraphs 6(a) through (e) of these specifications.
 4. Neither the provisions of any collective bargaining agreement, nor the failure by a union with whom the contractor has a collective bargaining agreement, to refer either minorities or women shall excuse the contractor's obligations under these specifications, Government Code, Section 12990, or the regulations promulgated pursuant thereto.
 5. In order for the nonworking training hours of apprentices and trainees to be counted, such apprentices and trainees must be employed by the contractor during the training period, and the contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor or the California Department of Industrial Relations.
 6. The contractor shall take specific actions to implement its nondiscrimination program. The evaluation of the contractor's compliance with these specifications shall be based upon its effort to achieve maximum results from its actions. The contractor must be able to demonstrate fully its efforts under Steps a. through e. below:
 - a. Ensure and maintain a working environment free of harassment, intimidation, and coercion at all sites, and at all facilities at which the contractor's employees are assigned to work. The contractor, where possible, will assign two or more women to each construction project. The contractor shall specifically ensure that all foremen, superintendents, and other on-site supervisory personnel are aware of and carry out the contractor's obligations to maintain such a working environment, with specific attention to minority or female individuals working at such sites or in such facilities.
 - b. Provide written notification within seven days to the director of DFEH when the union or unions with which the Contractor has a collective bargaining agreement has not referred to the Contractor a minority person or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.
 - c. Disseminate the Contractor's equal employment opportunity policy by providing notice of the policy to unions and training, recruitment and outreach programs and requesting their cooperation in assisting the Contractor to meet its obligations; and by posting the company policy on bulletin boards accessible to all employees at each location where construction work is performed.
 - d. Ensure all personnel making management and employment decisions regarding hiring, assignment, layoff, termination, conditions of work, training, rates of pay or other employment decisions, including all supervisory personnel, superintendents, general foremen, on-site foremen, etc., are aware of the Contractor's equal employment opportunity policy and obligations, and discharge their responsibilities accordingly.
 - e. Ensure that seniority practices, job classifications, work assignments and other personnel practices, do not have a discriminatory effect by continually monitoring all personnel and employment related activities to ensure that the equal employment opportunity policy and the Contractor's obligations under these specifications are being carried out.

7. Contractors are encouraged to participate in voluntary associations which assist in fulfilling their equal employment opportunity obligations. The efforts of a contractor association, joint contractor-union, contractor-community, or other similar group of which the contractor is a member and participant, may be asserted as fulfilling any one or more of its obligations under these specifications provided that the contractor actively participates in the group, makes every effort to assure that the group has a positive impact on the employment of minorities and women in the industry, ensures that the concrete benefits of the program are reflected in the Contractor's minority and female workforce participation, and can provide access to documentation which demonstrates the effectiveness of actions taken on behalf of the Contractor. The obligation to comply, however, is the Contractor's.
8. The Contractor is required to provide equal employment opportunity for all minority groups, both male and female, and all women, both minority and non-minority. Consequently, the Contractor may be in violation of the Fair Employment and Housing Act (Gov. Code, Section 12990 et seq.) if a particular group is employed in a substantially disparate manner.
9. Establishment and implementation of a bona fide affirmative action plan pursuant to Section 8104 (b) of this Chapter shall create a rebuttal presumption that a contractor is in compliance with the requirements of Section 12990 of the Government Code and its implementing regulations.
10. The Contractor shall not use the nondiscrimination standards to discriminate against any person because of race, color, religion, sex, national origin, ancestry, physical handicap, medical condition, marital status or age over 40.
11. The Contractor shall not enter into any subcontract with any person or firm decertified from state contracts pursuant to Government Code Section 12990.
12. The Contractor shall carry out such sanctions and penalties for violation of these specifications and the nondiscrimination clause, including suspension, termination and cancellation of existing subcontracts as may be imposed or ordered pursuant to Government Code Section 12990 and its implementing regulations by the awarding agency. Any Contractor who fails to carry out such sanctions and penalties shall be in violation of these specifications and Government Code Section 12990.
13. The Contractor shall designate a responsible official to monitor all employment related activity to ensure that the company equal employment opportunity policy is being carried out, to submit reports relating to the provisions hereof as may be required by OCP and to keep records. Records shall at least include for each employee the name, address, telephone numbers, construction trade, union affiliation if any, employee identification number when assigned, social security number, race, sex, status, (e.g., mechanic, apprentice trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in any easily understandable and retrievable form; however, to the degree that existing records satisfy this requirement, contractors shall not be required to maintain separate records.

NOTE: Authority cited: Sections 12935(a) and 12990(d), Government Code. Reference: Section 12990, Government Code.

5-1.01C Prevailing Wage

The Contractor and any subcontractor under the Contractor shall comply with Labor Code Sections 1774 and 1775. Pursuant to Section 1775, the Contractor and any subcontractor under the Contractor shall forfeit to the State or political subdivision on whose behalf the contract is made or awarded a penalty of not more than fifty dollars (\$50) for each calendar day, or portion thereof, for each worker paid less than the prevailing rates as determined by the Director of Industrial Relations for the work or craft in which the worker is employed for any public work done under the contract by the Contractor or by any subcontractor under the Contractor in violation of the provisions of the Labor Code and in particular, Labor Code Sections 1770 to 1780, inclusive. The amount of this forfeiture shall be determined by the Labor Commissioner and shall be based on consideration of the mistake, inadvertence, or neglect of the Contractor or subcontractor in failing to pay the correct rate of prevailing wages, or the previous record of the Contractor or subcontractor in meeting their respective prevailing wage obligations, or the willful failure by the Contractor or subcontractor to pay the correct rates of prevailing wages. A mistake, inadvertence, or neglect in failing to pay the correct rate of prevailing wages is not excusable if the Contractor or subcontractor had knowledge of their obligations under the Labor Code. In addition to the penalty and pursuant to Labor Code Section 1775, the difference between the prevailing wage rates and the amount paid to each worker for each calendar day or portion thereof for which each worker was paid less than the prevailing wage rate shall be paid to each worker by the Contractor or subcontractor. If a worker employed by a subcontractor on a public works project is not paid the general prevailing per diem wages by the subcontractor, the prime contractor of the project is not liable for the penalties described above unless the prime contractor had knowledge of that failure of the subcontractor to pay the specified

prevailing rate of wages to those workers or unless the prime contractor fails to comply with all of the following requirements:

1. The contract executed between the contractor and the subcontractor for the performance of work on the public works project shall include a copy of the provisions of Sections 1771, 1775, 1776, 1777.5, 1813, and 1815 of the Labor Code.
2. The contractor shall monitor the payment of the specified general prevailing rate of per diem wages by the subcontractor to the employees, by periodic review of the certified payroll records of the subcontractor.
3. Upon becoming aware of the subcontractor's failure to pay the specified prevailing rate of wages to the subcontractor's workers, the contractor shall diligently take corrective action to halt or rectify the failure, including, but not limited to, retaining sufficient funds due the subcontractor for work performed on the public works project.
4. Prior to making final payment to the subcontractor for work performed on the public works project, the contractor shall obtain an affidavit signed under penalty of perjury from the subcontractor that the subcontractor has paid the specified general prevailing rate of per diem wages to the subcontractor's employees on the public works project and any amounts due pursuant to Section 1813 of the Labor Code.

Pursuant to Section 1775 of the Labor Code, the Division of Labor Standards Enforcement shall notify the Contractor on a public works project within 15 days of the receipt by the Division of Labor Standards Enforcement of a complaint of the failure of a subcontractor on that public works project to pay workers the general prevailing rate of per diem wages. If the Division of Labor Standards Enforcement determines that employees of a subcontractor were not paid the general prevailing rate of per diem wages and if the Department did not retain sufficient money under the contract to pay those employees the balance of wages owed under the general prevailing rate of per diem wages, the contractor shall withhold an amount of moneys due the subcontractor sufficient to pay those employees the general prevailing rate of per diem wages if requested by the Division of Labor Standards Enforcement. The Contractor shall pay any money retained from and owed to a subcontractor upon receipt of notification by the Division of Labor Standards Enforcement that the wage complaint has been resolved. If notice of the resolution of the wage complaint has not been received by the Contractor within 180 days of the filing of a valid notice of completion or acceptance of the public works project, whichever occurs later, the Contractor shall pay all moneys retained from the subcontractor to the Department. These moneys shall be retained by the Department pending the final decision of an enforcement action.

Pursuant to the provisions of Section 1773 of the Labor Code, the Department has obtained the general prevailing rate of wages (which rate includes employer payments for health and welfare, pension, vacation, travel time, and subsistence pay as provided for in Section 1773.8 of the Labor Code, apprenticeship or other training programs authorized by Section 3093 of the Labor Code, and similar purposes) applicable to the work to be done, for straight time, overtime, Saturday, Sunday and holiday work. The holiday wage rate listed shall be applicable to all holidays recognized in the collective bargaining agreement of the particular craft, classification or type of workmen concerned. The general prevailing wage rates and any applicable changes to these wage rates are available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated. For work situated in District 9, the wage rates are available at the Labor Compliance Office at the offices of the District Director of Transportation for District 6, located at Fresno. General prevailing wage rates are also available from the California Department of Industrial Relations' internet web site at: <http://www.dir.ca.gov>.

The wage rates determined by the Director of Industrial Relations for the project refer to expiration dates. Prevailing wage determinations with a single asterisk after the expiration date are in effect on the date of advertisement for bids and are good for the life of the contract. Prevailing wage determinations with double asterisks after the expiration date indicate that the wage rate to be paid for work performed after this date has been determined. If work is to extend past this date, the new rate shall be paid and incorporated in the contract. The Contractor shall contact the Department of Industrial Relations as indicated in the wage rate determinations to obtain predetermined wage changes.

Pursuant to Section 1773.2 of the Labor Code, general prevailing wage rates shall be posted by the Contractor at a prominent place at the site of the work.

Changes in general prevailing wage determinations which conform to Labor Code Section 1773.6 and Title 8 California Code of Regulations Section 16204 shall apply to the project when issued by the Director of Industrial Relations at least 10 days prior to the date of the Notice to Contractors for the project.

The State will not recognize any claim for additional compensation because of the payment by the Contractor of any wage rate in excess of the prevailing wage rate set forth in the contract. The possibility of wage increases is one of the elements to be considered by the Contractor in determining the bid, and will not under any circumstances be considered as the basis of a claim against the State on the contract.

5-1.01D Travel And Subsistence Payments

Attention is directed to the requirements in Section 1773.8 of the Labor Code. The Contractor shall make travel and subsistence payments to each workman, needed to execute the work, in conformance with the requirements in Labor Code Section 1773.8.

5-1.01E Payroll Records

Attention is directed to the provisions of Labor Code Section 1776, a portion of which is quoted below. Regulations implementing Labor Code Section 1776 are located in Sections 16016 through 16019 and Sections 16207.10 through 16207.19 of Title 8, California Code of Regulations.

"1776. (a) Each contractor and subcontractor shall keep accurate payroll records, showing the name, address, social security number, work classification, straight time and overtime hours worked each day and week, and the actual per diem wages paid to each journeyman, apprentice, worker, or other employee employed by him or her in connection with the public work. Each payroll record shall contain or be verified by a written declaration that it is made under penalty of perjury, stating both of the following:

- (1) The information contained in the payroll record is true and correct.
- (2) The employer has complied with the requirements of Sections 1771, 1811, and 1815 for any work performed by his or her employees on the public works project.

"(b) The payroll records enumerated under subdivision (a) shall be certified and shall be available for inspection at all reasonable hours at the principal office of the contractor on the following basis:

- (1) A certified copy of an employee's payroll record shall be made available for inspection or furnished to the employee or his or her authorized representative on request.
- (2) A certified copy of all payroll records enumerated in subdivision (a) shall be made available for inspection or furnished upon request to a representative of the body awarding the contract, the Division of Labor Standards Enforcement, and the Division of Apprenticeship Standards of the Department of Industrial Relations.
- (3) A certified copy of all payroll records enumerated in subdivision (a) shall be made available upon request by the public for inspection or for copies thereof. However, a request by the public shall be made through either the body awarding the contract, the Division of Apprenticeship Standards, or the Division of Labor Standards Enforcement. If the requested payroll records have not been provided pursuant to paragraph (2), the requesting party shall, prior to being provided the records, reimburse the costs of preparation by the contractor, subcontractors, and the entity through which the request was made. The public shall not be given access to the records at the principal office of the contractor.

"(c) The certified payroll records shall be on forms provided by the Division of Labor Standards Enforcement or shall contain the same information as the forms provided by the division.

"(d) A contractor or subcontractor shall file a certified copy of the records enumerated in subdivision (a) with the entity that requested the records within 10 days after receipt of a written request.

"(e) Any copy of records made available for inspection as copies and furnished upon request to the public or any public agency by the awarding body, the Division of Apprenticeship Standards, or the Division of Labor Standards Enforcement shall be marked or obliterated in a manner so as to prevent disclosure of an individual's name, address, and social security number. The name and address of the contractor awarded the contract or the subcontractor performing the contract shall not be marked or obliterated.

"(f) The contractor shall inform the body awarding the contract of the location of the records enumerated under subdivision (a), including the street address, city and county, and shall, within five working days, provide a notice of a change of location and address.

"(g) The contractor or subcontractor shall have 10 days in which to comply subsequent to receipt of a written notice requesting the records enumerated in subdivision (a). In the event that the contractor or subcontractor fails to comply within the 10-day period, he or she shall, as a penalty to the state or political subdivision on whose behalf the contract is made or awarded, forfeit twenty-five dollars (\$25) for each calendar day, or portion thereof, for each worker, until strict compliance is effectuated. Upon the request of the Division of Apprenticeship Standards or the Division of Labor Standards Enforcement, these penalties shall be withheld from progress payments then due. A contractor is not subject to a penalty assessment pursuant to this section due to the failure of a subcontractor to comply with this section."

The penalties specified in subdivision (g) of Labor Code Section 1776 for noncompliance with the provisions of Section 1776 may be deducted from any moneys due or which may become due to the Contractor.

A copy of all payrolls shall be submitted weekly to the Engineer. Payrolls shall contain the full name, address and social security number of each employee, the employee's correct classification, rate of pay, daily and weekly number of hours worked, itemized deductions made and actual wages paid. They shall also indicate apprentices and ratio of apprentices to journeymen. The employee's address and social security number need only appear on the first payroll on which that name appears. The payroll shall be accompanied by a "Statement of Compliance" signed by the employer or the employer's agent indicating that the payrolls are correct and complete and that the wage rates contained therein are not less than those required by the contract. The "Statement of Compliance" shall be on forms furnished by the Department or on any form with identical wording. The Contractor shall be responsible for the submission of copies of payrolls of all subcontractors.

If by the 15th of the month, the Contractor has not submitted satisfactory payrolls for all work performed during the monthly period ending on or before the 1st of that month, the Department will retain an amount equal to 10 percent of the estimated value of the work performed during the month from the next monthly estimate, except that this retention shall not exceed \$10,000 nor be less than \$1,000. Retentions for failure to submit satisfactory payrolls shall be additional to all other retentions provided for in the contract. The retention for failure to submit payrolls for any monthly period will be released for payment on the monthly estimate for partial payments next following the date that all the satisfactory payrolls for which the retention was made are submitted.

The Contractor and each subcontractor shall preserve their payroll records for a period of 3 years from the date of completion of the contract.

5-1.01F Trench Safety

Attention is directed to the provisions of Section 6705 of the Labor Code concerning trench excavation safety plans.

The Construction Safety Orders of the Division of Occupational Safety and Health shall apply to all excavations. For all excavations 1.5 m or more in depth, the Contractor shall submit to the Engineer a detailed plan showing the design and details of the protective systems to be provided for worker protection from the hazard of caving ground during excavation. The detailed plan shall include any tabulated data and any design calculations used in the preparation of the plan. Excavation shall not begin until the detailed plan has been reviewed and approved by the Engineer.

Detailed plans of protective systems for which the Construction Safety Orders require design by a registered professional engineer shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California, and shall include the soil classification, soil properties, soil design calculations that demonstrate adequate stability of the protective system, and any other design calculations used in the preparation of the plan.

No plan shall allow the use of a protective system less effective than that required by the Construction Safety Orders.

If the detailed plan includes designs of protective systems developed only from the allowable configurations and slopes, or Appendices, contained in the Construction Safety Orders, the plan shall be submitted at least 5 days before the Contractor intends to begin excavation. If the detailed plan includes designs of protective systems developed from tabulated data, or designs for which design by a registered professional engineer is required, the plan shall be submitted at least 3 weeks before the Contractor intends to begin excavation.

In addition to these provisions detailed plans of the protective systems for excavations on or affecting railroad property will be reviewed for adequacy of protection provided for railroad facilities, property, and traffic. These plans for excavations on or affecting railroad property shall be submitted at least 9 weeks before the Contractor intends to begin excavation requiring the protective systems. Approval by the Engineer of the detailed plans for the protective systems will be contingent upon the plans being satisfactory to the railroad company involved.

5-1.01G Apprentices

Attention is directed to Sections 1777.5, 1777.6 and 1777.7 of the California Labor Code and Title 8, California Code of Regulations Section 200 et seq. To ensure compliance and complete understanding of the law regarding apprentices, and specifically the required ratio thereunder, each contractor or subcontractor should, where some question exists, contact the Division of Apprenticeship Standards, 455 Golden Gate Avenue, San Francisco, CA 94102, or one of its branch offices prior to commencement of work on the public works contract. Responsibility for compliance with this section lies with the prime Contractor.

It is State policy to encourage the employment and training of apprentices on public works contracts as may be permitted under local apprenticeship standards.

5-1.01H Fair Labor Standards Act

The attention of bidders is invited to the fact that the State of California, Department of Transportation, has been advised by the Wage and Hour Division, U.S. Department of Labor, that contractors engaged in construction work are required to meet the provisions of the Fair Labor Standards Act of 1938 and as amended (52 Stat. 1060).

5-1.01I Workers' Compensation

Pursuant to the requirements in Section 1860 of the Labor Code, the Contractor will be required to secure the payment of workers' compensation to the Contractor's employees in conformance with the requirements in Section 3700 of the Labor Code.

Prior to the commencement of work, the Contractor shall sign and file with the Engineer a certification in the following form:

"I am aware of the provisions of Section 3700 of the Labor Code which require every employer to be insured against liability for workers' compensation or to undertake self-insurance in accordance with the provisions of that code, and I will comply with the provisions of Section 3700 before commencing the performance of the work of this contract."

This certification is included in the contract, and signature and return of the contract as provided in Section 2-1.04, "Execution of Contract," of the Instructions to Bidders shall constitute signing and filing of the certificate.

5-1.01J Air Pollution Control

The Contractor shall comply with all air pollution control rules, regulations, ordinances and statutes which apply to any work performed pursuant to the contract, including any air pollution control rules, regulations, ordinances and statutes, specified in Section 11017 of the Government Code.

Unless otherwise provided in the special provisions, material to be disposed of shall not be burned, either inside or outside the premises.

5-1.01K Use Of Pesticides

The Contractor shall comply with all rules and regulations of the Department of Food and Agriculture, the Department of Health, the Department of Industrial Relations and all other agencies which govern the use of pesticides required in the performance of the work on the contract.

Pesticides shall include but shall not be limited to herbicides, insecticides, fungicides, rodenticides, germicides, nematocides, bactericides, inhibitors, fumigants, defoliant, desiccants, soil sterilants, and repellents.

Any substance or mixture of substances intended for preventing, repelling, mitigating, or destroying weeds, insects, diseases, rodents, or nematodes and any substance or mixture of substances intended for use as a plant regulator, defoliant or desiccant shall be considered a pesticide.

5-1.01L Sound Control Requirements

The Contractor shall comply with all local sound control and noise level rules, regulations and ordinances which apply to any work performed pursuant to the contract.

Each internal combustion engine, used for any purpose on the job or related to the job, shall be equipped with a muffler of a type recommended by the manufacturer. No internal combustion engine shall be operated on the project without the muffler.

5-1.01M Environmental Clearances

The Department will obtain all environmental clearances and authorizations necessary for the project as set forth in the plans and specifications. The Contractor shall comply with the provisions, including giving notices during construction when required, of these authorizations. In the event the obtaining of these authorizations delays completion of all or any portion of the work, an extension of time determined pursuant to the provisions in Section 6-1.08, "Liquidated Damages," of these General Conditions will be granted and the Contractor shall not be entitled to any additional compensation because of the delays.

5-1.01N Permits And Licenses

The Contractor shall procure all permits and licenses, pay all charges and fees, and give all notices necessary and incident to the due and lawful prosecution of the work.

The Environmental Quality Act (Public Resources Code, Sections 21000 to 21176, inclusive) may be applicable to permits, licenses and other authorizations which the Contractor must obtain from local agencies in connection with performing the work of the contract. The Contractor shall comply with the provisions of those statutes in obtaining the permits, licenses and other authorizations and they shall be obtained in sufficient time to prevent delays to the work.

In the event that the Department has obtained permits, licenses or other authorizations, applicable to the work, in conformance with the requirements in the Environmental Quality Act, the Contractor shall comply with the provisions of those permits, licenses and other authorizations.

5-1.01O Assignment Of Antitrust Actions

The Contractor's attention is directed to the following requirements in Public Contract Code 7103.5 and Government Code Sections 4553 and 4554, which shall be applicable to the Contractor and the Contractor's subcontractors:

"In entering into a public works contract or a subcontract to supply goods, services, or materials pursuant to a public works contract, the contractor or subcontractor offers and agrees to assign to the awarding body all rights, title, and interest in and to all causes of action it may have under Section 4 of the Clayton Act (15 U.S.C. Sec. 15) or under the Cartwright Act (Chapter 2 (commencing with Section 16700) of Part 2 of Division 7 of the Business and Professions Code), arising from purchases of goods, services, or materials pursuant to the public works contract or the subcontract. This assignment shall be made and become effective at the time the awarding body tenders final payment to the contractor, without further acknowledgement by the parties."

"If an awarding body or public purchasing body receives, either through judgment or settlement, a monetary recovery for a cause of action assigned under this chapter, the assignor shall be entitled to receive reimbursement for actual legal costs incurred and may, upon demand, recover from the public body any portion of the recovery, including treble damages, attributable to overcharges that were paid by the assignor but were not paid by the public body as part of the bid price, less the expenses incurred in obtaining that portion of the recovery.

"Upon demand in writing by the assignor, the assignee shall, within one year from such demand, reassign the cause of action assigned under this part if the assignor has been or may have been injured by the violation of law for which the cause of action arose and (a) the assignee has not been injured thereby, or (b) the assignee declines to file a court action for the cause of action."

5-1.01P Safety And Health Provisions

The Contractor shall conform to all applicable occupational safety and health standards, rules, regulations and orders established by the State of California.

Working areas utilized by the Contractor to perform work during the hours of darkness, shall be lighted to conform to the minimum illumination intensities established by California Division of Occupational Safety and Health Construction Safety Orders.

All lighting fixtures shall be mounted and directed in a manner precluding glare to approaching traffic.

5-1.01Q Suits To Recover Penalties And Forfeitures

Attention is directed to Sections 1730 to 1733, inclusive, of the Labor Code concerning suits to recover amounts withheld from payment for failure to comply with requirements of the Labor Code or contract provisions based on those laws.

Those sections provide that a suit on the contract for alleged breach thereof in not making the payment is the exclusive remedy of the Contractor or the Contractor's assignees with reference to amounts withheld for those penalties or forfeitures; and that the suit must be commenced and actual notice thereof received by the awarding authority prior to 90 days after completion of the contract and the formal acceptance of the job.

Submission of a claim under Section 7-1.07, "Final Payment and Claims," of these General Conditions for the amounts withheld from payment for those penalties and forfeitures is not a prerequisite for those suits and these claims will not be considered.

5-1.01R Water Pollution

The Contractor shall exercise every reasonable precaution to protect streams, lakes, reservoirs, bays, and coastal waters from pollution with fuels, oils, bitumens, calcium chloride and other harmful materials and shall conduct and schedule operations so as to avoid or minimize muddying and silting of streams, lakes, reservoirs, bays and coastal waters. Care shall be exercised to preserve roadside vegetation beyond the limits of construction.

Water pollution control work is intended to provide prevention, control, and abatement of water pollution to streams, waterways, and other bodies of water, and shall consist of constructing those facilities which may be shown on the plans, specified herein or in the special provisions, or directed by the Engineer.

In order to provide effective and continuous control of water pollution it may be necessary for the Contractor to perform the contract work in small or multiple units, on an out of phase schedule, and with modified construction procedures. The Contractor shall provide temporary water pollution control measures, including but not limited to, dikes, basins, ditches, and applying straw and seed, which become necessary as a result of the Contractor's operations. The Contractor shall coordinate water pollution control work with all other work done on the contract.

Before starting any work on the project, the Contractor shall submit, for acceptance by the Engineer, a program to control water pollution effectively during construction of the project. The program shall show the schedule for the erosion control work included in the contract and for all water pollution control measures which the Contractor proposes to take in connection with construction of the project to minimize the effects of the operations upon adjacent streams and other bodies of water. The Contractor shall not perform any clearing and grubbing or earthwork on the project, other than that specifically authorized in writing by the Engineer, until the program has been accepted.

If the measures being taken by the Contractor are inadequate to control water pollution effectively, the Engineer may direct the Contractor to revise the operations and the water pollution control program. The directions will be in writing and will specify the items of work for which the Contractor's water pollution control measures are inadequate. No further work shall be performed on those items until the water pollution control measures are adequate and, if also required, a revised water pollution control program has been accepted.

The Engineer will notify the Contractor of the acceptance or rejection of any submitted or revised water pollution control program in not more than 5 working days.

The State will not be liable to the Contractor for failure to accept all or any portion of an originally submitted or revised water pollution control program, nor for any delays to the work due to the Contractor's failure to submit an acceptable water pollution control program.

The Contractor may request the Engineer to waive the requirement for submission of a written program for control of water pollution when the nature of the Contractor's operation is such that erosion is not likely to occur. Waiver of this requirement will not relieve the Contractor from responsibility for compliance with the other provisions of this section. Waiver of the requirement for a written program for control of water pollution will not preclude requiring submittal of a written program at a later time if the Engineer deems it necessary because of the effect of the Contractor's operations.

Unless otherwise approved by the Engineer in writing, the Contractor shall not expose a total area of erodible earth material, which may cause water pollution, exceeding 70 000 m² for each separate location, operation, or spread of equipment before either temporary or permanent erosion control measures are accomplished.

Where erosion which will cause water pollution is probable due to the nature of the material or the season of the year, the Contractor's operations shall be so scheduled that permanent erosion control features will be installed concurrently with or immediately following grading operations.

Nothing in the terms of the contract nor in the provisions in this Section 5-1.01R shall relieve the Contractor of the responsibility for compliance with Sections 5650 and 12015 of the Fish and Game Code, or other applicable statutes relating to prevention or abatement of water pollution.

When borrow material is obtained from other than commercially operated sources, erosion of the borrow site during and after completion of the work shall not result in water pollution. The material source shall be finished, where practicable, so that water will not collect or stand therein.

The requirements of this section shall apply to all work performed under the contract and to all non-commercially operated borrow or disposal sites used for the project.

The Contractor shall also conform to the following provisions:

1. Where working areas encroach on live streams, barriers adequate to prevent the flow of muddy water into streams shall be constructed and maintained between working areas and streams, and during construction of the barriers, muddying of streams shall be held to a minimum.
2. Removal of material from beneath a flowing stream shall not be commenced until adequate means, such as a bypass channel, are provided to carry the stream free from mud or silt around the removal operations.
3. Should the Contractor's operations require transportation of materials across live streams, the operations shall be conducted without muddying the stream. Mechanized equipment shall not be operated in the stream channels of the live streams except as may be necessary to construct crossings or barriers and fills at channel changes.
4. Water containing mud or silt from aggregate washing or other operations shall be treated by filtration, or retention in a settling pond, or ponds, adequate to prevent muddy water from entering live streams.
5. Oily or greasy substances originating from the Contractor's operations shall not be allowed to enter or be placed where they will later enter a live stream.
6. Portland cement or fresh portland cement concrete shall not be allowed to enter flowing water of streams.
7. When operations are completed, the flow of streams shall be returned as nearly as possible to a meandering thread without creating possible future bank erosion, and settling pond sites shall be graded so they will drain and will blend in with the surrounding terrain.
8. Material derived from roadway work shall not be deposited in a live stream channel where it could be washed away by high stream flows.
9. Where there is possible migration of anadromous fish in streams affected by construction on the project, the Contractor shall conduct work operations so as to allow free passage of the migratory fish.

Compliance with the requirements of this section shall in no way relieve the Contractor from the responsibility to comply with the other provisions of the contract, in particular the responsibility for damage and for preservation of property.

5-1.02 PROTECTION AND USE OF PROPERTY

The Contractor shall be responsible for and provide and maintain all proper temporary walks, roads, guards, railings, lights, warning signs, and take precaution at all times to avoid injury or damage to any person or any property, and upon completion of the work, or at other times as directed, restore premises and adjacent property to a proper condition.

The Contractor shall protect adjoining property and nearby buildings, including State buildings, State roads, and public streets or roads, from dust, dirt, debris, or other nuisance arising out of the Contractor's operations or storage practices, and, if ordered by the Engineer, the Contractor shall provide and install suitable safeguards, approved by the Engineer, to protect objects from damage. If any objects are injured or damaged by reason of the Contractor's operations, they shall be replaced or restored at the Contractor's expense. The facilities shall be replaced or restored to a condition as good as when the Contractor entered upon the work, or as good as required by the specifications accompanying the contract, if any of the objects are a part of the work being performed under the contract.

If the Contractor damages any buildings, roads or other property which belong to the State, or any department or agency thereof, then the Engineer, at his option, may retain from the money due under the contract an amount sufficient to insure repair of the damage.

The Engineer may make or cause to be made those temporary repairs that are necessary to restore to service any damaged highway facility. The cost of the repairs shall be borne by the Contractor and may be deducted from any moneys due or to become due to the Contractor under the contract.

The fact that any underground facility is not shown upon the plans shall not relieve the Contractor of the responsibility of protecting underground improvements or facilities. It shall be the Contractor's responsibility, pursuant thereto, to ascertain the location of those underground improvements or facilities, which may be subject to damage by reason of the Contractor's operations.

5-1.03 (BLANK)

5-1.031 Indemnification

With the exception that this section shall in no event be construed to require indemnification by the Contractor to a greater extent than permitted by law, the Contractor shall defend, indemnify and save harmless the State, including its officers, directors, agents (excluding agents who are design professionals), and employees, and each of them (Indemnitees), from any and all claims, demands, causes of action, damages, costs, expenses, actual attorneys' fees, losses or liabilities, in law or in equity, of every kind and nature whatsoever (Claims), arising out of or in connection with the Contractor's performance of this contract for:

- A. Bodily injury including, but not limited to, bodily injury, sickness or disease, emotional injury or death to persons, including, but not limited to, the public, any employees or agents of the Contractor, State, Department, or any other contractor and;
- B. Damage to property of anyone including loss of use thereof;

caused or alleged to be caused in whole or in part by any negligent or otherwise legally actionable act or omission of the Contractor or anyone directly or indirectly employed by the Contractor or anyone for whose acts the Contractor may be liable.

Except as otherwise provided by law, the indemnification provisions above shall apply regardless of the existence or degree of fault of Indemnitees. The Contractor, however, shall not be obligated to indemnify Indemnitees for Claims arising from conduct delineated in Civil Code section 2782. Further, the Contractor's indemnity obligation shall not extend to Claims to the extent they arise from any defective or substandard condition of the roadway which existed at or prior to the time the Contractor commenced work, unless this condition has been changed by the work or the scope of the work requires the Contractor to maintain existing Roadway facilities and the claim arises from the Contractor's failure to maintain. The Contractor's indemnity obligation shall extend to Claims arising after the work is completed and accepted only if these Claims are directly related to alleged acts or omissions of the Contractor which occurred during the course of the work. No inspection by the Department, its employees or agents shall be deemed a waiver by the Department of full compliance with the requirements of this section.

The Contractor's obligation to defend and indemnify shall not be excused because of the Contractor's inability to evaluate liability or because the Contractor evaluates liability and determines that the Contractor is not liable to the claimant. The Contractor will respond within 30 days to the tender of any claim for defense and indemnity by the State, unless this time has been extended by the State. If the Contractor fails to accept or reject a tender of defense and indemnity within 30 days, in addition to any other remedy authorized by law, so much of the money due the Contractor under and by virtue of the contract as shall reasonably be considered necessary by the Department, may be retained by the State until disposition has been made of the claim or suit for damages, or until the Contractor accepts or rejects the tender of defense, whichever occurs first.

With respect to third party claims against the Contractor, the Contractor waives any and all rights of any type to express or implied indemnity against the State, its directors, officers, employees, or agents (excluding agents who are design professionals).

5-1.032 Insurance

Insurance shall conform to the following requirements:

5-1.032A Casualty Insurance

The Contractor shall, at the Contractor's expense, procure and maintain insurance on all of its operations with companies acceptable to the Department as follows. All insurance shall be kept in full force and effect from the beginning of the work through final acceptance by the State. In addition, the Contractor shall maintain completed operations coverage with a carrier acceptable to the Department through the expiration of the patent deficiency in construction statute of repose set forth in Section 337.1 of the Code of Civil Procedure.

5-1.032A(1) Workers' Compensation and Employer's Liability Insurance

Workers' Compensation insurance shall be provided as specified in Section 7-1.01A(6), "Workers' Compensation." Employer's Liability Insurance shall be provided in amounts not less than:

- (a) \$1,000,000 for each accident for bodily injury by accident.
- (b) \$1,000,000 policy limit for bodily injury by disease.
- (c) \$1,000,000 for each employee for bodily injury by disease.

If there is an exposure of injury to the Contractors' employees under the U.S. Longshoremen's and Harbor Workers' Compensation Act, the Jones Act or under laws, regulations or statutes applicable to maritime employees, coverage shall be included for such injuries or claims.

5-1.032A(2) Liability Insurance

The Contractor shall carry General Liability and Umbrella or Excess Liability Insurance covering all operations by or on behalf of the Contractor providing insurance for bodily injury liability, and property damage liability for the limits of liability indicated below and including coverage for:

- (a) premises, operations and mobile equipment
- (b) products and completed operations
- (c) broad form property damage (including completed operations)
- (d) explosion, collapse and underground hazards
- (e) personal injury
- (f) contractual liability

5-1.032A(3) Liability Limits/Additional Insureds

The limits of liability shall be at least:

- (a) \$1,000,000 for each occurrence (combined single limit for bodily injury and property damage).
- (b) \$2,000,000 aggregate for products-completed operations.
- (c) \$2,000,000 general aggregate. This general aggregate limit shall apply separately to the Contractor's work under this Agreement.
- (d) \$5,000,000 umbrella or excess liability. For projects over \$25,000,000 only, an additional \$10,000,000 umbrella or excess liability (for a total of \$15,000,000). Umbrella or excess policy shall include products liability completed operations coverage and may be subject to \$5,000,000 or \$15,000,000 aggregate limits. Further, the umbrella or excess policy shall contain a clause stating that it takes effect (drops down) in the event the primary limits are impaired or exhausted.

The State and the Department, including their officers, directors, agents (excluding agents who are design professionals), and State employees, shall be named as additional insureds under the General Liability and Umbrella Liability Policies with respect to liability arising out of or connected with work or operations performed by or on behalf of the Contractor under this contract. Coverage for those additional insureds shall not extend to liability:

- (1) arising from any defective or substandard condition of the Roadway which existed at or prior to the time the Contractor commenced work, unless that condition has been changed by the work or the scope of the work requires the Contractor to maintain existing Roadway facilities and the claim arises from the Contractor's failure to maintain; or
- (2) for claims occurring after the work is completed and accepted unless these claims are directly related to alleged acts or omissions of the Contractor which occurred during the course of the work; or
- (3) to the extent prohibited by Section 11580.04 of the Insurance Code.

The policy shall stipulate that the insurance afforded the additional insureds shall apply as primary insurance. Any other insurance or self insurance maintained by the Department or State will be excess only and shall not be called upon to contribute with this insurance. Those additional insured coverage shall be provided by a policy provision or by an endorsement providing coverage at least as broad as Additional Insured (Form B) endorsement form CG 2010, as published by the Insurance Services Office (ISO).

5-1.032B Automobile Liability Insurance

The Contractor shall carry automobile liability insurance, including coverage for all owned, hired and non-owned automobiles. The primary limits of liability shall be not less than \$1,000,000 combined single limit each accident for bodily injury and property damage. The umbrella or excess liability coverage required under Section 5-1.032A(3), "Liability Limits/Additional Insureds," shall also apply to automobile liability.

5-1.032C Policy Forms, Endorsements and Certificates

The Contractor's General Liability Insurance shall be provided under Commercial General Liability policy form no. CG0001 as published by the Insurance Services Office (ISO) or under a policy form at least as broad as policy form no. CG0001.

Evidence of insurance in a form acceptable to the Department, including the required "additional insured" endorsements, shall be furnished by the Contractor to the Department at or prior to the pre-construction conference. The evidence of insurance shall provide that there will be no cancellation, lapse, or reduction of coverage without thirty (30) days' prior written notice to the Department. Certificates of Insurance, as evidence of required insurance, for the General Liability, Auto Liability and Umbrella-Excess Liability policies shall set forth deductible amounts applicable to each policy and all exclusions which are added by endorsement to each policy. The Department may expressly allow deductible clauses, which it does not consider excessive, overly broad, or harmful to the interests of the State. Standard ISO form CG 0001 or similar exclusions will be allowed provided they are not inconsistent with the requirements of this section. Allowance of any additional exclusions is at the discretion of the Department. Regardless of the allowance of exclusions or deductions by the Department, the Contractor shall be responsible for any deductible amount and shall warrant that the coverage provided to the Department is consistent with the requirements of this section.

5-1.032D Enforcement

The Department may take any steps as are necessary to assure Contractor's compliance with its obligations. Should any insurance policy lapse or be canceled during the contract period the Contractor shall, within thirty (30) days prior to the effective expiration or cancellation date, furnish the Department with evidence of renewal or replacement of the policy. Failure to continuously maintain insurance coverage as herein provided is a material breach of contract. In the event the Contractor fails to maintain any insurance coverage required, the Department may, but is not required to, maintain this coverage and charge the expense to the Contractor or terminate this Agreement. The required insurance shall be subject to the approval of Department, but any acceptance of insurance certificates by the Department shall in no way limit or relieve the Contractor of the Contractor's duties and responsibilities under the Contract to indemnify, defend and hold harmless the State, its officers, agents, and employees. Insurance coverage in the minimum amounts set forth herein shall not be construed to relieve the Contractor for liability in excess of that coverage, nor shall it preclude the State from taking other actions as is available to it under any other provision of the contract or law. Failure of the Department to enforce in a timely manner any of the provisions of this section shall not act as a waiver to enforcement of any of these provisions at a later date.

5-1.032E Self-Insurance

Self-insurance programs and self-insured retentions in insurance policies are subject to separate annual review and approval by the State of evidence of the Contractor's financial capacity to respond. Additionally, self-insurance programs or retentions must provide the State with at least the same protection from liability and defense of suits as would be afforded by first-dollar insurance.

5-1.032F Miscellaneous

Nothing contained in the Contract is intended to make the public or any member thereof a third party beneficiary of the Insurance or Indemnity provisions of these General Conditions, nor is any term, condition or other provision of the Contract intended to establish a standard of care owed to the public or any member thereof.

5-1.04 OCCUPANCY BY THE DEPARTMENT PRIOR TO ACCEPTANCE

The Department reserves the right to occupy all or any part of the project prior to completion of the entire contract, upon written order therefor. In that event, the Contractor will be relieved of responsibility for any injury or damage to that part as results from the Department's occupancy and use by the Department. If the Contractor carries insurance against damage to the premises or against liability to third persons covering the premises so used and occupied by the Department, and if the occupancy results in increased premiums for insurance, the Department will pay to the Contractor the added cost for insurance during the period of occupancy.

This occupancy does not constitute acceptance by the Director either of the complete work or of any portion thereof, nor will it relieve the Contractor of full responsibility for correcting defective work or materials found at any time before the formal written acceptance of the entire contract by the Director or during the full guarantee period after project acceptance, as provided in Section 7-1.09, "Guarantee," of these General Conditions.

5-1.05 CONTRACTOR'S RESPONSIBILITY FOR THE WORK

Except as otherwise provided herein, the Contractor shall have the charge and care of the work and shall bear the risk of injury or damage to any part of the work by the action of the elements or from any other cause whether arising from the execution or from the nonexecution of the work until the acceptance of the contract by the Director. The Contractor shall rebuild, repair, restore, and make good all injuries or damages to any portion of the work occasioned by any cause before its completion and acceptance, and shall bear the expense thereof. In case of suspension of work from any cause whatever, the Contractor shall be responsible for the work and shall also be responsible for all materials, and shall properly store them if necessary, and shall provide suitable drainage and erect temporary structures where necessary.

The Contractor will be relieved of responsibility for any injury or damage to the work caused by the following:

- (1) An earthquake in excess of a magnitude of 3.5 on the Richter Scale or a tidal wave, when the effect of that event has been proclaimed a disaster or state of emergency by the Governor of the State of California or by the President of the United States, or was of such magnitude at the site of the work as to have been sufficient to have caused a proclamation of disaster or state of emergency, had it occurred in a populated area.
- (2) Occupancy and use by the Department or the public prior to the completion of the entire project.
- (3) Acts of the Federal Government or the public enemy.

5-1.06 RESPONSIBILITY FOR UTILITIES

The Contractor shall be responsible for the cost for any and all work, expense or special precautions caused or required by the existence or proximity of utilities encountered in performing the work, including without limitation thereon, repair of any or all damage and all hand or exploratory excavation required. The Contractor is cautioned that the utilities may include communication cables or electrical cables which may be high voltage, and when working or excavating in the vicinity of any cables, or the ducts enclosing cables, the Contractor shall observe any special precautions required and the cost of these special precautions. Suitable warning signs, barricades, and safety devices shall be erected as necessary or required.

However, if during the course of the work the Contractor encounters utility installations which are not shown or indicated on the plans or in the special provisions, or which are found in a location substantially different from that shown, and the utilities are not reasonably apparent from visual examination, then the Contractor shall promptly notify the Engineer in writing. Where necessary for the work of the contract, the Engineer shall issue a written order to the Contractor to make adjustment, rearrangement, repair, removal, alteration, or special handling of the utility, including repair of utility if damaged. The Contractor shall perform the work described in the written order, and compensation therefor will be made in conformance with the provisions in Section 3, "Changes in the Work," of these General Conditions, relating to changes in the work. Except for the items of cost specified in Section 3, "Changes in the Work," of these General Conditions, the Contractor shall receive no compensation for any other cost, damage, delay, interference, or hindrance to him due to the presence of these utilities. If the Contractor fails to give the notice specified above and thereafter acts without instructions from the Engineer, then the Contractor shall be liable for any or all damage to these utilities or other work of the contract which arises from the Contractor's operations subsequent to discovery thereof, and the Contractor shall repair and make good any damage at the Contractor's expense.

5-1.07 PROPERTY RIGHTS IN MATERIALS

Nothing in the contract shall be construed as vesting in the Contractor any right of property in the materials used after they have been attached or affixed to the work or soil or after partial payment has been made as provided in Section 7-1.05, "Partial Payments," of these General Conditions for material delivered on the ground or stored subject to or under the control of the State and unused. These material shall become the property of the State of California upon being so attached or affixed or upon payment for materials delivered on the ground or stored subject to or under the control of the State and unused, as provided in Section 7-1.05, "Partial Payments," of these General Conditions.

5-1.08 LEGAL ACTIONS AGAINST THE DEPARTMENT

If, pursuant to court order, the Department temporarily suspends performance of all or any portion of the work, an extension of time determined pursuant to the provisions in Section 6-1.08, "Liquidated Damages," of these General Conditions will be granted, and the Contractor shall not be entitled to any additional compensation because of the suspension.

5-1.09 NO PERSONAL LIABILITY

Neither the Director, the Engineer, nor any other officer or authorized employee of the Department of Transportation shall be personally responsible for any liability arising under the contract.

5-1.10 PATENTS

The Contractor shall assume all costs arising from the use of patented materials, equipment, devices, or processes used on or incorporated in the work, and agrees to indemnify and save harmless the State of California, the Director, the Engineer, and their duly authorized representatives, from all suits at law, or actions of every nature for, or on account of the use of any patented materials, equipment, devices, or processes.

5-1.11 PAYMENT OF TAXES

The contract price paid for the work shall include full compensation for all taxes which the Contractor is required to pay, whether imposed by Federal, State or local government, including, without being limited to, Federal excise tax. No tax exemption certificate nor any document designed to exempt the Contractor from payment of any tax will be furnished to the Contractor by the Department, as to any tax on labor, services, materials, transportation, or any other items furnished pursuant to the contract.

5-1.12 COOPERATION

Should construction be under way by State forces or other forces or by other contractors within or adjacent to the limits of the work or should work of any other nature be under way by other forces within or adjacent to those limits, the Contractor shall cooperate with all the other contractors or other forces to the end that any delay, interference or hindrance to their work will be avoided. The right is reserved to perform other or additional work at or near the site at any time, by the use of other forces.

SECTION 6

PROSECUTION AND PROGRESS

6-1.01 SUBLETTING AND SUBCONTRACTING

The Contractor shall be responsible for all work performed under the contract. All persons engaged in the work will be considered as employees of the Contractor. The Contractor shall give personal attention to the fulfillment of the contract and shall keep the work under the Contractor's control. When any subcontractor fails to prosecute a portion of the work in a manner satisfactory to the Engineer, the Contractor shall remove that subcontractor immediately upon written request of the Engineer, and the subcontractor shall not again be employed on the work. Although the sections of the contract may be arranged according to various trades, or general grouping of the work, the Contractor is not obligated to sublet the work in the same manner. The State will not arbitrate disputes among subcontractors or between the Contractor and one or more subcontractors concerning responsibility for performing any part of the work.

Subcontracts shall include provisions that the contract between the State and the Contractor is part of the subcontract, and that all terms and provisions of the contract are incorporated in the subcontract. Subcontracts shall also contain certification by the subcontractor that the subcontractor is experienced in and qualified to do, and knowledgeable about, the subcontracted work. Copies of subcontracts shall be available to the Engineer upon written request, and shall be provided to the Engineer at the time any litigation against the State concerning the project is filed.

Contract No. 09-307904

Pursuant to the provisions of Section 6109 of the Public Contract Code, the Contractor shall not perform work on a public works project with a subcontractor who is ineligible to perform work on the public works project pursuant to Section 1777.1 or 1777.7 of the Labor Code.

The Contractor shall not substitute any person as subcontractor in place of a subcontractor listed on the Contractor's bid proposal without the written approval of the Engineer. Substitutions must be in conformance with the provisions of the "Subletting and Subcontracting Fair Practices Act" beginning with Section 4100 of the Public Contract Code. Violations of this Act by the Contractor may subject him to penalties which may include cancellation of contract, assessment of 10 percent of the subcontractor's bid, and disciplinary action by the Contractors' State License Board.

6-1.02 ASSIGNMENT

The performance of the contract may not be assigned, except upon the written consent of the Director. Consent will not be given to any proposed assignment which would relieve the original Contractor or the Contractor's surety of their responsibilities under the contract nor will the Director consent to any assignment of a part of the work under the contract.

The Contractor may assign moneys due or to become due the Contractor under the contract and the assignment will be recognized by the Department, if given proper notice thereof, to the extent permitted by law, but any assignment of moneys shall be subject to all proper set-offs in favor of the Department and to all deductions provided for in the contract and particularly all money withheld, whether assigned or not, shall be subject to being used by the Department for the completion of the work in the event that the Contractor should be in default therein.

6-1.03 BEGINNING OF WORK

The Contractor shall begin work within 15 calendar days after receiving notice that the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department, and shall diligently prosecute the same to completion within the time limit provided in the special provisions.

The Contractor shall notify the Engineer, in writing, of the Contractor's intent to begin work at least 72 hours before work is begun. The notice shall be delivered to the Office of the District Director of Transportation in the district in which the work is situated and shall specify the date the Contractor intends to start. If the project has more than one location of work, a separate notice shall be given for each location.

Should the Contractor begin work in advance of receiving notice that the contract has been approved as above provided, any work performed by the Contractor in advance of the date of approval shall be considered as having been done by the Contractor at the Contractor's own risk and as a volunteer unless the contract is approved.

The delivery to the State for execution and approval of the contract properly executed on behalf of the Contractor and surety and the minimum 72 hours advance written notice as required above shall constitute the Contractor's authority to enter upon the site of the work and to begin operations, subject to the Contractor's assumption of the risk of the disapproval of the contract, as above provided, and subject also to the following:

- (1) The Contractor shall, on commencing operations, take all precautions required for public safety and shall observe all the provisions in these General Conditions and the special provisions.
- (2) In the event of disapproval, the Contractor shall at the Contractor's expense do that work that is necessary to leave the site in a neat condition to the satisfaction of the Engineer.
- (3) All work done according to the contract prior to its approval, will, when the contract is approved, be considered authorized work and will be paid for as provided in the contract.
- (4) The Contractor shall not be entitled to any additional compensation or an extension of time for any delay, hindrance or interference caused by or attributable to commencement of work prior to the date on which the contract was approved by the Attorney General or the attorney appointed and authorized to represent the Department, except to the extent the delay, hindrance or interference would have been compensable hereunder had work been commenced on the date of the approval and the progress thereof been the same as that actually made.

6-1.04 PROGRESS SCHEDULE

The Contractor shall submit to the Engineer a practicable progress schedule within 15 days of approval of the contract, and within 7 days of the Engineer's written request at any other time.

The Contractor may furnish the schedule on a form of the Contractor's choice or, if requested, the Engineer will furnish a form for the Contractor's use. If the Engineer furnishes a form, the Engineer will also furnish to the Contractor, on request, on or before the last day of each month a copy of the form showing the status of work actually completed during the preceding estimate period.

The schedule shall show the order in which the Contractor proposes to carry out the work, the dates on which the Contractor will start the several salient features of the work, and the contemplated dates for completing those salient features.

The progress schedules submitted shall be consistent in all respects with the time and order of work requirements of the contract.

Subsequent to the time that submittal of a progress schedule is required in conformance with these General Conditions, no progress payment will be made for any work until a satisfactory schedule has been submitted to the Engineer.

6-1.05 SCHEDULE OF VALUES

The Contractor shall submit to the Engineer a schedule of values for each lump sum item. The sum of the items listed in the schedule of values shall equal the contract lump sum prices. Overhead and profit shall not be listed as separate items. The schedule of values shall be approved by the Engineer before any partial payment estimate is prepared.

6-1.06 TEMPORARY SUSPENSION OF WORK

The Engineer shall have the authority to suspend the work wholly or in part, for any time period as the Engineer deems necessary, due to unsuitable weather, or to such other conditions as are considered unfavorable for the suitable prosecution of the work, or for any time period as the Engineer deems necessary due to the failure on the part of the Contractor to carry out orders given, or to perform any provision of the contract.

The Contractor shall immediately comply with the written order of the Engineer to suspend the work wholly or in part. The suspended work shall be resumed when conditions are favorable and methods are corrected, as ordered or approved in writing by the Engineer.

If the Engineer orders a suspension of all of the work or a portion of the work which is the current controlling operation or operations, due to unsuitable weather or to such other conditions as are considered unfavorable to the suitable prosecution of the work, the days on which the suspension is in effect shall not be considered working days as defined in Section 6-1.07, "Time of Completion," of these General Conditions. If a portion of work at the time of the suspension is not a current controlling operation or operations, but subsequently does become the current controlling operation or operations, the determination of working days will be made on the basis of the then current controlling operation or operations.

If a suspension of work is ordered by the Engineer, due to the failure on the part of the Contractor to carry out orders given or to perform any provision of the contract, the days on which the suspension order is in effect shall be considered working days if those days are working days within the meaning of the definition set forth in Section 6-1.07, "Time of Completion," of these General Conditions.

In the event of a suspension of work under any of the conditions set forth in this Section 6-1.06, the suspension of work shall not relieve the Contractor of the Contractor's legal responsibilities as set forth in these General Conditions.

The Contractor shall have no claim for damage or compensation for any delay, interference or hindrance resulting from an ordered temporary suspension of the work.

In addition to the requirements specified above, the following shall apply:

If the performance of all or any portion of the work is suspended or delayed by the Engineer in writing for an unreasonable period of time (not originally anticipated, customary, or inherent to the construction industry) and the Contractor believes that additional compensation or contract time or additional compensation and contract time is due as a result of the suspension or delay, the Contractor shall submit to the Engineer in writing a request for adjustment within 7 calendar days of receipt of the notice to resume work. The request shall set forth the reasons and support for the adjustment.

Upon receipt, the Engineer will evaluate the Contractor's request. If the Engineer agrees that the cost or time or cost and time required for the performance of the contract has increased as a result of the suspension and the suspension was caused by conditions beyond the control of and not the fault of the Contractor, the Contractor's suppliers, or subcontractors at any approved tier, and not caused by weather, the Engineer will make an adjustment (excluding profit) and modify the contract in writing accordingly. The Engineer will notify the Contractor of the Engineer's determination whether or not an adjustment of the contract is warranted.

No contract adjustment will be allowed unless the Contractor has submitted the request for adjustment within the time prescribed.

No contract adjustment will be allowed under the provisions specified in this section to the extent that performance would have been suspended or delayed by any other cause, or for which an adjustment is provided for or excluded under any term or condition of this contract.

6-1.07 TIME OF COMPLETION

The Contractor shall complete all or any designated portion of the work called for under the contract in all parts and requirements within the time set forth in the special provisions.

A working day is defined as any day, except Saturdays, Sundays and legal holidays and days on which the Contractor is specifically required by the special provisions to suspend construction operations, and except days on which the Contractor is prevented by inclement weather or conditions resulting immediately therefrom adverse to the current controlling operation or operations, as determined by the Engineer, from proceeding with at least 75 percent of the normal labor and equipment force engaged on the controlling operation or operations for at least 60 percent of the total daily time being currently spent on the controlling operation or operations.

Should the Contractor prepare to begin work at the regular starting time in the morning of any day on which inclement weather, or the conditions resulting from the weather, or the condition of the work, prevents the work from beginning at the usual starting time and the crew is dismissed as a result thereof and the Contractor does not proceed with at least 75 percent of the normal labor and equipment force engaged in the current controlling operation or operations for at least 60 percent of the total daily time being currently spent on the controlling operation or operations, the Contractor will not be charged for a working day whether or not conditions should change thereafter during that day and the major portion of the day could be considered to be suitable for those construction operations.

The current controlling operation or operations is to be construed to include any feature of the work which, if delayed, will delay the time of completion of the contract.

Determination that a day is a nonworking day by reason of inclement weather or conditions resulting immediately therefrom shall be made and agreed upon during that day by conference between the Engineer and the Contractor. In the event of failure to agree, the Contractor will be allowed 15 days from the issuance of the weekly statement of working days in which to file a written protest setting forth in what respects the Contractor differs from the Engineer, otherwise the decision of the Engineer shall be deemed to have been accepted by the Contractor as correct. The Engineer will furnish the Contractor a weekly statement showing the number of working days charged to the contract for the preceding week, the number of working days of time extensions being considered or approved, the number of working days originally specified for the completion of the contract and the number of working days remaining to complete the contract and the extended date for completion thereof, except when working days are not being charged in conformance with the provisions in Section 6-1.06, "Temporary Suspension of Work," of these General Conditions.

6-1.08 LIQUIDATED DAMAGES

It is agreed by the parties to the contract that in case all the work called for under the contract in all parts and requirements is not finished or completed within the number of working days as set forth in the special provisions, damage will be sustained by the State of California, and that it is and will be impracticable and extremely difficult to ascertain and determine the actual damage which the State will sustain in the event of and by reason of the delay; and it is therefore agreed that the Contractor will pay to the State of California, the sum set forth in the special provisions per day for each and every calendar day's delay in finishing the work in excess of the number of working days prescribed; and the Contractor agrees to pay the liquidated damages herein provided for, and further agrees that the Department may deduct the amount thereof from any moneys due or that may become due the Contractor under the contract.

It is further agreed that in case the work called for under the contract is not finished and completed in all parts and requirements within the number of working days specified, the Director shall have the right to increase the number of working days or not, as the Director may deem best to serve the interest of the State, and if the Director decides to increase the number of working days, the Director shall further have the right to charge to the Contractor, the Contractor's heirs, assigns or sureties and to deduct from the final payment for the work all or any part, as the Director may deem proper, of the actual cost of engineering, inspection, superintendence, and other overhead expenses which are directly chargeable to the contract, and which accrue during the period of the extension, except that cost of final surveys and preparation of final statement shall not be included in the charges.

The Contractor will be granted an extension of time and will not be assessed with liquidated damages or the cost of engineering and inspection for any portion of the delay in completion of the work beyond the time named in the special provisions for the completion of the work caused by acts of God or of the public enemy, fire, floods, tsunamis, earthquakes, epidemics, quarantine restrictions, strikes, labor disputes, shortage of materials and freight embargoes, provided, that the Contractor shall notify the Engineer in writing of the causes of delay within 15 days from the beginning of that delay. The Engineer shall ascertain the facts and the extent of the delay, and the Engineer's findings thereon shall be final and conclusive.

No extension of time will be granted for a delay caused by a shortage of materials unless the Contractor furnishes to the Engineer documentary proof that the Contractor has made every effort to obtain the materials from all known sources within reasonable reach of the work in a diligent and timely manner, and further proof in the form of supplementary progress schedules, as required in Section 6-1.04, "Progress Schedule," of these General Conditions that the inability to obtain the materials when originally planned, did in fact cause a delay in final completion of the entire work which could not be compensated for by revising the sequence of the Contractor's operations. The term "shortage of materials," as used in this section, shall apply only to materials, articles, parts or equipment which are standard items and are to be incorporated in the work. The term "shortage of materials," shall not apply to materials, parts, articles, or equipment which are processed, made, constructed, fabricated or manufactured to meet the specific requirements of the contract. Only the physical shortage of material will be considered under these provisions as a cause for extension of time. Delays in obtaining materials due to priority in filling orders will not constitute a shortage of materials.

If the Contractor is delayed in completion of the work by reason of changes made under Section 3, "Changes in the Work," of these General Conditions or by any act of the Engineer or of the Department, not contemplated by the contract, an extension of time commensurate with the delay in completion of the work thus caused will be granted and the Contractor shall be relieved from any claim for liquidated damages, or engineering and inspection charges or other penalties for the period covered by that extension of time; provided that the Contractor shall notify the Engineer in writing of the causes of delay within 15 days from the beginning of the delay. The Engineer shall ascertain the facts and the extent of the delay, and the Engineer's findings thereon shall be final and conclusive.

Except as provided in Public Contract Code Section 7102, the Contractor shall have no claim for damage or compensation for any delay or hindrance whether or not contemplated by the contract.

It is the intention of the above provisions that the Contractor shall not be relieved of liability for liquidated damages or engineering and inspection charges for any period of delay in completion of the work in excess of that expressly provided for in this Section 6-1.08.

6-1.09 TERMINATION

6-1.09A Termination Of Contract - "Convenience Of State"

The Department reserves the right to terminate the contract at any time if the Director determines that to do so would be in the best interest of the State.

Termination of the contract and the total compensation payable to the Contractor in the event of termination shall be governed by the following:

- (1) The Engineer will issue the Contractor a written notice signed by the Director, specifying that the contract is to be terminated. Upon receipt of that written notice and, except as otherwise directed in writing by the Engineer, the Contractor shall:
 - (a) Stop all work under the contract except that specifically directed to be completed prior to acceptance.
 - (b) Perform work the Engineer deems necessary to secure the project for termination.
 - (c) Remove equipment from the site of the work.
 - (d) Take the required action as is necessary to protect materials from damage.
 - (e) Notify all subcontractors and suppliers that the contract is being terminated and that their contracts or orders are not to be further performed unless otherwise authorized in writing by the Engineer.
 - (f) Provide the Engineer with an inventory list of all materials previously produced, purchased or ordered from suppliers for use in the work and not yet used in the work, including its storage location, and any other information as the Engineer may request.
 - (g) Dispose of materials not yet used in the work as directed by the Engineer. It shall be the Contractor's responsibility to provide the State with good title to all materials purchased by the State hereunder, including materials for which partial payment has been made as provided in Section 7-1.05, "Partial Payments," of these General Conditions and with bills of sale or other documents of title for the materials.
 - (h) Subject to the prior written approval of the Engineer, settle all outstanding liabilities and all claims arising out of subcontracts or orders for materials terminated hereunder. To the extent directed by the Engineer, the Contractor shall assign to the Department all the right, title and interest of the Contractor under subcontracts or orders for materials terminated hereunder.
 - (i) Furnish the Engineer with the documentation required to be furnished by the Contractor under the provisions of the contract including, on projects as to which Federal funds are involved, all documentation required under the Federal requirements included in the contract.

(j) Take other actions as the Engineer may direct.

- (2) Acceptance of the contract as hereinafter specified shall not relieve the Contractor of responsibility for damage to materials except as follows:

The Contractor's responsibility for damage to materials for which partial payment has been made as provided in Section 7-1.05, "Partial Payments," of these General Conditions and for materials furnished by the State for use in the work and unused shall terminate when the Engineer certifies that the materials have been stored in the manner and at the locations the Engineer has directed.

The Contractor's responsibility for damage to materials purchased by the State subsequent to the issuance of the notice that the contract is to be terminated shall terminate when title and delivery of those materials has been taken by the State.

When the Engineer determines that the Contractor has completed the work under the contract directed to be completed prior to termination and all other work as may have been ordered to secure the project for termination, the Engineer will recommend that the Director formally accept the contract, and immediately upon and after the acceptance by the Director, the Contractor will not be required to perform any further work thereon and shall be relieved of contractual responsibilities for injury to persons or damage to property which occurs after the formal acceptance of the project by the Director.

- (3) The total compensation to be paid to the Contractor shall be determined by the Engineer on the basis of the following:

(a) The reasonable cost to the Contractor, without profit, for all work performed under the contract, including mobilization, demobilization and work done to secure the project for termination.

When in the opinion of the Engineer the cost of the work is excessively high due to costs incurred to remedy or replace defective or rejected work, the reasonable cost to be allowed will be the estimated reasonable cost of performing that work in compliance with the requirements of the plans and special provisions and the excessive actual cost shall be disallowed.

(b) A reasonable allowance for profit on the cost of work performed as determined under Subsection (a), provided the Contractor establishes to the satisfaction of the Engineer that it is reasonably probable that the Contractor would have made a profit had the contract been completed and provided further, that the profit allowed shall in no event exceed 4 percent of the cost.

(c) The reasonable cost to the Contractor of handling material returned to the vendor, delivered to the Department or otherwise disposed of as directed by the Engineer.

(d) A reasonable allowance for the Contractor's administrative costs in determining the amount payable due to termination of the contract.

All records of the Contractor and subcontractors, necessary to determine compensation in conformance with the provisions of this Section shall be open to inspection or audit by representatives of the Department at all times after issuance of the notice that the contract is to be terminated and for a period of 3 years, and these records shall be retained for that period.

After acceptance of the work by the Director, the Engineer may make payments on the basis of interim estimates pending issuance of the Final Statement, when in the Engineer's opinion the amount thus paid, together with all amounts previously paid or allowed, will not result in total compensation in excess of that to which the Contractor will be entitled. All payments, including payment upon the Final Statement, shall be subject to deduction for prior payments and amounts, if any, to be kept or retained under the provisions of the contract.

The provisions of this Section shall be included in all subcontracts.

6-1.09B Termination Of Control - "Default Of Contractor"

Failure to supply an adequate working force, or material of proper quality, or failure to comply with Section 10262 of the State Contract Act, or in any other respect to prosecute the work with the diligence and force specified by the contract, is grounds for termination of the Contractor's control over the work and for taking over the work by the State. The procedures for termination, completion of the work, and the rights and obligations of the parties are provided for in the State Contract Act (Public Contract Code Sections 10253-10260).

If the Contractor's control of the work is terminated or the Contractor abandons the work and the contract work is completed in conformance with the provisions in Section 10255 of the State Contract Act, any dispute concerning the amount to be paid by the State to the Contractor or the Contractor's surety or to be paid to the State by the Contractor or the Contractor's surety, under the provisions in Section 10258 of the State Contract Act, shall be subject to arbitration in conformance with the provisions in Section 7-1.10, "Arbitration," of these General Conditions. The surety shall be bound by the arbitration award and is entitled to participate in the arbitration proceedings.

SECTION 7

ACCEPTANCE AND PAYMENT

7-1.01 ACCEPTANCE

The contract will be accepted in writing by the Director when the whole shall have been completed in all respects in conformance with the provisions of the contract to the full satisfaction of the Department.

7-1.02 SCOPE OF PAYMENT

The Contractor shall accept the compensation provided in the contract as full payment for furnishing all labor, materials, tools, equipment, and incidentals necessary to the completed work and for performing all work contemplated and embraced under the contract; also for loss or damage arising from the nature of the work, or from the action of the elements, or from any unforeseen difficulties which may be encountered during the prosecution of the work until the acceptance by the Director and for all risks of every description connected with the prosecution of the work, also for all expenses incurred in consequence of the suspension or discontinuance of the work as provided in the contract; and for completing the work according to the contract. Neither the payment of any estimate nor of any retained percentage shall relieve the Contractor of any obligation to make good any defective work or material.

No compensation will be made in any case for loss of anticipated profits.

7-1.03 Notice of Potential Claim

The Contractor shall not be entitled to the payment of any additional compensation for any act, or failure to act, by the Engineer, including failure or refusal to issue a change order, or for the happening of any event, thing, occurrence, or other cause, unless the Contractor shall have given the Engineer due written notice of potential claim as hereinafter specified. Compliance with this Section 7-1.03 shall not be a prerequisite as to matters within the scope of the protest provisions in Section 3, "Changes in the Work," or Section 6-1.07, "Time of Completion," or the notice provisions in Section 2-1.045, "Differing Site Conditions," or Section 6-1.08, "Liquidated Damages," or Section 5-1.06, "Responsibility for Utilities," of these General Conditions.

The written notice of potential claim shall be submitted to the Engineer prior to the time that the Contractor performs the work giving rise to the potential claim for additional compensation, if based on an act or failure to act by the Engineer, or in all other cases within 15 days after the happening of the event, thing, occurrence, or other cause, giving rise to the potential claim.

The written notice of potential claim shall be submitted on Form CEM-6201 furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650 - 12655. The notice shall set forth the reasons for which the Contractor believes additional compensation will or may be due and the nature of the costs involved. Unless the amount of the potential claim has been stated in the written notice, the Contractor shall, within 15 days of submitting the notice, furnish an estimate of the cost of the affected work and impacts, if any, on project completion. The estimate of costs may be changed or updated by the Contractor when conditions have changed. When the affected work is completed, the Contractor shall submit substantiation of the Contractor's actual costs. Failure to do so shall be sufficient cause for denial of any claim subsequently filed on the basis of that notice of potential claim.

It is the intention of this Section 7-1.03 that differences between the parties arising under and by virtue of the contract be brought to the attention of the Engineer at the earliest possible time in order that those matters may be settled, if possible, or other appropriate action promptly taken. The Contractor hereby agrees that the Contractor shall have no right to additional compensation for any claim that may be based on any act, failure to act, event, thing or occurrence for which no written notice of potential claim as herein required was filed.

Should the Contractor, in connection with or subsequent to the assertion of a potential claim, request inspection and copying of documents or records in the possession of the Department that pertain to the potential claim, the Contractor's records of the project, as deemed by the Department to be pertinent to the potential claim, shall be made available to the Department for inspection and copying.

7-1.04 STOP NOTICES

The State of California, by and through the Department or other appropriate State office or officers, may at its option and at any time retain out of any amounts due the Contractor, sums sufficient to cover claims, filed pursuant to Section 3179 et seq of the Civil Code.

Stop notice information may be obtained from the Departmental Disbursing Office at 1801 30th Street, East Building, Sacramento, California.

7-1.05 PARTIAL PAYMENTS

The Department, once in each month upon request of the Contractor for partial payments, shall cause an estimate in writing to be made by the Engineer. The estimate shall include the total amount of work done and acceptable materials furnished to the time of the estimate, and the value thereof. The acceptable materials shall include materials that are furnished and delivered to the work site and are not incorporated in the work.

The Department shall retain 10 percent of the estimated value of the work done and 10 percent of the value of materials so estimated to have been furnished and delivered and not incorporated in the work as aforesaid as part security for the fulfillment of the contract by the Contractor, except that at any time after 20 percent of the work has been completed, if the Engineer finds that satisfactory progress is being made, the Department may reduce the total amount being retained from payment pursuant to the above requirements to 5 percent of the total estimated value of the work and materials and may also reduce the amount retained from any of the remaining partial payments to 5 percent of the estimated value of the work and materials. In addition, on any partial payment made after 95 percent of the work has been completed, the Department may reduce the amount withheld from payment pursuant to the requirements of this Section 7-1.05, to such lesser amount as the Department determines is adequate security for the fulfillment of the balance of the work and other requirements of the contract, but in no event will that amount be reduced to less than 125 percent of the estimated value of the work yet to be completed as determined by the Engineer. The reduction will only be made upon the written request of the Contractor and shall be approved in writing by the surety on the Performance Bond and by the surety on the Payment Bond. The approval of the surety shall be submitted to the Disbursing Officer of the Department; the signature of the person executing the approval for the surety shall be properly acknowledged and the power of attorney authorizing the person to give that consent must either accompany the document or be on file with the Department.

The Department shall pay monthly to the Contractor, while carrying on the work, the balance not retained, as aforesaid, after deducting therefrom all previous payments and all sums to be kept or retained under the provisions of the contract. No monthly estimate or payment shall be required to be made when, in the judgment of the Engineer, the work is not proceeding in conformance with the provisions of the contract.

No monthly estimate or payment shall be construed to be an acceptance of any defective work or improper materials.

Attention is directed to the prohibitions and penalties pertaining to unlicensed contractors as provided in Business and Professions Code Sections 7028.15(a) and 7031.

7-1.06 PAYMENT OF WITHHELD FUNDS

Attention is directed to Section 7-1.05, "Partial Payments," of these General Conditions and in particular to the retention provisions of Section 7-1.05, of these General Conditions.

Upon the Contractor's request, pursuant to Public Contract Code Section 10263, the Department will make payment of funds withheld from progress payments to ensure performance of the contract if the Contractor deposits in escrow with the State Treasurer, or with a bank acceptable to the Department, securities equivalent to the amount withheld. The Contractor shall be beneficial owner of any securities substituted for moneys withheld and shall receive any interest thereon. Upon satisfactory completion of the contract, the securities shall be returned to the Contractor.

Alternatively, upon the Contractor's request, the Department will make payment of retentions earned directly to the escrow agent. The Contractor may direct the investment of the payments into securities and the Contractor shall receive the interest earned on the investments upon the same terms provided for securities deposited by the Contractor. Upon satisfactory completion of the contract, the Contractor shall receive from the escrow agent all securities, interest, and payments received by the escrow agent from the Department, pursuant to the terms in Section 10263 of the Public Contract Code.

Alternatively, and subject to the approval of the Department, the payment of retentions earned may be deposited directly with a person licensed under Division 6 (commencing with Section 17000) of the Financial Code as the escrow agent. Upon written request of an escrow agent that has not been approved by the Department under subdivision (c) of Section 10263 of the Public Contract Code, the Department will provide written notice to that escrow agent within 10 business days of receipt of the request indicating the reason or reasons for not approving that escrow agent. The payments will be deposited in a trust account with a Federally chartered bank or savings association within 24 hours of receipt by the escrow agent. The Contractor shall not place any retentions with the escrow agent in excess of the coverage provided to that escrow agent pursuant to subdivision (b) of Section 17314 of the Financial Code. In all respects not inconsistent with subdivision (c) of Section 10263 of the Public Contract Code, the remaining provisions of Section 10263 of the Public Contract Code shall apply to escrow agents acting pursuant to subdivision (c) of Section 10263 of the Public Contract Code.

Securities eligible for investment shall include those listed in Section 16430 of the Government Code, bank or savings and loan certificates of deposit, interest-bearing demand deposit accounts, standby letters of credit, or any other security mutually agreed to by the Contractor and the Department.

The escrow agreement used pursuant to this Section 7-1.06 shall be substantially similar to the "Escrow Agreement for Security Deposits In Lieu of Retention" in Section 10263 of the Public Contract Code, deemed as incorporated herein by reference.

The Contractor shall obtain the written consent of the surety to the agreement.

7-1.07 FINAL PAYMENT AND CLAIMS

After acceptance of the work by the Director, the Department will make a final monthly payment pending approval of the final statement. The final monthly payment will be the balance found to be due after deduction of all previous payments, all amounts to be kept or retained under the provisions of the contract, and such further amounts as the Engineer determined to be necessary pending approval of the final statement. The Engineer will promptly submit to the Contractor a final statement of the sum due the Contractor under the contract. The statement shall take into account the contract price, as adjusted by any change order; amounts already paid; and sums to be withheld for incomplete work, liquidated damages, and for any other cause under the contract. The Contractor shall submit written approval of the final statement or submit a written statement of all claims arising under or by virtue of the contract so that the Engineer receives the written approval or statement of claims no later than close of business of the thirtieth day after receiving the final statement of the sum due the Contractor. If the thirtieth day falls on a Saturday, Sunday or legal holiday, then receipt of the written approval or statement of claims by the Engineer shall not be later than the close of business of the next business day. The approval of that statement or the failure to file a claim within the specified 30 day period shall constitute a waiver by the Contractor of any additional right to compensation under or by reason of the contract and the payment so made by the State shall thereupon become a complete statement between the State and the Contractor.

To constitute the filing of a claim, the Contractor shall set forth in writing the basis for the claim and the amount of money for which demand is made and shall submit the same to the Engineer. No demand by the Contractor shall be recognized as a claim by the State unless it is filed in conformance with this paragraph.

Claims filed by the Contractor shall be in sufficient detail to enable the Engineer to ascertain the basis and amount of those claims. If additional information or details are required by the Engineer to determine the basis and amount of the claims, the Contractor shall furnish additional information or details so that the information or details are received by the Engineer no later than the fifteenth day after receipt of the written request from the Engineer. If the fifteenth day falls on a Saturday, Sunday or legal holiday, then receipt of the information or details by the Engineer shall not be later than close of business of the next business day. Failure to submit the information and details to the Engineer within the time specified will be sufficient cause for denying the claim.

The Contractor shall keep full and complete records of the costs and additional time incurred for any work for which a claim for additional compensation is made. The Engineer or any designated claim investigator or auditor shall have access to those records and any other records as may be required by the Engineer to determine the facts or contentions involved in the claims. Failure to permit access to those records shall be sufficient cause for denying the claims.

Claims submitted by the Contractor shall be accompanied by a notarized certificate containing the following language:

Under the penalty of law for perjury or falsification and with specific reference to the California False Claims Act, Government Code Section 12650 et. seq., the undersigned,

(name)

(title) of

(company)

hereby certifies that the claim for the additional compensation and time, if any, made herein for the work on this contract is a true statement of the actual costs incurred and time sought, and is fully documented and supported under the contract between parties.

Dated _____

/s/ _____

Subscribed and sworn before me this _____ day

of _____.

Notary Public
My Commission Expires _____

Failure to submit the notarized certificate will be sufficient cause for denying the claim.

Any claim for overhead type expenses or costs, in addition to being certified as stated above, shall be supported by an audit report of an independent Certified Public Accountant. Any claim for overhead shall also be subject to audit by the State at its discretion.

Any costs or expenses incurred by the State in reviewing or auditing any claims that are not supported by the Contractor's cost accounting or other records shall be deemed to be damages incurred by the State within the meaning of the California False Claims Act.

The District Director of the District which administers the contract will make the final determination of any claims which remain in dispute after completion of claim review by the Engineer. A board or person designated by the District Director will review those claims and make a written recommendation thereon to the District Director. The Contractor may meet with the review board or person to make a presentation in support of those claims.

Upon final determination of the claims, the Engineer will then make and issue the Engineer's final statement in writing and within 30 days thereafter the State will pay the entire sum, if any, found due thereon. That final statement shall be conclusive and binding against both parties to the contract on all questions relating to the amount of work done and the compensation payable therefor, except as otherwise provided in Section 7-1.08, "Clerical Errors," of these General Conditions.

7-1.08 CLERICAL ERRORS

Notwithstanding the provisions in Section 7-1.07, "Final Payment And Claims," of these General Conditions, for a period of 3 years after acceptance of the work, all estimates and payments made pursuant to Section 7-1.07, including the final statement and payment, shall be subject to correction and adjustment for clerical errors in the calculations involved in the determination of quantities and payments. The Contractor and the Department agree to pay to the other any sum due under the provisions of this Section 7-1.08, provided, however, if the total sum to be paid is less than \$200, no payment shall be made.

7-1.09 GUARANTEE

The Contractor hereby unconditionally guarantees that the mechanical and electrical equipment and related components in the building work will be done in conformance with the requirements of the contract, and further guarantees the same to be and remain free of defects in workmanship and materials for a period of 6 months from the date of acceptance of the contract. The Contractor hereby agrees to repair or replace any and all mechanical and electrical equipment and related components in the building work that may prove to be not in conformance with the requirements of the contract or that may be defective in

its workmanship or material within the guarantee period specified, without any expense whatsoever to the Department, ordinary wear and tear and unusual abuse or neglect excepted.

A portion of the performance bond for the contract in a sum equal to one half the value of the mechanical and electrical equipment and related components in the building work, shall remain in full force and effect during the guarantee period. The value of those mechanical and electrical equipment and related components shall be the value determined in conformance with the requirements specified in Section 6-1.05, "Schedule of Values" of the General Conditions.

The Contractor further agrees that, within 10 calendar days after being notified in writing by the Department of any mechanical and electrical equipment and related components in the building work not in conformance with the requirements of the contract or any defects in the mechanical and electrical equipment and related components in the building work, he shall commence and prosecute with due diligence all work necessary to fulfill the terms of this guarantee, and shall complete the work within a reasonable period of time, and, in the event the Contractor fails to comply, he does hereby authorize the Department to proceed to have such work done at the Contractor's expense and he shall honor and pay the cost and charges therefor upon demand. The Department shall be entitled to all costs and expenses, including reasonable attorney's fees, necessarily incurred upon the Contractor's refusal to honor and pay the above costs and charges.

7-1.10 ARBITRATION

Sections 10240-10240.13, inclusive of the Public Contract Code provides for the resolution of contract claims by arbitration.

Claims (demands for monetary compensation or damages) arising under or related to performance of the contract shall be resolved by arbitration unless the Department and the Contractor agree in writing, after the claim has arisen, to waive arbitration and to have the claim litigated in a court of competent jurisdiction. Arbitration shall be pursuant to Public Contract Code Sections 10240-10240.13, inclusive, and applicable regulations (see Subchapter 3 [Sections 301-382, inclusive] of Chapter 2 of Title 1 of the California Code of Regulations). The arbitration decision shall be decided under and in conformance with the law of this State, supported by substantial evidence and, in writing, contain the basis for the decision, findings of fact, and conclusions of law.

Arbitration shall be initiated by a Complaint in Arbitration made in compliance with the requirements of those regulations. A Complaint in Arbitration by the Contractor shall be made not later than 90 days after the date of service in person or by mail on the Contractor of the final written decision by the Department on the claim.

**STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION**

SPECIAL PROVISIONS

Annexed to Contract No. 09-307904

DIVISION 0 BIDDING AND CONTRACT REQUIREMENTS

0.1 INSTRUCTIONS TO BIDDERS AND GENERAL CONDITIONS

The work embraced herein shall conform to the provisions in the Instructions to Bidders and General Conditions for Building Construction of the Department of Transportation, dated January, 2002, a single publication attached hereto and referred to herein as "Instructions to Bidders" and "General Conditions", and the following special provisions.

In case of conflict between the Instructions to Bidders or the General Conditions and these special provisions, the special provisions shall take precedence over and be used in lieu of the conflicting portions.

The Department is gradually changing the style and language of the specifications. The new style and language includes:

1. Use of:
 - 1.1. Imperative mood
 - 1.2. Introductory modifiers
 - 1.3. Conditional clauses

2. Elimination of:
 - 2.1. Language variations
 - 2.2. Definitions for industry-standard terms
 - 2.3. Redundant specifications
 - 2.4. Needless cross-references

The use of this new style does not change the meaning of a specification not yet using this style.

The specifications are written to the Bidder before award and the Contractor after. Before award, interpret sentences written in the imperative mood as starting with "The Bidder must" and interpret "you" as "the Bidder" and "your" as "the Bidder's." After award, interpret sentences written in the imperative mood as starting with "The Contractor must" and interpret "you" as "the Contractor" and "your" as "the Contractor's."

Unless an object or activity is specified to be less than the total, the quantity or amount is all of the object or activity.

A list in the specifications is inclusive unless the items listed are specified as choices.

Interpret terms as defined in the Contract documents. A term not defined in the Contract documents has the meaning defined in Means Illustrated Construction Dictionary, Condensed Version, Second Edition.

0.15 DEFINITIONS AND TERMS

Attention is directed to the provisions in Section 1, "Definitions and Terms," of the General Conditions.

Section 1-1.26, "Abbreviations," of the General Conditions is amended as follows:

The following abbreviations are added:

CMC	California Mechanical Code (2001 Edition)
CPC	California Plumbing Code (2001 Edition)
NPCA	National Precast Concrete Association
AREMA	American Railway Engineering and Maintenance-of-Way Association

The following abbreviation is deleted:

AREA American Railway Engineering Association

The following abbreviations are modified:

CBC California Building Code (2001 Edition)
CEC California Electrical Code (2001 Edition)
UBC Uniform Building Code (1997 Edition)

Attention is directed to the provisions in Section 1, "Definitions and Terms," of the General Conditions.

The following definitions are added:

1-1.042 BUSINESS DAY

Day on the calendar except Saturday or holiday.

1-1.047 CALIFORNIA Manual on Uniform Traffic Control Devices

The California Manual on Uniform Traffic Control Devices for Streets and Highways (California MUTCD) is issued by the Department of Transportation and is the Federal Highway Administration's MUTCD 2003 Edition, as amended for use in California. Part 6 of the California MUTCD, "Temporary Traffic Control," supersedes the Department's Manual of Traffic Controls.

1-1.114 HOLIDAY

Day designated as a State holiday under Govt Code § 6700 et seq. except September 9th, "Admission Day." The day after Thanksgiving Day is a non-working day. Interpret "legal holiday" as "holiday."

1-1.146 OFFICES OF STRUCTURE DESIGN

When the specifications require working drawings to be submitted to the Offices of Structure Design, the drawings shall be submitted to: Offices of Structure Design, Documents Unit, Mail Station 9-4/4I, 1801 30th Street, Sacramento, CA 95816, Telephone (916) 227-8252.

The following definition is deleted:

Section 1-1.13, "Legal Holidays"

The following definition is modified:

1-1.21 STATE

The State of California, including its agencies, departments, or divisions, whose conduct or action is related to the work.

0.2 PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder's attention is directed to the provisions in Section 1, "Proposal Requirements and Conditions," of the Instructions to Bidders, and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the proposal form and the submission of the bid.

The bidder shall examine carefully the site of the work contemplated, the plans, special provisions, Instructions to Bidders, General Conditions and the proposal and contract forms therefor. The submission of a bid shall be conclusive evidence that the bidder has investigated and is satisfied as to the general and local conditions to be encountered, as to the character, quality, and scope of work to be performed, the quantities of materials to be furnished, and as to the requirements of the plans, special provisions, Instructions to Bidders, General Conditions, proposal and contract.

The submission of a bid shall also be conclusive evidence that the bidder is satisfied as to the character, quality and quantity of surface and subsurface materials or obstacles to be encountered insofar as this information was reasonably ascertainable from an inspection of the site and the records of exploratory work done by the Department as shown in the bid documents, as well as from the plans, special provisions, instructions to bidders, and general conditions made a part of the contract.

Where the Department has made investigations of site conditions, including subsurface conditions in areas where work is to be performed under the contract, bidders or contractors may, upon written request, inspect the records of the Department as to those investigations subject to and upon the conditions hereinafter set forth.

Where there has been prior construction by the Department or other public agencies within the project limits, records of the prior construction that are currently in the possession of the Department and which have been used by, or are known to, the designers and administrators of the project will be made available for inspection by bidders or contractors, upon written request, subject to the conditions hereinafter set forth. The records may include, but are not limited to, as-built drawings, design calculations, foundation and site studies, project reports and other data assembled in connection with the investigation, design, construction and maintenance of the prior projects.

Inspection of the records of investigations and project records may be made at the office of the district in which the work is situated, or in the case of records of investigations related to structure work, at the Transportation Laboratory in Sacramento, California.

The Department assumes no responsibility for conclusions or interpretations made by a bidder or contractor based on the information or data made available by the Department. The Department does not assume responsibility for representation made by its officers or agents before the execution of the contract concerning surface or subsurface conditions, unless that representation is expressly stated in the contract.

No conclusions or interpretations made by a bidder or contractor from the information and data made available by the Department will relieve a bidder or contractor from properly fulfilling the terms of the contract.

The bidder shall complete the "List of Subcontractors" form in the Proposal and Contract book, listing the name, address, and portion of work to be performed by each subcontractor listed. In addition to the subcontractors required to be listed in conformance Section 1-1.05, "Required Listing of Proposed Subcontractors," of the Instructions to Bidders, the bidder shall list on this form each first tier Disabled Veteran Business Enterprise subcontractor to be used for credit in meeting the goal. A first tier subcontractor is one to whom the bidder proposes to directly subcontract portions of the work. The Bidder's Bond form mentioned in the last paragraph in Section 1-1.07, "Proposal Guaranty," of the Instructions to Bidders will be found following the signature page of the Proposal.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

Failure of the bidder to fulfill the requirements of the Special Provisions for submittals required to be furnished after bid opening, (including but not limited to DVBE submittals, and escrowed bid documents or prequalification materials when required), may subject the bidder to a determination of the bidder's responsibility in the event it is the apparent low bidder on any subsequent public works contracts.

0.21 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)

It is the policy of the Department that Disabled Veteran Business Enterprises (DVBEs) shall be provided the opportunity for full participation in the performance of contracts financed solely with state funds. The Contractor shall take all necessary and reasonable steps to ensure that DVBEs have such opportunity to participate in the performance of this contract. The Contractor shall not discriminate on the basis of race, color, national origin, or sex in the award and performance of subcontracts.

It is the bidder's responsibility to make a sufficient portion of the work available to subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DVBE subcontractors and suppliers, so as to assure meeting the goal for DVBE participation or to provide information to establish that, prior to bidding, the bidder made good faith efforts to do so.

Section 999, et seq., of the Military and Veterans Code sets forth requirements for DVBE participation goals, summarized as follows:

1. "Disabled Veteran Business Enterprise" (DVBE) means a business concern certified as a DVBE by the Office of Small Business and DVBE Services, Department of General Services.
2. DVBEs must be certified on the date bids for the project are opened before credit may be allowed toward the DVBE goal. It is the Contractor's responsibility to verify that DVBEs are certified.
3. The disabled veteran business owner must be domiciled in the State of California.
4. A DVBE may participate as a prime contractor, as a subcontractor, as a joint venture partner with a prime or subcontractor, or as a vendor of material or supplies.
5. The DVBE must perform a commercially useful function, that is, be responsible for the execution of a distinct element of the work and carry out its responsibility by actually performing, managing, or supervising the work. An extra participant will not be considered to perform a commercially useful function.
6. Credit for DVBE prime contractors will be 100 percent of the contract price.

7. Credit for participation of a DVBE subcontractor, supplier, or broker will be 100 percent provided such DVBE is performing a commercially useful function.
8. A DVBE broker shall submit the required declarations and federal tax returns at the time of performance.

The Office of Small Business and DVBE Services, Department of General Services, is located at 707 Third Street, West Sacramento, CA 95605. It may be contacted at (800) 559-5529 or (916) 375-4940 or its internet web site at <http://www.pd.dgs.ca.gov/smbus/default.htm> for program information.

Failure to carry out the requirements of Section 999, et seq., of the Military and Veterans Code shall constitute a material breach of this contract and may result in termination of the contract or other remedy the Department deems appropriate.

Section 10115 of the Public Contract Code requires the Department to establish a goal for Disabled Veteran Business Enterprise (DVBE) participation in contracts.

A DVBE joint venture partner must be responsible for specific contract items of work, or portions thereof. The DVBE joint venture partner must share in the ownership, control, management responsibilities, risks, and profits of the joint venture. The DVBE joint venture must submit the joint venture agreement with the Caltrans Bidder DVBE Information form required in Division 0.26, "Submission of DVBE Information," elsewhere in these special provisions.

0.215 DVBE GOAL FOR THIS PROJECT

The Disabled Veteran Business Enterprise (DVBE) participation goal for this project: 3 percent.

0.22 SUBMISSION OF DVBE INFORMATION

The required DVBE information shall be submitted on the "CALTRANS BIDDER - DVBE INFORMATION" form included in the Proposal. If this information is not submitted with the bid, the DVBE information forms shall be removed from the documents prior to submitting the bid.

If the DVBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit the DVBE information to the following address: Department of Transportation, MS 43, Attn: Office Engineer, 1727 30th Street, Sacramento, California 95816 so the information is received by the Department no later than 4:00 p.m. on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening. Failure to submit the required DVBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DVBE information unless requested to do so by the Department.

The bidder's DVBE information shall establish that either it met the goal or that, prior to bidding, it made good faith efforts to meet the goal. Information demonstrating that a good faith effort to meet the DVBE goal has been made by the bidder shall be submitted on the "DVBE INFORMATION GOOD FAITH EFFORTS" form included in the Proposal.

Bidders are cautioned that even though their submittal indicates they will meet the stated DVBE goal, their submittal should also include their good faith efforts information along with their DVBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The bidder's DVBE information shall include the names of all DVBE firms that will participate, with a complete description of work or supplies to be provided by each and the dollar value of each DVBE transaction. When 100 percent of a contract item of work is not to be performed or furnished by a DVBE, a description of the exact portion of that work to be performed or furnished by that DVBE shall be included in the DVBE information, including the planned location of that work.

A bidder shall be deemed to have made good faith efforts if, within the time specified by the Department, it submits documentary evidence that all of the following actions were taken:

1. Contact was made with the Office of Small Business and DVBE services, Department of General Services or their web site at <http://www.pd.dgs.ca.gov/smbus/default.htm> to identify Disabled Veteran Business Enterprises.
2. Advertising was published in trade media and media focusing on Disabled Veteran Business Enterprises, unless time limits imposed by the Department do not permit that advertising.
3. Invitations to bid were submitted to potential Disabled Veteran Business Enterprise contractors.
4. Available Disabled Veteran Business Enterprises were considered.

0.23 SMALL BUSINESS AND NON-SMALL BUSINESS SUBCONTRACTOR PREFERENCES

Attention is directed to the Small Business Procurement and Contract Act, Government Code Section 14835, et seq. and to the Small Business regulations at Title 2, California Code of Regulations, Section 1896, et seq.

Bidders, subcontractors, and suppliers who wish to be certified as Small Businesses under the provisions of those laws and regulations, shall be certified as Small Business by the Office of Small Business and DVBE Services, Department of General Services, 707 Third Street, West Sacramento, CA 95605.

Attention is directed to "Award and Execution of Contract" of these special provisions.

0.231 SMALL BUSINESS PREFERENCE

To request Small Business Preference, bidders shall fill out and sign the "Request for Small Business Preference and Non-small Business Subcontractor Preference" form in the Proposal and shall attach a copy of their Office of Small Business and DVBE Services Small Business certification letter to the form. The bidder's signature on the "Request for Small Business Preference" certifies that the bidder is certified as a Small Business at the time and day of bid opening or has applied for certification and is subsequently certified by the Department of General Services.

0.232 NON-SMALL BUSINESS SUBCONTRACTOR PREFERENCE

To request Non-small Business Subcontractor Preference, bidders shall fill out and sign the "Request for Small Business Preference and Non-small Business Subcontractor Preference" form in the Proposal. The bidder's signature certifies that the bidder commits to subcontract at least 25 percent of its bid amount with one or more subcontractors or suppliers that are certified as small businesses.

The bidder shall also fill out the "CALTRANS BIDDER – SMALL BUSINESS SUBCONTRACTOR - INFORMATION" form. If the Small Business Subcontractor information is not submitted with the bid, the form shall be removed from the documents and submitted in the same time and manner specified for DVBE information in "Submission of DVBE Information" of these special provisions. The bidder shall attach a copy of the Office of Small Business and DVBE Services Small Business certification letter for each listed subcontractor or supplier, to the form. The listed subcontractors and suppliers shall be certified as Small Business at the time and day of bid opening or have applied for certification and are subsequently certified by the Department of General Services. Each listed subcontractors or supplier shall be designated to perform a commercially useful function.

0.24 CALIFORNIA COMPANY PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

In conformance with the requirements of Section 6107 of the Public Contract Code, a "California company" will be granted a reciprocal preference for bid comparison purposes as against a nonresident contractor from any state that gives or requires a preference to be given contractors from that state on its public entity construction contracts.

A "California company" means a sole proprietorship, partnership, joint venture, corporation, or other business entity that was a licensed California contractor on the date when bids for the public contract were opened and meets one of the following:

1. Has its principal place of business in California.
2. Has its principal place of business in a state in which there is no local contractor preference on construction contracts.
3. Has its principal place of business in a state in which there is a local contractor construction preference and the contractor has paid not less than \$5000 in sales or use taxes to California for construction related activity for each of the five years immediately preceding the submission of the bid.

To carry out the "California company" reciprocal preference requirements of Section 6107 of the Public Contract Code, all bidders shall fill out and sign the California Company Preference form in the Proposal. The bidder's signature on the California Company Preference form certifies, under penalty of perjury, that the bidder is or is not a "California company" and if not, the amount of the preference applied by the state of the nonresident Contractor.

A nonresident Contractor shall disclose any and all bid preferences provided to the nonresident Contractor by the state or country in which the nonresident Contractor has its principal place of business.

Proposals without the California Company Preference form filled out and signed may be rejected.

0.3 AWARD AND EXECUTION OF CONTRACT

The bidder's attention is directed to the provisions in Section 2, "Award and Execution of Contract," of the Instructions to Bidders and these special provisions for the requirements and conditions concerning award and execution of contract.

Requests for relief of bid and bid protests are to be delivered to the following address: Department of Transportation, MS 43, Attn: Office Engineer, 1727 30th Street, Sacramento, CA 95816 or by facsimile to the Office Engineer at (916) 227-6282.

0.32 INSURANCE POLICIES

The successful bidder shall submit:

1. Copy of its commercial general liability policy and its excess policy, including the declarations page, all amendments, riders, endorsements, and other modifications in effect at the time of contract execution. Standard ISO form No. CG 0001 or similar exclusions are allowed if not inconsistent with Sections 5-1.031, "Indemnification" and 5-1.032, "Insurance." Allowance of any additional exclusions is at the discretion of the Department.
2. Certificate of Insurance showing all other required coverages. Certificates of Insurance, as evidence of required insurance for the auto liability and any other required policy shall set forth deductible amounts applicable to each policy and all exclusions that are added by endorsement to each policy. The evidence of insurance shall provide that no cancellation, lapse, or reduction of coverage will occur without 10 days prior written notice to the Department.

If the successful bidder uses any form of self-insurance, it shall submit:

1. A notice of election to self-insure
2. The coverages for which self-insurance applies
3. The amount of self-insurance
4. Declaration under the penalty of perjury by a certified public accountant certifying the accountant has applied Generally Accepted Accounting Principles (GAAP) guidelines and the successful bidder has sufficient funds or other resources to cover the self-insurance amounts
5. Copy of its commercial general liability policy and its excess policy, including the declarations page, all amendments, riders, endorsements and other modifications in effect at the time of contract execution, for those amounts not covered by self-insurance

The award of the contract, if made, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DVBE participation or has demonstrated, to the satisfaction of the Department, good faith efforts to do so.

The contract shall be signed by the successful bidder and returned, together with the contract bonds and the insurance documents mentioned above within 10 business days of receiving the contract for execution.

Failure of the lowest responsible bidder, the second lowest responsible bidder, or the third lowest responsible bidder to execute the contract within 10 business days of receiving the contract for execution shall be just cause for the forfeiture of the proposal guaranty. The successful bidder may file with the Department a written notice, signed by the bidder or the bidder's authorized representative, specifying that the bidder will refuse to execute the contract if it is presented. The filing of this notice shall have the same force and effect as the failure of the bidder to execute the contract and furnish acceptable bonds within the time specified. The executed contract documents shall be delivered to the following address: Department of Transportation MS 43, Attn: Office Engineer, 1727 30th Street, Sacramento, CA 95816.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract, contract bonds and the insurance documents mentioned above. For the purposes of the form, payee shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 20 percent of payments due the contractor and penalties of up to \$20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

Attention is also directed to "Small Business and Non-small Business Subcontractor Preferences" of these special provisions.

A bidder who is certified as a small business by the Office of Small Business and DVBE Services, Department of General Services, will be allowed a preference in the award of this contract under the following conditions:

1. The bidder filled out and signed the "Request for Small Business Preference and Non-small Business Subcontractor Preference" form, requesting small business preference, and attached a copy of its Office of Small Business and DVBE Services small business certification letter to the form; and
2. The apparent low bidder is not certified as a small business.

A bidder who is not certified as a small business by the Office of Small Business and DVBE Services, Department of General Services, will be allowed a preference in the award of this contract under the following conditions:

1. The bidder filled out and signed the "Request for Small Business Preference and Non-small Business Subcontractor Preference" form, requesting Non-small Business Subcontractor preference and notifying the Department that it commits to subcontract at least 25 percent of its bid amount with one or more small businesses, and submitted the "CALTRANS BIDDER – SMALL BUSINESS SUBCONTRACTOR – INFORMATION" form listing the subcontractors and suppliers it commits to subcontract with; and
2. The apparent low bidder is not certified as a small business, and has not filled out and signed the "Request for Small Business Preference and Non-small Business Subcontractor Preference."

The Small Business preference will be a reduction in the bid submitted by the Small Business Contractor, for bid comparison purposes, by an amount equal to 5 percent of the amount bid by the apparent low bidder, the amount not to exceed \$50,000. If this reduction results in the Small Business Contractor becoming the low bidder, or in a precise tie with a non-small business apparent low bidder, then the contract will be awarded to the Small Business Contractor on the basis of the actual bid of the Small Business Contractor notwithstanding the reduced bid price used for bid comparison purposes.

The Non-small Business Subcontractor preference will be a reduction in the bid submitted by the Non-small Business Contractor requesting the preference, for bid comparison purposes, by an amount equal to 5 percent of the amount bid by the apparent low bidder, the amount not to exceed \$50,000. If this reduction results in the Non-small Business Contractor requesting the preference becoming the low bidder, or in a precise tie with a non-small business apparent low bidder not requesting the preference, then the contract will be awarded to the Non-Small Business Contractor requesting the preference on the basis of its actual bid notwithstanding the reduced bid price used for bid comparison purposes. Application of the Non-small Business Subcontractor preference shall not result in the displacement of a small business in winning the award.

Attention is also directed to "California Company Preference" of these special provisions.

The amount of the California company reciprocal preference shall be equal to the amount of the preference applied by the state of the nonresident contractor with the lowest responsive bid, except where the "California company" is eligible for a California small business preference or a California non-small business subcontractor preference, in which case the preference applied shall be the greater of the two, but not both.

If the bidder submitting the lowest responsive bid is not a "California company" and with the benefit of the reciprocal preference, a "California company's" responsive bid is equal to or less than the original lowest responsive bid, the "California company" will be awarded the contract at its submitted bid price except as provided below.

Small business bidders shall have precedence over nonsmall business bidders in that the application of the "California company" preference for which non-small business bidders may be eligible shall not result in the denial of the award to a small business bidder.

DVBE bidders shall have precedence over non-DVBE bidders in that in the event the application of the small business preference to more than one bidder results in a precise tie in the bid amounts used for comparison purposes, the award shall go to the DVBE that is also a small business. This precedence shall not apply to the application of the California company reciprocal preference.

0.4 BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

Attention is directed to the provisions in Section 6-1.03, "Beginning of Work," Section 6-1.07, "Time of Completion," and Section 6-1.08, "Liquidated Damages," of the General Conditions and these special provisions.

The Contractor shall begin work within 15 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

This work shall be diligently prosecuted to completion before the expiration of **125 WORKING DAYS** beginning on the fifteenth calendar day after approval of the contract.

The Contractor shall pay to the State of California the sum of \$1200 per day, for each and every calendar day's delay in finishing the work in excess of **125 WORKING DAYS**.

0.551 LINES AND GRADES

Stakes or marks will be set by the Engineer in conformance with the requirements in Chapter 12, "Construction Surveys," of the Department's Surveys Manual.

0.552 COST REDUCTION INCENTIVE

Attention is directed to the provisions in Section 2-1.11, "Cost Reduction Incentive," of the General Conditions. The following paragraph is added:

If a cost reduction proposal submitted by the Contractor, and subsequently approved by the Engineer, provides for a reduction in contract time, 50 percent of that contract time reduction shall be credited to the State by reducing the contract working days. Attention is directed to "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions regarding the working days.

0.553 ARCHAEOLOGICAL DISCOVERIES

If archaeological materials, including but not limited to human skeletal material and disarticulated human bone, are discovered at the job site, protect and leave undisturbed and in place archaeological materials in accordance with the following codes and these special provisions:

1. California Public Resources Code, Division 5, Chapter 1.7 § 5097.5
2. California Public Resources Code, Division 5, Chapter 1.75 § 5097.98 and § 5097.99
3. California Administrative Code, Title 14 § 4308
4. California Penal Code, Part 1, Title 14 § 622-1/2
5. California Health and Safety Code, Division 7, Part 1, Chapter 2, § 7050.5

Archaeological materials are the physical remains of past human activity and include historic-period archaeological materials and prehistoric Native American archaeological materials. Nonhuman fossils are not considered to be archaeological except when showing direct evidence of human use or alteration or when found in direct physical association with archaeological materials as described in these special provisions.

Historic-period archaeological materials include cultural remains beginning with initial European contact in California, but at least 50 years old. Historical archaeological materials include:

1. Trash deposits or clearly defined disposal pits containing tin cans, bottles, ceramic dishes, or other refuse indicating previous occupation or use of the site
2. Structural remains of stone, brick, concrete, wood, or other building material found above or below ground or
3. Human skeletal remains from the historic period, with or without coffins or caskets, including any associated grave goods

Prehistoric Native American archaeological materials include:

1. Human skeletal remains or associated burial goods such as beads or ornaments
2. Evidence of tool making or hunting such as arrowheads and associated chipping debris of fine-grained materials such as obsidian, chert, or basalt
3. Evidence of plant processing such as pestles, grinding slabs, or stone bowls
4. Evidence of habitation such as cooking pits, stone hearths, packed or burnt earth floors or
5. Remains from food processing such as concentrations of discarded or burnt animal bone, shellfish remains, or burnt rocks used in cooking

Immediately upon discovery of archaeological materials, stop all work within a 60-foot radius of the archaeological materials and immediately notify the Engineer. Archaeological materials found during construction are the property of the State. Do not resume work within the 60-foot radius of the find until the Engineer gives you written approval. If, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of an archeological find or investigation or recovery of archeological materials, you will be compensated for resulting losses and an extension of time will be granted.

The Department may use other forces to investigate and recover archaeological materials from the location of the find. When ordered by the Engineer furnish labor, material, tools and equipment, to secure the location of the find, and assist in the investigation or recovery of archaeological materials.

0.561 SAMPLING AND TESTING OF MATERIALS

Attention is directed to the provisions in Section 4-1.03, "Sampling and Testing of Materials," of the General Conditions. The following paragraphs are added:

Whenever the provisions of Section 4-1.03, "Sampling and Testing of Materials," of the General Conditions refer to tests or testing, it shall mean tests to assure the quality and to determine the acceptability of the materials and work.

The Engineer will deduct the costs for testing of materials and work found to be unacceptable, as determined by the tests performed by the Department, and the costs for testing of material sources identified by the Contractor which are not used for the work, from moneys due or to become due to the Contractor. The amount deducted will be determined by the Engineer.

0.562 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If performance of the Contractor's current controlling operation is delayed in the area, and the delay could not be avoided by the judicious handling of forces, equipment, and plant, an extension of time determined in conformance with the provisions in Section 6-1.08, "Liquidated Damages," of the General Conditions will be granted. Compensation for the delay will be made only for the Contractor's actual losses due to idle time of equipment, necessary payments for idle time of workers, and cost of extra moving of equipment, in conformance with the provisions in Section 3-1.01E, "Allowable Costs for Changes," of the General Conditions, except that no markups will be added.

0.563 SOLID WASTE DISPOSAL AND RECYCLING REPORT

This work shall consist of reporting disposal and recycling of construction solid waste, as specified in these special provisions. For the purposes of this section, solid waste includes construction and demolition waste debris, but not hazardous waste.

Annually by the fifteenth day of January, the Contractor shall complete and certify Form CEM-4401, "Solid Waste Disposal and Recycling Report," which quantifies solid waste generated by the work performed and disposed of in landfills or recycled during the previous calendar year. The amount and type of solid waste disposed of or recycled shall be reported in either tons or cubic feet. The Contractor shall also complete and certify Form CEM-4401 within 5 days following contract acceptance.

Form CEM-4401, "Solid Waste Disposal and Recycling Report" can be downloaded at:

<http://www.dot.ca.gov/hq/construc/manual2001>

If the Contractor has not submitted Form CEM-4401, by the dates specified above, the Department will withhold the amount of \$10,000 for each missing or incomplete report. The moneys withheld will be released for payment on the next monthly estimate for partial payment following the date that a complete and acceptable Form CEM-4401 is submitted to the Engineer. Upon completion of all contract work and submittal of the final Form CEM-4401, remaining withheld funds associated with this section, "Solid Waste Disposal and Recycling Report," will be released for payment. Withheld funds in conformance with this section shall be in addition to other moneys withheld provided for in the contract. No interest will be due the Contractor on withheld amounts.

0.571 WORKERS' COMPENSATION

Section 5-1.01I, "Workers' Compensation," of the General Conditions is amended to read:

5-1.01I- (Blank)

0.572 INDEMNIFICATION AND INSURANCE

- The Contractor's obligations regarding indemnification of the State of California and the requirements for insurance shall conform to the provisions in Division 0.32, "Insurance Policies," and Division 0.572A, "Indemnification," and Division 0.572B, "Insurance," of this Division 0.572.

0.572A Indemnification

- The Contractor shall defend, indemnify, and save harmless the State, including its officers, employees, and agents (excluding agents who are design professionals) from any and all claims, demands, causes of action, damages, costs, expenses, actual attorneys' fees, losses or liabilities, in law or in equity (Division 0.572A Claims) arising out of or in connection with the Contractor's performance of this contract for:

1. Bodily injury including, but not limited to, bodily injury, sickness or disease, emotional injury or death to persons, including, but not limited to, the public, any employees or agents of the Contractor, the State, or any other contractor; and
2. Damage to property of anyone including loss of use thereof; caused or alleged to be caused in whole or in part by any negligent or otherwise legally actionable act or omission of the Contractor or anyone directly or indirectly employed by the Contractor or anyone for whose acts the Contractor may be liable.

- Except as otherwise provided by law, these requirements apply regardless of the existence or degree of fault of the State. The Contractor is not obligated to indemnify the State for Claims arising from conduct delineated in Civil Code Section 2782 and to Claims arising from any defective or substandard condition of the highway that existed at or before the start of work, unless this condition has been changed by the work or the scope of the work requires the Contractor to maintain existing highway facilities and the Claim arises from the Contractor's failure to maintain. The Contractor's defense and indemnity obligation shall extend to Claims arising after the work is completed and accepted if the Claims are directly related to alleged acts or omissions by the Contractor that occurred during the course of the work. State inspection is not a waiver of full compliance with these requirements.

- The Contractor's obligation to defend and indemnify shall not be excused because of the Contractor's inability to evaluate liability or because the Contractor evaluates liability and determine that the Contractor is not liable. The Contractor shall respond within 30 days to the tender of any Claim for defense and indemnity by the State, unless this time has been extended by the State. If the Contractor fails to accept or reject a tender of defense and indemnity within 30 days, in addition to any other remedy authorized by law, the Department may withhold such funds the State reasonably considers necessary for its defense and indemnity until disposition has been made of the Claim or until the Contractor accepts or rejects the tender of defense, whichever occurs first.

- With respect to third-party claims against the Contractor, the Contractor waives all rights of any type to express or implied indemnity against the State, its officers, employees, or agents (excluding agents who are design professionals).

- Nothing in the Contract is intended to establish a standard of care owed to any member of the public or to extend to the public the status of a third-party beneficiary for any of these indemnification specifications.

0.572B Insurance

0.572B(1) General

- Nothing in the contract is intended to establish a standard of care owed to any member of the public or to extend to the public the status of a third-party beneficiary for any of these insurance specifications.

0.572B(2) Casualty Insurance

- The Contractor shall procure and maintain insurance on all of its operations with companies acceptable to the State as follows:

1. The Contractor shall keep all insurance in full force and effect from the beginning of the work through contract acceptance.
2. All insurance shall be with an insurance company with a rating from A.M. Best Financial Strength Rating of A- or better and a Financial Size Category of VII or better.
3. The Contractor shall maintain completed operations coverage with a carrier acceptable to the State through the expiration of the patent deficiency in construction statute of repose set forth in Code of Civil Procedure Section 337.1.

0.572B(3) Workers' Compensation and Employer's Liability Insurance

- In accordance with Labor Code Section 1860, the Contractor shall secure the payment of worker's compensation in accordance with Labor Code Section 3700.

- In accordance with Labor Code Section 1861, the Contractor shall submit to the Department the following certification before performing the work:

I am aware of the provisions of Section 3700 of the Labor Code which require every employer to be insured against liability for workers' compensation or to undertake self-insurance in accordance with the provisions of that code, and I will comply with such provisions before commencing the performance of the work of this contract.

- Contract execution constitutes certification submittal.
- The Contractor shall provide Employer's Liability Insurance in amounts not less than:
 1. \$1 000 000 for each accident for bodily injury by accident
 2. \$1 000 000 policy limit for bodily injury by disease
 3. \$1 000 000 for each employee for bodily injury by disease

- If there is an exposure of injury to the Contractor's employees under the U.S. Longshoremen's and Harbor Workers' Compensation Act, the Jones Act, or under laws, regulations, or statutes applicable to maritime employees, coverage shall be included for such injuries or claims.

0.572B(4) Liability Insurance

0.572B(4)(a) General

- The Contractor shall carry General Liability and Umbrella or Excess Liability Insurance covering all operations by or on behalf of the Contractor providing insurance for bodily injury liability and property damage liability for the following limits and including coverage for:

1. Premises, operations, and mobile equipment
2. Products and completed operations
3. Broad form property damage (including completed operations)
4. Explosion, collapse, and underground hazards
5. Personal injury
6. Contractual liability

0.572B(4)(b) Liability Limits/Additional Insureds

- The limits of liability shall be at least the amounts shown in the following table:

Total Bid	For Each Occurrence ¹	Aggregate for Products/Completed Operation	General Aggregate ²	Umbrella or Excess Liability ³
≤\$1 000 000	\$1 000 000	\$2 000 000	\$2 000 000	\$5 000 000
>\$1 000 000				
≤\$5 000 000	\$1 000 000	\$2 000 000	\$2 000 000	\$10 000 000
>\$5 000 000				
≤\$25 000 000	\$2 000 000	\$2 000 000	\$4 000 000	\$15 000 000
>\$25 000 000	\$2 000 000	\$2 000 000	\$4 000 000	\$25 000 000
1. Combined single limit for bodily injury and property damage. 2. This limit shall apply separately to the Contractor's work under this contract. 3. The umbrella or excess policy shall contain a clause stating that it takes effect (drops down) in the event the primary limits are impaired or exhausted.				

- The Contractor shall not require certified Small Business subcontractors to carry Liability Insurance that exceeds the limits in the table above. Notwithstanding the limits specified herein, at the option of the Contractor, the liability insurance limits for certified Small Business subcontractors of any tier may be less than those limits specified in the table. For Small Business subcontracts, "Total Bid" shall be interpreted as the amount of subcontracted work to a certified Small Business.

- The State, including its officers, directors, agents (excluding agents who are design professionals), and employees, shall be named as additional insureds under the General Liability and Umbrella Liability Policies with respect to liability arising out of or connected with work or operations performed by or on behalf of the Contractor under this contract. Coverage for such additional insureds does not extend to liability:

1. Arising from any defective or substandard condition of the roadway which existed at or before the time the Contractor started work, unless such condition has been changed by the work or the scope of the work requires the Contractor to maintain existing roadway facilities and the claim arises from the Contractor's failure to maintain;
2. For claims occurring after the work is completed and accepted unless these claims are directly related to alleged acts or omissions of the Contractor that occurred during the course of the work; or
3. To the extent prohibited by Insurance Code Section 11580.04

- Additional insured coverage shall be provided by a policy provision or by an endorsement providing coverage at least as broad as Additional Insured (Form B) endorsement form CG 2010, as published by the Insurance Services Office (ISO), or other form designated by the Department.

0.572B(4)(c) Contractor's Insurance Policy is Primary

- The policy shall stipulate that the insurance afforded the additional insureds applies as primary insurance. Any other insurance or self-insurance maintained by the State is excess only and shall not be called upon to contribute with this insurance.

0.572B(5) Automobile Liability Insurance

- The Contractor shall carry automobile liability insurance, including coverage for all owned, hired, and nonowned automobiles. The primary limits of liability shall be not less than \$1 000 000 combined single limit each accident for bodily injury and property damage. The umbrella or excess liability coverage required under Division 0.572B(4)(b) also applies to automobile liability.

0.572B(6) Policy Forms, Endorsements, and Certificates

- The Contractor shall provide its General Liability Insurance under Commercial General Liability policy form No. CG0001 as published by the Insurance Services Office (ISO) or under a policy form at least as broad as policy form No. CG0001.

0.572B(7) Deductibles

- The State may expressly allow deductible clauses, which it does not consider excessive, overly broad, or harmful to the interests of the State. Regardless of the allowance of exclusions or deductions by the State, the Contractor is responsible for any deductible amount and shall warrant that the coverage provided to the State is in accordance with Division 0.572B, "Insurance."

0.572B(8) Enforcement

- The Department may assure the Contractor's compliance with its insurance obligations. Ten days before an insurance policy lapses or is canceled during the contract period, the Contractor shall submit to the Department evidence of renewal or replacement of the policy.

- If the Contractor fails to maintain any required insurance coverage, the Department may maintain this coverage and withhold or charge the expense to the Contractor or terminate the Contractor's control of the work in accordance with Section 6-1.09, "Termination," of the General Conditions.

- The Contractor is not relieved of its duties and responsibilities to indemnify, defend, and hold harmless the State, its officers, agents, and employees by the Department's acceptance of insurance policies and certificates.

- Minimum insurance coverage amounts do not relieve the Contractor for liability in excess of such coverage, nor do they preclude the State from taking other actions available to it, including the withholding of funds under this contract.

0.572B(9) Self-Insurance

- Self-insurance programs and self-insured retentions in insurance policies are subject to separate annual review and approval by the State.

- If the Contractor uses a self-insurance program or self-insured retention, the Contractor shall provide the State with the same protection from liability and defense of suits as would be afforded by first-dollar insurance. Execution of the contract is the Contractor's acknowledgement that the Contractor will be bound by all laws as if the Contractor were an insurer as defined under Insurance Code Section 23 and that the self-insurance program or self-insured retention shall operate as insurance as defined under Insurance Code Section 22.

0.573 INDEMNIFICATION AND INSURANCE

Attention is directed to the provisions in Section 5-1.03, "(Blank)," of the General Conditions. The section title is amended to read Section 5-1.03, "Indemnification and Insurance."

0.581 SUBCONTRACTING

Attention is directed to the provisions in Section 6-1.01, "Subletting and Subcontracting," of the General Conditions and Division 0.2, "Proposal Requirements and Conditions," and Division 0.3, "Award and Execution of Contract," these special provisions.

Pursuant to the provisions in Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at:

<http://www.dir.ca.gov/DLSE/Debar.html>

Unauthorized substitution of a listed subcontractor may constitute a violation of the "Subletting and Subcontracting Fair Practices Act" and may subject the Contractor to the penalties imposed therein.

The DVBEs listed by the Contractor in response to the provisions in Division 0.22, "Submission of DVBE Information," and Division 0.3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DVBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Unauthorized substitution of a DVBE may also constitute a violation of California Code of Regulations Section 1896.64. The Contractor shall not be entitled to payment for the work or material unless it is performed or supplied by the listed DVBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

The provisions in Division 0.21, "Disabled Veteran Business Enterprise (DVBE)," of these special provisions that DVBEs shall be certified on the date bids are opened does not apply to substitutions after award of the contract.

The Contractor shall maintain records of all subcontracts entered into with certified DVBE subcontractors and records of materials purchased from certified DVBE suppliers. The records shall show the name and business address of each DVBE subcontractor or vendor and the total dollar amount actually paid each DVBE subcontractor or vendor.

The Contractor agrees that the awarding department will have the right to review, obtain and copy all records pertaining to performance of DVBEs during the contract. The Contractor agrees to provide the awarding department with any relevant information requested and shall permit access to its premises, upon reasonable notice, during normal business hours for the purpose of interviewing employees and inspecting and copying such books, records, accounts and other material that may be relevant to a matter under investigation for the purpose of determining compliance with Public Contract Code Section 10115 et seq. The Contractor further agrees to maintain such records for a period of three (3) years after final payment under the contract.

0.5811 NON-SMALL BUSINESS SUBCONTRACTING

The Small Business subcontractors listed by the Contractor in response to the provisions in Division 0.232, "Non-small Business Subcontractor Preference," and Division 0.3, "Award and Execution of Contract," these special provision, which are determined by the Department to be certified as Small Business, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Unauthorized substitution of a Small Business subcontractor may also constitute a violation of California Code of Regulations Section 1896.10 and may subject the Contractor to the sanctions referenced therein.

The provisions in Division 0.232, "Non-small Business Subcontractor Preference," of these special provisions that Small Business subcontractors shall be certified on the date bids are opened does not apply to substitutions after award of the contract.

The Contractor shall maintain records of all subcontracts entered into with certified Small Business subcontractors and records of materials purchased from certified Small Business suppliers. The records shall show the name and business address of each Small Business subcontractor or vendor and the total dollar amount actually paid each Small Business subcontractor or vendor.

The Contractor agrees that the awarding department will have the right to review, obtain and copy all records pertaining to performance of Small Businesses during the contract. The Contractor agrees to provide the awarding department with any relevant information requested and shall permit access to its premises, upon reasonable notice, during normal business hours for the purpose of interviewing employees and inspecting and copying such books, records, accounts and other material that may be relevant to a matter under investigation for the purpose of determining compliance with California Code of Regulations Section 1896, et seq. The Contractor further agrees to maintain such records for a period of three (3) years after final payment under the contract.

0.591 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code and Section 7108.5 of the Business and Professions Code concerning prompt payment to subcontractors.

0.592 PAYMENT OF WITHHELD FUNDS

Attention is directed to the provisions in Section 7-1.06, "Payment of Withheld Funds," of the General Conditions. The following paragraph is added:

Funds withheld from progress payments to ensure performance of the contract that are eligible for payment into escrow or to an escrow agent pursuant to Section 10263 of the California Public Contract Code do not include funds withheld or deducted from payment due to failure of the Contractor to fulfill a contract requirement.

0.593 INTEREST ON PAYMENTS

Interest shall be payable on progress payments, payments after acceptance, final statement, ordered changes in the work payments, and claim payments as follows:

1. Unpaid progress payments, payment after acceptance, and final statements shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
2. Unpaid ordered changes in work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed bill for ordered changes in the work. To be properly submitted, the bill must be submitted within 7 days of the performance of the ordered change in the work and in conformance with the provisions in Section 3, "Changes in the Work," and Section 7-1.05, "Partial Payments," of the General Conditions. An undisputed ordered change in the work bill not submitted within 7 days of performance of the ordered change in the work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
3. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and ordered change in the work payments shall be 10 percent per annum.
4. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of that claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

0.594 NOTICE OF POTENTIAL CLAIM

It is the intention of this section that disputes between the parties arising under and by virtue of the contract be brought to the attention of the Engineer at the earliest possible time in order that the matters may be resolved, if possible, or other appropriate action promptly taken.

Disputes will not be considered unless the Contractor has first complied with specified notice or protest requirements, including Section 3, "Changes in the Work," the notice provisions in Section 2-1.045, "Differing Site Conditions," Section 6-1.07, "Time of Completion," Section 6-1.08, "Liquidated Damages," and Section 5-1.06, "Responsibility for Utilities," of these General Conditions.

For disputes arising under and by virtue of the contract, including an act or failure to act by the Engineer, the Contractor shall provide a signed written initial notice of potential claim to the Engineer within 5 days from the date the dispute first arose. The initial notice of potential claim shall provide the nature and circumstances involved in the dispute which shall remain consistent through the dispute. The initial notice of potential claim shall be submitted on Form CEM-6201A furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655. The Contractor shall assign an exclusive identification number for each dispute, determined by chronological sequencing, based on the date of the dispute.

The exclusive identification number for each dispute shall be used on the following corresponding documents:

1. Initial notice of potential claim
2. Supplemental notice of potential claim
3. Full and final documentation of potential claim
4. Corresponding claim included in the Contractor's written statement of claims

The Contractor shall provide the Engineer the opportunity to examine the site of work within 5 days from the date of the initial notice of potential claim. The Contractor shall proceed with the performance of contract work unless otherwise specified or directed by the Engineer.

Throughout the disputed work, the Contractor shall maintain records that provide a clear distinction between the incurred direct costs of disputed work and that of undisputed work. The Contractor shall allow the Engineer access to the Contractor's project records deemed necessary by the Engineer to evaluate the potential claim within 20 days of the date of the Engineer's written request.

Within 15 days of submitting the initial notice of potential claim, the Contractor shall provide a signed supplemental notice of potential claim to the Engineer that provides the following information:

1. The complete nature and circumstances of the dispute which caused the potential claim
2. The contract provisions that provide the basis of claim
3. The estimated cost of the potential claim, including an itemized breakdown of individual costs and how the estimate was determined
4. A time impact analysis of the project schedule that illustrates the effect on the scheduled completion date due to schedule changes or disruptions where a request for adjustment of contract time is made

The information provided in items 1 and 2 above shall provide the Contractor's complete reasoning for additional compensation or adjustments.

The supplemental notice of potential claim shall be submitted on Form CEM-6201B furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655. The Engineer will evaluate the information presented in the supplemental notice of potential claim and provide a written response to the Contractor within 20 days of its receipt. If the estimated cost or effect on the scheduled completion date changes, the Contractor shall update information in items 3 and 4 above as soon as the change is recognized and submit this information to the Engineer.

Within 30 days of the completion of work related to the potential claim, the Contractor shall provide the full and final documentation of potential claim to the Engineer that provides the following information:

1. A detailed factual narration of events fully describing the nature and circumstances that caused the dispute, including, but not limited to, necessary dates, locations, and items of work affected by the dispute
2. The specific provisions of the contract that support the potential claim and a statement of the reasons these provisions support and provide a basis for entitlement of the potential claim
3. When additional monetary compensation is requested, the exact amount requested calculated in conformance with Section 3, "Changes in the Work," including an itemized breakdown of individual costs. These costs shall be segregated into the following cost categories:
 - 3.1. Labor – A listing of individuals, classifications, regular hours and overtime hours worked, dates worked, and other pertinent information related to the requested reimbursement of labor costs
 - 3.2. Materials – Invoices, purchase orders, location of materials either stored or incorporated into the work, dates materials were transported to the project or incorporated into the work, and other pertinent information related to the requested reimbursement of material costs

- 3.3. Equipment – Listing of detailed description (make, model, and serial number), hours of use, dates of use and equipment rates. Equipment rates shall be at the applicable State rental rate as listed in the Department of Transportation publication entitled "Labor Surcharge and Equipment Rental Rates," in effect when the affected work related to the dispute was performed.
- 3.4. Other categories as specified by the Contractor or the Engineer
4. When an adjustment of contract time is requested the following information shall be provided:
 - 4.1. The specific dates for which contract time is being requested
 - 4.2. The specific reasons for entitlement to a contract time adjustment
 - 4.3. The specific provisions of the contract that provide the basis for the requested contract time adjustment
 - 4.4. A detailed time impact analysis of the project schedule. The time impact analysis shall show the effect of changes or disruptions on the scheduled completion date to demonstrate entitlement to a contract time adjustment.
5. The identification and copies of the Contractor's documents and the substance of oral communications that support the potential claim

The full and final documentation of the potential claim shall be submitted on Form CEM-6201C furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655.

Pertinent information, references, arguments, and data to support the potential claim shall be included in the full and final documentation of potential claim. Information submitted subsequent to the full and final documentation submittal will not be considered. Information required in the full and final documentation of potential claim, as listed in items 1 to 5 above, that is not applicable to the dispute may be exempted as determined by the Engineer. No full and final documentation of potential claim will be considered that does not have the same nature and circumstances, and basis of claim as those specified on the initial and supplemental notices of potential claim.

The Engineer will evaluate the information presented in the full and final documentation of potential claim and provide a written response to the Contractor within 30 days of its receipt unless otherwise specified. The Engineer's receipt of the full and final documentation of potential claim shall be evidenced by postal receipt or the Engineer's written receipt if delivered by hand. If the full and final documentation of potential claim is submitted by the Contractor after acceptance of the work by the Director, the Engineer need not provide a written response.

Provisions in this section shall not apply to those claims for overhead costs and administrative disputes that occur after issuance of the proposed final estimate. Administrative disputes are disputes of administrative deductions or retentions, contract item quantities, contract item adjustments, interest payments, protests of contract change orders as provided in Section 3-1.01D, "Failure to Agree to the Cost of Changes," and protests of the weekly statement of working days as provided in Section 6-1.07, "Time of Completion." Administrative disputes that occur prior to issuance of the proposed final estimate shall follow applicable requirements of this section. Information listed in the supplemental notice and full and final documentation of potential claim that is not applicable to the administrative dispute may be exempted as determined by the Engineer.

Unless otherwise specified in the special provisions, the Contractor may pursue the administrative claim process pursuant to Section 7-1.07, "Final Payment and Claims," for any potential claim found by the Engineer to be without merit.

Failure of the Contractor to conform to specified dispute procedures shall constitute a failure to pursue diligently and exhaust the administrative procedures in the contract, and is deemed as the Contractor's waiver of the potential claim and a waiver of the right to a corresponding claim for the disputed work in the administrative claim process in conformance with Section 7-1.07, "Final Payment and Claims," and shall operate as a bar to arbitration pursuant to Section 10240.2 of the California Public Contract Code.

0.597 FINAL PAYMENT AND CLAIMS

After acceptance by the Director, the Engineer will make a proposed final estimate in writing of the total amount payable to the Contractor, including an itemization of the total amount, segregated by contract item quantities, extra work and other bases for payment, and shall also show each deduction made or to be made for prior payments and amounts to be kept or retained under the provisions of the contract. Prior estimates and payments shall be subject to correction in the proposed final estimate. The Contractor shall submit written approval of the proposed final estimate or a written statement of claims arising under or by virtue of the contract so that the Engineer receives the written approval or statement of claims no later than close of business of the thirtieth day after receiving the proposed final estimate. If the thirtieth day falls on a Saturday,

Sunday or legal holiday, then receipt of the written approval or statement of claims by the Engineer shall not be later than close of business of the next business day. The Contractor's receipt of the proposed final estimate shall be evidenced by postal receipt. The Engineer's receipt of the Contractor's written approval or statement of claims shall be evidenced by postal receipt or the Engineer's written receipt if delivered by hand.

On the Contractor's approval, or if the Contractor files no claim within the specified period of 30 days, the Engineer will issue a final estimate in writing in conformance with the proposed final estimate submitted to the Contractor, and within 30 days thereafter the State will pay the entire sum so found to be due. That final estimate and payment thereon shall be conclusive and binding against both parties to the contract on all questions relating to the amount of work done and the compensation payable therefor, except as otherwise provided in Section 7-1.08, "Clerical Errors."

If the Contractor within the specified period of 30 days files claims, the Engineer will issue a semifinal estimate in conformance with the proposed final estimate submitted to the Contractor and within 30 days thereafter the State will pay the sum found to be due. The semifinal estimate and corresponding payment shall be conclusive and binding against both parties to the contract on each question relating to the amount of work done and the compensation payable therefor, except insofar as affected by the claims filed within the time and in the manner required hereunder and except as otherwise provided in Section 7-1.08, "Clerical Errors."

Except for claims for overhead costs and administrative disputes that occur after issuance of the proposed final estimate, the Contractor shall only provide the following two items of information for each claim:

1. The exclusive identification number that corresponds to the supporting full and final documentation of potential claim
2. The final amount of requested additional compensation

If the final amount of requested additional compensation is different than the amount of requested compensation included in the full and final documentation of potential claim, the Contractor shall provide in the written statement of claims the reasons for the changed amount, the specific provisions of the contract which support the changed amount, and a statement of the reasons the provisions support and provide a basis for the changed amount. If the Contractor's claim fails to provide an exclusive identification number or if there is a disparity in the provided exclusive identification number, the Engineer will notify the Contractor of the omission or disparity. The Contractor shall have 15 days after receiving notification from the Engineer to correct the omission or disparity. If after the 15 days has elapsed, there is still an omission or disparity of the exclusive identification number assigned to the claim, the Engineer will assign the number. No claim will be considered that has any of the following deficiencies:

1. The claim does not have the same nature, circumstances, and basis as the corresponding full and final documentation of potential claim.
2. The claim does not have a corresponding full and final documentation of potential claim.
3. The claim was not included in the written statement of claims.
4. The Contractor did not comply with applicable notice or protest requirements of Sections 3, "Changes in the Work," 2-1.045, "Differing Site Conditions," 6-1.07, "Time of Completion," 6-1.08, "Liquidated Damages," 5-1.06, "Responsibility for Utilities," and 7-1.03, "Notice of Potential Claim" of these General Conditions.

Administrative disputes that occur after issuance of the proposed final estimate shall be included in the Contractor's written statement of claims in sufficient detail to enable the Engineer to ascertain the basis and amounts of those claims.

The Contractor shall keep full and complete records of the costs and additional time incurred for work for which a claim for additional compensation is made. The Engineer or designated claim investigators or auditors shall have access to those records and any other records as may be required by the Engineer to determine the facts or contentions involved in the claims. Failure to permit access to those records shall be sufficient cause for denying the claims.

The written statement of claims submitted by the Contractor shall be accompanied by a notarized certificate containing the following language:

Under the penalty of law for perjury or falsification and with specific reference to the California False Claims Act, Government Code Section 12650 et. seq., the undersigned,

(name) _____ of
(title) _____
(company) _____

hereby certifies that the claim for the additional compensation and time, if any, made herein for the work on this contract is a true statement of the actual costs incurred and time sought, and is fully documented and supported under the contract between parties.

Dated _____
/s/ _____
Subscribed and sworn before me this _____ day
of _____

(Notary Public)
My Commission
Expires _____

Failure to submit the notarized certificate will be sufficient cause for denying the claim.

Any claim for overhead, in addition to being certified as stated above, shall be supported and accompanied by an audit report of an independent Certified Public Accountant. Omission of a supporting audit report of an independent Certified Public Accountant shall result in denial of the claim and shall operate as a bar to arbitration, as to the claim, in conformance with the requirements in Section 10240.2 of the California Public Contract Code. Any claim for overhead shall be subject to audit by the State at its discretion. The costs of performing an audit examination and submitting the report shall be borne by the Contractor. The Department will deduct an offset amount for field and home office overhead paid on all added work from any claim for overhead as appropriate, as determined by the Department. The value of the added work equals the value of the work completed minus the total bid. The home office overhead offset equals 5 percent of the added work. The field office overhead offset equals 5-1/2 percent of the added work. The Certified Public Accountant's audit examination shall be performed in conformance with the requirements of the American Institute of Certified Public Accountants Attestation Standards. The audit examination and report shall depict the Contractor's project and company-wide financial records and shall specify the actual overall average daily rates for both field and home office overhead for the entire duration of the project, and whether the costs have been properly allocated. The rates of field and home office overhead shall exclude unallowable costs as determined in Title 48 of the Federal Acquisition Regulations, Chapter 1, Part 31. The audit examination and report shall determine if the rates of field and home office overhead are:

1. Allowable in conformance with the requirements in Title 48 of the Federal Acquisition Regulations, Chapter 1, Part 31.
2. Adequately supported by reliable documentation.
3. Related solely to the project under examination.

Costs or expenses incurred by the State in reviewing or auditing claims that are not supported by the Contractor's cost accounting or other records shall be deemed to be damages incurred by the State within the meaning of the California False Claims Act.

If the Engineer determines that a claim requires additional analysis, the Engineer will schedule a board of review meeting. The Contractor shall meet with the review board or person and make a presentation in support of the claim. Attendance by the Contractor at the board of review meeting shall be mandatory.

The District Director of the District that administered the contract will make the final determination of any claims which remain in dispute after completion of claim review by the Engineer or board of review meeting.

The final determination of claims will be sent to the Contractor by hand delivery or deposit in the U.S. mail. The Engineer will then make and issue the Engineer's final estimate in writing and within 30 days thereafter the State will pay the entire sum, if any, found due thereon. That final estimate shall be conclusive and binding against both parties to the contract on all questions relating to the amount of work done and the compensation payable therefor, except as otherwise provided in Section 7-1.08, "Clerical Errors."

Failure of the Contractor to conform to the specified dispute procedures shall constitute a failure to pursue diligently and exhaust the administrative procedures in the contract and shall operate as a bar to arbitration in conformance with the requirements in Section 10240.2 of the California Public Contract Code.

0.599 GUARANTEE

Section 7-1.09, "Guarantee," of the General Conditions is amended to read:

7-1.09 GUARANTEE.—The Contractor hereby unconditionally guarantees that the work will be done in conformance with the requirements of the contract, and further guarantees the work of the contract to be and remain free of defects in workmanship and materials for a period of one year from the date of acceptance of the contract, unless a longer guarantee period is required by the special provisions. The Contractor hereby agrees to repair or replace any and all work, together with any other adjacent work which may be displaced in so doing, that may prove to be not in conformance with the requirements of the contract or that may be defective in its workmanship or material within the guarantee period specified, without any expense whatsoever to the Department, ordinary wear and tear and unusual abuse or neglect excepted.

Contract bonds shall remain in full force and effect during the guarantee period.

The Contractor further agrees, that within 10 calendar days after being notified in writing by the Department of any work not in conformance with the requirements of the contract or any defects in the work, the Contractor shall commence and prosecute with due diligence all work necessary to fulfill the terms of this guarantee, and shall complete the work within a reasonable period of time, and, in the event the Contractor fails to comply, the Contractor does hereby authorize the Department to proceed to have the work done at the Contractor's expense and the Contractor shall honor and pay the cost and charges therefor upon demand. The Department shall be entitled to all costs and expenses, including reasonable attorney's fees, necessarily incurred upon the Contractor's refusal to honor and pay the above costs and charges.

DIVISION 1. GENERAL REQUIREMENTS

1.01 SCOPE

The building work described herein and as shown on the plans shall conform to the requirements of the General Conditions and these special provisions.

The building work to be done consists, in general, of constructing a mechanics facility, including related mechanical and electrical work and such other items or details, not mentioned above, that are required by the plans, General Conditions, or these special provisions to be performed, placed, constructed or installed at the McGee Maintenance Station.

1.02 STATE-FURNISHED MATERIALS

Attention is directed to Section 4-1.01, "Materials," of the General Conditions and these special provisions.

The Contractor shall submit a written request to the Engineer for the delivery of State-furnished materials at least 15 days in advance of the date of their intended use. The request shall state the quantity and type of each material.

The Contractor shall be responsible for all materials furnished to him, and shall pay all demurrage and storage charges. State-furnished materials lost or damaged from any cause whatsoever shall be replaced by the Contractor at his expense. The Contractor shall be liable to the Department for the cost of replacing State-furnished material and such costs may be deducted from any monies due or to become due the Contractor.

All State-furnished materials that are not used in the work shall remain the property of the State and shall be delivered to the Engineer.

The following materials will be furnished free of charge to the Contractor at the site of the work:

Sufficient quantities of gasoline, diesel, LPG, lubricants, oils, and asphaltic emulsion, as required, for testing the respective systems.

1.03 AREAS FOR CONTRACTOR'S USE

No area is available within the contract limits for the exclusive use of the Contractor. The Contractor shall arrange with the Engineer for areas to store equipment and materials within the work area.

1.04 COOPERATION

Attention is directed to Sections 5-1.06, "Responsibility for Utilities," and 5-1.12, "Cooperation," of the General Conditions and these special provisions.

Work by State forces will be in progress within the contract limits during the working period for this contract.

The Contractor shall comply with all security policies and normal working hours of the State concerning the McGee Maintenance Station.

The Contractor shall plan his work to minimize interference with State forces and the public. Interruptions to any services for the purpose of making or breaking a connection shall be made only after consultation with and for such time periods as directed by the Engineer.

1.05 MEASUREMENT AND PAYMENT

The contract lump sum price paid for building work shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the building work, complete in place, as shown on the plans, as specified in the General Conditions and these special provisions, and as directed by the Engineer

Full compensation for any incidental materials and labor, not shown on the plans or specified, which are necessary to complete the building work shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

1.06 PROJECT INFORMATION

The information in this section has been compiled specifically for this project and is made available for bidders and Contractors. Bidders and Contractors shall be responsible for knowing the procedures for obtaining information.

Cross sections are not available for this project.

The District Office in which the work is situated is located at 500 South Main Street, Bishop, CA 93514.

1.07 SUBMITTALS

Shop drawings, material lists, descriptive data, samples and other submittals specified in these special provisions shall be submitted for approval in accordance with the provisions in Section 2-1.04, "Shop Drawings, Descriptive Data, Samples, and Alternatives," of the General Conditions and these special provisions

Unless otherwise permitted in writing by the Engineer and except submittals for "Alternatives" in conformance with the provisions of said Section 2-1.04 of the General Conditions, all submittals required by these special provisions shall be submitted within 35 days after the contract has been approved.

Attention is directed to the provisions in Section 2-1.01, "Authority of Engineer," of the General Conditions. The Engineer may request submittals for materials or products where submittals have not been specified in these special provisions, or may request that additional information be included in specified submittals, as necessary to determine the quality or acceptability of such materials or products.

Submittals shall be delivered to the locations indicated in these special provisions. If a specific location is not indicated, the submittal shall be delivered to the Division of Structure Design, Documents Unit, Fourth Floor, Mail Station 9-4/4I, 1801 30th Street, Sacramento, California 95816, telephone (916) 227-8252, or the submittals shall be mailed to the Division of Structure Design, Documents Unit, Mail Station 9-4/4I, P. O. Box 942874, Sacramento, California 94274-0001.

1.08 SCHEDULE OF VALUES

The Contractor shall prepare and submit to the Engineer for approval 2 copies of a Schedule of Values within 15 working days of approval of the contract. The Engineer shall be allowed 15 working days for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete the review within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 6-1.08, "Liquidated Damages," of the General Conditions.

The Schedule of Values shall cover each lump sum item for building work and shall be accurately divided into sections representing the cost of each separate building or structure. Any site work that is not part of a separate building or structure shall be included under a specific section as General Work and not included in the building or structure cost. Indirect costs and general condition items are to be listed as a separate line item of work. The sections representing each building or structure must be identified as to the building or structure they represent and be broken down to show the corresponding value of each craft, trade or other significant portion of the work. A sub-total for each section shall be provided.

The Schedule of Values shall be approved by the Engineer before any partial payment estimate is prepared.

The sum of the items listed in the Schedule of Values shall equal the contract lump sum price for building work. Overhead and profit shall not be listed as separate items, but shall be appropriately distributed across all line items of cost.

1.09 OBSTRUCTIONS

Attention is directed to Sections 5-1.02, "Protection and Use of Property," 5-1.03, "Responsibility for Damage," and 5-1.06, "Responsibility for Utilities," of the General Conditions and these special provisions.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 5 working days prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include but are not limited to the following:

Underground Service Alert
Northern California (USA)
Telephone: 1(800)642-2444

Underground Service Alert
Southern California (USA)
Telephone: 1(800)422-4133

South Shore Utility
Coordinating Council (DIGS)
Telephone: 1(800)541-3447

Western Utilities
Underground Alert, Inc.
Telephone: 1(800)424-3447

1.10 PRESERVATION OF PROPERTY

Attention is directed to Sections 5-1.02, "Protection and Use of Property," 5-1.03, "Responsibility for Damage," 5-1.05, "Contractor's Responsibility for the Work," and 5-1.06, "Responsibility for Utilities," of the General Conditions.

Operations shall be conducted in such a manner that existing facilities, surfacing, installations, and utilities which are to remain in place will not be damaged. Temporary surfacing, facilities, utilities and installations shall also be protected until they are no longer required. The Contractor, at his expense shall furnish and install piling, sheet piling, cribbing, bulkheads, shores, or whatever means may be necessary to adequately support material carrying such facilities, or to support the facilities themselves and shall maintain such support until they are no longer needed.

1.11 WATER POLLUTION CONTROL

Water pollution control work shall conform to the provisions in Section 5-1.01R, "Water Pollution," of the General Conditions and these special provisions.

This project lies within the boundaries of the Lahontan Regional Water Quality Control Board (RWQCB).

The State Water Resources Control Board (SWRCB) has issued a permit to the Department which governs storm water and non-storm water discharges from its properties, facilities and activities. The Department's Permit is entitled: "Order No. 99-06-DWQ, NPDES No. CAS000003, National Pollutant Discharge Elimination System (NPDES) Permit, Storm Water Permit and Waste Discharge Requirements (WDRs) for the State of California, Department of Transportation Properties, Facilities, and Activities." Copies of the Department's Permit are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254, and may also be obtained from the SWRCB Internet website at: <http://www.swrcb.ca.gov/stormwtr/caltrans.html>.

The Department's Permit references and incorporates by reference the current Statewide General Permit issued by the SWRCB entitled "Order No. 99-08-DWQ, National Pollutant Discharge Elimination System (NPDES) General Permit No. CAS000002, Waste Discharge Requirements (WDRs) for Discharges of Storm Water Associated with Construction Activity," which regulates discharges of storm water and non-storm water from construction activities disturbing 2 or more hectares of soil in a common plan of development. Sampling and analysis requirements as specified in SWRCB Resolution No. 2001-46 are added to the Statewide General Permit. Copies of the Statewide General Permit and modifications thereto are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254 and may also be obtained from the SWRCB Internet website at: <http://www.swrcb.ca.gov/stormwtr/construction.html>.

The NPDES permit that regulate this project, as referenced above, are hereafter collectively referred to as the "Permits."

This project shall conform to the Permits and modifications thereto. The Contractor shall maintain copies of the Permits at the premises and shall make the Permits available during construction.

The Permits require the preparation of a Storm Water Pollution Prevention Plan (SWPPP). The SWPPP shall be prepared in conformance with the requirements of the Permits, the Department's "Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Program (WPCP) Preparation Manual," and the Department's "Construction Site Best Management Practices (BMPs) Manual," including addenda issued up to and including the date of advertisement of the project. These manuals are hereinafter referred to, respectively, as the "Preparation Manual" and the "Construction Site BMPs Manual," and collectively, as the "Manuals." Copies of the Manuals may be obtained from the Department of Transportation, Materiel Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520, and may also be obtained from the Department's Internet website at: <http://www.dot.ca.gov/hq/construc/stormwater.html>.

The Contractor shall know and fully comply with applicable provisions of the Permits and all modifications thereto, the Manuals, and Federal, State, and local regulations and requirements that govern the Contractor's operations and storm water and non-storm water discharges from both the premises and areas of disturbance outside the premises during construction. Attention is directed to Sections 5-1.01, "Laws to be Observed," 5-1.031, "Indemnification," and 5-1.032, "Insurance," of the General Conditions.

The Permits shall apply to storm water and certain permitted non-storm water discharges from areas outside the premises which are directly related to construction activities for this contract including, but not limited to, material borrow areas, staging areas, storage yards and access roads. The Contractor shall comply with the Permits and the Manuals for those areas and shall implement, inspect and maintain the required water pollution control practices. Installing, inspecting and maintaining water pollution control practices on areas outside the premises not specifically arranged and provided for by the Department for the execution of this contract, will not be paid for.

The Contractor shall be responsible for penalties assessed or levied on the Contractor or the Department as a result of the Contractor's failure to comply with the provisions in this division, "Water Pollution Control," including, but not limited to, compliance with the applicable provisions of the Permits, the Manuals, and Federal, State and local regulations and requirements as set forth therein.

Penalties as used in this division, "Water Pollution Control," shall include fines, penalties and damages, whether proposed, assessed, or levied against the Department or the Contractor, including those levied under the Federal Clean Water Act and the State Porter-Cologne Water Quality Control Act, by governmental agencies or as a result of citizen suits. Penalties shall also include payments made or costs incurred in settlement for alleged violations of the Permits, the Manuals, or applicable laws, regulations, or requirements. Costs incurred could include sums spent instead of penalties, in mitigation or to remediate or correct violations.

RETENTION OF FUNDS

Notwithstanding any other remedies authorized by law, the Department may retain money due the Contractor under the contract, in an amount determined by the Department, up to and including the entire amount of Penalties proposed, assessed, or levied as a result of the Contractor's violation of the Permits, the Manuals, or Federal or State law, regulations or requirements. Funds may be retained by the Department until final disposition has been made as to the Penalties. The Contractor shall remain liable for the full amount of Penalties until such time as they are finally resolved with the entity seeking the Penalties.

Retention of funds for failure to conform to the provisions in this division, "Water Pollution Control," shall be in addition to the other retention amounts required by the contract. The amounts retained for the Contractor's failure to conform to provisions in this division will be released for payment on the next monthly estimate for partial payment following the date when an approved SWPPP has been implemented and maintained, and when water pollution has been adequately controlled, as determined by the Engineer.

When a regulatory agency identifies a failure to comply with the Permits and modifications thereto, the Manuals, or other Federal, State or local requirements, the Department may retain money due the Contractor, subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to retain funds from partial payments which may become due to the Contractor prior to acceptance of the contract. Retention of funds from payments made after acceptance of the contract may be made without prior notice to the Contractor.
- B. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 7-1.05, "Partial Payments," of the General Conditions.
- C. If the Department has retained funds, and it is subsequently determined that the State is not subject to the entire amount of the Costs and Liabilities assessed or proposed in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained for the period of the retention. The interest rate payable shall be 6 percent per annum.

During the first estimate period that the Contractor fails to conform to the provisions in this division, "Water Pollution Control," the Department may retain an amount equal to 25 percent of the estimated value of the contract work performed.

The Contractor shall notify the Engineer immediately upon request from the regulatory agencies to enter, inspect, sample, monitor, or otherwise access the premises or the Contractor's records pertaining to water pollution control work. The Contractor and the Department shall provide copies of correspondence, notices of violation, enforcement actions or proposed fines by regulatory agencies to the requesting regulatory agency.

STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND AMENDMENTS

As part of the water pollution control work, a Storm Water Pollution Prevention Plan (SWPPP) is required for this contract. The SWPPP shall conform to the provisions in Section 5-1.01R, "Water Pollution," of the General Conditions, the requirements in the Manuals, the requirements of the Permits, and these special provisions. Upon the Engineer's approval of the SWPPP, the SWPPP shall be considered to fulfill the provisions in Section 5-1.01R, "Water Pollution," of the General Conditions for development and submittal of a Water Pollution Control Program.

No work having potential to cause water pollution, shall be performed until the SWPPP has been approved by the Engineer. Approval shall not constitute a finding that the SWPPP complies with applicable requirements of the Permits, the Manuals and applicable Federal, State and local laws, regulations, and requirements.

The Contractor shall designate a Water Pollution Control Manager. The Water Pollution Control Manager shall be responsible for the preparation of the SWPPP and required modifications or amendments, and shall be responsible for the implementation and adequate functioning of the various water pollution control practices employed. The Contractor may designate different Water Pollution Control Managers to prepare the SWPPP and to implement the water pollution control practices. The Water Pollution Control Manager(s) shall serve as the primary contact for issues related to the SWPPP or its implementation. The Contractor shall submit to the Engineer a statement of qualifications, describing the training, previous work history and expertise of the individual selected by the Contractor to serve as Water Pollution Control Manager(s). The Water Pollution Control Manager(s) shall have a minimum of 24 hours of formal storm water management training or certification as a Certified Professional in Erosion and Sediment Control (CPESC). The Engineer will reject the Contractor's submission of a Water Pollution Control Manager if the submitted qualifications are deemed to be inadequate.

Within 10 working days after the approval of the contract, the Contractor shall submit 3 copies of the draft SWPPP to the Engineer. The Engineer will have 5 working days to review the SWPPP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the SWPPP within 5 working days of receipt of the Engineer's comments. The Engineer will have 5 working days to review the revisions. Upon the Engineer's approval of the SWPPP, 4 approved copies of the SWPPP, incorporating the required changes, shall be submitted to the Engineer. In order to allow construction activities to proceed, the Engineer may conditionally approve the SWPPP while minor revisions are being completed. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for resulting losses, and an extension of time will be granted, as provided in Section 6-1.08, "Liquidated Damages," of the General Conditions.

The SWPPP shall apply to the areas within or outside of the premises that are directly related to construction including, but not limited to, material borrow areas, staging areas, storage yards, and access roads.

The SWPPP shall incorporate water pollution control practices in the following categories:

- A. Soil stabilization.
- B. Sediment control.
- C. Wind erosion control.
- D. Tracking control.
- E. Non-storm water management.
- F. Waste management and materials pollution control.

The Contractor shall develop a Water Pollution Control Schedule that describes the timing of grading or other work activities that could affect water pollution. The Water Pollution Control Schedule shall be updated by the Contractor to reflect changes in the Contractor's operations that would affect the necessary implementation of water pollution control practices.

The Contractor shall complete the "Construction Site BMPs Consideration Checklist" presented in the Preparation Manual and shall incorporate water pollution control practices into the SWPPP. Water pollution control practices include the "Minimum Requirements" and other Contractor-selected water pollution control practices from the "Construction Site BMPs Consideration Checklist" and the "Project-Specific Minimum Requirements" identified in the Water Pollution Control Cost Break-Down of this division.

The following work shall be incorporated into the SWPPP as "Temporary Water Pollution Control Practices": Temporary Silt Fence. The Contractor's attention is directed to the special provisions provided for Temporary Water Pollution Control Practices.

The following work, as shown on the project plans or as specified elsewhere in these special provisions, shall be identified in the SWPPP as permanent water pollution control practice: Fiber Roll (Type 2). This permanent water pollution control practice shall be constructed and utilized during the construction period. The Contractor shall maintain and protect the permanent water pollution control practices throughout the duration of the project and shall restore these controls to the lines, grades and conditions shown on the plans prior to acceptance of the contract.

The SWPPP shall include, but not be limited to, the items described in the Manuals, Permits and related information contained in the contract documents. The SWPPP shall also include a copy of the following: Notification of Construction.

The Contractor shall prepare an amendment to the SWPPP when there is a change in construction activities or operations which may affect the discharge of pollutants to surface waters, ground waters, municipal storm drain systems, or when the Contractor's activities or operations violate a condition of the Permits, or when directed by the Engineer. Amendments shall identify additional water pollution control practices or revised operations, including those areas or operations not identified in the initially approved SWPPP. Amendments to the SWPPP shall be prepared and submitted for review and approval within a time approved by the Engineer, but in no case longer than the time specified for the initial submittal and review of the SWPPP.

The Contractor shall keep one copy of the approved SWPPP and approved amendments at the premises. The SWPPP shall be made available upon request by a representative of the Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency, or the local storm water management agency. Requests by the public shall be directed to the Engineer.

COST BREAK-DOWN

The Contractor shall include a Water Pollution Control Cost Break-Down in the SWPPP which itemizes the cost for water pollution control work shown in the SWPPP. The Contractor shall use the Water Pollution Control Cost Break-Down provided in this division as the basis for the cost break-down submitted with the SWPPP. The Contractor shall use the Water Pollution Control Cost Break-Down to identify items, quantities and values for water pollution control work. The Contractor shall be responsible for the accuracy of the SWPPP quantities and values used in the cost break-down submitted with the SWPPP. Partial payment for water pollution control will not be made until the Water Pollution Control Cost Break-Down is approved by the Engineer.

Line items indicated in the Water Pollution Control Cost Break-Down in this division with a specified Estimated Quantity shall be considered "Project-Specific Minimum Requirements." The Contractor shall incorporate Project-Specific Minimum Requirements with Contractor-designated quantities and values into the Water Pollution Control Cost Break-Down submitted with the SWPPP.

Line items indicated in the Water Pollution Control Cost Break-Down in this division without a specified Estimated Quantity shall be considered by the Contractor for selection to meet the applicable "Minimum Requirements" as defined in the Manuals, or for other water pollution control work as identified in the "Construction Site BMPs Consideration Checklist" presented in the Preparation Manual. In the Water Pollution Control Cost Break-Down submitted with the SWPPP, the Contractor shall list only those water pollution control practices selected for the project, including quantities and values required to complete the work for those items.

The sum of the amounts for the work listed in the Water Pollution Control Cost Break-Down shall be equal to the cost shown for water pollution control in the cost break-down for building work. Overhead and profit, shall be included in the individual items listed in the Water Pollution Control Cost Break-Down.

WATER POLLUTION CONTROL COST BREAK-DOWN

Contract No. 09-307904

ITEM	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	VALUE	AMOUNT
SS-9	Earth Dikes/Drainage Swales & Lined Ditches	M			
SS-10	Outlet Protection/Velocity Dissipation Devices	EA			
SS-11	Slope Drains	EA			
SC-1	Silt Fence	M			
SC-2	Desilting Basin	EA			
SC-3	Sediment Trap	EA			
SC-4	Check Dam	EA			
SC-5	Fiber Rolls	M			
SC-6	Gravel Bag Berm	M			
SC-7	Street Sweeping and Vacuuming	LS			
SC-8	Sandbag Barrier	M			
SC-9	Straw Bale Barrier	M			
SC-10	Storm Drain Inlet Protection	EA			
WE-1	Wind Erosion Control	LS			
TC-1	Stabilized Construction Entrance/Exit	EA			
TC-2	Stabilized Construction Roadway	EA			
TC-3	Entrance/Outlet Tire Wash	EA			
NS-3	Paving and Grinding Operations	LS			
NS-6	Illicit Connection/Illegal Discharge Detection and Reporting	LS			
NS-7	Potable Water/Irrigation	LS			
NS-8	Vehicle and Equipment Cleaning	LS			
NS-9	Vehicle and Equipment Fueling	LS			
NS-10	Vehicle and Equipment Maintenance	LS			
WM-1	Material Delivery and Storage	LS			
WM-2	Material Use	LS			
WM-3	Stockpile Management	LS			
WM-4	Spill Prevention and Control	LS			

Contract No. 09-307904

ITEM	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	VALUE	AMOUNT
WM-5	Solid Waste Management	LS			
WM-6	Hazardous Waste Management	LS			
WM-7	Contaminated Soil Management	LS			
WM-8	Concrete Waste Management	LS			
WM-9	Sanitary/Septic Waste Management	LS			
WM-10	Liquid Waste Management	LS			

TOTAL _____

Adjustments in the quantities listed in the approved Water Pollution Control Cost Break-Down shall be made when required to address amendments to the SWPPP, except when the adjusted items are paid for in conformance with the provisions in Section 3, "Changes," of the General Conditions.

No adjustment in compensation will be made for work completed as shown on the approved SWPPP. No adjustment in compensation will be made for ordered changes to correct SWPPP work resulting from the Contractor's own operations or from the Contractor's negligence.

The approved cost break-down will be used to determine partial payments during the progress of the work and as the basis for calculating the adjustment in compensation for increases or decreases of quantities ordered by the Engineer. When an ordered change increases or decreases the quantities of an approved cost break-down item, the adjustment in compensation will be determined in conformance with the provisions in Section 3, "Changes," of the General Conditions. If an ordered change requires a new item which is not on the approved cost break-down, the adjustment in compensation will be determined in conformance with the provisions in Section 3, "Changes," of the General Conditions.

If requested by the Contractor and approved by the Engineer, changes to the water pollution control practices listed in the approved cost break-down, including addition of new water pollution control practices, will be allowed. Changes shall be included in the approved amendment of the SWPPP. If the requested changes result in a net cost increase, an adjustment in compensation will be made. The net cost increase to the lump sum item Building Work will be paid for in conformance with the provisions in Section 3, "Changes," of the General Conditions.

SWPPP IMPLEMENTATION

Unless otherwise specified, upon approval of the SWPPP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting, maintaining, removing, and disposing of the water pollution control practices specified in the SWPPP and in the amendments. Unless otherwise directed by the Engineer, the Contractor's responsibility for SWPPP implementation shall continue throughout temporary suspensions of work ordered in conformance with the provisions in Section 6-1.06, "Temporary Suspension of Work," of the General Conditions. Requirements for installation, construction, inspection, maintenance, removal, and disposal of water pollution control practices shall conform to the requirements in the Manuals and these special provisions.

If the Contractor or the Engineer identifies a deficiency in the implementation of the approved SWPPP or amendments, the deficiency shall be corrected immediately unless requested by the Contractor and approved by the Engineer in writing, but shall be corrected prior to the onset of precipitation. If the Contractor fails to correct the identified deficiency by the date agreed or prior to the onset of precipitation, the project shall be in nonconformance with this division, "Water Pollution Control." Attention is directed to Section 2-1.01, "Authority of Engineer," of the General Conditions, and to "Retention of Funds" of this division for possible nonconformance penalties.

If the Contractor fails to conform to the provisions of this division, "Water Pollution Control," the Engineer may order the suspension of construction operations until the project complies with the requirements of this division.

Implementation of water pollution control practices may vary by season. The Construction Site BMPs Manual and these special provisions shall be followed for control practice selection of year-round, rainy season and non-rainy season water pollution control practices.

Year-Round Implementation Requirements

The Contractor shall have a year-round program for implementing, inspecting and maintaining water pollution control practices for wind erosion control, tracking control, non-storm water management, and waste management and materials pollution control.

The National Weather Service weather forecast shall be monitored and used by the Contractor on a daily basis. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted, the necessary water pollution control practices shall be deployed prior to the onset of the precipitation.

Disturbed soil areas shall be considered active whenever the soil disturbing activities have occurred, continue to occur or will occur during the ensuing 21 days. Non-active areas shall be protected as prescribed in the Construction Site BMPs Manual within 14 days of cessation of soil disturbing activities or prior to the onset of precipitation, whichever occurs first.

Rainy Season Implementation Requirements

Soil stabilization and sediment control practices conforming to the requirements of these special provisions shall be provided throughout the rainy season, defined as between October 15 and May 15.

Throughout the defined rainy season, the active disturbed soil area of the premises shall be not more than 0.6 hectares. The Engineer may approve, on a case-by-case basis, expansions of the active disturbed soil area limit. Soil stabilization and sediment control materials shall be maintained on site sufficient to protect disturbed soil areas. A detailed plan for the mobilization of sufficient labor and equipment shall be maintained to deploy the water pollution control practices required to protect disturbed soil areas prior to the onset of precipitation.

Winter Shutdown

Unless granted a variance by the RWQCB Executive Officer, there shall be neither removal of vegetation nor disturbance of existing ground surface conditions between October 15 of each year and May 1 of the following year, except when there is an emergency situation that threatens the public health or welfare.

Non-Rainy Season Implementation Requirements

The non-rainy season shall be defined as days outside the defined rainy season. The Contractor's attention is directed to the Construction Site BMPs Manual for soil stabilization and sediment control implementation requirements on disturbed soil areas during the non-rainy season. Disturbed soil areas within the project shall be protected in conformance with the requirements in the Construction Site BMPs Manual with an effective combination of soil stabilization and sediment control.

MAINTENANCE

To ensure the proper implementation and functioning of water pollution control practices, the Contractor shall regularly inspect and maintain the construction site for the water pollution control practices identified in the SWPPP. The construction site shall be inspected by the Contractor as follows:

- A. Prior to a forecast storm.
- B. After a precipitation event which causes site runoff.
- C. At 24 hour intervals during extended precipitation events.
- D. Routinely, a minimum of once every two weeks outside of the defined rainy season.
- E. Routinely, a minimum of once every week during the defined rainy season.

The Contractor shall use the Storm Water Quality Construction Site Inspection Checklist provided in the Preparation Manual or an alternative inspection checklist provided by the Engineer. One copy of each site inspection record shall be submitted to the Engineer within 24 hours of completing the inspection.

REPORTING REQUIREMENTS

Report of Discharges, Notices or Orders

If the Contractor identifies discharges into surface waters or drainage systems in a manner causing, or potentially causing, a condition of pollution, or if the project receives a written notice or order from a regulatory agency, the Contractor shall immediately inform the Engineer. The Contractor shall submit a written report to the Engineer within 7 days of the discharge event, notice or order. The report shall include the following information:

- A. The date, time, location, nature of the operation, and type of discharge, including the cause or nature of the notice or order.
- B. The water pollution control practices deployed before the discharge event, or prior to receiving the notice or order.
- C. The date of deployment and type of water pollution control practices deployed after the discharge event, or after receiving the notice or order, including additional measures installed or planned to reduce or prevent reoccurrence.
- D. An implementation and maintenance schedule for affected water pollution control practices.

Report of First-Time Non-Storm Water Discharge

The Contractor shall notify the Engineer at least 3 days in advance of first-time non-storm water discharge events, excluding exempted discharges. The Contractor shall notify the Engineer of the operations causing non-storm water discharges and shall obtain field approval for first-time non-storm water discharges. Non-storm water discharges shall be monitored at first-time occurrences and routinely thereafter.

Annual Certifications

By June 15 of each year, the Contractor shall complete and submit an Annual Certification of Compliance, as contained in the Preparation Manual, to the Engineer.

PAYMENT

Except as provided herein, full compensation for water pollution control shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

Attention is directed to Section 7-1.05, "Partial Payment," and Section 7-1.07, "Final Payment and Claims," of the General Conditions. Payments for prepare storm water pollution prevention plan will be made as follows:

- A. After the SWPPP has been approved by the Engineer, 75 percent of the cost shown in the Water Pollution Control Plan Cost Break-Down for prepare storm water pollution prevention plan will be included in the monthly partial payment estimate.
- B. After acceptance of the contract in conformance with the provisions in Section 7-1.07, "Final Payment and Claims," of the General Conditions, payment for the remaining 25 percent of the cost shown in the Water Pollution Control Plan Cost Break-Down for prepare storm water pollution prevention plan will be made.

10-1.12 FIBER ROLLS

Fiber rolls shall be furnished and installed in conformance with details shown on the plans and these special provisions and as directed by the Engineer.

Fiber rolls shall be installed on excavation and embankment slopes and other disturbed soil areas.

Fiber rolls shall be Type 2.

MATERIALS

Fiber Roll

Fiber roll shall be either:

1. Constructed with a premanufactured blanket consisting of either wood excelsior, rice or wheat straw, or coconut fibers or a combination of these materials. The blanket shall be between 2.0 m and 2.4 m in width and between 20 m and 29 m in length. Wood excelsior shall be individual fibers, of which 80 percent shall be 150 mm or longer in length. The blanket shall have a photodegradable plastic netting or biodegradable jute, sisal, or coir fiber netting on at least one side. The blanket shall be rolled along the width and secured with jute twine spaced 2 m apart along the full length of the roll and placed 150 mm from the ends of each roll. The finished roll shall be between 200 mm and 250 mm in diameter, a minimum of 6 m in length, and shall weigh at least 0.81-kg/m. More than one blanket may be required to achieve the finished roll diameter. When more than one blanket is required, blankets shall be jointed longitudinally with an overlap of 150 mm along the length of the blanket.
2. A premanufactured roll of rice or wheat straw, wood excelsior, or coconut fiber encapsulated within a photodegradable plastic or biodegradable jute, sisal, or coir fiber netting. The netting shall have a minimum durability of one year after installation. The netting shall be secured tightly at each end of the roll. Rolls shall be between 200 mm and 300 mm in diameter. Rolls between 200 mm and 250 mm in diameter shall have a minimum weight of 1.6 kg/m and a minimum length of 6 m. Rolls between 250 mm and 300 mm in diameter shall have a minimum weight of 4.5 kg/m and a minimum length of 3 m.

Stakes

Wood stakes shall be a minimum of 19 mm x 38 mm x 450 mm in size for Type 2 installation. Wood stakes shall be untreated fir, redwood, cedar, or pine and cut from sound timber. They shall be straight and free of loose or unsound knots and other defects which would render them unfit for the purpose intended. Metal stakes shall not be used.

Rope

Rope shall be biodegradable, such as sisal or manila, with a minimum diameter of 6.35 mm.

INSTALLATION

Fiber rolls shall be installed as follows:

1. Fiber rolls (Type 2): Rope and notched stakes shall be used to restrain the fiber rolls against the slope. Stakes shall be driven into the slope until the notch is even with the top of the fiber roll. Rope shall be knotted at each stake and laced between stakes. After installation of the rope, stakes shall be driven into the slope such that the rope will hold the fiber roll tightly to the slope. Furrows will not be required.
2. Fiber rolls shall be placed as shown on the plans.
3. The bedding area for the fiber rolls shall be cleared of obstructions including rocks, clods, and debris greater than 25 mm in diameter before installation.
4. Fiber rolls shall be installed approximately parallel to the slope contour.
5. Fiber rolls shall be installed before the application of other soil stabilization materials in the same area.

If the intended function of the fiber rolls to disperse concentrated water runoff and to reduce runoff velocities is impaired, the Contractor shall take action to repair or replace the fiber rolls. Split, torn, or unraveling rolls shall be repaired or replaced. Broken or split stakes shall be replaced. Sagging or slumping fiber rolls shall be repaired with additional stakes or replaced. Locations where rills and other evidence of concentrated runoff have occurred beneath the rolls shall be corrected. Fiber rolls shall be repaired or replaced within 24 hours of identifying the deficiency.

PAYMENT

Except as provided herein, full compensation for fiber roll (Type 2) shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

Damage to fiber rolls resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

10-1.13 TEMPORARY SILT FENCE

Temporary silt fence shall be furnished, installed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary silt fence shall be one of the water pollution control practices for sediment control. The SWPPP shall include the use of temporary silt fence.

MATERIALS

Temporary silt fence shall either be prefabricated or constructed with silt fence fabric, posts, and fasteners.

Silt Fence Fabric

Silt fence fabric shall be geotextile manufactured from woven polypropylene or polymer material. Silt fence fabric may be virgin, recycled, or a combination of virgin and recycled polymer materials. No virgin or recycled polymer materials shall contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance to the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Silt fence fabric shall conform to the following requirements:

Specification	Requirements
Width, mm, min.	900
Grab tensile strength (25-mm grip), kilonewtons, min. in each direction ASTM Designation: D 4632*	0.55
Elongation, percent minimum in each direction ASTM Designation: D 4632*	15
Permittivity, 1/sec., min. ASTM Designation: D 4491	0.05
Flow rate, liters per minute per square meter, min. ASTM Designation: D 4491	400
Ultraviolet stability, percent tensile strength retained after 500 hours, min. ASTM Designation: D 4355 (xenon-arc lamp and water spray weathering method)	70

* or appropriate test method for specific polymer

Posts

Posts for temporary silt fence shall be one of the following:

1. Untreated fir or pine, a minimum of 34 mm x 40 mm in size, and 1.2 m in length. One end of the post shall be pointed.
2. Steel and have a "U," "T," "L," or other cross sectional shape that can resist failure from lateral loads. The steel posts shall have a minimum mass per length of 1.1 kg/m and a minimum length of 1.2 m. One end of the steel posts shall be pointed and the other end shall be capped with an orange or red plastic safety cap which fits snugly to the steel post. The Contractor shall submit to the Engineer for approval a sample of the capped steel post before installation.

Fasteners

Fasteners for attaching silt fence fabric to posts shall be as follows:

1. When prefabricated silt fence is used, posts shall be inserted into sewn pockets.
2. Silt fence fabric shall be attached to wooden posts with nails or staples as shown on the plans or as recommended by the manufacturer or supplier. Tie wire or locking plastic fasteners shall be used to fasten the silt fence fabric to steel posts. Maximum spacing of fasteners shall be 200 mm along the length of the steel post.

INSTALLATION

Temporary silt fence shall be installed parallel with the slope contour in reaches not to exceed 150 m. A reach is considered a continuous run of temporary silt fence from end to end or from an end to an opening, including joined panels. Each reach shall be constructed so that the elevation at the base of the fence does not deviate from the contour more than 1/3 of the fence height.

The silt fence fabric shall be installed on the side of the posts facing the slope. The silt fence fabric shall be anchored in a trench as shown on the plans. The trench shall be backfilled and mechanically or hand tamped to secure the silt fence fabric in the bottom of the trench.

Mechanically pushing 300 mm of the silt fence fabric vertically through the soil may be allowed if the Contractor can demonstrate to the Engineer that the silt fence fabric will not be damaged and will not slip out of the soil resulting in sediment passing under the silt fence fabric.

The maximum post spacing may be increased to 3 m if the fence is reinforced by a wire or plastic material by prefabrication or by field installation. The field-assembled reinforced temporary silt fence shall be able to retain saturated sediment without collapsing.

Temporary silt fence shall be joined as shown on the plans. The tops of the posts shall be tied together by minimum of 2 wraps of tie wire of a minimum 1.5-mm diameter. The silt fence fabric shall be attached to the posts at the joint as specified in these special provisions.

When no longer required as determined by the Engineer, temporary silt fence shall become the property of the Contractor and be removed and disposed of outside of the highway right of way. Trimming the silt fence fabric and leaving it in place will not be allowed.

Ground disturbance, including holes and depressions, caused by the installation and removal of the temporary silt fence shall be backfilled and repaired in conformance with the provisions in Sections 5-1.02, "Protection and Use of Property," 5-1.03, "Responsibility for Damage," 5-1.05, "Contractor's Responsibility for the Work," and 5-1.06 "Responsibility for Utilities," of the General Conditions.

MAINTENANCE

Temporary silt fence shall be maintained to provide a sediment holding capacity of approximately 1/3 the height of the silt fence fabric above ground. When sediment exceeds this height or when directed by the Engineer, sediment shall be removed. The removed sediment shall be deposited within the project limits so that the sediment is not subject to erosion by wind or by water.

Temporary silt fence shall be repaired or replaced the same day the damage occurs. Damage to the temporary silt fence resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

PAYMENT

Except as provided herein, full compensation for temporary silt fence shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

1.14 UTILITY CONNECTION

The Contractor shall make all arrangements and obtain all permits and licenses required for the extension of and connection to each utility service applicable to this project, shall furnish all labor and materials necessary for such extensions which are not performed or provided by the utility, and shall furnish and install any intermediate equipment required by the serving utilities.

Upon written request by the Contractor, the State will pay all utility permits, licenses, connection charges, and excess length charges directly to the utility. Such request shall be submitted not less than 45 days before service connections are required.

The costs incurred by the Contractor for the extension of utilities beyond the limits shown on the plans, and in furnishing and installing any intermediate equipment required by the serving utilities, will be paid for as an ordered change as provided in Section 3, "Changes in the Work," of the General Conditions.

Full compensation for any costs incurred by the Contractor to obtain the permits and licenses shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

1.15 TEMPORARY UTILITIES

The Contractor may obtain electrical power and water from existing State outlets within the contract limits free of charge for contract operations where such utilities exist, provided that such utility services are in service and are not required by the State for other purposes and subject to the provisions in "Cooperation" of these special provisions.

The Contractor, at his own expense, shall obtain any additional electrical power and water or other utilities required for his operations and shall make and maintain the necessary service connections.

The Contractor shall provide and pay for telephone service he may require. State telephone facilities shall not be used.

The Contractor shall provide adequate temporary lighting to perform the work and allow the Engineer to inspect the project as each portion is completed.

1.16 SANITARY FACILITIES

When operational, State sanitary facilities will be available for use by the Contractor's employees, during normal State working hours. Tools shall not be cleaned nor shall cleaning liquids be disposed of in State sanitary facilities or sewers.

During periods when State-owned sanitary facilities are not operational, the Contractor shall provide and pay for wash facilities, drinking water fixtures and a minimum of two temporary toilet units for State forces. Separate toilet facilities shall be provided for Contractor personnel. Facilities shall include the periodic flushing, waste removal and cleaning of such facilities. Units shall be maintained in a clean and sanitary condition, including a supply of toilet tissue, toilet seat covers, paper towels and paper cups. Waste material shall be disposed of off site in a lawful manner. Temporary toilet units shall be single occupant units of the chemical, aerated recirculation or combustion type, properly vented and fully enclosed with a glass fiber reinforced polyester shell or similar nonabsorbent material.

1.17 REFERENCES

Attention is directed to Section 1-1.26, "Abbreviations," of the General Conditions

When reference is made to the Uniform Building Code (UBC) on the plans or in the special provisions, it shall be the 1997 Uniform Building Code as amended by the 1998 Title 24 California Building Standards Code.

1.18 PROJECT RECORD DRAWINGS

The Contractor shall prepare and maintain one set of project record drawings, using an unaltered set of original project plans, to clearly show all as-constructed information for the project. As a minimum, the information to be shown shall include 1) any plan clarifications or change orders, 2) locations of any underground utilities, or 3) the location, size, type, and manufacturer of all major products or components selected by the Contractor for use in the work.

All markings shall be placed on the project record drawings using red ink or red pencil. Original figures shall not be eradicated nor written over and superseded material shall be neatly lined out. Additional drawings shall be submitted if the required information cannot be clearly shown on the original set of project plans. The additional drawings shall be not less than 279 mm x 432 mm in size and shall have the contract number on each sheet. The Contractor shall sign and date each sheet of the project record drawings to verify that all as-constructed information shown on the drawings is correct.

The Contractor shall periodically review the set of project record drawings with the Engineer during the progress of the work to assure that all changes and other required information are being recorded.

Before completion of the work, the Contractor shall request a review of the project record drawings to determine the completeness and adequacy of them. If the project record drawings are unacceptable, the Contractor shall inspect, measure, and survey the project as necessary to record the required additional information.

The set of completed project record drawings shall be delivered to the Engineer prior to acceptance of the contract.

1.19 FIELD ENGINEERING

This section specifies administrative and procedural requirements for field engineering services to be performed by the Contractor.

Lines and grades.--Such stakes or marks will be set by the Engineer as he determines to be necessary to establish the lines and grades required for the completion of the work shown on the plans and as specified in these special provisions. In general, these will consist of the primary vertical and horizontal control points.

Stakes and marks set by the Engineer shall be carefully preserved by the Contractor. In case such stakes and marks are destroyed or damaged they will be replaced at the Engineer's earliest convenience. The Contractor will be charged for the cost of necessary replacement or restoration of such stakes and marks which in the judgment of the Engineer were carelessly or willfully destroyed or damaged by the Contractor's operations. This charge will be deducted from any moneys due or to become due the Contractor.

All other stakes or marks required to establish the lines and grades required for the completion of the work shall be the responsibility of the Contractor.

Existing utilities and equipment.--The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, the Contractor shall investigate and verify the existence and location of underground utilities and other construction.

Prior to construction, the Contractor shall verify the location and invert elevation at points of connection of sanitary and septic sewers, storm sewer, and water or fire service piping.

Surveys for layout and performance.--The Contractor shall perform all surveys for layout and performance, reduce field notes, and make all necessary calculations and drawings necessary to carry out the work.

The Contractor shall locate and layout site improvements, and other work requiring field engineering services, including pavements, stakes for grading, fill and topsoil placement, utility slopes and invert elevations by instrumentation and similar appropriate means.

Batter boards shall be located and laid out for structures, building foundations, column grids and locations, floor levels and, control lines and levels required for mechanical and electrical work.

Survey accuracy and tolerances.--The tolerances generally applicable in setting survey stakes for foundations, slabs, and underground work shall not exceed the following:

Survey Stakes or Markers	Tolerance
Rough grading or excavation	30 mm
Trimming or preparation of subgrade for roadways	15 mm
Roadway surfacing, steel or concrete pipe	6 mm
Structures or building construction	3 mm

Such tolerance shall not supersede stricter tolerances required by the plans or special provisions, and shall not otherwise relieve the Contractor of responsibility for measurements in compliance therein.

1.20 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the inch-pound (imperial) system which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following requirements:

Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.

Before other non-metric materials and products will be considered for use the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish all information necessary as required to the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision shall be final.

When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, a list of substitutions to be made shall be submitted for approval.

The following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325M	
METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	IMPERIAL SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR REINFORCEMENT	
METRIC BAR DESIGNATION NUMBER AS SHOWN ON THE PLANS	IMPERIAL BAR DESIGNATION NUMBER TO BE SUBSTITUTED
10	3
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

SUBSTITUTION TABLE FOR WELDED PLAIN WIRE REINFORCEMENT, ASTM DESIGNATION: A 185	
	US CUSTOMARY UNITS SIZE TO BE SUBSTITUTED inch ² x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

The sizes in the following tables of materials and products are exact conversions of metric sizes of materials and products and are listed as acceptable equivalents:

Contract No. 09-307904

CONVERSION TABLE FOR SIZES OF: (1) STEEL FASTENERS FOR GENERAL APPLICATIONS, ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55, and (2) HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325 or A 449 DIAMETER	
METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
6, or 6.35	1/4
8 or 7.94	5/16
10, or 9.52	3/8
11, or 11.11	7/16
13 or 12.70	1/2
14, or 14.29	9/16
16, or 15.88	5/8
19, or 19.05	3/4
22, or 22.22	7/8
24, 25, or 25.40	1
29, or 28.58	1-1/8
32, or 31.75	1-1/4
35, or 34.93	1-3/8
38 or 38.10	1-1/2
44, or 44.45	1-3/4
51, or 50.80	2
57, or 57.15	2-1/4
64, or 63.50	2-1/2
70 or 69.85	2-3/4
76, or 76.20	3
83, or 82.55	3-1/4
89 or 88.90	3-1/2
95, or 95.25	3-3/4
102, or 101.60	4

CONVERSION TABLE FOR NOMINAL THICKNESS OF SHEET METAL			
UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED (GALVANIZED) SHEETS	
METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT US STANDARD GAGE inch	METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT GALVANIZED SHEET GAGE inch
7.94	0.3125		
6.07	0.2391		
5.69	0.2242		
5.31	0.2092		
4.94	0.1943		
4.55	0.1793		
4.18	0.1644	4.270	0.1681
3.80	0.1495	3.891	0.1532
3.42	0.1345	3.510	0.1382
3.04	0.1196	3.132	0.1233
2.66	0.1046	2.753	0.1084
2.28	0.0897	2.372	0.0934
1.90	0.0747	1.994	0.0785
1.71	0.0673	1.803	0.0710
1.52	0.0598	1.613	0.0635
1.37	0.0538	1.461	0.0575
1.21	0.0478	1.311	0.0516
1.06	0.0418	1.158	0.0456
0.91	0.0359	1.006 or 1.016	0.0396
0.84	0.0329	0.930	0.0366
0.76	0.0299	0.853	0.0336
0.68	0.0269	0.777	0.0306
0.61	0.0239	0.701	0.0276
0.53	0.0209	0.627	0.0247
0.45	0.0179	0.551	0.0217
0.42	0.0164	0.513	0.0202
0.38	0.0149	0.475	0.0187

CONVERSION TABLE FOR WIRE		
METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT USA STEEL WIRE THICKNESS	GAGE NO.
mm	inch	
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

CONVERSION TABLE FOR COMMON NAILS				
NAIL SIZE	METRIC mm		ENGLISH inch	
	Length	Diameter	Length	Diameter
8d	63.5	3.33	2 1/2	0.131
10d	76.2	3.76	3	0.148
16d	88.9	4.11	3 1/2	0.162

CONVERSION TABLE FOR LUMBER	
METRIC NOMINAL SURFACE DRY SIZE	EQUIVALENT NOMINAL SURFACE DRY U S SIZE
mm	inch
51	2
102	4
152	6
203	8
254	10
305	12

CONVERSION TABLE FOR PLYWOOD	
METRIC mm	ENGLISH inch
6.4	1/4
7.9	5/16
9.5	3/8
11.1	7/16
11.9	15/32
12.7	1/2
15.1	19/32
15.9	5/8
18.3	23/32
19.1	3/4
22.2	7/8
25.4	1
28.6	1 1/8

CONVERSION TABLE FOR INSULATION R-VALUE	
METRIC (K m ² /W)	ENGLISH (HR FT ² F/BTU)
0.5	3
0.7	4
1.4	8
1.9	11
2.3	13
2.5	14
3.3	19
5.3	30

CONVERSION TABLE FOR VAPOR TRANSMISSION RATING	
METRIC (Perm-m)	ENGLISH (perm-inch)
0.29	0.02

CONVERSION TABLE FOR LOW PRESSURE	
METRIC (Pa)	ENGLISH (Inches of Water Column)
30	0.125
60	0.25
90	0.375
120	0.50
150	0.60
155	0.625
175	0.70
185	0.75
200	0.80
250	1.00
310	1.25

CONVERSION TABLE FOR PRESSURE	
METRIC (kPa)	ENGLISH (psi)
10	1.5
210	30
280	40
350	50
690	100
860	125
1040	150
1100	160
1210	175
1380	200
1730	250
2070	300
2170	315
2410	350
2590	375
2760	400
4830	700
5170	750
5520	800
13800	2000
17200	2500
20700	3000
27600	4000
34500	5000
137900	20000

CONVERSION TABLE FOR MIL THICKNESS	
METRIC (mm)	ENGLISH (inch/1000)
0.10	4
0.13	5
0.15	6
0.50	20
0.75	30
1.00	40

CONVERSION TABLE FOR HVAC DUCTING.	
METRIC (mm)	ENGLISH (inch)
100	4
125	5
150	6
175	7
200	8
225	9
250	10
300	12
360	14
410	16
460	18
510	20
560	22
610	24
660	26
710	28
760	30

CONVERSION TABLE FOR MECHANICAL PIPING		
METRIC (GSP, PVC, BSP, DUCTILE IRON)	METRIC (mm)	ENGLISH (inch)
NPS 1/2	15	1/2
NPS 3/4	20	3/4
NPS 1	25	1
NPS 1 1/4	32	1 1/4
NPS 1 1/2	40	1 1/2
NPS 2	50	2
NPS 2 1/2	65	2 1/2
NPS 3	75	3
NPS 4	100	4
NPS 6	150	6

CONVERSION TABLE FOR LUBRICATION PIPING TUBING WALL THICKNESS	
METRIC (mm)	ENGLISH (inch)
2.1	0.083
0.9	0.035

CONVERSION TABLE FOR HOSE/TUBING SIZES O. D.	
METRIC (mm)	ENGLISH (inch)
6	1/4
10	3/8
13	1/2
16	5/8
19	3/4
22	7/8
25	1

CONVERSION TABLE FOR DRUM SIZES			
METRIC		ENGLISH	
L	kg	gallons	pounds
205	180	55	400
60	55	16	120
19	16	5	35

CONVERSION TABLE FOR POWER	
METRIC (kW)	ENGLISH (HP)
0.037	1/20
0.075	1/10
0.18	1/4
0.25	1/3
0.37	1/2
0.55	3/4
0.75	1
1.1	1 1/2
1.5	2
2.2	3
3.7	5
5.5	7 1/2
7.5	10
11	15
15	20
18.5	25
22	30
30	40
37	50
45	60
55	75
75	100
90	120
110	150

CONVERSION TABLE FOR IMPELLER BALANCE		
SYNCHRONOUS RPM	METRIC (g mm/kg)	ENGLISH (ounce- inch/pound)
720	94	0.059
900	73	0.046
1200	54	0.034
1800	41	0.026
3600	17	0.011

CONVERSION TABLE FOR ELECTRICAL CONDUIT	
METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
16	1/2
21	3/4
27	1
35	1 1/4
41	1 1/2
53	2
103	4

DIVISION 2. SITEWORK

2.01 CLEARING AND GRUBBING

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of removing all objectionable material from the building site in accordance with the details shown on the plans and these special provisions.

Clearing and grubbing shall be performed in advance of any other grading or construction operations.

The area to be cleared and grubbed shall be within the building work construction area and within the excavation and embankment slope lines.

SITE CONDITIONS.--

Protection of existing landscaping and trees.--Existing landscaping and trees which are to remain in place shall be protected from injury or damage. Existing trees shall be protected with a temporary fence around the drip line.

PART 2.- PRODUCTS (Not applicable.)

PART 3.- EXECUTION

SITE CLEARING.--

General.--Remove trees, shrubs, grass and other vegetation, concrete and masonry, improvements, or obstructions interfering with the new construction.

Trees to be removed shall be grubbed to a depth of not less than 0.6 meter below finished grade.

REMOVAL OF WASTE MATERIAL.--

Hauling.--When hauling is done over highways or city streets, and when directed by the Engineer, the loads shall be trimmed and all material removed from shelf areas of the vehicles.

Disposal.--Trees, shrubs, grass, weeds and other vegetation, debris, and any obstructions above or below the ground surface that interfere with the building work, shall be removed and disposed of off the premises.

2.02 EARTHWORK FOR BUILDING WORK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of performing earthwork for building work in accordance with the details shown on the plans and these special provisions.

Earthwork for building work shall consist of structure excavation and structure backfill. Structure excavation shall include excavation for footings, foundations, slabs, and trenches. Structure backfill shall include backfilling under slabs; backfilling under and around footings; backfilling for pipes and conduits; backfilling holes resulting from removal of existing facilities. In addition to structure excavation and structure backfill, earthwork for building work shall include any other earthwork, not mentioned, but necessary to complete the building work.

Attention is directed to the requirements of "Field Engineering" in Division 1, "General Requirements," of these special provisions.

QUALITY ASSURANCE.--

Samples.--Samples of sand weighing not less than 11 kg, shall be submitted to the Engineer at the jobsite for approval.

SITE CONDITIONS.--

Existing underground piping and conduit.--The location of existing underground piping and conduit is based on the best records available. Before beginning work, the Contractor shall accurately locate the piping and conduit involved in the work. If the location of the existing piping or conduit deviates from the location shown on the plans by more than 1.5 meters, or, if no elevations are indicated and the piping or conduit is more than 0.9 meter below grade, the cost of the additional excavation, backfill, piping or conduit, and removal and replacement of concrete, if any, will be paid for as an ordered change in accordance with the requirements specified in Section 3, "Changes in the Work," of the General Conditions.

Existing surfaced or planted areas.--Existing surfaced or planted areas that are removed, broken or damaged by the Contractor's operations shall be restored to their original condition except as otherwise shown on the plans or specified herein.

Restoration materials shall be equal to or better than the original materials. Surfacing shall be replaced to match the material thickness, grades, and finish of the adjacent surrounding surfaces.

PART 2.- PRODUCTS

BACKFILL MATERIALS.--

Structure backfill.--

Structure and trench backfill shall be free of organic and other deleterious material and shall be suitable for the required compaction. Gravel without sand matrix shall not be used except as free draining granular material beneath slabs and footings.

Sand.--

Sand shall be clean, washed sand, free from clay or organic material graded such that 100 percent passes the 6 mm sieve, 90 percent to 100 percent passes the 4.75 mm sieve and not more than 5 percent passes the 75 µm sieve size.

PART 3.- EXECUTION

PREPARATION & RESTORATION.--

Sawcutting.--Prior to excavation or trenching, existing surfacing shall be removed to saw cut lines, or to existing wood dividers or expansion joints, if any. The saw cut shall be to a neat line and have a depth not less than 25 mm.

Restoration.--Surfacing shall be replaced to match the thickness, grades and finish of the adjacent surrounding surfaces.

STRUCTURE EXCAVATION.--

General.--Unless otherwise noted, all excavation for building work shall be classified as structure excavation.

Footing excavation.--The bottom of excavations shall not be disturbed. The contractor shall excavate by hand to the final grade. The bottom of concrete footings shall be poured against undisturbed material. Unless otherwise noted, compaction of the bottom of footing excavation is not required unless the material is disturbed. The footing depths shown on the plans shall be changed to suit field conditions when directed by the Engineer. Solid rock at or near required depths shall not be disturbed. Unsuitable material shall be excavated down to firm bearing as directed by the Engineer. Work and materials required because of excavation in excess of the depths shown on the plans, when such excavation has been ordered by the Engineer, will be paid for as an ordered change in accordance with the requirements in Section 3, "Changes in the Work," of the General Conditions.

Excavate to the elevations and dimensions within a tolerance of ± 12 mm. Limits of the excavation shall allow for adequate working space for installing materials and as required for safety of personnel. Such working space excavation shall be replaced in kind and compacted at the Contractor's expense.

Overdepth excavation for footings shall be backfilled with concrete or such other material recommended by the Contractor and approved by the Engineer. Relative compaction shall be not less than 95 percent.

Excavation for pipes and conduits.--Pipes or conduits in the same trench shall have a minimum clear distance between pipes or conduits of 150 mm. Pipes or conduits shall have not less than 0.75 meter of cover from top of pipes or conduits to finished grade unless otherwise shown on the plans or specified.

Trenching shall be of sufficient depth to permit placing a minimum depth of 100 mm of compacted sand under all pipes and conduits.

Excavation adjacent to trees shall be performed by hand methods where necessary to avoid injury to trees and roots. Roots 50 mm in diameter and larger shall be protected with heavy burlap. Roots smaller than 50 mm in diameter adjacent to trees shall be hand trimmed. Cuts through roots 13 mm in diameter and larger shall be sealed with tree trimmers' asphaltic emulsion. If trenches remain open more than 24 hours, the side of the trench adjacent to the tree shall be shaded with burlap and kept damp. Materials shall not be stockpiled within the drip line of trees.

Dewatering.--Excavations shall be kept clear of standing water. Water shall be removed by pumping if necessary. Water removed from excavation shall be carried away from the building site and disposed of in a manner that will not harm State or adjacent property.

STRUCTURE BACKFILLING.--

General.--Unless otherwise noted, all backfill for building work shall be classified as structure backfill. Backfill shall be placed and compacted in horizontal layers, not more than 150 mm thick prior to compaction, and to the lines and grades shown on the plans or to original ground.

Structure backfill.--After structures are in place and forms are removed, wood and other debris shall be removed from excavations before placing structure backfill.

Backfilling pipes and conduits.--Backfill placed under pipe and conduits shall be compacted sand, 100 mm minimum depth. Backfill material placed to a level 150 mm above tops of pipes and conduits shall be sand or fine earth and particles shall not exceed 13 mm in greatest dimension. For wrapped, coated, or plastic pipe or conduits, sand shall be used for backfill. Backfill material placed higher than 150 mm above tops of pipes or conduits shall consist of material free of stones or lumps exceeding 100 mm in greatest dimension except:

- (a) The top 300 mm of backfill under walks or paving shall consist of aggregate base material.
- (b) The top 150 mm of backfill in planted areas shall consist of topsoil.

COMPACTION.--

General.--Relative compaction shall be determined in accordance with California Test 216 or 231. Unless otherwise noted below, all backfill shall be compacted to a minimum relative compaction of 90 percent. Unless approved in writing by the Engineer, compaction by jetting or ponding will not be permitted.

Compact original ground.--Original ground surface under fill with surfacing of concrete and asphalt concrete shall be compacted to a relative compaction of not less than 95 percent for a minimum depth of 150 mm.

Subgrade preparation.--Preparation of subgrade material for placing aggregate base, surfacing, or slabs thereon shall include fine grading, compaction, reworking as necessary. The upper 150 mm of the subgrade shall have the same compaction as the fill to be placed over it.

The prism of backfill directly underneath the building foundation and sloping downward at 1:1 shall be compacted to 95 percent.

Structure backfill.--Structure backfill shall be compacted to not less than 95 percent relative compaction.

Trench backfill.--Trench backfill placed beneath slabs or paved areas shall be compacted to a relative compaction of not less than 95 percent.

DISPOSAL.--

Surplus material.--Surplus material from the excavation shall be disposed of away from the premises.

FIELD QUALITY CONTROL.--

Inspection.--When the excavation is substantially completed to grade, the Contractor shall notify the Engineer. No concrete shall be placed until the foundation has been approved by the Engineer.

Testing.--The State will conduct compaction tests during the backfilling and compacting operations.

2.03 FREE DRAINING GRANULAR MATERIAL

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and placing free draining granular material beneath slabs in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Free draining granular material.--

Free draining granular material shall be clean, hard, durable, free-draining rock. The material gradation shall be such that all passes the 25 mm screen, and not more than 10 percent passes the 4.75 mm sieve as determined by California Test 202. Granular material shall be free from organic material, clay balls or other deleterious substances.

PART 3.- EXECUTION.--

SPREADING AND CONSOLIDATING.--

General.--Free draining granular material shall be placed, spread and consolidated by tamping or vibrating.

2.04 ASPHALT CONCRETE

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing, spreading, placing and compacting asphalt concrete for asphalt concrete surfacing, asphalt concrete dike, applying asphaltic emulsion paint binder and fog seal coat, in accordance with the details shown on the plans and these special provisions.

Asphalt concrete shall be commercial quality, produced at a central mixing plant, 13 mm maximum, medium grade, as specified herein.

Areas to be surfaced with asphalt concrete shall be as shown on the plans. Areas to be surfaced with asphalt concrete shall include those locations where existing bituminous surfacing has been removed to facilitate the required work. Asphalt concrete dike shall be placed as shown on the plans.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of Compliance shall be furnished for asphalt concrete and asphaltic emulsion in accordance with the requirements specified in Section 4-1.04, "Certificates of Compliance," of the General Conditions.

PART 2.- PRODUCTS

MATERIALS.--

Asphalts.--

Asphalt binder for asphalt concrete shall be steam-refined paving asphalt Grade AR-4000 (asphalt graded by viscosity), conforming to the requirements in AASHTO Designation: M 226.

Asphalt emulsion for paint binder and fog seal coat shall be asphaltic emulsion Grade SS1h conforming to the requirements in AASHTO Designation: M 140.

Aggregates.--

Aggregate for asphalt concrete shall be commercial quality asphalt concrete aggregate, and shall have a Sand Equivalent value of 30 minimum, when determined by California Test 217.

The combined aggregate gradings for the respective asphalt concrete mixture shall conform to the following gradations when determined by California Test 202:

13 mm Maximum Grading	
Sieve Sizes	Percentage Passing
19 mm	100
13 mm	95 - 100
4.75 mm	55 - 72
600 µm	18 - 33
75 µm	4 - 8

MIXING.--

General.--Asphalt binder to be mixed with the aggregate shall be between 5 percent and 8 percent by weight of the dry aggregate as determined by the Engineer.

PART 3.- EXECUTION

PREPARATION.--

Subgrade.--Immediately prior to placing asphalt concrete thereon, the surface of the grading plane shall not vary more than 0.015 meter above or below the grade established by the Engineer.

At the time of placing the asphalt concrete material thereon, the moisture content of the subgrade shall not be more than 3 percent above or below the optimum moisture content of the subgrade material as determined by California Test 216.

Paint binder.--Paint binder shall be furnished and applied to all existing surfacing upon which asphalt concrete is to be placed, vertical surfaces against which additional asphalt concrete material is to be placed and other surfaces designated by the Engineer.

SPREADING AND COMPACTING.--

Spreading.--The mixture shall be spread at a temperature of not less than 121°C. Spreading shall be performed by methods that will produce an asphalt concrete surfacing of uniform smoothness and texture. Asphalt concrete shall be placed only when the atmospheric temperature is above 10°C.

Compacting.--Asphalt concrete shall be placed in one or more layers of 0.04 meter or less in compacted thickness to match the thickness as shown on the plans. The first coverage of initial or breakdown compaction shall be performed when the temperature of the mixture is not less than 121°C, and all breakdown compaction shall be completed before the temperature of the mixture drops below 93°C.

Asphalt concrete shall be thoroughly compacted with a self-propelled tandem roller, weighing not less than 7260 kg. At locations where asphalt concrete is to be placed and which are inaccessible to rolling equipment, compaction shall be obtained by hand rollers, vibrating plates, impactors or other methods approved by the Engineer.

FOG SEAL.--

General.--A fog seal coat of asphaltic emulsion shall be applied to all new, completed, asphalt concrete. The fog seal coat shall be applied in one application at a rate between 0.22 liter and 0.45 liter of bituminous binder per square meter of surface covered. The exact rate of application will be determined by the Engineer.

The spraying equipment used for the application of the fog seal coat shall be suitable for the intended use and shall be capable of producing a uniform application of emulsion material in the amounts specified herein. Application shall be at the pressures and temperatures recommended by the spray equipment manufacturer. Hand spray equipment shall be approved by the Engineer.

2.05 PAINTED PAVEMENT MARKINGS

PART 1.- GENERAL.--

Scope.--This work shall consist of furnishing and applying paint for pavement markings in accordance with the details shown on the plans and these special provisions.

Pavement markings include, but are not limited to, word and symbol markings, and parking stall markings.

Alternatives.--At the option of the Contractor, striping tape may be placed instead of the painted pavement markings specified herein.

PART 2.- PRODUCTS.--

Paint.--

Paint shall be top commercial quality for pavement marking, formulated for the use intended, and manufactured by a nationally recognized manufacturer of paint and other coating products.

The kind of paint to be used (solvent or water borne) shall be determined by the Contractor, based on local air pollution control regulations and weather conditions.

Striping tape.--

Striping tape shall be permanent type striping tape. Striping tape shall be Brite-Line, Series 1000; Swarco Industries, Director; 3M Stamark Brand, Pliant Polymer Grade Series 5730; 3M Stamark Brand, Bisymmetric 1.75 Grade Series 5730; or equal.

PART 3.- EXECUTION.--

ALIGNMENT AND LAYOUT.--All necessary alignment and layout work shall be performed by the Contractor, in a manner that will not damage the pavement.

Unless otherwise shown on the plans, the width of parking stall markings shall be 105 mm.

EQUIPMENT AND OPERATION.--Mechanical means shall be used to paint pavement markings.

All equipment used in the application of paint shall produce pavement markings of uniform quality.

All spray equipment shall be the proper type and of adequate capacity for the work involved.

Air atomized spray equipment shall be equipped with oil and water extractors and pressure regulators, and shall have adequate air volume and compressor recovery capacity. Spray gun tip needle assemblies and orifices shall be the proper size.

Rapid dry paint shall be applied only with airless type equipment.

Stencils and hand spray equipment shall be used to paint word and symbol markings. Stencils shall be furnished by the Contractor. The stencil layout shall conform to the dimensions shown on the plans.

SURFACE PREPARATION.--Surfaces which are to receive paint shall be cleaned of all dirt and loose material.

APPLICATION.--Paint shall be applied only on dry surfaces, and only during periods of favorable weather, in accordance with the manufacturer's recommendations.

On new surfacing, paint shall be applied in 2 coats. The first coat shall be dry before application of the second coat is applied.

On existing surfacing, paint shall be applied in one coat.

Completed pavement markings shall have clean and well-defined edges, and shall conform to the dimensions shown on the plans or as specified in these special provisions.

Drips, oversprays, improper markings, and paint material tracked by traffic shall be immediately removed from the pavement by methods approved by the Engineer. All such removal shall be at the Contractor's expense.

If used, striping tape shall be applied in accordance with the manufacturer's specifications.

APPLICATION RATES.--Each application of paint shall be applied at the rates recommended by the paint manufacturer for the type of surface involved.

PROTECTION.--Newly placed pavement markings shall be protected from damage by traffic or other causes until the paint is thoroughly dry.

DISABLED ACCESSIBLE PARKING STALL SYMBOL.--Each parking space reserved for persons with physical disabilities shall have a minimum 0.9 m x 0.9 m surface identification with the international symbol of accessibility. The symbol and border shall be white and the background shall be blue conforming to Federal Standard 595B, Color No. 15090.

2.06 GUARD POSTS

PART 1.- GENERAL

Scope.--This work shall consist of constructing guard posts in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Steel posts.--

Steel posts for guard posts shall be standard weight, galvanized steel pipe conforming to the details shown on the plans.

Concrete.--

Concrete for guard posts shall be commercial quality concrete, proportioned to provide a workable mix suitable for the intended use, with not less than 300 kilograms of cement per cubic meter.

PART 3.- EXECUTION

Installation.--The length and diameter of the guard posts shall conform to the details shown on the plans.

Guard posts shall be placed in holes excavated to the depth and cross section shown on the plans, and shall be installed plumb.

Guard posts shall be backfilled with concrete as shown on the plans.

Painting.--Guard posts shall be prepared and painted in accordance with the requirements specified under "Painting" in Division 9, "Finishes," of these special provisions.

2.07 ACCESSIBLE PARKING AND AUTHORIZATION SIGNS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing accessible parking and authorization signs in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and sign fastening details shall be submitted for approval.

PART 2.- PRODUCTS

Accessible parking stall identification sign.--

Accessible parking stall identification sign shall be a metal sign with baked enamel finish and the international symbol of accessibility. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Symbol, lettering and border shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Van accessible sign.--

Van accessible sign shall be a metal sign with baked enamel finish and the international symbol of accessibility. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Lettering and border shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Unauthorized vehicles parking sign.--

Unauthorized vehicles parking sign shall be a metal sign with baked enamel finish. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Lettering and border shall be white and shall conform to Federal Standard 595B, Color No. 17886. Lettering shall be not less than 25 mm in height and shall read as shown on the plans.

Support post.--

Support post shall be commercial quality, standard weight, galvanized steel pipe. Pipe diameter shall be 35 mm.

Fastening hardware.--

Fastening hardware shall be galvanized or cadmium plated.

Concrete.--

Concrete for support posts shall be commercial quality concrete, proportioned to provide a workable mix suitable for the intended use, with not less than 300 kilograms of cement per cubic meter.

PART 3.- EXECUTION

Installation.--Support posts shall be placed in holes excavated to the depth and cross-section shown on the plans. Posts shall be set vertical and shall be firmly embedded in concrete backfill. The top of the concrete backfill around the post shall be crowned to drain water.

Support posts shall be fitted with a rainproof top.

Sign shall be fastened rigidly and securely to the support post.

The Engineer will provide the Contractor with the necessary information for the disabled authorization sign.

2.08 SALVAGE FENCE

Existing fence, where shown on the plans to be salvaged, shall be removed and salvaged.

Salvaged fence materials shall be stockpiled at the McGee Creek Maintenance Station yard at a location as designated by the Engineer.

Existing concrete foundations shall be completely removed and disposed of.

2.09 AGGREGATE BASE

PART 1.-GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing, spreading and compacting aggregate base in accordance with the details shown on the plans and these special provisions.

PART 2.-PRODUCTS

Aggregate base.--

Aggregate base shall be commercial quality aggregates consisting of broken stone; crushed gravel; natural, clean, rough-surfaced gravel and sand; or a combination thereof.

Aggregate base shall conform to the following grading as determined by California Test 202:

Sieve or Screen Size	Percentage Passing
25 mm	100
19 mm	90 - 100
4.75 mm	35 - 60
600 µm	10 - 30
75 µm	2 - 9

Aggregate base shall also conform to the following quality requirements:

Tests	California Test No.	Test Requirements
Durability Index	229	35 Min.
Resistance (R-Value)	301	78 Min.
Sand Equivalent	217	22 Min.

PART 3.-EXECUTION

SPREADING AND COMPACTING.--

Spreading.--Aggregate base shall be placed and compacted to the lines and grades shown on the plans.

Spreading and compacting shall be performed by methods that will produce a uniform base, free from pockets of coarse or fine material.

Compaction.--Relative compaction of each layer of compacted base material shall be not less than 95 percent, as determined by California Test 216 or 231.

DIVISION 3. CONCRETE AND REINFORCEMENT

3.01 CAST-IN-PLACE CONCRETE

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of constructing cast-in-place concrete facilities in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for admixtures, expansion joint material, vapor barrier, hardener, and sealer shall be submitted for approval.

Descriptive data shall be delivered to the Engineer at the jobsite.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of Compliance shall be furnished for cement, reinforcement, and admixtures in accordance with the requirements specified in Section 4-1.04, "Certificates of Compliance," of the General Conditions.

PART 2.- PRODUCTS

CONCRETE MIXES.--

Concrete (structural work).--

Commercial quality concrete shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 350 kg/m³ of cement; 0 to 50 mm penetration, inclusive, as determined by California Test 533.

The air content of the freshly mixed concrete shall be $6 \pm 1 \frac{1}{2}$ percent, as determined by California Test 504.

Concrete (minor work).--

Commercial quality concrete for aprons and pads shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 300 kg/m³ of cement; 0 to 50 mm penetration, inclusive, as determined by California Test 533.

The air content of the freshly mixed concrete shall be $6 \pm 1 \frac{1}{2}$ percent, as determined by California Test 504.

CONCRETE MATERIALS.--

Cement.--

Cement shall conform to ASTM Designation: C 150, Types II, or III portland cement; or Type IP (MS) Modified cement. Type IP (MS) Modified shall conform to ASTM Designation: C 595 and shall be comprised of an intimate mixture of Type II Modified cement and not more than 20 percent of a pozzolanic material.

Aggregates.--

Aggregates shall be free from deleterious coatings, clay balls and other extraneous materials.

Aggregates proposed for use shall conform to the requirements for freezing and thawing shall as determined by California Test 528.

A list of sources of aggregates which have previously passed the freeze-thaw test is available in the District Office at 500 South Main Street, Bishop, CA 93514.

Admixtures.--

Admixtures used in portland cement concrete shall be included on the Department's current list of approved admixtures, and shall conform to ASTM Designation: C 494, Types A, B, D, F or G for chemical admixtures; ASTM Designation: C 260 for air-entraining admixtures; and ASTM Designation: C 618 for mineral admixtures, except loss on ignition shall not exceed 4 percent. Properties of admixtures shall be uniform in each lot.

FORM MATERIALS.--

Forms for exposed finish concrete.--

Forms for exposed surfaces shall be plywood, metal or other panel type materials. Plywood shall be not less than 16 mm thick and without scars, dents, and delaminations. Forms shall be furnished in largest practical pieces to minimize number of joints.

Plywood shall conform to the requirements of U. S. Product Standard PS-1 for Exterior B-B (Concrete Form) Class I.

Forms for edges of slabs shall be nominal 50 mm solid stock lumber, plywood, or metal forms.

Forms for unexposed finish concrete.--

Forms for unexposed finish concrete surfaces shall be plywood, lumber, metal or other acceptable material.

Form ties.--

Form ties shall be factory fabricated, removable or snapoff metal ties for use as necessary to prevent spreading of forms during concrete placement.

Form oil.--

Form oil shall be commercial quality form oil which will permit the ready release of the forms and will not discolor the concrete.

REINFORCING MATERIALS.--

Bar reinforcement.--

Bar reinforcement shall conform to ASTM Designation: A 615/A 615M, Grade 60 [420], or ASTM Designation: A 706/A 706M.

Bar supports.--

Bar supports for reinforcement shall be precast mortar blocks or ferrous metal chairs, spacers, metal hangers, supporting wires, and other approved devices of sufficient strength to resist crushing under applied loads.

RELATED MATERIALS.--

Expansion joint material.--

Expansion joint material shall be commercial quality asphalt impregnated pressed fiber sheets, 13 mm minimum thickness.

Vapor barrier.--

Vapor barrier shall be commercial quality polyethylene sheets not less than 0.15 mm thick.

Type A control joints.--

Type A control joints shall be commercial quality, preformed, T-shaped plastic strips with detachable top flange.

Keyed construction joint forms.--

Keyed construction joint forms shall be commercial quality, galvanized metal or plastic, factory fabricated construction joint forms. Forms shall produce a rabbeted key type joint.

Mortar.--

Mortar shall consist of one part cement to 2 parts clean sand and only enough water to permit placing and packing.

Curing compound.--

Curing compound shall be a non-pigmented curing compound with fugitive dye conforming to the requirements of ASTM Designation: C 309, Type 1-D, Class A.

Concrete hardener.--

Concrete hardener shall be commercial quality water borne penetrating type magnesium fluosilicate, zinc fluosilicate or combination thereof.

Concrete sealer.--

Concrete sealer shall be commercial quality VOC-compliant, silane type sealer with hydrophobic and oleophobic properties. Concrete sealer shall be ProSoCo, Inc., Standoff Tile and Masonry Protector (TMP); Tamms Industries, Hey'Di H.O.S.; Textured Coatings of America, Inc., Rainstopper 1750W-Clear; or equal.

ADMIXTURES.--

General.--Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option to conserve cement or to facilitate any construction operation.

Calcium chloride shall not be used in any concrete.

Admixtures shall be combined with concrete materials by methods that produce uniform properties throughout the concrete.

If more than one admixture is used, said admixtures shall be compatible with each other so that the desirable effects of all admixtures will be realized.

Mineral admixtures may be used to replace up to 15 percent of Type II portland cement provided the weight of mineral admixture used is not less than the weight of cement replaced. Mineral admixtures shall not be used to replace Type IP (MS) Modified or Type III cements. Chemical admixtures may be used to reduce up to 5 percent of the portland cement except that the cement content shall not be less than 300 kg/m³. When both chemical and mineral admixtures are used with Type II cement, the weight of cement replaced by mineral admixture may be considered as cement in determining the resulting cement content.

Mineral admixtures will be required in the manufacture of concrete containing aggregates that are determined to be "deleterious" or "potentially deleterious" when tested in accordance with ASTM Designation: C 289. The use of mineral admixture in such concrete shall conform to the requirements in this section except that the use of set retarding admixtures will not be permitted.

When the use of a chemical admixture is specified or is ordered by the Engineer, the admixture shall be used at the rate specified or ordered. If no rate is specified or ordered, or if the Contractor uses a chemical admixture for his own convenience, the admixture shall be used at the dosage normally recommended by the admixture manufacturer.

When air-entrainment is specified or is ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce concrete having the specified or ordered air content as determined by California Test 504. If the Contractor uses air-entrainment for his own convenience, the average air content shall not exceed 4 percent and no single test shall exceed 5 1/2 percent.

Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers shall have sufficient capacity to measure at one time the total quantity required for each batch. If more than one liquid admixture is used in the concrete, a separate measuring unit shall be provided for each liquid admixture and dispensing shall be such that the admixtures are not mixed at high concentrations. When air-entraining admixtures are used with other liquid admixtures, the air-entraining admixtures shall be the first to be incorporated into the mix. Unless liquid admixtures are added to premeasured water for the batch, they shall be discharged to flow into the stream of water so that the admixtures are well dispersed throughout the batch.

BAR REINFORCING STEEL.--

Bending.--Reinforcing steel bars shall accurately conform to the dimensions shown on the plans.

Bars shall be bent or straightened in a manner that will not crack or break the material. Bars with kinks or improper bends shall not be used.

Hooks, bends and splices shall conform to the provisions of the Building Code Requirements for Reinforced Concrete of the American Concrete Institute.

MIXING AND TRANSPORTING CONCRETE.--

General.--When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be complete within 1 1/2 hours, or before 250 revolutions of the drum or blades, whichever comes first, after the introduction of cement to the aggregates.

Truck mixers or agitator shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified. The counters shall be of the continuous-registering type, which accurately register the number of revolutions and shall be mounted on the truck so that the Engineer may safely and conveniently inspect them from alongside the truck. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, a time less than 1 1/2 hours may be required.

When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be complete within one hour after the introduction of cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C, or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.

The temperature of mixed concrete, immediately before placing, shall be not less than 10°C nor more than 32°C.

Each load of concrete for the work shall be accompanied by a trip ticket, a copy of which shall be delivered to the Engineer at the jobsite. The trip ticket shall show volume of concrete, weight of cement and aggregates, quantity of each admixture, quantity of water including water added at the jobsite, time of day the concrete is batched, and revolution counter readings on transit mix trucks at the times the truck is charged and unloaded.

PART 3.- EXECUTION

PREPARATION.--

Forms.--Forms shall be mortar tight, true to the dimensions, lines, and grades shown on the plans, securely fastened and supported, and of adequate rigidity to prevent distortion during placing of concrete.

Forms for exposed surfaces shall be constructed with triangular fillets not less than 19 mm x 19 mm attached so as to prevent mortar runs and to produce smooth straight chamfers at all sharp edges of the concrete.

Form fasteners shall be removable without chipping, spalling, heating or otherwise damaging the concrete surface. Form ties shall be removed to a depth of at least 25 mm below the surface of the concrete.

The inside surfaces of forms shall be cleaned of all dirt, mortar and foreign material. Forms shall be thoroughly coated with form oil prior to use.

Forms shall not be stripped until at least 40 hours after placing concrete, except soffit forms and supports shall not be released or removed until at least 10 days after placing concrete.

Anchorage and embedded items shall be placed and rigidly secured at their planned locations prior to placing concrete.

Reglets or embedded flashing shall be installed on concrete forms before the concrete is placed.

Vapor barrier.--Vapor barrier shall be lapped 150 mm and securely taped at splices. Vapor barrier shall be protected with a 75 mm layer of clean uncompacted sand cover.

Unless otherwise shown on the plans, vapor barrier shall be placed under portions of the floor slab scheduled to receive finish flooring.

Placing reinforcing steel.--Reinforcing steel bars shall be accurately placed to the dimensions shown on the plans.

Bar reinforcement shall be lapped at least 45 diameters.

Bars shall be firmly and securely held in position by means of wiring and approved bar supports. The spacing of supports and ties shall prevent displacement of the reinforcing or crushing of supports.

Tie wire shall be clear of concrete formwork and concrete surfaces.

All reinforcing steel shall be in place and inspected before concrete placement begins. Placing of bars on fresh layers of concrete will not be permitted.

Ground bar.--A continuous reinforcing steel bar shall be installed in the building foundation at the location indicated on the plans for the electrical ground bar. The use of epoxy coated reinforcing bar is not permitted. The end of the ground bar shall extend beyond the concrete surface and shall be protected from damage by construction operations.

PLACING CONCRETE.--

General.--Concrete shall be placed and consolidated by means of internal vibrators to form dense, homogeneous concrete free of voids and rock pockets.

Forms and subgrade shall be thoroughly moistened with water immediately before placing concrete.

Concrete shall be placed as nearly as possible to its final location and the use of vibrators for extensive shifting of the concrete will not be permitted.

Concrete shall be deposited and consolidated in a continuous operation within limits of construction joints, until the placing of the panel or section is completed.

When concrete is to be placed in large areas requiring more than two pours, concrete shall be placed in alternate long strips between construction joints and the final slab infilled.

FINISHING CONCRETE SURFACES.--

Finishing unformed surfaces.--Slabs shall be placed full thickness to finish elevation and leveled to screeds by use of long straightedges. The screeds shall be set to grade at approximately 1.8 meter centers. After leveling, screeds shall be removed and the surface shall be floated with wooden floats.

Type A control joint strips shall be inserted into the floated concrete so that the bottom of the top flange is flush with the finish elevation. Strips shall be standard manufactured lengths and shall be placed on an approximate straight line. The top flange of the strips shall be removed after the concrete has set and cured.

The floated surface shall be trowelled with steel trowels. Troweling shall form a dense, smooth and true finish. Walkways and outdoor slabs for pedestrian traffic shall be given a non-slip broom finish unless a different finish is called for on the plans or in these special provisions.

The application of cement dust coat will not be permitted.

Steel trowel finish and broom finish will not be required for slabs to receive exposed aggregate finish.

Finished surfaces of floor slabs shall not deviate more than 3 mm from the lower edge of a 3-meter long straight edge.

Finishing formed surfaces.--Formed concrete surfaces shall be finished by filling holes or depressions in the surface, repairing all rock pockets, and removing fins. All surfaces of formed concrete exposed to view shall have stains and discolorations removed, unsightly bulges removed, and all areas which do not exhibit the required smooth, even surface of uniform texture and appearance shall be sanded with power sanders or other approved abrasive means until smooth, even surfaces of uniform texture and appearance are obtained.

Cement mortar, patching and finishing materials used to finish exposed surfaces of concrete shall closely match the color of surrounding surfaces.

CURING CONCRETE.--

General.--Freshly placed concrete shall be protected from premature drying and excessive cold or hot temperatures.

Initial curing of floor slabs shall start as soon as free water has disappeared from the concrete surface. The concrete shall be kept continuously wet by application of water for not less than 7 days after the concrete has been placed.

Cotton mats, rugs, carpets, or sand blankets may be used as a curing medium to retain the moisture during the curing period. Curing materials that will stain or discolor concrete shall not be used on surfaces exposed to view.

Prior to placing the curing medium, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing mediums.

Concrete surfaces, other than floor slabs, shall be kept moist for a period of at least 5 days by leaving the forms in place or by covering the exposed surfaces using moist rugs, cotton mats or other curing materials approved by the Engineer.

Concrete collars and pads may be cured with a curing compound.

PROTECTING CONCRETE.--

General.--Concrete shall not be placed on frozen or frost covered surfaces.

Concrete shall be protected from damage due to rain, freezing or inclement weather, and shall be maintained at a temperature of not less than 4°C for 72 hours. When required by the Engineer, the Contractor shall provide a written outline of his proposed methods of protecting concrete.

Vehicles, equipment, or concentrated loads weighing more than 140 kg individually and material stockpiles weighing more than 240 kg/m² will not be permitted on the concrete within 10 calendar days after placing.

SPECIAL TREATMENTS.--

Concrete hardener.--Chemical concrete hardener shall be applied to the floor surfaces shown on the plans, prior to the application of concrete sealer. Surfaces shall be clean and dry before the application of hardener.

The solution shall be applied in accordance with the manufacturer's instructions.

After the hardener has dried, the surface shall be mopped with water to remove encrusted salts.

Concrete sealer.--Concrete sealer shall be applied to the concrete surfaces designated on the plans in accordance with the manufacturer's instructions for heavy duty use. The sealer shall be applied to dry concrete surfaces.

DIVISION 4. MASONRY (Blank)

DIVISION 5. METALS

5.01 BUILDING MISCELLANEOUS METAL

PART 1.- GENERAL

Scope.--This work shall consist of fabricating, furnishing and installing building miscellaneous metal in accordance with the details shown on the plans and these special provisions.

Building miscellaneous metal shall consist of angles, rods, and all anchors, fastenings, hardware, accessories and other supplementary parts necessary to complete the work.

SUBMITTALS.--

Product data.--Submit manufacturer's specifications, anchor details and installation instructions for products used in miscellaneous metal fabrications.

Shop drawings.--Shop drawings of fabricated items shall be submitted for approval.

Contract No. 09-307904

QUALITY ASSURANCE.--

Shop assembly.--Preassemble items in shop to the greatest extent possible to minimize field splicing and assembly. Disassemble units only as necessary for shipping and handling limitations. Clearly mark all units for reassembly and installation.

Inspection and tests.--Materials and fabrication procedures shall be subject to inspection and tests by the Engineer, in mill, shop and field. Such tests will not relieve the Contractor of responsibility of providing materials and fabrication procedures in compliance with specified requirements.

PART 2.- PRODUCTS

MATERIALS.--

Steel hot-rolled shapes.--

Steel hot-rolled shapes shall conform to ASTM Designation: A 36/A 36M.

Anchor bolts, threaded rods, nuts and washers.--

Nonheaded anchor bolts shall conform to ASTM Designation: A 36/A 36M, with a minimum hook length of 6.2 diameters.

Headed anchor bolts shall conform to ASTM Designation: A 307, Grade A.

Threaded rods shall conform to ASTM Designation: A 36/A 36M.

Nuts shall conform to ASTM Designation: A 563M, Grade A.

Washers for anchor bolts shall be commercial quality.

Exposed anchor bolts, nuts, and washers shall be hot dipped galvanized.

Mechanical expansion anchors.--

Expansion anchors shall be ICBO approved for the purpose intended, integral stud type anchor or internally threaded type with independent stud, hex nut and washer.

Powder driven anchors.--

Powder driven anchors shall be plated, spring steel alloy drive pin or threaded stud type anchors for use in concrete or steel. Spring steel shall conform to ASTM Designation: A 227M, Class 1. The diameter, length and type of shank and the number and type of washer shall be as recommended by the manufacturer for the types and thickness of material being anchored or fastened.

Mortar.--

Mortar shall consist of one part cement, measured by volume, to 2 parts clean sand and only enough water to permit placing and packing.

FABRICATION.--

Workmanship and finish.--Workmanship and finish shall be equal to the best general practice in modern shops.

Miscellaneous metal shall be clean and free from loose mill scale, flake rust and rust pitting, and shall be well formed and finished to shape and size with sharp lines and angles. Bends from shearing or punching shall be straightened.

The thickness of metal and details of assembly and support shall give ample strength and stiffness.

Built-up parts shall be true to line and without sharp bends, twists and kinks. Exposed ends and edges of metal shall be milled or ground smooth, with corners slightly rounded.

Joints exposed to the weather shall be made up to exclude water.

Galvanizing.--Items indicated on the plans to be galvanized shall be hot-dip galvanized after fabrication. The weight of galvanized coating shall be at least 460 grams per square meter of surface area.

Painting.--Building miscellaneous metal items not galvanized shall be cleaned and prime painted prior to erection in accordance with the requirements specified for steel and other ferrous metals under "Painting" in Division 9, "Finishes," of these special provisions.

PART 3.- EXECUTION

GENERAL.--

Anchorage.--Anchorage devices and fasteners shall be provided for securing miscellaneous metal in-place construction; including threaded fasteners for concrete inserts, toggle bolts, through bolts, lag bolts, wood screws and other connectors.

Cutting, drilling and fitting shall be performed as required for installation of miscellaneous metal fabrications. Work is to set accurately in location, alignment and elevation, plumb, level, true and free of rack, measured from established lines and levels.

Powder driven anchors.--Powder driven anchors shall be installed with low velocity powder actuated equipment in accordance with the manufacturer's instructions and State and Federal OSHA regulations.

DAMAGED SURFACES.--

General.--Galvanized surfaces that are abraded or damaged at any time after the application of the zinc coating shall be repaired by thoroughly wire brushing the damaged areas and removing all loose and cracked coating, after which the clean areas shall be painted with 2 applications of unthinned zinc-rich primer (organic vehicle type). Aerosol cans shall not be used.

DIVISION 6. WOOD AND PLASTICS

6.01 ROUGH CARPENTRY

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing materials and performing rough carpentry work including wood framing, furring, and sheathing in accordance with the details shown on the plans and these special provisions.

Rough carpentry includes carpentry work not specified as part of other sections and which is generally not exposed.

SUBMITTALS.--

Product Data.--Manufacturer's material data and installation instructions shall be submitted for gypsum sheathing, framing hardware and underlayments.

Wood treatment data.--Chemical treatment manufacturer's instructions shall be submitted for the handling, sorting, installation, and finishing of treated materials.

For each type of preservative treatment used, certification by treating plant shall include type of preservative solution and pressure process used, net amount of preservative retained and conformance with the applicable standards of the American Wood Preservers Association.

DELIVERY, HANDLING AND STORAGE.--

Delivery and storage.--Materials shall be kept under cover and dry. All materials shall be protected from exposure to weather and contact with damp or wet surfaces with blocking and stickers. All lumber, plywood and other panels shall be stacked in such a manner to provide air circulation within and around the stacks.

PART 2.- PRODUCTS

LUMBER.--

General.--Lumber shall be manufactured to comply with PS 20, "American Softwood Lumber Standard," and with applicable grading rules of inspection.

Softwood lumber shall be quality grade stamped or shall be accompanied by a certificate of inspection. Inspection certificates or grade stamps shall indicate compliance with the grading requirements of WWPA, WCLIB, RIS, or other approved lumber inspection agencies.

All lumber used shall be nominal sized and dressed S4S unless otherwise specified in these special provisions.

Framing lumber shall be solid stock lumber, Douglas Fir-Larch, and the grades indicated under WCLIB or WWPA rules. Moisture content shall not exceed 19 percent and shall be grade stamped "S-Dry."

DIMENSION LUMBER.--

Except as otherwise shown on the plans, lumber shall have the following grades.

Vertical framing lumber.--

Vertical framing lumber, nominal 51 mm x 51 mm through 102 mm x 102 mm, shall be Construction grade or better.

Vertical framing lumber, nominal 51 mm x 152 mm through 102 mm x 152 mm shall be No. 2 or better.

Horizontal framing lumber.--

Horizontal framing lumber, nominal 51 mm x 102 mm and wider, including joists and rafters, shall be No. 2 or better.

Horizontal framing lumber, nominal 102 mm x 102 mm and wider, including joist and rafters, shall be No. 1 or better.

Exposed framing lumber.--

Exposed framing lumber which is not concealed and is to receive a stain or natural finish shall be the same grade and species as indicated for structural framing and hand selected for appearance.

Miscellaneous lumber.--

Miscellaneous lumber for support or attachment of other work including rooftop equipment curbs and support bases, cant strips, bucks, nailers, blocking, furring, grounds, stripping and similar members shall be not less than No. 2 or better.

Lumber in contact with concrete construction shall be pressure treated Douglas Fir-Larch.

PLYWOOD PANELS.--

General.—Plywoodpanels shall comply with Voluntary Product Standard PS1, "U. S. Product Standard for Construction and Industrial Plywood."

Plywood panels shall be Group 1 unless otherwise noted.

Each plywood panel shall be factory marked with APA or other trademark evidencing compliance with grade requirements.

Structural plywood wall sheathing.--

Structural plywood wall sheathing for walls shall be APA RATED SHEATHING, Exposure 1. Thickness and grade shall be as shown on the plans.

Structural plywood roof sheathing.--

Structure plywood roof sheathing shall be APA RATED SHEATHING, Exposure 1. Span rating, thickness and grade shall be as shown on the plans.

MISCELLANEOUS MATERIALS.--

Rough Carpentry Hardware.--

Steel plates and rolled sections shall be mild, weldable steel, conforming to AISI grades 1016 through 1030 except 1017.

Nails, screws, bolts, nuts, washers shall be commercial quality. Exposed fasteners shall be hot dipped galvanized or stainless steel.

Joist hangers, clips and other standard framing hardware shall be ICBO approved, commercial quality, galvanized sheet steel or hot dipped galvanized, of the size shown on the plans.

Expansion anchors and powder driven anchors shall be as specified under "Building Miscellaneous Metal," in Division 5, "Metals," of these special provisions.

Nails.--

Nails shall conform to ASTM F 1667-95. "Common" nails shall conform to the following table:

Nail Size	Length (mm)	Diameter (mm)
8d	63.5	3.33
10d	76.2	3.76
16d	88.9	4.11

Adhesive.--

Adhesive for plywood glue-nailed systems shall conform to APA Specification: AFG-01.

WOOD TREATMENT BY PRESSURE PROCESS.--

Preservative treatment.--

Preservative treatment shall be copper naphthenate, pentachlorophenol or water-borne arsenicals (ACQ, CCA or ACZA).

The following items shall be treated:

Wood cants, nailers, curbs, equipment support bases, blocking, stripping and similar members in connection with roofing, flashing, vapor barriers and waterproofing.

Wood sills, sleepers, blocking, furring and other similar members in contact with concrete.

All holes, daps and cut ends of treated lumber shall be thoroughly swabbed with 2 applications of copper naphthenate.

PART 3.- EXECUTION

INSTALLATION.--

Wood framing.--Wood framing shall be in accordance with Chapter 23 of the California Building Code.

Framing members shall be of sizes and spacing shown on the plans. Unless otherwise shown on the plans, structural members shall not be spliced between supports.

Wood framing shall be accurately cut and assembled to provide closely fitted members. Framing shall be erected true to the lines and grades shown on the plans and shall be rigidly secured in place as shown and as required by recognized standards. Bracing shall be placed wherever necessary to support all loads on the structure during erection.

The size and spacing of fasteners and the edge distance for nails shall be as shown on the plans.

Nailing schedule shall be as shown on the plans and shall comply with the California Building Code.

Wall coverings exposed to the weather shall have a backing of building paper applied weatherboard fashion to the framing or sheathing. Backing shall be lapped 50 mm at horizontal joints, 152 mm at vertical joints and 305 mm at building corners.

Plywood panels.--Plywood panels shall be attached to the framing as shown on the plans and these special provisions. All structural plywood sheathing shall be nailed with "Common" nails.

Plywood sheathing shall be nailed to the framing system and shall be continuous over 2 or more supports. Roof panels shall be installed with the long dimension across the supports, with end joints staggered 1.22 m. Wall sheathing shall have all edges blocked. Spacing between panels shall be 3 mm.

DIVISION 7. THERMAL AND MOISTURE PROTECTION

7.01 INSULATION (GENERAL)

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing insulation in accordance with the details shown on the plans and these special provisions.

Insulation materials shall be as specified in these special provisions, and shall be compatible with existing or new materials incorporated in the building.

SUBMITTALS.--

Product data.--A list of materials, manufacturer's descriptive data, location schedule, and time schedule shall be submitted for approval.

The list of materials to be used shall include the trade name, manufacturer's name, smoke developed and flame spread classification, resistance rating and thickness for the insulation materials and accessories.

Schedules.--A location schedule and time schedule shall be submitted for approval.

The location schedule shall show where each material is to be installed.

The Contractor shall provide the Engineer at the jobsite with an accurate time schedule of the areas of the building to be insulated each day. The time schedule shall be submitted 3 working days in advance of the work.

Samples.--Samples of insulation material shall be submitted to the Engineer at the jobsite.

QUALITY ASSURANCE.--

Codes and standards.--All insulating materials shall be certified to comply with the California Quality Standards for Insulating Materials and shall be listed in the Department of Consumer Affairs publication "Consumer Guide and Directory of Certified Insulation Material."

DELIVERY, STORAGE AND HANDLING.--

General.--Insulating materials shall be delivered to the jobsite and stored in a safe dry location with labels intact and legible.

Insulating materials shall be protected from physical damage and from becoming wet or soiled.

In the event of damage, materials shall be repaired or replaced as necessary to comply with these specifications.

PART 2.- PRODUCTS (Not applicable.)

PART 3.- EXECUTION (Not applicable.)

7.02 BATT AND BLANKET INSULATION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing batt or blanket insulation in accordance with the details shown on the plans and these special provisions.

Batt insulation shall include acoustical batts for sound control .

QUALITY ASSURANCE.--

Laminator's qualifications.--Laminator for bonding polyethylene vapor-retarder to insulating batts shall be approved by the insulation manufacturer.

The name of the laminator shall be submitted with the Product Data.

Codes and standards.--All batt or blanket insulation, including facings such as vapor barriers, shall have a flame-spread rating not to exceed 25 and a smoke density not to exceed 450 when tested in accordance with CBC Standard No. 8-1.

The flame-spread and smoke density limitations do not apply to facings on batt insulation installed between ceiling joists, or in roof-ceiling or wall cavities, provided the facing is installed in substantial contact with the surface of the ceiling or wall finish.

PART 2.- PRODUCTS

INSULATING MATERIALS.--

General.--Fiberglass batts shall be thermal insulation produced by combining glass fibers with thermosetting resins to comply with ASTM Designation: C 665.

Wall insulation.--

Wall insulation shall be R-3.3 K• m²/W fiberglass batts with paper-laminate vapor-retarder membrane on one face. Insulation shall conform to ASTM Designation: C 665, Type II, Class C.

Ceiling insulation.--

Ceiling insulation shall be R-5.3 K• m²/W fiberglass batts with paper-laminate vapor-retarder membrane on one face. Insulation shall conform to ASTM Designation: C 665, Type II, Class C.

Acoustical insulation.--

Acoustical insulation shall be 89 mm, unfaced fiberglass insulation batts. Insulation shall conform to ASTM Designation: C 665, Type I.

AUXILIARY INSULATION MATERIALS.--**Insulation tape.--**

Insulation tape shall be as recommended by the insulation manufacturer.

Insulation adhesive.--

Insulation adhesive shall be the type recommended by the insulation manufacturer and complying with the requirements for fire resistance.

PART 3.- EXECUTION**INSTALLATION.--**

General.--Unless otherwise shown on the plans or specified elsewhere in these special provisions, insulation shall be kept 75 mm to 100 mm clear of lighting fixtures and heat producing electrical appliances and equipment.

Installing batt type insulation.--Insulation batts shall be installed to completely fill the space between framing members. Apply a single layer of insulation of required thickness, unless otherwise shown on the plans or required to make up total thickness. Installation shall conform to the manufacturer's recommendations and these special provisions.

7.03 INSULATION FOR PRE-ENGINEERED STEEL BUILDING**PART 1.- GENERAL****SUMMARY.--**

Scope.--This work shall consist of furnishing and installing a batt or blanket insulation for pre-engineered steel building in accordance with the details shown on the plans and these special provisions.

Insulation for pre-engineered steel building shall be blanket or batt for ceilings and walls. Insulating materials and details of fastening and support systems shall be compatible with the pre-engineered building being furnished and shall be of a type approved by the building manufacturer.

Vapor retarder requirements may be waived for certain alternative systems that have a suitable finish on the exposed surfaces.

QUALITY ASSURANCE.--

Laminator's qualifications.--Laminator for bonding polyethylene vapor-retarder to insulating batts or blankets shall be approved by the insulation manufacturer.

The name of the laminator shall be submitted to the Engineer with the Product Data.

Codes and standards.--All batt or blankets insulation, including facings such as vapor barriers, shall have a flame-spread rating not to exceed 25 and a smoke density not to exceed 450 when tested in accordance with CBC Standard No. 8-1.

The flame-spread and smoke density limitations do not apply to facings on batt or blanket insulation installed between ceiling joists, or in roof-ceiling or wall cavities, provided the facing is installed in substantial contact with the surface of the ceiling or wall finish.

PART 2.- PRODUCTS

INSULATING MATERIALS.--

General.--Fiberglass batts or blankets shall be thermal insulation produced by combining glass fibers with thermosetting resins to comply with ASTM Designation: C 665.

Insulation.--

Insulation shall be glass fiber blanket or batt. Areas without interior finish shall have insulation and integral vapor retarder. Minimum thermal resistance rating shall be $R-5.3 \text{ K} \cdot \text{m}^2/\text{W}$ for the roof and $R-3.3 \text{ K} \cdot \text{m}^2/\text{W}$ for the walls.

Polyethylene vapor-retarder.--

Polyethylene vapor-retarder shall be factory-applied, 0.15 mm, white polyethylene film, a blend of fiberglass and polyester reinforcement, and metallized polyester film laminated with a flame resistant adhesive.

Fasteners, supports and adhesive.--

Fasteners, supports and adhesive shall be as recommended by the insulation manufacturer. Adhesives shall be non flammable, water resistant and nontoxic vehicle.

PART 3.- EXECUTION

INSTALLATION.--

General.--The insulation shall be installed to completely cover the exterior walls and the underside of the roof areas.

The vapor retarder shall be toward the interior of the building. Joints in the vapor retarder shall be sealed by application of a continuous bead of sealant approved by the insulation manufacturer.

Seams, tears, and punctures in the vapor retarders shall be sealed promptly, and before the insulation is contaminated with moisture condensation.

Installing blanket insulation.--Blanket type insulation, up to a maximum thickness of 100 mm of uncompressed insulation, may be draped over the purlins and wall framing members to insulate between the framing and the sheathing. The insulating blanket draped over the purlins and wall framing members shall not cause undulation of the sheathing panels or dimpling of the panels at the connectors. Draped blankets that exceed 50 mm in uncompressed thickness shall be separated from the sheathing panels by a continuous 25 mm minimum thickness spacer block or rigid board type insulation. The spacer block shall be not less than 150 mm wide, nor less than the width of the flange of the supporting member, whichever is greater.

Insulating blankets shall be tensioned and fastened to the framing members to minimize sags and wrinkles. Insulating blankets shall be adequately supported near termination points, and shall be fastened to provide a permanent thermal barrier without holes or discontinuities. The insulating blankets shall be butted together without gaps at joints.

The installed insulation shall not cause the sheathing to be dimpled at the fasteners, nor cause the sheathing to undulate or be distorted between supports. Dimpled sheathing and undulating, distorted sheathing shall be removed and replaced. The insulation beneath dimpled, undulating or distorted sheathing shall be removed and reinstalled to eliminate the undulations, distortions and dimples in the sheathing.

Installing batt insulation.--Batt type insulation shall be installed in accordance with the manufacturer's recommendations and shall completely cover the area between the framing members. Insulation shall be sized to fit tightly between framing members without being doubled over or unnecessarily compressed. Openings shall not be covered.

Installation at electrical apparatus.--Insulation shall be kept a minimum of 75 mm clear of lighting fixtures, ballasts, motors, fans blowers, heaters, wiring components, and other heat producing devices.

Thermal insulation shall not surround conduits for No. 8 or larger conductors.

Thermal insulation shall not impair accessibility of devices that may require periodic servicing.

Damaged insulation.--All punctures and tears in the vapor retarder facing shall be sealed with pressure sensitive patching tape matching the facing.

7.04 SEALANTS AND CAULKING

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and applying sealants and caulking which are required for this project, but not specified elsewhere, in accordance with the details shown on the plans and these special provisions.

Related work.--Pourable polyurethane joint sealant shall conform to the requirements under "Joint Sealant" elsewhere in this Division 7.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of compliance shall be furnished for the sealants and caulking in accordance with the requirements specified in Section 4-1.04, "Certificates of Compliance," of the General Conditions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and installation instructions for all sealants shall be submitted for approval.

Samples.--Color samples of all sealants shall be submitted for approval. Unless otherwise shown on the plans, colors will be selected by the Engineer from the manufacturer's standard colors.

PART 2.- PRODUCTS

MATERIALS.--

General.--All sealants, primers and accessories shall be non-staining to adjacent exposed surfaces. Products having similar applications and usage shall be of the same type and same manufacturer. Gun consistency compound shall be used unless otherwise required by the job conditions.

Acrylic sealant.--

Acrylic sealant shall be one compound, solvent release acrylic sealant.

Butyl sealant.--

Butyl sealant shall be one component, skinning type.

Silicone sealant.--

Silicone sealant shall be one component, low modulus building sealant. Sealant shall be tack-free in one hour, shall not sag or flow, shall be ozone resistant and capable of 100 percent extension without failure.

Joint sealant.--

Joint sealant shall be a two-part, non sag polysulfide base, synthetic rubber sealant formulated from liquid polysulfide polymer.

Backer rod.--

Backer rod shall be round, open or closed cell polyurethane. Backer rod shall be sized such that it must be compressed between 25 and 75 percent of its uncompressed diameter during installation in the joint.

Neoprene.--

Neoprene shall conform to the requirements of ASTM Designation: C 542.

PART 3.- EXECUTION**APPLICATION.--**

General.--Unless otherwise shown on the plans, sealants shall be applied in accordance with the manufacturer's instructions.

Silicone sealants shall not be used in locations where painting is required.

Butyl sealants shall not be used in exterior applications, and acrylic sealants shall not be used in interior applications.

Sealants shall be applied in a continuous operation for the full length of the joint. Immediately following the application of the sealant, the sealant shall be tooled smooth using a tool similar to that used to produce concave masonry joints. Following tooling, the sealant shall remain undisturbed for not less than 48 hours.

DIVISION 8. DOORS AND WINDOWS**8.01 HINGED DOORS**

GENERAL.--This work shall consist of furnishing and installing hinged doors and frames in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions for fire rated assemblies and a door schedule shall be submitted for approval. The door schedule shall include a description of the type, location and size of each door and frame.

PRODUCTS.--**Metal door.--**

Metal door shall be flush, seamless steel door factory prepared and reinforced to receive hardware and having cold rolled stretcher leveled sheet steel face sheets not less than 1.2 mm thick (18-gage). Face sheets shall be bonded with thermosetting adhesive to rigid board honeycomb or precured foam core; or face sheets shall be welded to all parts of an assembled grid of cold formed pressed metal stiffeners and framing members located around edges, ends, openings and at all locations necessary to prevent buckling of face sheets. Seams shall be tack welded, filled and ground smooth. Bottom edge and internal stiffeners of grid type core shall have moisture vents. Welds on exposed surfaces shall be ground smooth. Glazed openings shall be provided where shown on the plans.

Where fire rated doors are required, doors shall be listed and labeled for the fire rating shown on the plans.

Door shall be cleaned and treated by the bonderized process or approved phosphatizing process and then given one factory application of metal protective rust inhibitive primer. Primer shall not contain lead type pigments.

Glazing for doors.--

Glazing for doors shall be safety glass as specified under "Glazing" in Division 8, "Doors and Windows," of these special provisions. Glazing shall be not less than 5 mm thick.

Pressed metal frame.--

Pressed metal frame shall be not less than 1.5 mm thick (16-gage) sheet steel with integral stop, mitered corners, face welded and ground smooth corners. Frames shall be reinforced for all hardware and shall be cleaned and treated by the bonderized process or an approved phosphatizing process and then given one factory application of metal protective rust inhibitive primer. Primer shall not contain lead type pigments. Frames for fire rated doors shall be listed for the same rating shown on the plans for fire rated doors.

Sealants.--

Sealants shall be ultraviolet and ozone resistant, gun grade polysulfide or polyurethane, multicomponent, Federal Specification: TT-S-227.

EXECUTION.--

INSTALLATION.--Doors and frames shall be installed rigidly, securely, plumb and true and in such a manner that the doors operate freely without rubbing or binding. Clearance between frame and door shall be not more than 3 mm. The exterior frame shall be sealed weathertight.

Pressed metal frames shall be secured with clips and anchors as shown on the plans.

Fire rated assemblies shall be installed according to the manufacturer's recommendations.

Fire rated assemblies shall include doors, door frames, automatic smoke-actuated closers, self-closing mechanisms, panic hardware, wire glass, and fire rated louvers. Assemblies shall be approved by the California State Fire Marshal.

PAINTING.--Except for the primer application specified herein, doors and frames shall be cleaned, prepared and painted in accordance with the requirements specified under "Painting" in Division-9, "Finishes," of these special provisions.

8.02 SECTIONAL OVERHEAD DOORS**PART 1.- GENERAL****SUMMARY.--**

Scope.--This work shall consist of furnishing and installing sectional overhead doors in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, roughing-in diagram and installation instructions for each size and type of door shall be submitted for approval.

Manufacturer's descriptive data shall include door panel construction and material thickness, door track size and material thickness, counterbalance spring service life and motor operator specifications.

Materials list shall contain all items proposed to be furnished and installed under this section of these special provisions.

Shop drawings shall show details of special components and installations which are not fully dimensioned or detailed in manufacturer's descriptive data.

QUALITY ASSURANCE.--

Single source.--Each sectional door shall be provided as a complete unit produced by one manufacturer, including frames, sections, bracket guides, tracks, counterbalance mechanisms, hardware, operators and installation accessories, to suit opening and head room available.

Wind loading.--Design and reinforce section overhead doors to withstand a 960 PA wind load with a midspan deflection not to exceed 1/120 span.

PART 2.- PRODUCTS

MANUFACTURERS.--

Available manufacturers.--Subject to compliance with the specifications, manufacturers offering products which may be incorporated into the work include, but are not limited to the following: Clopay Corp.; Overhead Door Corp.; Raynor Garage Doors.

STEEL SECTIONS.--

Door sections.--

Door sections shall be galvanized commercial quality steel sheets and a minimum of G60 zinc coating complying with ASTM Designation: A 525.

Face sheets shall be not less than 0.86mm (20-gage). Back sheet shall be not less than 0.45 mm (26-gage).

Sections shall be fabricated from a single sheet to provide sections not more than 610 mm high, and nominal 50 mm deep. Meeting horizontal edges shall be rolled to a continuous shiplap, rabbeted, or keyed weather seal, with a reinforcing flange return.

Intermediate and end stiles shall be 1.52 mm (16-gage) galvanized steel welded in place. Intermediate stiles shall be spaced at not more than 1220 mm on center.

Bottom section shall be reinforced with a continuous channel or angle conforming to the bottom section profile.

Insulation.--

Insulation shall be the manufacturer's glass fiber, polystyrene or polyurethane foam type insulation and have an R-Value not less than 1.4 K•m²/W.

Finish.--

Finish shall be the manufacturer's standard baked on polyester or epoxy prime and finish coats, applied to interior and exterior faces.

TRACKS, SUPPORTS. AND ACCESSORIES.--

Door tracks.--

Door tracks shall be the manufacturers standard galvanized steel track system, sized for door size and weight, and designed for the clearances shown on the plans. Complete track assembly shall be provided, including brackets, bracing and reinforcing for rigid support of ball bearing roller guides, for required door type and size.

Track reinforcement and supports.--

Track reinforcement and supports shall be galvanized steel. Tracks shall be reinforced and supported as required for the size and weight of door to provide strength and rigidity, and to ensure against sag, sway and vibration during operation.

Door seals.--

Doors shall have perimeter gasket seals at head and jambs and seal shall have a replaceable vinyl or neoprene bottom seal.

Vision panels.--

Vision panels shall be door manufacturer's standard glazed opening with wire safety glass, metal frame and vinyl or neoprene glazing gasket for water tight construction. The approximate size shall be as shown on the plans.

Adjustable louvers.--

Adjustable louvers shall be factory fabricated units of extruded aluminum alloy not less than 2.0 mm thick or galvanized steel not less than 0.91 mm thick (20-gage) with standard "Z" type blades set in a continuous channel frame, with a 6 mm mesh galvanized bird-screen in a removable frame on the inside.

Blades shall have center pivot on 10 mm aluminum rods in stainless steel ball bearings in cadmium plated races.

Adjustable louvers shall be equipped with hand-hold fixed to the operating bar for easy adjustment with wingnut spring tension to lock louvers in desired position.

HARDWARE.--

General.--Hardware shall be heavy-duty, rust-resistant, with galvanized or cadmium-plated or stainless steel fasteners, to suit type of door.

Hinges.--

Heavy steel hinges shall be provided at each end stile and at intermediate stiles, per manufacturer's recommendations for size of door.

Rollers.--

Rollers shall be heavy-duty with steel ball bearings in case-hardened steel races, mounted to suit slope of track. Rollers shall have case-hardened tires.

COUNTERBALANCE MECHANISMS.--**Counterbalance spring.--**

The door shall have a torsion spring counterbalance on a continuous cross header shaft; the entire assembly shall be all-bearing mounted. The spring shall have a rated service life of not less than 25,000 cycles.

ELECTRIC DOOR OPERATORS.--

Door operator shall be heavy duty, commercial type. Motor shall be a 240-volt, one-phase, high starting torque motor with single reduction worm gear, completely housed and running in an oil bath. Motor shall be of sufficient capacity to raise and lower the door at speed of approximately 0.2 m per second.

Door operator and assembly shall be equipped with solenoid brake, limit switches for upper and lower limits of door travel, emergency hand chain with electrical interlock to break motor circuit when hand chain is engaged, 3-button operating station in a NEMA Type 4 enclosure, and a factory wired NEMA Type 1 control panel.

Control panel shall contain an instrument transformer, reversing magnetic contactor with overload relay, and all necessary control relays and other devices required for complete automatic operation of the door. Motor shall be removable for repair without affecting emergency operation. Motor shall be centermounted or sidemounted as shown on the plans.

Reversing door edge.--

Reversing door edge shall be an electrically or pneumatically operated safety device extending across the full width of the bottom of the door which shall cause the door to stop automatically and return to open position upon contact with any obstruction.

PART 3.- EXECUTION

INSTALLATION.--

General.--Door, track, and operating equipment, complete with necessary hardware, jamb and head mold stops, anchors, inserts, hangers, and equipment supports, shall be installed in accordance with the final drawings, manufacturer's installation instructions and these special provisions.

Vertical track assembly shall be fastened to framing at not less than 610 mm on center. Horizontal track shall be hung from structural overhead framing with angle or channel hangers, welded or bolted into place. Sway bracing, diagonal bracing, and reinforcing as required for rigid installation of track and door operating equipment.

8.03 WINDOWS

PART 1.- GENERAL

SUMMARY.--This work shall consist of furnishing and installing windows in accordance with the details shown on the plans and these special provisions.

Windows shall be commercial (C) grade aluminum prime windows unless otherwise shown on the plans.

Windows shall meet the requirement of NAFS-1, "Voluntary Performance Specification for Windows, Skylights, and Glass Doors," and shall meet the C30 (Commercial) product designation unless otherwise shown on the plans. Windows shall be labeled with the AAMA label.

Finish for windows shall be Architectural Class I, clear anodized finish meeting American Architectural Manufacturer's Association Standard 611 unless otherwise shown on the plans.

Glazing for windows shall be in accordance with the requirements specified under "Glazing" in Division 8, "Doors and Windows," of these special provisions.

CERTIFICATES OF COMPLIANCE.--Certificates of compliance shall be furnished for all windows in accordance with the requirements specified in Section 4-1.04, "Certificates of Compliance," of the General Conditions.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions and schedule shall be submitted for approval.

Manufacturer's descriptive data and installation instructions shall show window elevations, plan views, full size sections, anchoring details to all substrates, anchors and hardware.

Installation schedule shall show location, size and type for each window.

PART 2.- PRODUCTS

Door windows.--

Door windows shall be door or door frame manufacturer's standard window framing, glazing stops and glazing accessories.

Fixed windows.--

Fixed windows shall be non-operable glazed panel inserted into a frame to include muntins, glazing stops, and glazing accessories.

Horizontal sliding windows.--

Horizontal sliding windows shall be horizontal slide by windows with tightly contacting weatherstripped meeting stiles, self-lubricating rollers, glazing accessories, tubular sill, snap locks and push handle. Vents shall be screened.

Aluminum.--

Aluminum shall be extruded 6063-T5 aluminum alloy.

Screws, fasteners and window accessories.--

Screws, fasteners and window accessories shall be non-corrosive metals compatible with aluminum except guides and rollers may be vinyl and nylon respectively. Finish for locks, operators, strikes, keepers and other metal hardware shall match window finish.

Weatherstripping.--

Weatherstripping shall be continuous, replaceable type, wool pile mounted in metal or double runs of ultraviolet resistant neoprene or vinyl.

Vent screen.--

Vent screen shall be aluminum frame with 18 x 14 mesh aluminum screening and polyvinyl-chloride splines. Screen frames shall be removable from interior of building. Finish of screen frame shall match window finish.

Sealant.--

Sealant shall be single-component, solvent type acrylic, self-leveling, non-sag, conforming to Federal Specification: TT-S-230.

Tape.--

Tape shall be compatible with sealant; Pecora, "B-44 Extra-Seal;" Pittsburg Plate Glass, "Duribbon;" Protective Treatment, "PTU 606;" Tremco, "440 Tape;" or equal.

PART 3.- EXECUTION

FABRICATION.--Frame and sash shall be accurately machined and fitted to hairline joinery that develops the members. Joints shall be factory sealed weathertight.

Outward opening vents without roto-type operators shall be provided with adjustable sliding friction type hold-open assemblies.

Sash shall be removable from the interior only. Sash shall have concealed condensation weeps to the outside.

DELIVERY AND STORAGE.--Windows shall be delivered in original, unopened, unbroken containers, wrappings, or bags with labels bearing the brand name, name of manufacturer or supplier, standard of manufacture, and product description.

Windows and accessories shall be stored off the ground, kept dry, fully protected from weather and damage

INSTALLATION.--Window units shall be set straight, level, plumb and in true alignment in prepared openings. Windows shall be centered in openings. Clearance between the window unit and the building framing shall be from 4 mm to 6 mm at the sides and 13 mm at the top. Ventilator sash shall be adjusted after glazing for easy, smooth and proper operation.

The installation shall be flashed and sealed weathertight.

All aluminum surfaces in contact with steel or other incompatible materials shall be isolated with pressure sensitive tape, zinc chromate primer, bituminous paint or such other material recommended by the window manufacturer and approved by the Engineer.

8.04 FINISH HARDWARE**PART 1.- GENERAL****SUMMARY.--**

This work shall consist of furnishing and installing hardware items for doors in accordance with the details shown on the plans and these special provisions.

Hardware for special doors and frames, if required, shall be as specified under "Hinged Doors" in Division 8, "Doors and Windows," of these special provisions.

Hardware assemblies shall comply with the fire code and the disabled accessibility requirements indicated on the plans and specified in these special provisions.

SUBMITTALS.—

Manufacturer's technical information and catalog cuts for each item of door hardware and a door hardware schedule shall be submitted for approval prior to installation.

Manufacturer's catalog cuts shall include catalog numbers, material, grade, type, size, function, design, quality and finish of hardware.

The door hardware schedule shall indicate the location and size of door opening, the door and frame material, and the size, style, finish and quantity of the hardware components required.

FINISHES.—

Hardware shall be provided with standard US 26D metal plated finish or sprayed finish where indicated.

KEYING INSTRUCTIONS.—

New facilities shall have a building master key system established.

Locks shall have cylinders with figure eight interchangeable cores with six pin barrels. Permanent cores and keys shall be delivered to the Engineer for final installation at completion of project.

The Contractor shall also provide figure eight interchangeable cores for use during construction which shall remain the property of the State.

Key bows shall be stamped "State of California" and "Do Not Duplicate."

PART 2.- PRODUCTS.--

GENERAL.—

Door hardware equal in material, grade, type, size, function, design, quality and manufacture to that specified herein may be submitted for approval.

Butt hinges.--

Butt hinges shall be steel, 1 1/2-pair per door unless otherwise specified or shown on the plans. Nonremovable pins shall be provided at outswing exterior doors. Hinge size shall be 114 mm x 114 mm unless otherwise noted.

Standard weight hinges shall be:

Hager	BB 1279
McKinney	TB 2714
Stanley	BB 179
or equal.	

Mortise locksets.--

Mortise locksets shall be steel case with 32 mm x 203 mm face plate and 70 mm backset. Door and frame preparation for mortise locksets shall conform to ANSI A115.1.

Lever operated lockset shall be:

Best	35H 6FW 15H
Falcon	LM521 DG
Schlage	L9453R x 06
or equal.	

Cylindrical locksets and privacy sets.--

Cylindrical locksets and privacy sets shall be steel chassis, 54 mm diameter, 70 mm backset. Door and frame preparation for cylindrical lockset and privacy sets shall conform to ANSI A115.1.

Lever operated lockset shall be:

Best	93K6 AB 9C
Schlage	D53RD RHO
Falcon	LY501 DG
or equal.	

Lever operated privacy set shall be:

Best	93K OL 9C
Falcon	LY301 DG
Schlage	D40S RHO
or equal.	

Cylindrical dead locks.--

Cylindrical dead locks shall have 25 mm throw bolt with concealed hardened steel inserts and 25 mm diameter bolt housing, 70 mm backset.

Single cylinder dead lock with inside thumb turn shall be:

Best	83T 7K
Falcon	D441
Schlage	B460R
or equal.	

Door closers.--

Parallel arms for closers shall be installed at outswing exterior doors. Closers shall have sprayed finish to match other hardware on door.

Door closers shall be:

LCN	4040
Norton	3501-BF
Dorma	7800
or equal.	

Mop plates.--

Mop plates shall be stainless steel, 1.52 mm (16-gage), 152 mm in height x 51 mm less than the door width.

Mop plates shall be:

Trimco
Ives
or equal.

Floor mounted stops.--

Floor mounted stops shall be dome type. The height of the stop shall be determined by the clearance required when a threshold is used.

Stops for openings with thresholds shall be:

Builders Brass	8063
Quality	431
Trimco	1213
or equal.	

Wall bumpers.--

Wall bumpers base diameter shall be 64 mm with a 25 mm projection.

Bumpers shall be:

Builders Brass	WC9
Quality	302
Trimco	1270CV
or equal.	

Automatic door bottom.--

Automatic door bottom shall be heavy duty, full mortise.

Bottom shall be:

Pemko	434 AR
Zero	360
or equal.	

Thresholds, rain drips, door sweeps and door shoes.--

Thresholds, rain drips, door sweeps and door shoes shall conform to the sizes and configurations shown on plans. Thresholds at door openings with accessibility requirements shall not exceed 13 mm in height.

Threshold, rain drip, door sweep and door shoe manufacturers shall be Pemko, Reese, Zero, or equal.

Threshold bedding sealant.--

Threshold bedding sealant shall conform to Federal Specification: SS-C-153.

Weatherstrip and draft stop.--

Weatherstrip and draft stop shall conform to the sizes and shapes shown on plans. Assemblies shall be UL listed and shall be provided where shown on the plans or as specified in these special provisions.

Weatherstrip and draft stop manufacturers shall be Pemko, Reese, Zero, or equal.

Door signs and name plates.--

Door signs and name plates shall be as specified under "Signs" in Division 10, "Specialties," of these special provisions.

PART 3.- EXECUTION

DOORS AND FRAMES.--Doors and frames shall be set square and plumb and be properly prepared before the installation of hardware.

INSTALLATION.--Hardware items shall be accurately fitted, securely applied, and adjusted and lubricated in accordance with the manufacturer's instructions. Installation shall provide proper operation without bind or excessive play.

Hinges shall be installed at equal spacing with the center of the end hinges not more than 244 mm from the top and bottom of the door. Pushplates and door pulls shall be centered 1118 mm from the finished floor. Locksets, latchsets, privacy sets and panic exit mechanisms shall be 1024 mm from the finished floor. Kickplates shall be mounted on the push side of the doors, 25 mm clear of door edges.

Thresholds shall be set in a continuous bed of sealant material.

Door controls shall be set so that the effort required to operate doors with closers shall not exceed 37.8 N maximum for exterior doors and 22.3 N maximum for interior doors. The effort required to operate fire doors may be increased above the values shown for exterior and interior doors but shall not exceed 66.7 N maximum.

Door stops located on concrete surfaces shall be fastened rigidly and securely in place with expansion anchoring devices. Door stops mounted elsewhere shall be securely attached with wood screws or expansion devices as required.

Backing shall be provided in wall framing at wall bumper locations.

The location and inscriptions for door signs and name plates shall be as shown on the plans.

Hardware, except hinges, shall be removed from surfaces to be painted before painting.

Upon completion of installation and adjustment, the Contractor shall deliver to the Engineer all dogging keys, closer valve keys, lock spanner wrenches, and other factory furnished installation aids, instructions and maintenance guides.

DOOR HARDWARE GROUPS AND SCHEDULE.--Hardware groups specified herein shall correspond to those shown on the plans:

GROUP 1

- 1 1/2-pair butt hinges
- 1 each, Mortise lever operated lockset
- 1 each, door closer
- 1 each, floor mounted stop
- 1 each, automatic door bottom
- 1 each, threshold
- 1 each, weatherstrip and draft stop

GROUP 2

- 1 1/2-pair butt hinges
- 1 each, cylindrical lever operated lockset
- 1 each, wall bumper
- 1 each, door closer

GROUP 3

- 1 1/2-pair butt hinges
- 1 each, cylindrical lever operated lockset
- 1 each, cylindrical dead lock

GROUP 4

- 1 1/2-pair butt hinges
- 1 each, cylindrical lever operated privacy set
- 1 each, mop plate
- 1 each, wall bumper

8.05 GLAZING

PART 1.- GENERAL

SUMMARY.---

This work shall consist of furnishing and installing glazing in accordance with the details shown on the plans and these special provisions.

Glazing shall consist of glass for windows, doors and other glazed openings.

All glass shall conform to ASTM Designation: C 1036 and the classifications specified herein and shall be clear glass except as noted.

Safety glass shall be furnished and installed at all locations designated in Consumer Product Safety Commission's Safety Standard For Architectural Glazing Materials 16 CFR 1201.

SUBMITTALS.—

A detailed list of glazing materials including glass, sealants, tapes, setting blocks, shims, compression seals, and glazing channels shall be submitted for approval. The list shall include a schedule of the materials to be used at each location.

LABELS.—

Each individual pane of fully tempered glass shall bear an identification label in accordance with ASTM Designation: C 1048.

PART 2.- PRODUCTS

Sheet glass, float glass, or plate glass.--

Sheet glass, float glass, or plate glass shall be Type I, Class 1, Quality q4 or better, double strength for panes to 0.93 m², 5 mm thick for panes between 0.93 m² and 2.6 m², and 6 mm thick for panes over 2.6 m², except as otherwise shown on the plans.

Safety glass.--

Safety glass shall conform to Consumer Product Safety Commission Safety Standard For Architectural Glazing Materials: 16 CFR 1201, and ANSI Standard Z97.1 and shall be one of the following:

Tempered glass.--

Tempered glass shall conform to ASTM Designation: C 1048, Kind FT, Condition A, Type 1, Quality q4 or better.

Wire glass.--

Wire glass shall be Type II, Class 1, Form 1, Mesh m1; 6 mm thick clear polished wire glass with diamond mesh.

Insulating glass assemblies.--

Insulating glass assemblies shall be double pane units consisting of 2 pieces of glass separated by a spacer and hermetically sealed with double seal sealants. The entrapped air shall be at atmospheric pressure and maintained in a hydrated condition by a drying agent located in the spacer

Seals, caulks, putties, setting blocks, shims, tapes, compression seals, felt, spacers, and channels.--

Seals, caulks, putties, setting blocks, shims, tapes, compression seals, felt, spacers, and channels shall be top grade, commercial quality, as recommended by the glass manufacturer and shall conform to the requirements in the publications of the Flat Glass Marketing Association.

PART 3.- EXECUTION

INSTALLATION.—

Glazing shall conform to the general conditions and applicable details in the publications of the Flat Glass Marketing Association.

Panes shall be bedded fully and evenly, set straight and square within panels in such a manner that the pane is entirely free of any contact with metal edges and surfaces.

For all panes on the exterior of the building, the glazing on both sides of window panes shall provide a watertight seal and watershed. Seals shall extend not more than 2 mm beyond the holding members. A void shall be left between the vertical edges of the panes and the glazing channel. Weep systems shall be provided to drain condensation to the outside.

Panes in assemblies using extruded gasket glazing shall be set in accordance with the assembly manufacturer's instructions using gaskets and stops supplied by the manufacturer.

Whenever welding or burning of metal is in progress within 4.6 m of glazing materials, a protective cover shall be provided over exposed surfaces.

REPLACEMENT AND CLEANING.—

All broken or cracked glass and glass with scratches which reduce the strength shall be replaced before completion of the project.

Panes shall be kept clean of cement and plaster products, cleansers, sealants, tapes and all other foreign material that may cause discoloration, etching, staining, or surface blemishes to the materials.

Excess sealant left on the surface of the glass or surrounding materials shall be removed during the work life of the sealant.

Solvents and cleaning compounds shall be chemically compatible with materials, coatings and glazing compounds to remain. Cleaners shall not have abrasives that scratch or mar the surfaces.

All panes shall be cleaned just before the final inspection. All stains and defects shall be removed. Paint, dirt, stains, labels (except etched labels), and surplus glazing compound shall be removed without scratching or marring the surface of the panes or metal work.

DIVISION 9. FINISHES

9.01 GYPSUM WALLBOARD

GENERAL.--This work shall consist of furnishing, installing and finishing gypsum wallboard in accordance with the details shown on the plans and these special provisions.

Where assembly fire ratings are indicated on the plans, construction shall provide the fire resistance in accordance with the applicable standards in the Fire Resistance Design Manual published by the Gypsum Association.

Wallboard backing for use in restroom and shower areas shall be water-resistant gypsum backing board.

PRODUCTS.--

Gypsum wallboard.--

Gypsum wallboard shall conform to ASTM Designation: C 36/C 36M.

Gypsum backing board.--

Gypsum backing board shall conform to ASTM Designation: C 442/C 442M.

Water-resistant gypsum backing board.--

Water-resistant gypsum backing board shall conform to ASTM Designation: C 630/C C 630M.

Gypsum sheathing board.--

Gypsum sheathing board shall conform to ASTM Designation: C 79/C 79M.

Joint tape and joint and finishing compound.--

Joint tape and joint and finishing compound shall conform to ASTM Designation: C 475.

Corner beads, metal trim and control joints.--

Corner beads, metal trim and control joints shall be galvanized steel of standard manufacture.

Resilient metal channel.--

Resilient metal channel shall be galvanized sheet steel channels of standard manufacture for reducing sound transmission in wood frame partitions.

Fasteners.--

Fasteners shall be gypsum wallboard nails conforming to ASTM Designation: C 514 or steel drill screws conforming to ASTM Designation: C 1002.

EXECUTION.--

DELIVERY AND STORAGE.--Materials shall be delivered in original packages, containers or bundles bearing brand name, applicable standard of manufacture, and name of manufacturer or supplier and shall be kept dry and fully protected from weather and direct sunlight exposure. Gypsum wallboard shall be stacked flat with adequate support to prevent sagging or damage to edges, ends and surfaces.

INSTALLATION.--Wallboard panels to be installed on ceilings and soffits shall be installed with the long dimension of the panels perpendicular to the framing members. Wallboard panels to be installed on walls may be installed with the long dimension of the panels either parallel or perpendicular to the framing members. The direction of placing the panels shall be the same on any one wall or partition assembly.

Edges of wallboard panels shall be butted loosely together. All cut edges and ends shall be smoothed as needed for neat fitting joints.

All edges and ends of gypsum wallboard panels shall coincide with the framing members, except those edges and ends which are perpendicular to the framing members. End joints on ceiling and on the opposite sides of a partition assembly shall be staggered.

Except where closer spacings are shown on the plans, the spacing of fasteners shall not exceed the following:

Nails	175 mm
Screws	300 mm
Screws at perimeter of panels for fire resistive assemblies having metal framing	200 mm

Type S steel drill screws shall be used to fasten wallboard to metal framing. Nails or Type W steel drill screws shall be used to fasten wallboard to wood framing. Except as shown on the plans, screws shall not be used in fire resistive assemblies.

Adhesives shall not be used for securing wallboard to framing.

Gypsum wallboard shall be fastened to all framing members except at the following locations:

At internal angles formed by ceiling and walls; ceiling panels shall be installed first with the fasteners terminating at a row 175 mm from the walls, except for walls parallel to ceiling framing. Wall panels shall butt the ceiling panels. The top row of wall panel fasteners shall terminate 200 mm from the ceiling.

At internal vertical angles formed by the walls; fasteners shall not be installed along the edge or end of the panel that is installed first. Fasteners shall be installed only along the edge or end of the panel that butts and overlaps the panel installed first.

Fasteners shall be located at least 10 mm from wallboard panel edges and ends. Nails shall penetrate into wood framing at least 30 mm. Screws shall penetrate into wood framing at least 20 mm. All metal fasteners shall be driven slightly below surface level without breaking the paper or fracturing the core.

Metal trim shall be installed at all free edges of panels, at locations where wallboard panels abut dissimilar materials and at locations shown on the plans. Corner beads shall be installed at external corners. Control joints shall be installed at the locations shown on the plans.

Joints between face panels, the internal angles formed by ceiling and walls and the internal vertical angles formed by walls shall be filled and finished with joint tape and at least 3 coats of joint compound. Tape in the corners shall be folded to conform to the angle of the corner. Tape at joints and corners shall be embedded in joint compound.

Dimples at nail and screw heads, dents, and voids or surface irregularities shall be patched with joint compound. Each patch shall consist of at least 3 coats and each coat shall be applied in a different direction.

Flanges of corner beads, control joints and trim shall be finished with a least 3 coats of joint compound.

Each coat of joint compound shall be feathered out onto the panel surface and shall be dry and lightly sanded before applying the next coat. The finished surfaces of joint compound at the panel joints, internal angles, patches and at the flanges of trim, corner beads and control joints shall be flat and true to the plane of the surrounding surfaces and shall be lightly sanded.

Good lighting of the work area shall be provided during the final application and sanding of the joint compound.

Gypsum wallboard used as backing boards for tile or rigid sheet wall covering or wainscoting shall be water resistant. Joints in backing board shall not be taped or filled and dimples at the fastener heads shall not be patched. Edges of cuts and holes in backing board shall be sealed with a primer or sealer that is compatible with the wall covering or wainscoting adhesive to be used.

Surfaces of wallboard to be textured shall receive an orange peel texture, unless otherwise shown on the plans.

9.02 FIBERGLASS REINFORCED PLASTIC PANELS

GENERAL.--This work shall consist of furnishing and installing fiberglass reinforced plastic (FRP) panels and trim molding in accordance with details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions, and finish options shall be submitted for approval.

Product descriptive data shall show the manufacturer's name and shall indicate conformance to these special provisions.

Installation instructions shall show the FRP panel manufacturer's recommended method of installation.

Finish options shall show the manufacturer's standard color palette for FRP panels and trim molding. Color shall be as shown on the plans.**PRODUCTS.--**

FRP panel.--

FRP panel shall be Class I flame-spread, minimum nominal thickness of 2 mm; Marlite, Class A/I FRP; Kemlite, Fire-X Glasbord; or equal.

Trim molding.--

Trim molding shall be manufacturer's standard vinyl molding with nailing flanges and a 9 mm deep channel of sufficient width to receive panels and sealant.

Adhesive and sealant.--

Adhesive and sealant shall be as recommended by the FRP panel manufacturer.

EXECUTION.--

INSTALLATION.--The FRP panels and trim molding shall be installed in accordance with the manufacturer's installation instructions.

Trim molding shall be nailed through the flange into solid wood backing. All nails shall be concealed by FRP panels in the completed installation. Trim shall be one continuous piece along each wall unless the wall length exceeds the manufacturer's standard trim length. If more than one piece is used on one wall, the pieces shall be approximately equal length, with no piece less than 1 m in length. All FRP panel edges shall be covered by a trim molding.

Panels shall be one continuous piece along each wall unless the wall length exceeds the manufacturer's standard panel length. If more than one panel piece is used on one wall, the pieces shall be approximately equal length, with no piece less than one meter in length.

CLEAN-UP.--Adjacent surfaces shall be protected from adhesive or sealant. Excess adhesive and sealant shall be removed as the installation progresses using a solvent or cleaning agent recommended by the FRP panel manufacturer.

9.03 RESILIENT SHEET FLOORING

GENERAL.--This work shall consist of furnishing and installing resilient sheet flooring in accordance with the details shown on the plans and these special provisions.

Resilient sheet flooring shall also include cove molding, metal caps, edger strips, floor wax and flooring manufacturer's recommended primers and adhesives.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions, color and pattern samples shall be submitted for approval. Samples of sheet flooring shall be 305 mm x 305 mm in size.

PRODUCTS.--

Resilient sheet flooring.--

Resilient sheet flooring shall be flexible vinyl sheet not less than 2 mm thick. Color and pattern shall be as shown on the plans.

Primer, leveling compound crack filler and adhesives.--

Primer, leveling compound crack filler and adhesives shall be waterproof types as recommended by the flooring manufacturer.

Wax.--

Wax shall be water emulsion, self-polishing type containing not less than 16 percent wax solids, wetting agents, and a nonslip agent. The wax shall meet UL antislip standards.

Cove molding.--

Cove molding shall be commercial quality wood, rubber or plastic.

Edger strips.--

Edger strips shall be commercial quality, stainless steel or aluminum.

Metal caps.--

Metal caps shall be commercial quality, noncorrosive metal.

EXECUTION.--

PREPARATION.--Before placing adhesives, all surfaces to receive resilient sheet flooring shall be made free of localized depressions or bumps. Bumps shall be ground flat. Holes, depressions and cracks shall be filled with crack filler or leveling compound.

Immediately prior to installation of the resilient sheet flooring, the surface to be covered shall be thoroughly dry, free of paint, oil, grease, mortar, plaster droppings, scaly surfaces or other irregularities and shall be broom clean. Primer, when recommended, shall be thoroughly brushed on the surface at the rate recommended by the adhesive manufacturer and shall be completely dry before application of adhesives.

The rooms where resilient sheet flooring is to be installed shall be maintained at a temperature of at least 21°C for not less than 72 hours before installation, during installation and for 5 days after installation.

INSTALLATION.--Resilient sheet flooring shall be laid to a true, straight, smooth and even finish surface in accordance with the manufacturer's instructions. Resilient sheet flooring shall be laid parallel to building lines with the minimum of seams using manufacturer's standard widths. Seams shall be tight fitting, fully bonded along their length and present a continuous pattern.

Resilient sheet flooring shall be placed before floor mounted fixtures are installed.

After resilient sheet flooring has been installed, the finished surface shall be rolled and crossrolled with a roller weighing 50 kg or more.

Edger strips shall be installed at free edges.

Upon completion of the flooring installation, all stains, surplus adhesive, dirt and debris resulting from the work shall be removed and the floor left broom clean. Resilient sheet flooring shall be protected from damage at all times during construction. As a last order of work, floor covering shall be washed with soap and warm water, rinsed, and then waxed in accordance with the floor covering and wax manufacturers' printed instructions. Not less than 2 applications of wax shall be placed on the floor covering.

PATCHING EXISTING FLOOR COVERING.--Resilient sheet flooring for patching shall closely match the color and pattern of the existing floor covering, except flooring of contrasting color and pattern may be use when approved by the Engineer.

REPLACEMENT OF EXISTING FLOORING.--Replacement of existing flooring where ordered by the Engineer will be paid for in accordance with the requirements specified in Section 3-1.01 of the General Conditions.

9.04 PAINTING

PART 1.- GENERAL

SUMMARY.--This work shall consist of preparing surfaces to receive coatings, and furnishing and applying coatings, in accordance with the schedules and details shown on the plans, and these special provisions.

The coatings specified in this section are in addition to any factory finishes, shop priming, or surface treatment specified elsewhere in these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, a materials list, and color samples shall be submitted for approval.

Product descriptive data shall include product description, manufacturer's recommendations for product mixing, thinning, tinting, handling, site environmental requirements, product application and drying time.

Materials list shall include manufacturer's name, trade name, and product numbers for each type coating to be applied.

Color samples shall be manufacturer's color cards, approximately 50 mm x 75 mm, for each color of coating shown on the plans.

REGULATORY REQUIREMENTS.--Coatings and applications shall conform to the rules for control of volatile organic compound emissions adopted by the air quality control district in the air basin in which the coatings are applied.

SITE ENVIRONMENTAL REQUIREMENTS.--Coatings shall not be applied when the air temperature is below 10°C (20°C for varnishes) or when the relative humidity exceeds 75 percent.

The surface to be coated shall be maintained at a minimum temperature of 7°C for a period of 24 hours prior to, and 48 hours after the application of the coating. Heating facilities shall be provided when necessary.

Continuous ventilation shall be provided during application of the coatings.

A minimum lighting level of 865 lux, measured 1 m from the surface to be coated, shall be provided while surfaces are being prepared for coatings and during coating applications.

DELIVERY, STORAGE, AND HANDLING.--Products shall be delivered to the site in sealed, labeled containers and stored in a well ventilated area at an ambient air temperature of not less than 7°C. Container labeling shall include manufacturer's name, type of coating, trade name, color designation, drying time, and instructions for tinting, mixing, and thinning.

MAINTENANCE STOCK.--Upon completion of coating work, a full 3.8 liter container of each type and color of finish coat and stain used shall be delivered to the location at the project site designated by the Engineer. Containers shall be tightly sealed and labeled with color, texture, and room locations where used, in addition to the manufacturer's standard product label.

PART 2.- PRODUCTS

GENERAL.--The products shall be the best quality grade coatings of the specified types as regularly manufactured by nationally recognized paint and varnish manufacturers that have not less than 10 years experience in manufacturing paints and varnishes. Products that do not bear the manufacturer's identification as the best quality grade product shall not be used. Products for each coating system shall be by a single manufacturer and shall not contain lead type pigments.

Thinners, shellac, fillers, patching compounds, coloring tint, and other products required to achieve the specified finish shall be the manufacturer's best quality and shall be used as recommended.

PART 3.- EXECUTION

INSPECTION.--Surfaces to be coated at the jobsite shall be approved by the Engineer prior to the application of coatings. The Contractor shall notify the Engineer at least 3 working days prior to the application of coatings.

SURFACE PREPARATION.--Surfaces scheduled to be coated shall be prepared in accordance with the following, except that the surfaces not specified herein shall be prepared as recommended by the coating manufacturer.

GENERAL.--Hardware, cover plates, light fixture trim, and similar items shall be removed prior to preparing surfaces for coating. Following the application of the finish coating, the removed items shall be reinstalled in their original locations.

WOOD.--Oil and grease shall be removed by solvent wash. Mildew shall be removed by mildew wash. Surfaces to be coated shall be cleaned of all dirt, excess material, or filler by hand cleaning. Smooth surfaced wood shall be sanded lightly.

A sealer composed of equal parts of shellac and alcohol shall be spot applied to knots, sap, pitch, tar, creosote, and other bleeding substances.

After the application of the prime coat, all nail holes, cracks, open joints, dents, scars, and surface irregularities shall be filled, hand cleaned, and spot primed to provide smooth surfaces for the application of finish coats.

Irregularities in wood surfaces to receive a clear finish shall be filled and hand cleaned before the application of coatings. The color of the filler shall match the color of the coated wood.

GALVANIZED METAL.--Oils, grease, and fabrication lubricants shall be removed by solvent wash. Surfaces shall be cleaned of remaining surface treatments by hand cleaning. New surfaces shall be roughened by hand cleaning or light abrasive blasting.

Abraded or corroded areas shall be hand cleaned and spot coated with one coat of vinyl wash pretreatment. Abraded or corroded areas on new surfaces not scheduled to be painted shall be cleaned by solvent wash, hand cleaned, and given 2 spot applications of zinc rich paint.

STEEL AND OTHER FERROUS METALS.--Oils, grease, and fabrication lubricants shall be removed by solvent wash. Dirt, water soluble chemicals, and similar surface contamination shall be removed by detergent wash or steam cleaning. Mill scale and rust shall be removed by hand cleaning or abrasive blasting.

ALUMINUM AND OTHER NON-FERROUS METALS.--Oils, grease, and fabrication lubricants shall be removed by solvent wash. Dirt, water soluble chemicals, and similar surface contamination shall be removed by detergent wash.

GYPSUM BOARD.--Holes, cracks, and other surface imperfections shall be filled with joint compound or suitable filler prior to application of coatings. Taped joints and filled areas shall be hand sanded to remove excess joint compound and filler.

PREVIOUSLY COATED AND SHOP PRIMED SURFACES.--Dirt, oil, grease, or other surface contaminants shall be removed by water blasting, steam cleaning, or TSP wash. Minor surface imperfections shall be filled as required for new work. Mildew shall be removed by mildew wash. Chalking paint shall be removed by hand cleaning. The surfaces of existing hard or glossy coatings shall be abraded to dull the finish by hand cleaning or light abrasive blasting. Abrasive blasting shall not be used on wood or non-ferrous metal surfaces.

Chipped, peeling, blistered, or loose coatings shall be removed by hand cleaning, water blasting, or abrasive blasting. Bare areas shall be pretreated and primed as required for new work.

DEFINITIONS.--

DETERGENT WASH.--Removal of dirt and water soluble chemicals by scrubbing with a solution of detergent and water, and removal of all solution and residues with clean water.

HAND CLEANING.--Removal of dirt, loose rust, mill scale, excess base material, filler, aluminum oxide, chalking paint, peeling paint, or paint which is not firmly bonded to the surfaces by using hand or powered wire brushes, hand scraping tools, power grinders, or sandpaper and removal of all loose particles and dust prior to coating.

MILDEW WASH.--Removal of mildew by scrubbing with a solution of detergent, hypochlorite-type household bleach, and warm water, and removal of all solution and residues with clean water.

ABRASIVE BLASTING.--Removal of oil, grease, form release agents, paint, dirt, rust, mill scale, efflorescence, weak concrete, or laitance, by the use of airborne abrasives, and removal of loose particles, dust, and abrasives by blasting with clean air.

Abrasives shall be limited to clean dry sand, mineral grit, steel grit, or steel shot, and shall be graded to produce satisfactory results. Unwashed beach sand containing salt or silt shall not be used.

Abrasive blasting shall conform to the requirements of SSPC-SP6-85, Commercial Blast Cleaning, as defined in the Steel Structures Painting Council Manual.

Light abrasive blasting shall conform to the requirements of SSPC-SP7-85, Brush-Off Blast Cleaning, as defined in the Steel Structures Painting Council Manual.

SOLVENT WASH.--Removal of oil, grease, wax, dirt, or other foreign matter by using solvents, such as mineral spirits or xylol, or other approved cleaning compounds.

STEAM CLEANING.--Removal of oil, grease, dirt, rust, scale, or other foreign matter by using steam generated by commercial steam cleaning equipment, from a solution of water and steam cleaning compounds, and removal of all residues and cleaning compounds with clean water.

TSP WASH.--Removal of oil, grease, dirt, paint gloss, and other foreign matter by scrubbing with a solution of trisodium phosphate and warm water, and removal of all solution and residues with clean water.

WATER BLASTING.--High pressure, low volume water stream for removing dirt, light scale, chalking or peeling paint. Water blasting equipment shall produce not less than a 13 800 MPa minimum output pressure when used. Heated water shall not exceed 66°C. If a detergent solution is used, it shall be biodegradable and shall be removed from all surfaces with clean water.

PROTECTION.--The Contractor shall provide protective devices, such as tarps, screens or covers, as necessary to prevent damage to the work and to other property or persons from all cleaning and painting operations.

Paint or paint stains on surfaces not designated to be painted shall be removed by the Contractor at the Contractor's expense and the original surface restored to the satisfaction of the Engineer.

APPLICATION.--

GENERAL.--Coatings shall be applied in accordance with the printed instructions and at the application rates recommended by the manufacturer to achieve the dry film thickness specified in these special provisions.

Mixing, thinning and tinting shall conform to the manufacturer's printed instructions. Thinning will be allowed only when recommended by the manufacturer.

Coatings shall be applied only when surfaces are dry and properly prepared.

Cleaning and painting shall be scheduled so that dust and other contaminants from the cleaning process will not fall on wet, newly coated surfaces.

Materials required to be coated shall have coatings applied to all exposed surfaces, including the tops and bottoms of wood and metal doors and other surfaces not normally visible from eye level.

APPLICATION SURFACE FINISH.--Each coat shall be applied to a uniform finish. Finished surfaces shall be free of surface deviations and imperfections such as skips, cloudiness, spotting, holidays, laps, brush marks, runs, sags, curtains, ropiness, improper cutting in, overspray, drips, ridges, waves, and variations in color and texture.

Each application of a multiple application finish system shall closely resemble the final color coat, except each application shall provide enough contrast in shade to distinguish the separate applications.

WORK REQUIRED BETWEEN APPLICATIONS.--Each application of material shall be cured in accordance with the coating manufacturer's recommendations before applying the succeeding coating. Enamels and clear finishes shall be lightly sanded, dusted, and wiped clean between applications.

Stain blocking primer shall be spot applied whenever stains bleed through the previous application of a coating.

TIMING OF APPLICATIONS.--The first application of the specified coating system shall be applied prior to any deterioration of the newly prepared surface. Metal surfaces shall be prepared and prime coated the same day that cleaning of bare metal is performed. Additional prime coats shall be applied as soon as drying time of the preceding coat permits.

Metal surfaces shall be prime coated within 12 hours of application of vinyl wash pretreatment.

Shellac sealer shall be allowed to dry at least 12 hours before applying the next coat.

Drying time between applications of water borne coatings shall be at least 12 hours.

APPLICATION METHODS.--Coatings shall be applied by brush, roller or spray. Rollers shall be of a type which do not leave a stippled texture in the paint film. Extension handles for rollers shall not be greater than 2 m in length.

If spray methods are used, surface deviations and imperfections such as, overspray, thickness deviations, lap marks, and orange peel shall be considered as evidence that the work is unsatisfactory and the Contractor shall apply the remainder of the coating by brush or roller, as approved by the Engineer.

DRY FILM THICKNESS.--

Vinyl wash pretreatment	0.007 mm to 0.13 mm, maximum.
Bituminous paint	0.1 mm, minimum.
Epoxy polyamide primer	0.1 mm, minimum.
Aliphatic polyurethane enamel	0.05 mm, minimum.
Other primers, undercoats, sealers, and coatings	As recommended by the manufacturer.

BACKPRIMING.--The first application of the specified coating system shall be applied to all wood surfaces (face, back, edges, and ends) of wood materials that are not factory coated, immediately upon delivery to the project site, except surfaces of interior finish woodwork that adjoin concrete shall be coated with one application of alkyd exterior wood primer before installation.

When clear or stain type coatings are required on millwork, trim, or paneling, varnish, reduced 25 percent by mineral spirits, shall be used for coating the back faces.

PATCHES IN PREVIOUSLY COATED SURFACES.--Where patches are made on surfaces of previously coated walls or ceilings, the entire surface to corners on every side of the patch shall be coated with a minimum of one application of the finish coat.

FINISHING MECHANICAL AND ELECTRICAL COMPONENTS.--Shop primed mechanical and electrical components shall be finish coated in accordance with the coating system entitled, "Shop Primed Steel." Louvers, grilles, covers, and access panels on mechanical and electrical components shall be removed and coated separately.

Interior surfaces of air ducts which are visible through grilles or louvers shall be coated with one application of flat black enamel, to limit of the sight line.

Exposed conduit, piping, and other mechanical and electrical components visible in public areas shall be painted.

Both sides and all surfaces, including edges and back of wood mounting panels for electrical and telephone equipment shall be finish coated before installing equipment.

CLEANING.--Upon completion of all operations, the coated surfaces shall be thoroughly cleaned of dust, dirt, grease, or other unsightly materials or substances.

Surfaces marred or damaged as a result of the Contractor's operations shall be repaired, at the Contractor's expense, to match the condition of the surfaces prior to the beginning of the Contractor's operations.

COATING SYSTEMS.--The surfaces to be coated shall be as shown on the plans and as specified elsewhere in these special provisions. When a coating system is not shown or specified for a surface to be finish coated, the coating system to be used shall be as specified for the substrate material. The number of applications specified for each coating system listed herein is a minimum. Additional coats shall be applied if necessary to obtain a uniform color, texture, appearance, or required dry film thickness.

SYSTEM 1- ALUMINUM AND OTHER NON-FERROUS METALS.--

1 pretreat coat: vinyl wash pretreatment
1 prime coat: aluminum primer
2 finish coats: acrylic, exterior enamel, semi-gloss

SYSTEM 2- GALVANIZED METAL.--

1 pretreat coat: vinyl wash pretreatment
1 prime coat: galvanized metal primer
2 finish coats: acrylic, exterior enamel, semi-gloss

SYSTEM 3- GYPSUM BOARD.--

1 prime coat: PVA wall sealer
2 finish coats: acrylic, interior enamel, semi-gloss

SYSTEM 4- SHOP PRIMED STEEL.--

1 prime coat : red oxide ferrous metal primer
2 finish coats: alkyd, exterior enamel, semi-gloss

SYSTEM 5- STEEL AND OTHER FERROUS METALS.--

2 prime coats: red oxide ferrous metal primer
2 finish coats: alkyd, exterior enamel, semi-gloss

SYSTEM 6- STEEL, ALIPHATIC POLYURETHANE.--

1 prime coat: epoxy polyamide primer
2 finish coats: aliphatic polyurethane enamel, gloss

SYSTEM 7- WOOD, CLEAR FINISH.--

1 prime coat: polyurethane varnish, satin, reduced 25 percent by mineral spirits
2 finish coats: polyurethane varnish, satin

SYSTEM 8- WOOD, PAINTED.--

1 prime coat: alkyd, exterior wood primer
2 finish coats: acrylic, exterior enamel, semi-gloss

COLOR SCHEDULE.--Colors shall be as shown on the plans.

DIVISION 10. SPECIALTIES

10.01 SIGNS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing signs in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for sign materials, colors and graphics, and for fastening hardware and material shall be submitted for approval.

PART 2.- PRODUCTS

Plastic signs (permanent room identification).--

Plastic signs for permanent room identification for other than restrooms shall be scratch resistant, non-static, fire retardent, washable melamine laminate with a non-glare surface, not less than 3 mm thick. Letters and numbers shall be upper case Helvetica, 25 mm in height, 0.80 mm above and integral with sign material, accompanied by Grade 2 Braille.

Grade 2 Braille dots shall be 2.5 mm on centers in each cell with 5 mm space between cells. Dots shall be raised a minimum of 0.6 mm above the background.

Plastic sign (restroom).--

Plastic sign for restroom shall be not less than 6 mm acrylic plastic, except plastic sign for permanent restroom identification shall be not less than 3 mm thick. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Symbols and lettering shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Unisex restroom identification shall be a male and female symbol on a 305 mm equilateral triangle superimposed on a 305 mm diameter circle.

Permanent restroom identification shall be an international symbol of accessibility with a white border on a 254 mm square. Lettering shall be 0.80 mm above and integral with sign material, accompanied by Grade 2 Braille.

Grade 2 Braille dots shall be 2.5 mm on centers in each cell with 5 mm space between cells. Dots shall be raised a minimum of 0.6 mm above the background.

Accessible building entrance sign.--

Accessible building entrance sign shall be pressure sensitive decal, not less than 100 mm x 100 mm with the international symbol of accessibility.

Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Symbol and border shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Self-luminous sign (exit).--

Self-luminous sign shall be internally illuminated, self-luminous exit sign powered by permanent integral tritium gas source. Sign shall be listed by the California State Fire Marshal, and UL or other approved testing laboratory.

Sign housing shall be ABS molding. Faceplate shall be acrylic.

Fastening hardware and material.--

Fastening hardware and material shall be as recommended by the sign manufacturer. Fasteners shall be noncorrosive.

PART 3.- EXECUTION

Inscription.--Except for exit signs, sign messages shall be as shown on the plans.

Installation.--Plastic signs for room identification and restrooms shall be fastened or secured to clean, finished surfaces in accordance with the sign manufacturer's instructions. Signs shall be installed at a location and height as shown on the plans.

Metal signs shall be attached securely with galvanized or cadmium plated fasteners.

Fastening hardware and material shall be installed within the sign as shown on the plans.

10.02 FIRE EXTINGUISHERS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing fire extinguishers with mounting brackets in accordance with the details shown on the plans and these special provisions.

REFERENCES.--

General.--Fire Extinguishers shall conform to the requirements in California Code of Regulations, Title 19 Division 1, Chapter 3, "Portable Fire Extinguishers."

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and installation instructions shall be submitted for approval.

QUALITY ASSURANCE.--

Codes and standards.--Fire extinguishers shall be Underwriters Laboratories or Factory Mutual Laboratories approved for the type, rating and classification of extinguisher specified.

PART 2.- PRODUCTS

MANUFACTURER'S.--

Acceptable manufacturers.--Subject to contract compliance, manufacturers shall be J. L. Industries; Larsen's Manufacturing; Potter-Roemer; or equal.

COMPONENTS.--

Fire extinguisher.--

Fire extinguisher shall be fully charged, multi-purpose dry chemical type, with charge indicator, hose and nozzle, and attached service record tag. Fire extinguisher shall be of the capacity and type rating shown on the plans.

Mounting bracket.--

Mounting bracket shall be the manufacturer's standard painted, surface mounted type.

PART 3.- EXECUTION

INSTALLATION.--

General.--Fire extinguishers shall be installed in locations and at mounting heights shown on the plans, or if not shown, at a height of 1220 mm from the finished floor to the top of the fire extinguisher.

Fire extinguisher mounting brackets shall be attached to structure, square and plumb, in accordance with the manufacturer's recommendations.

IDENTIFICATION.--

Bracket-mounted.--Extinguishers shall be identified with red letter decals spelling "FIRE EXTINGUISHER" applied to wall surface. Letter size, style and location as selected by the Engineer.

SERVICING.--

General.--Fire extinguishers shall be serviced, charged, and tagged not more than 5 days prior to contract acceptance.

10.03 FREE STANDING STEEL SHELVING

GENERAL.--This work shall consist of furnishing and installing free standing steel shelving in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions and standard color palette shall be submitted for approval. The color will be selected by the Engineer after the award of the contract.

PRODUCTS.--

Shelving.--

Shelving shall be factory fabricated steel shelves and supports capable of supporting loads of 1200 Pa of shelf area. Shelves shall not deflect more than 8 mm when subjected to the loads specified herein and shall show no permanent deflection after removal of such loads. Shelves shall be supported and attached by means of clips. Studs or bolts shall not be used. Shelves shall be adjustable in vertical increments of 75 mm or less. Shelving shall be of the approximate dimensions and number shown on the plans and shall have a baked enamel finish.

EXECUTION.--Free standing steel shelving shall be installed in accordance with the manufacturer's instructions.

10.04 TOILET AND SHOWER ACCESSORIES

PART 1.- GENERAL

Scope.--This work shall consist of furnishing and installing toilet and shower accessories in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and installation instructions and details shall be submitted for approval.

PART 2.- PRODUCTS

Toilet tissue dispenser.--

Toilet tissue dispenser shall be dual roll, surface mounted, stainless steel with satin finish, approximately 150 mm x 290 mm x 150 mm deep. Dispenser shall utilize standard toilet tissue rolls. The top roll shall automatically drop into place after the bottom roll is depleted. One dispenser per toilet stall.

Combination paper towel dispenser and waste receptacle.--

Combination paper towel dispenser and waste receptacle shall be semi-recessed unit of stainless steel with satin finish. The approximate size shall be 355 mm x 1880 mm x 190 mm deep with 102 mm skirt. The paper towel dispenser shall have a capacity of 1000 single fold paper towels. The waste receptacle shall have a capacity of not less than 37 liters. One unit per lavatory.

Toilet seat cover dispenser.--

Toilet seat cover dispenser shall be white plastic dispenser, approximately 210 mm x 320 mm x 48 mm deep, single pack. One dispenser per toilet stall.

Napkin receptacle.--

Napkin receptacle shall be wall hung, white enameled sheet steel napkin receptacle with hinged top and bottom, disposable liner, approximate 3.8 liter capacity container. One receptacle per women's toilet stall.

Clothes hook.--

Clothes hook shall be stainless steel clothes hook with 2 prongs.

Powdered soap dispenser.--

Powdered soap dispenser shall be surface mounted, white enameled sheet steel dispenser with a capacity of at least 887 mL. The dispenser shall have an adjustable soap dispensing mechanism and a lockable top. One dispenser per lavatory.

Mirror, wall hung with shelf.--

Mirror, wall hung shall be Number 1 quality, 6 mm thick, electrolytically copper plated float or plate glass mirror with nonmoisture-absorbing filler. Mirror shall have a heavy gage galvanized steel back and stainless steel frame with integral 127 mm wide stainless steel shelf. The frame shall have a satin finish and shall be mitered and welded and the corners shall be ground smooth. Fasteners shall not penetrate surfaces of the frame exposed to view. Mirror shall conform to Federal Specification: DD-M-411b and shall be guaranteed against silver spoilage for not less than 10 years.

Steel grab bars.--

Steel grab bars shall be stainless steel, 38 mm diameter bars and escutcheon covered integral mounting flanges.

Folding seat.--

Folding seat shall be factory fabricated with teakwood or woodgrain phenolic slats, Type 304 stainless steel tube frame with satin finish, wall bracket and hinge. Wood slats shall be factory stained and varnished. Size shall be as shown on the plans. Folding seat shall be Bradley, Bobrick, or equal.

Privacy curtain.--

Privacy curtain shall be flame resistant, one-way draw, nylon reinforced, anti-bacterial vinyl fabric. Curtain shall be 1.8 meters long.

Privacy curtain rod shall be stainless steel, fixed mounted shower rod with stainless steel mounting plates.

PART 3.- EXECUTION

Installation.--Toilet and shower accessories shall be installed in accordance with the manufacturer's recommendations. Fasteners for mounting accessories shall be concealed and tamper proof.

Toilet and shower accessories shall be mounted after painting work is complete.

All toilet room accessories shall be mounted plumb, secure and rigid. Grab bars shall be supported adequately so the bars will withstand an applied load of 113 kg at any point.

Support assembly for folding seat shall bear solidly on the wall without rocking and shall be fastened rigidly and securely to the wall in accordance with the manufacturer's recommendations.

DIVISION 11. EQUIPMENT**11.01 LUBRICATION AND COMPRESSED AIR SYSTEMS****PART 1.- GENERAL****SUMMARY.--**

Scope.--This work shall consist of furnishing and installing lubrication and compressed air systems in accordance with the details shown on the plans and these special provisions.

The lubrication system shall include drum dollies; overhead hose reels and pneumatic pumps for dispensing chassis lubricant, motor oil, automatic transmission fluid, gear lubricant and hydraulic fluid; overhead electric light, overhead air; and all connecting pipelines, hoses, accessories and mounting assemblies.

The compressed air system shall include a compressor, regulators, gauges and compressed air piping.

Pipes and fittings shall be in accordance with the requirements specified under "Pipes, Fittings, and Valves," in Division 15, "Mechanical," of these special provisions.

Permits to operate.--Attention is directed to the latest Division of Industrial Safety (DIS) regulations regarding tank mounted air compressors.

The Contractor shall provide all permits to operate pressure vessels in accordance with the requirements of the DIS and shall pay all costs for such permits. Such permits shall be posted under glass at the work site.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data shall be submitted for approval.

Manufacturer's descriptive data shall include a complete description, performance data and installation instructions for the materials and equipment specified herein.

Performance data shall include the product delivery rate and discharge pressure for each type of pump assembly.

CLOSEOUT SUBMITTALS.--

Operation and maintenance manuals.--Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be in a bound manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material shall be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

WARRANTY.--

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

PART 2.- PRODUCTS

OVERHEAD HOSE REEL ASSEMBLIES.--

General.--Overhead hose reel assemblies shall be heavy duty assemblies of steel construction with connecting hoses, locking automatic ratchets, guide rollers and heavy duty spring activated hose pickups. Reels shall have bushings, swivels, ball stops, delivery hoses and control valves. The reels shall have a baked enamel finish. Manufacturer's reel mounting brackets shall be supplied with reels.

The Contractor shall submit to the Engineer for approval the proposed hanging arrangement of overhead hose reel assemblies.

Chassis lubrication reel assembly.--

The chassis lubricant reel assembly shall have a 12 m minimum length, minimum 6 mm outside diameter, high pressure delivery hose and outlet control valve. The delivery hose shall be rated for 34.5 MPa working pressure and 137.9 MPa bursting pressure. The chassis lubricant reel assembly shall be Lincoln, 85051; Graco, 224-363, 224-417, and 202-577; or equal.

Motor oil reel assembly.--

The motor oil reel assembly shall have a 10 liter metering shutoff valve assembly with totalizer, non-drip nozzle extension, strainer and a 12 m minimum length of 13 mm inside diameter, medium pressure delivery hose. The delivery hose shall be rated for 5520 kPa working pressure and 27.6 MPa bursting pressure. The motor oil reel assembly shall be Lincoln, 83464 and 899; Graco, 224-057, 218-549, 222-648, 203-265, 157-958, and 108-478; or equal.

Automatic transmission fluid reel assembly.--

Automatic transmission fluid (ATF) reel assembly shall have a volume control valve, non-drip nozzle and 12 m minimum length of 13 mm outside diameter, medium pressure delivery hose. The delivery hose shall be rated for 5520 kPa working pressure and 27.6 MPa bursting pressure. The ATF reel assembly shall be a Lincoln, 83464 and 776; Graco, 224-057, 218-549, and 222-413; or equal.

Gear lubricant reel assembly.--

Gear lubricant reel assembly shall have an 10 liter metering shut-off valve assembly with totalizer, non-drip nozzle and a 12 m minimum length of 13 mm outside diameter, medium pressure delivery hose. The delivery hose shall be rated for 5520 kPa working pressure and 27.6 MPa bursting pressure. The gear lubricant reel assembly shall be Lincoln, 83464 and 881; Graco, 224-057, 218-549,222-648, 201-701, 157-958 and 108-478; or equal.

Hydraulic fluid reel assembly.--

The hydraulic fluid reel assembly shall have a shutoff valve assembly with totalizer, non-drip nozzle extension, strainer and a 12 m minimum length of 13 mm outside diameter, medium pressure delivery hose. The delivery hose shall be rated for 5520 kPa working pressure and 27.6 MPa bursting pressure. The hydraulic fluid reel assembly shall be Lincoln, 83464 and 776; Graco, 224-057, 218-549, 222-413; or equal.

Compressed air reel assembly.--

Compressed air reel assembly shall have 12 m minimum length of 10 mm inside diameter delivery hose with heavy duty air gauge control valve and foot truck chuck. The air chuck shall have a 300 mm length of hose to an in-line valve and gauge. Compressed air reel assembly shall be Lincoln; Alemite; or equal.

PUMP ASSEMBLIES.--

General.--Pump assemblies shall be lubricant and oil type pump assemblies with air driven motors and shall be suitable for operation with stationary, exposed drums. Pump assemblies shall include pressure relief kits. Air connector hose shall be rated for 1720 kPa minimum working pressure. Product connector hose shall be as specified for the individual reel assembly. Pump assemblies shall produce the flowrates and pressures as specified under "Testing".

Chassis lubricant pump assembly.--

Chassis lubricant pump assembly shall be suitable for use with stationary, exposed 55 kg drums, complete with drum cover, air coupler and follower plate, and shall have a minimum pressure ratio of 45:1 and a maximum pressure ratio of 50:1. The chassis lubricant pump assembly shall be Lincoln, 918; Alemite, 8550; Graco, 225-014; or equal.

Motor oil, hydraulic fluid, ATF and gear oil pump assemblies.--

Motor oil, hydraulic fluid, ATF and gear oil pump assemblies shall be suitable for use with stationary, exposed 205 liter drums and equipped with a bung bushing and an air expeller in the pump tube and shall have a 76 mm air motor. The motor oil pump assembly shall be equipped with a flow compensator. Pump assemblies shall be Lincoln, 424; Alemite, 8569; Graco, 225-640; or equal.

MISCELLANEOUS COMPONENTS.--

Light reel assembly.--

Light reel assembly shall be overhead type light reel with a positive reel latch cord lock mechanism, release mechanism, reel cord retractor, 9 m minimum length of 3-wire cord, 600 mm pigtail, ball stop, vapor-tight high impact phenolic plastic holder without switch or receptacle with heavy duty lamp guard and 100-watt incandescent bulb or 15-watt fluorescent tube. The incandescent light reel assembly shall be Alemite, 330005C; or equal. The fluorescent light reel assembly shall be Hi Reel, 3005-AFL; Woodhead, 945-3SW-1003-3S; or equal.

Air compressor.--

Air compressor shall be 2-stage, 1210 kPa design, 860 kPa output, mounted on an ASME code vertical type receiver. The air compressor shall be complete with unloader, V-belt drive, belt guard, oil and air pressure gauges, automatic pressure controller, outlet valve, ASME relief valve, air intake filter, ball valve drain and an automatic tank drain operated by either the compressor unloader or a governor. Motor shall be high efficiency type, open dripproof with class B insulation. Air compressor shall be Champion, Ingersol Rand, Kellogg, or equal.

Pressure regulator.--

Pressure regulator shall be combination type with filter, bowl, pressure regulator and pressure gauge.

The filter bowl shall be the quick disconnect type, plastic with metal guard, manual drain, and 5 micron filter.

Pressure regulator shall be diaphragm controlled, balanced valve type, rated for 0 to 1100 kPa operation and shall be equipped with pressure gage, bottom clean-out plugs and internal strainers. Regulator shall be Wilkerson, Lincoln, Wabco, or equal.

Flexible coupling.--

Flexible coupling shall be brass flexible metal hose with threaded union ends and a minimum working pressure of 1380 kPa.

Pressure gage.--

Pressure gage shall be rotary type ANSI Standard: B40.1, Grade A, with 90 mm dial, liquid filled with cover, plain case, reset screw and bottom inlet. Pressure gage movement shall be phosphor bronze bushed. Gage shall read from 0 kPa to 1100 kPa. Each gage shall be equipped with a gage cock. Pressure gage shall be Marsh, Ashcroft, US Gage, or equal.

Drum dolly.--

Drum dolly shall have welded steel construction with a cross braced bottom and a 50 mm continuous perimeter lip, 4 ball bearing casters with steel or semi-steel wheels. Drum dolly shall be sized for 55 kg, drums or 205 liter drums as applicable.

PART 3.- EXECUTION**INSTALLATION.--**

General.--The hose reels shall be installed rigidly and securely to the reel mounting bracket. The mounting bracket shall be attached to the overhead structure as shown on the plans.

Pipelines shall be cleaned and flushed immediately prior to connecting the control valves.

Pressure relief kits shall be installed on the discharge side of the gear lube, ATF and motor oil pumps as recommended by the pump manufacturer.

Air compressor shall be installed with drain piping, vibration isolation pads and expansion anchors.

Unions shall be installed before and after the pressure regulator/ball valve assembly.

Each pump assembly drum shall be supplied with a drum dolly.

FIELD QUALITY CONTROL.--

Testing.--All tests, including general performance tests to demonstrate the proper operation of the lubrication systems and the air compressor, shall be performed by the Contractor in the presence of the Engineer.

The air compressor system shall be tested for the operational range, the cut-off pressure and the operation of air drops and system components.

The lubrication system, including piping and hoses, shall be tested for leaks and the rates of delivery specified herein. The lubrication connections shall show no visible signs of leaks when the system is filled with the specified lubricant and tested at 1040 kPa lubricant pump inlet air pressure.

The Contractor shall demonstrate that the completed lubrication system will deliver the given product at the flowrate and discharge pressure specified by the pump assembly manufacturer. If no specification is given the lubricants shall be delivered at the following rates at 1040 kPa lubricant pump inlet air pressure:

Lubricant Material	Delivery Rate
Chassis lubricant NLGI No. 2 grease	0.7 liters per minute
Motor oil (10W/40)	7 liters per minute
Gear oil (85W/140)	6 liters per minute
ATF (SAE 10)	8 liters per minute
Hydraulic fluid	8 liters minute

The required delivery rate values may be adjusted, as determined by the Engineer, when testing for delivery rates with different materials or at temperatures other than 21°C.

The drums and lubricating material for testing the lubrication system will be State-furnished as provided under "State-Furnished Materials" in Division 1, "General Requirements," of these special provisions.

11.02 EXHAUST EVACUATION HOSE REEL AND FAN

PART 1.- GENERAL

Scope.--This work shall consist of furnishing and installing exhaust evacuation hose reel and fan equipment, including overhead fume exhaust fan, hose reel, hose and remote operating station. All work shall be done in accordance with the details shown on the plans and these special provisions.

Supports, Mechanical and Electrical work and all other work incidental to, and necessary for, the proper installation and operation of the items of equipment shall conform to the requirements specified for similar work elsewhere in these special provisions.

SUBMITTALS.--

The Contractor shall submit to the Engineer for approval the proposed supporting arrangement and wall framing of exhaust evacuation hose reel and fan.

Product data.--Manufacturer's description data, installation recommendations, shop drawings, schematic diagram, interconnection diagram, including reel installation mounting brackets, shall be submitted for approval. Fan, hose reel and push button station shall be from same manufacturer. System shall be Nederman, CarMon or equal.

PART 2.- PRODUCTS

Exhaust evacuation fan.--

Exhaust evacuation fan shall be centrifugal AMCA certified exhaust fan suitable for diesel or gasoline powered vehicle exhaust applications. Fan parts exposed to air stream shall be coated to prevent acid corrosion. The exhaust evacuation fan shall be mounted with vibration isolators on the reel. The fan size and performance shall be as shown on plans.

Hose reel assembly.--

Hose reel assembly shall be provided with 9 m minimum of 150 mm diameter flexible hose. The hose reel shall be motor operated and shall be capable of unwinding and recoiling the hose from a remote operating station. All electrical equipment necessary for operation shall be mounted on the hose reel assembly except for the remote operating station. The hose reel motor shall be interlocked with an adjustable limit switch that stops the reel when the tubing has been fully extended or fully retracted.

Hose.--

Exhaust hose shall be fabricated of a high strength woven glass fiber cloth supported by a helically wound spring steel wire. The hose shall be capable of withstanding temperatures of 150°C and shall be supplied with a rubber nozzle of the same size as hose provided.

Pushbutton station.--

Pushbutton operating station shall consist of a 3 button (up, down, on/off) controller wired directly to the hose reel assembly. The up and down buttons shall be momentary push button type.

Control panel.--

Control panel shall be a complete system routinely advertised, furnished and guaranteed by the exhaust evacuation hose reel and fan manufacturer.

Control panel shall include circuit breakers, starters, fan motor contactor, power supply, limit switch and controls that are required for proper operation.

PART 3.- EXECUTION**INSTALLATION.--**

General.--The exhaust evacuation hose reel and fan shall be installed in accordance with the manufacturer's recommendations. The exhaust evacuation units and pushbutton station shall be located as shown on the plans.

FIELD QUALITY CONTROL.--

Testing.--The test shall consist of a general performance test to demonstrate the proper operation of the exhaust evacuation hose reel and fan system. The test shall be performed by the Contractor in the presence of the Engineer.

11.03 WORKBENCH**PART 1.- GENERAL****SUMMARY.--**

Scope.--This work shall consist of furnishing and installing a workbench in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and standard color palette shall be submitted for approval.

PART 2.- PRODUCTS**Workbench.--**

Workbench shall be standard, factory fabricated and factory painted heavy duty workbench unit with plywood reinforced steel top, drawers, curb and shelves. Plywood top reinforcement shall consist of two layers of securely fastened 19 mm thick exterior type plywood. The drawers, shelves and curb shall be as shown on the plans. Paint shall be an industrial grade enamel.

Leg anchors.--

Leg anchors shall be ICBO approved, integral stud type expansion anchors or internally threaded type anchors with independent stud.

PART 3.- EXECUTION

Installation.--The workbench shall be installed with the top level and the legs rigidly and securely fastened to the floor. Anchors for the legs shall be installed in accordance with the manufacturer's instructions.

DIVISION 12. FURNISHINGS (Blank)**DIVISION 13. SPECIAL CONSTRUCTION****13.01 PRE-ENGINEERED STEEL BUILDING**

GENERAL.--This work shall consist of designing, fabricating, furnishing and erecting a pre-engineered steel building in accordance with the details shown on the plans and these special provisions.

Pre-engineered steel building shall be of the rigid frame type with tapered columns and shall include structural steel framing, permanent lateral bracing, anchor bolts, base plate ties, fasteners, roof panels, wall panels, gutters and downdrains, sealants, doors, windows, louvers, insulation, ventilators, flashings, and such other parts, elements or components of the frame and outside walls and roof, not mentioned, which are required for the complete construction of a rigid, waterproof building.

The building dimensions shown on the plans are minimal and may be increased to accommodate manufacturer's standards. No additional compensation will be allowed for any changes required by such increased dimensions.

DESIGN CRITERIA.--The building and the building design shall be in accordance with the applicable requirements in the latest edition of the following publications: "Specification for the Design, Fabrication and Erection of Structural Steel for Buildings," published by AISC; "Specification for the Design of Cold-Formed Steel Structural Members," published by AISI; the "Metal Building Systems Manual," published by the Metal Building Manufacturers Association, and the Uniform Building Code, including the modification to loads or stresses indicated therein.

The building shall be designed for simple erection with only bolted type field connections for framing.

The building shall be designed to support the weight of the building components and the live load, snow load, wind load, seismic load, and other loads shown in the design notes on the plans. In addition, the building shall be designed to support collateral loads, which include additional dead loads other than the weight of the metal building system such as ceilings and mechanical and electrical systems, and auxiliary loads, which include dynamic live loads such as those generated by materials-handling equipment.

The maximum vertical deflection of the building main framing members shall not exceed 1/180th of their respective spans. The maximum vertical deflection due to live load in roof panel and purlins shall not exceed 1/240th of their respective spans. The maximum horizontal deflection on wall panels and girts shall be limited to 1/180th of their respective spans.

The design shall include wind and earthquake bracing, weathertight features, and reinforcement at openings for accessories.

Horizontal acting forces shall be applied parallel and perpendicular to the direction of the bents.

Diagonal rods or rigidly connected structural framing shall be used to resist lateral loads, except wall and roof panels may be used to resist lateral loads, provided that design calculations and laboratory test data, satisfactory to the Engineer, are submitted to substantiate their adequacy. Cables shall not be used for permanent lateral bracing.

The roof covering system shall be designed for an Underwriter Laboratory Class 60 minimum wind uplift rating.

Weathertight features of the design shall include closures and continuous seals at panel ends and sides, flashing, sealing, lapping of panels in the direction of prevailing winds, and seals under fastener heads.

SUBMITTALS.--Complete shop drawings, erection instructions and drawings, design calculations, complete material descriptive information and manufacturer's standard color palette shall be submitted for approval. Submittals shall be approved prior to the start of fabrication.

Shop drawings, erection drawings and design calculations shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California. The expiration date of the registration shall be shown.

Contract No. 09-307904

Shop drawings shall show the size, thickness, shape, configuration, type, grade, class, description and coating, if any, of all materials used in the building. Joint details, connection and anchoring details and details of all temporary and permanent bracing shall be shown.

Shop drawings shall show the size, location, and framing for any doors, windows, duct penetrations, and any additional supports required for wall mounted equipment. Method of attachment of overhead doors to the building shall be shown.

Calculations for the design of the building and the bracing shall include a list of applied loads and load combinations with the resulting member forces and member stresses. Maximum upward acting, downward acting and horizontal acting forces at the base of columns shall be included.

If the design calculations consist of computerized or tabulated calculations, the values pertaining to the building design for this project shall be identified, described or indexed in such a manner that a design check can be performed.

The manufacturer's color palette shall show the standard color line of baked polyester enamel coatings for building and accent colors. The colors shall be as shown on the plans.

CERTIFICATES OF COMPLIANCE.--Certificates of Compliance shall be furnished for the pre-engineered steel building in accordance with the requirements specified in Section 4-1.04, "Certificates of Compliance," of the General Conditions.

DELIVERY, STORAGE AND HANDLING.--The pre-engineered steel building components shall be transported and handled in such a manner as to prevent damage due to twisting, distortion or deformation. Building components shall be stored off the ground.

PRODUCTS.--

Primary and secondary steel framing members.--

Primary and secondary steel framing members shall be manufacturer's standards for the type, size and shape of building to be constructed. The minimum steel strength shall be as shown on the plans.

Roof panels.--

Roof panels shall be not less than 0.55 mm thick (26-gage), cold-formed, zinc-coated (galvanized) sheet steel conforming to ASTM Designation: A 653/653M, Grade 33 [230] with G90 [Z275] coating. Panels shall have primary vertical ribs spaced at 300 mm maximum with 3 intermediate secondary ribs located between the primary ribs. The depth of the primary ribs shall be between 19 mm and 38 mm. The net minimum width of the panels shall be 600 mm. Each roof panel shall have an integral anti-siphon trough or break. Roof panels shall be continuous from ridge to eaves for all roof slopes 10.7 meters or less in length.

Wall panels.--

Wall panels shall be not less than 0.55 mm thick (26-gage), cold-formed, zinc-coated (galvanized) sheet steel conforming to ASTM Designation: A 653/653M, Grade 33 [230] with G90 [Z275] coating. Wall panels shall be continuous from eaves or gables to sill except at wall openings.

Insulation.--

Insulation shall be as specified under "Insulation for Pre-engineered Steel Building" in Division 7, "Thermal and Moisture Protection," of these special provisions.

Fastener.--

Fasteners for the steel frame, roof panels, wall panels and accessories shall be the building manufacturer's standards and shall be of the size, type and spacing required by the design.

Sealant.--

Sealant shall be single component polysulfide or butyl conforming to Federal Specification: TT-S-230A and ASTM Designation: C 920. Sealant shall be clear, translucent or opaque white.

Backer rod.--

Backer rod shall be round, open cell polyurethane, sized such that it must be compressed between 25 and 75 percent of its uncompressed diameter when inserted in the joint.

Bituminous sealant.--

Bituminous sealant shall conform to Federal Specification: SS-C-153.

Rib and flute closures.--

Rib and flute closures shall be ultraviolet and weather resistant rubber, neoprene or closed cell polyethylene.

Accessories.--**Hinged doors and frames, windows, overhead doors, and finish hardware.--**

Hinged doors and frames, windows, overhead doors, and finish hardware shall be as specified in Division 8, "Doors and Windows," of these special provisions.

Roof and wall jacks (flue and plumbing vents)--

Roof and wall jacks (flue and plumbing vents) shall be building manufacturer's standard galvanized sheet . The size and shape of the base assemblies shall be as required to fit the profile of the roof and wall panels and the flues and vents. Provide snow guard bracing as shown on the plans. Finish shall be powder coated to match roofing panels.

Access door.--

Access door shall be building manufacturer's standard with frame, semi-concealed hinges and provisions for keyed lock in the closed position.

Fascia, trim, metal soffit, coping, ridge cover, gutters, downspouts, flashings, clips and miscellaneous support shapes.--

Fascia, trim, metal soffit, coping, ridge cover, flashings, clips and miscellaneous support shapes shall be building manufacturer's standards.

EXECUTION.--

Polycarbonate snow guards shall be installed along the lower flat of all roof panels along eaves. A minimum of two mechanical fasteners per snow guard shall be used. Finish color shall match roof panels. Mechanical fastening installation shall provide leakproof and watertight seal.

FABRICATION.--Building frame components shall have all the bolt holes necessary for erecting, assembling and fastening made at the factory.

Bolt holes shall be either punched full size, drilled full size, subpunched and reamed, or subdrilled and reamed. The finished holes shall be cylindrical, perpendicular to the plane of the connection and shall be not more than 2 mm larger than the nominal diameter of the bolt. Mispunched or misdrilled holes shall not be corrected by welding unless approved by the Engineer.

FRAMING ERECTION.--Framing shall be erected plumb and true in accordance with the requirements of the AISC specifications and shall be secured rigidly in place in accordance with the details shown on the approved shop drawings and the recommendations to the building manufacturer.

Anchor bolts for the framing columns and the lateral tie rods shall be cast into the foundation foundations.

Temporary bracing shall be installed during erection to hold the framing plumb and true and in a safe position until sufficient permanent bracing and construction is in place to provide full stability. All permanent bracing shall be secured in place before any sustained permanent loads are applied to the framing system. Bracing shall be positioned to clear electrical work and openings for accessories.

Openings for accessories shall be plumb and level, of the correct dimensions, located approximately where shown on the plans and reinforced to support the loads of the accessories.

Cutting, welding or altering of the framing members at the site shall not be allowed without written approval of the Engineer.

ROOF AND WALL PANEL INSTALLATION.--Roof and wall panels shall be installed in accordance with the manufacturer's recommendations.

Prior to the installation of the wall panels, the joint between the concrete and the wall base angle shall be waterproofed by fully bedding the angle in bituminous sealant.

Panels shall be adjusted to final position and brought to bear on the structural supports prior to fastening. Side laps shall be as recommended by the building manufacturer and shall be located over structural supports.

Cutting and fitting of the panels shall present a neat and true appearance with exposed burrs removed. Openings through the panels shall be cut square and shall be reinforced as recommended by the manufacturer.

Fasteners for panels shall be installed with an electric screwdriver equipped with a depth sensing nosepiece. Adjustment of the depth sensing nosepiece shall be checked prior to each day's use and when directed by the Engineer.

Isolation coatings shall be provided between surfaces of dissimilar metals.

Closures shall be installed and sealant shall be applied as recommended by the manufacturer to prevent weather penetration.

Roof and wall jacks for flues and vents and louvers shall be installed with the roof and wall panels and shall be weathertight.

The completed installation shall be without defacements, bends, sags, dimples, undulations, or other deformations; shall be free of vibration, rattles and noise due to wind or thermal movement; and shall be weathertight.

SEALING JOINTS.--Joints shall be sealed as shown on the plans. Sealant shall be applied in accordance with manufacturer's recommendations. Applications shall be a continuous operation for the length of the joint. Following the application of the sealant, the joint shall be tooled using a tool similar to that used to produce concave masonry joints. The joint shall remain undisturbed after tooling for not less than 48 hours.

PAINTING.--Surfaces of wall and roof sheathing panels and trim exposed to view shall be cleaned, treated by either the bonderizing or an approved phosphatizing process, given at least 2 applications of the polyester enamel finish paint, and then oven baked.

All surfaces of steel framing shall be cleaned and painted with 2 coats of primer at the factory. Two applications of the finish coating shall be applied to exposed surfaces of steel framing either at the factory or after erection. Cleaning and painting shall be in accordance with the requirements specified for steel and other ferrous metals under "Painting" in Division 9, "Finishes," of these special provisions.

After erection, all areas where the factory applied primer or finish coatings have been damaged or have deteriorated shall be thoroughly cleaned and spot painted. Spot painted areas of primer shall be approved prior to the application of the finish coats. Spot painting of the finish coating shall extend to edges, corners or other features that conceal the differences between new painting and shop applied coatings.

Other surfaces exposed to view, that are not coated at the factory, shall be coated. Cleaning and coating shall be in accordance with the requirements specified for the particular type of substrate material under "Painting" in Division 9, "Finishes," of these special provisions.

CLEAN-UP.--Sheathing panels, trim and other prefinished metal surfaces shall be cleaned after installation as recommended by the building manufacturer. Exposed cuts in sheathing panels shall be touched-up with a durable primer and paint as recommended by the building manufacturer.

DIVISION 14. CONVEYING SYSTEMS (Blank)

DIVISION 15. MECHANICAL

15.01 MECHANICAL WORK

GENERAL.--

Scope.--This work shall consist of performing mechanical work in accordance with the details shown on the plans and these special provisions.

Mechanical work shall include furnishing all labor, materials, equipment and services required for providing heating, ventilating, air conditioning, plumbing and liquefied petroleum gas (LPG) distribution systems.

Earthwork, foundations, sheet metal, painting, electrical, and such other work incidental and necessary to the proper installation and operation of the mechanical work shall be in accordance with the requirements specified for similar type work elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of pipes, ducts, etc., and location of equipment is to be governed by structural conditions and obstructions. Equipment requiring maintenance and inspection is to be readily accessible.

Roof penetrations shall be flashed and sealed watertight in accordance with the requirements specified under "Sheet Metal Flashing" in Division 7, "Thermal and Moisture Protection," of these special provisions.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for plumbing fixtures, and component layout shall be included where applicable.

Manufacturer's descriptive data shall be submitted for the following:

- All pipes, valves and fittings
- All plumbing fixtures and accessories
- Declassification fan
- Electric water cooler
- Exhaust evacuation hose reel and fan
- Fume exhaust fan
- Emergency shower and eye wash
- Heat pump
- Unit heater
- Exhaust fans
- Water heater
- Pipe insulation
- Heat-vent light combination
- Backflow preventer
- Infra-red radiant heaters
- Thermostats
- Time switch
- Electric water heater

CLOSEOUT SUBMITTALS.--

Operation and maintenance manuals.--Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be indexed and bound in a manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material shall be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

Operation and maintenance manuals shall be submitted for the following equipment:

Contract No. 09-307904

Declassification fan
Exhaust fans
Electric water cooler
Exhaust evacuation hose reel and fan
Fume exhaust fan
Heat pump
Water heater
Unit heater
Thermostat
Infra-red radiant heaters

QUALITY ASSURANCE.--

Codes and standards.--Mechanical work, including equipment, materials and installation, shall conform to the California Building Standards Code, Title 24, and to the California Code of Regulations, Title 8, Chapter 4, Division of Industrial Safety (DIS).

WARRANTY.--

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

SYSTEM IDENTIFICATION.--

Piping and equipment.--Identification of piping and equipment shall be as shown on the plans or these special provisions:

Above ground piping.--Markers shall be provided on lines which are either exposed or concealed in accessible spaces. For piping systems, except drain and vent lines, indicate the fluid conveyed or its abbreviation; either by preprinted markers or stenciled markings, and include arrows to show the direction of flow. Colors shall comply with ANSI Standard: A13.1. Locate markers at ends of lines, near major branches and other interruptions including equipment in the line, where lines pass through penetrations in floors, walls or ceilings or otherwise pass into inaccessible spaces, and at 15 m maximum intervals along exposed portions of the lines. Marking of short branches and repetitive branches for equipment connections is not required.

Equipment.--All equipment shall be identified with a plastic laminated, engraved nameplate which bears the unit mark number as indicated on the drawings (for example, AC-4). Provide 13 mm high lettering, white on black background. Nameplates shall be permanently secured to the unit.

15.02 PIPE, FITTINGS AND VALVES

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing pipes, fittings and valves in accordance with the details shown on the plans and these special provisions. Pipe, fittings and valves shall include such plumbing and piping accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the plumbing and piping systems.

All piping insulation and associated material shall be in accordance with the requirements specified under "Mechanical Insulation," elsewhere in this Division 15.

Cathodic protection for underground piping shall be in accordance with the requirements specified under "Cathodic Protection," in Division 15, "Mechanical," of these special provisions.

The pipe sizes shown on the plans are nominal pipe size. No change in the pipe size shown on the plans shall be permitted without written permission from the Engineer.

The pipe and fitting classes and material descriptions shall be as specified herein. No change in class or description shall be permitted without written permission from the Engineer.

QUALITY ASSURANCE.--

Codes and standards.--Pipe, fittings and valves shall be installed in accordance with the requirements in the latest edition of the Uniform Plumbing Code, the manufacturer's recommendations and the requirements specified herein.

PART 2.- PRODUCTS

MATERIALS.--

PIPE AND FITTINGS --

Class Description

A1.--

Schedule 40 galvanized steel pipe conforming to ASTM Designation: A 53, with 1040 kPa galvanized malleable iron banded screwed fittings and galvanized steel couplings. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.

A2.--

Schedule 40 galvanized steel pipe conforming to ASTM Designation: A 53, with black cast iron recessed drainage fittings. For rainwater leaders, neoprene-gasket compression couplings, Smith Blair, Dresser, or equal, may be used. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.

B2.--

Schedule 40 black steel pipe conforming to ASTM Designation: A 53, with 1040 kPa black malleable iron banded screwed fittings and black steel couplings.

Steel pipe coating, where required, shall be factory applied plastic. Pipe coating shall be Standard Pipe Protection, X-Tru-Coat (0.50 mm thick); Pipe Line Service Corporation, Republic; 3M Company, Scotchkote 205 (0.30 mm thick); or equal.

B3.--

Schedule 80 black steel pipe conforming to ASTM Designation: A 53 grade B, 50 mm and smaller shall be 20 700 kPa WOG socket welding fittings and couplings or 13 800 kPa WOG threaded forged steel, ASTM Designation: A 105. 65 mm and larger shall be extra strong weight butt welding fittings and couplings.

C1.--

Hub and plain end cast iron soil pipe with neoprene gaskets conforming to Cast Iron Soil Pipe Institute's Standard 301. Pipe, fittings and gaskets shall be of one manufacturer.

C2.--

Hubless cast iron soil pipe with neoprene gaskets, corrugated stainless steel shields and stainless steel clamps conforming to Cast Iron Soil Pipe Institute's Standard 301. Joint materials shall be furnished by pipe manufacturer.

H1.--

Type DWV hard copper tubing conforming to ASTM Designation: B 306, with DWV drainage fittings, stop type couplings and threaded adapters.

H2.--

Type K hard copper tubing conforming to ASTM Designation: B 88, with wrought copper or cast bronze solder joint pressure fittings, stop type couplings and threaded adapters. Solder shall be lead-free.

H3.--

Type L hard copper tubing conforming to ASTM Designation: B 88, with wrought copper or cast bronze solder joint pressure fittings, stop type couplings and threaded adapters. Solder shall be lead-free.

LP1.--

2.1 mm thick seamless steel tubing with high pressure flareless steel tube fittings. Bends, if required, shall be made with tube bender on 115 mm minimum radius.

LP2.--

0.9 mm thick seamless steel tubing with high pressure flareless steel tube fittings. Bends, if required, shall be made with tube bender on 115 mm minimum radius.

P1.--

Polyvinyl chloride (PVC) gravity sewer plastic pipe and fittings conforming to ASTM Designation: D 3034, Standard Dimension Ratio (SDR) 35, with integral bell and bell and spigot rubber gasketed joints or conforming to ASTM Designation: D2665 with solvent welded fittings. Rubber gaskets shall conform to ASTM Designation: F 477. Stainless steel clamps with rubber boots shall not be used.

P2.--

Polyvinyl chloride (PVC) plastic pipe and fittings conforming to ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 1380 kPa working pressure at 23°C, National Sanitation Foundation approved. Pipe shall have bell ends conforming to ASTM Designation: D 3139 with triple edge rubber sealing ring. For pipe sizes 50 mm diameter and smaller, plain end pipe with solvent welded fittings ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 1380 kPa may be used.

P3.--

Polyvinyl chloride (PVC) standard weight pipe and fittings, Schedule 40, conforming to ASTM Designation: D 1785. Pipe shall meet or exceed requirements of National Sanitation Foundation Standard No. 14. Pipe shall have bell ends conforming to ASTM Designation: D 2672. For pipe sizes 75 mm and smaller, plain end pipe with solvent welded fittings conforming to ASTM Designation: D 2241, may be used.

P4.--

Polyvinyl chloride (PVC) plastic pipe and fittings shall conform to AWWA Designation: C900, class 150, Standard Dimension Ratio (SDR) 18. Pipe shall have bell end with a solid cross section elastomeric ring conforming to ASTM Designation: D 1869. Pipe shall be listed for fire protection.

Unions (for steel pipe)--

Unions (for steel pipe) shall be 1730 kPa, threaded malleable iron, ground joint, brass to iron seat, galvanized or black to match piping.

Unions (for copper or brass pipe)--

Unions (for copper or brass pipe) shall be 1040 kPa cast bronze, ground joint, bronze to bronze seat with silver brazing threadless ends or 860 kPa cast brass, ground joint, brass to brass seat with threaded ends.

Unions (for brass waste and flush pipes).--

Unions (for brass waste and flush pipes) shall be slip or flange joint unions with soft rubber or leather gaskets. Unions shall be placed on the fixture side of the traps.

Dielectric waterway.--

Dielectric waterway shall be a premanufactured unit that incorporates an insulated interior lining at least 75 mm in length between the 2 pipes being connected while maintaining metal to metal contact on the exterior surface. Dielectric water way shall be listed by IAPMO (International Association of Plumbing and Mechanical Officials).

Insulating union.--

Insulating union or flange as applicable shall be suitable for the service on which used. Connections shall be constructed such that the 2 pipes being connected are completely insulated from each other with no metal to metal contact. Insulating couplings shall not be used. Insulating union shall be F. H. Maloney; Central Plastics; EPCO; or equal.

Insulating connection (to water heater).--

Insulating connection (to water heater) shall be 150 mm minimum, flexible copper tubing with dielectric union at each end and designed to withstand a pressure of 1040 kPa and a temperature of 93°C.

VALVES.--**Gate valve (65 mm and smaller).--**

Gate valve (65 mm and smaller) shall be bronze body and trim, removable bonnet and non rising stem, Class 125 and same size as pipe in which installed. Gate valve shall be Crane, 438; Nibco Scott, T-113; Jenkins, 370; or equal.

Gate valve in nonferrous water piping systems may be solder joint type with bronze body and trim. Valve shall be Kitz, 59; Nibco Scott, S-113; Jenkins, 1240; or equal.

Ball valve.--

Ball valve shall be two piece, minimum 2760 kPa WOG, bronze body and chrome plated or brass ball with full size port. Valve shall be Nibco Scott, T-580; Watts, B-6000; Kitz, 56; or equal.

LPG gas valve.--

87

LPG gas valve shall be listed, 1730 kPa (minimum) WOG bronze ball valve. Valve shall be Jenkins, Model 30-A; Crane, Accesso; Watts; or equal.

Check valve (40 mm and smaller).--

Check valve (40 mm and smaller) shall be silent spring loaded type, threaded bronze body, nylon or teflon disc, beryllium or stainless steel helical spring and shaft, Class 125 and same size as pipe in which installed. Check valve shall be Nibco/Scott, T-480; CPV, 36; Kitz, 26; or equal.

FAUCET .--**Hose faucet.--**

Hose faucet shall be compression type, angle pattern, wall flange at exterior locations, tee handle, 20 mm female thread with hose end, rough chrome or nickel plated finish for locations inside building, rough brass finish for others. Hose faucet shall be supplied with an integral or nonremovable threaded outlet vacuum breaker which meets the requirements of the American Society of Sanitary Engineering (ASSE) Standard: 1011. Hose faucet shall be Nibco, No. 63VB; Chicago, No. 13T; or equal.

CLEANOUTS.--

Cleanout through floor.--

Cleanout through floor shall have nonslip scoriated nickel bronze access plate and adjustable frame with square pattern top for ceramic tile and round pattern top for other finishes. Where floors are constructed with a membrane, access frame shall be provided with membrane clamping flange. Plug shall be countersunk brass or bronze with tapered threads. Cleanout shall be Wade, W-7000 Series; Smith, 4023 Series; Zurn, No. 1400; or equal.

Cleanout through floors in exterior locations shall be heavy duty, floating pipe type with cast iron cover. Cleanouts shall be Wade, No. W-8300-HF; Smith, No. 4253; Zurn, No. 1474; or equal.

Cleanout to grade.--

Cleanout to grade shall be cast iron ferrule type. Plug shall be countersunk brass or bronze with tapered threads. Cleanout to grade shall be Wade, No. W-8450; Smith, 4420; Zurn, No 1440; or equal.

MISCELLANEOUS ITEMS.--

Water hammer arrestor.--

Water hammer arrestor shall be stainless steel body with bellows or piston. Arrestor compression chambers shall be pneumatically charged. Water hammer arrestors shall be tested and certified in accordance with the Plumbing and Drainage Institute Standard: PDI-WH201 and sized as shown on the plans.

Access door.--

Access door shall be 1.52 mm prime coated steel, face mounting square frame, minimum 300 mm x 300 mm door with concealed hinge and screwdriver latch.

Compression stop (exposed).--

Compression stop (exposed) shall be metal full free waterway, angle type, ground joint union, non-rising stem, molded rubber seat and wheel handle.

Gas regulator.--

Gas regulator shall be listed as suitable for gas and equipped with full capacity relief valve, low pressure safety shut-off and weatherproof and insect proof vent for outside installation. Capacity shall be as shown on the plans. Gas regulator shall be Fisher; Reliance; Rockwell; or equal.

Backflow preventer.--

Backflow preventer shall be factory assembled with 2 check valves, one pressure differential relief valve, 2 ball valves and 4 test cocks. Backflow preventers shall be of the approved type reduced pressure principle devices listed by the County of Los Angeles Department of Health Services, Cross-Connection and Water Pollution Control Section, 2525 Corporate Place, Monterey Park, California 91754, Telephone (213) 881-4140.

Pipe hanger (for piping supported from overhead).--

Pipe hanger (for piping supported from overhead) shall be Grinnell, Model 269; Super Struct, C711; or equal.

Pipe wrapping tape and primer.--

Pipe wrapping tape shall be pressure sensitive polyvinyl chloride or pressure sensitive polyethylene tape having nominal thickness of 0.50 mm. Wrapping tape shall be Polyken, 922; Manville, Trantex VID-20; Scotchrap, 51; or equal.

Pipe wrapping primer shall be compatible with the pipe wrapping tape used.

Floor, wall, and ceiling plates.--

Floor, wall, and ceiling plates shall be chromium plated steel or plastic plates having screw or spring clamping devices and concealed hinges. Plates shall be sized to completely cover the hole.

Valve box.--

Valve box shall be precast high density concrete with polyethylene face and cast iron traffic rated cover marked "WATER," "GAS" or "CO-SS" as applicable. Extension shall be provided as required. Valve box shall be Christy, B3; Brooks Products Company, 3TL; Frazer, 3; or equal.

Floor drain.--

Floor drain shall be cast iron body and flashing collar, adjustable nickel bronze 150 mm strainer head with seepage openings and caulk or no-hub outlet. Floor drain shall be round or square as shown on the Architectural plans. Floor drain shall be J. R. Smith, 2005/2010; Wade, W-1100; Zurn, Z-415; or equal.

PART 3.- EXECUTION

INSTALLATION.--

INSTALLATION OF PIPES AND FITTINGS.--

Pipe and fittings.--Pipe and fittings shall be installed in accordance with the following designated uses:

Designated Use	Pipe and Fitting Class
Domestic water (CW and HW) in buildings	H3 or A1
Domestic water underground within 1.5 m of the building	A1 or H2
Domestic water underground 1.5 m beyond the building	P2, P3, P4, A1 or H2
Sanitary drain piping above ground in building	H1, C1, or C2
Sanitary drain and vent piping underground within 1.5 m of the building	C1 or C2
Sanitary vent piping above ground in building	A2, H1, C1, or C2
Sanitary drain pipe, 1.5 m beyond the building	C1, C2, or P1
Liquefied petroleum gas (LPG), 860 kPa or less, above ground	A1 or B2
LPG, 860 kPa or less, underground	B2 (plastic coated)
LPG, exceeding 860 kPa	B3
Lubrication piping, less than 30 m in length	LP1 (16 mm outside diameter)
Gear oil, motor oil, and automatic transmission fluid (ATF) piping; less than 8 m in length	LP2 or H3 (16 mm outside diameter)
Gear oil, motor oil, and ATF piping; over 8 m in length	LP2 or H3 (22 mm outside diameter)
Compressed air	A1
Equipment drains and relief valve discharge	H3 or A1

Installing piping.--Water piping shall be installed generally level, free of traps and bends, and arranged to conform to the building requirements.

Piping installed underground shall be tested as specified elsewhere in these special provisions before backfilling.

Public use areas, offices, rest rooms, locker rooms, crew rooms, training rooms, storage rooms in office areas, hallway type rooms, and similar type use areas shall have concealed piping.

Warehouse rooms, equipment bays, and loft areas shall have exposed piping.

Piping shall not be run in floor fill, except as shown on the plans.

Piping shall be installed parallel to walls. All obstructions shall be cleared, headroom preserved and openings and passageways kept clear whether shown or not. Piping shall not interfere with other work.

Where pipes pass through exterior walls, a clear space around pipe shall be provided. Space shall be caulked water tight with silicone caulk.

Underground copper pipe shall have brazed joints. Underground plastic pipe shall be buried with No. 14 solid bare copper wire. Wire ends at pipe ends shall be brought up 200 mm and looped around pipe.

Exposed supply and drain piping in rest rooms shall be chrome finished.

Compressed air piping shall be pitched to low point. Ball valved drips shall be provided at all low points. Branches shall be taken off top of main.

Gas piping shall not be installed under building concrete slabs or structure. An insulating connection and valve shall be installed above ground at each building supply.

Gas piping shall be pitched to equipment or to low point and provided with a 200 mm minimum dirt leg.

Transition to Class B2 plastic coated shall be before meter, regulator, or building wall with approved metal to plastic transition fitting. Forty-five degree bends shall be used where offsets are required in venting. Vent pipe headers shall be sloped to eliminate any water or condensation.

Vent piping shall extend a minimum of 200 mm above the roof.

Horizontal sanitary sewer pipe inside buildings shall be installed on a uniform grade of not less than 2 percent unless shown otherwise on the plans.

Drainage pipe shall be run as straight as possible and shall have easy bends with long turns.

Wye fittings and 1/8 or 1/16 bends shall be used where possible. Long sweep bends and combination Wye and 1/8 bends may be used only for the connection of branch pipes to fixtures and on vertical runs of pipe.

Water pipe near sewers.--Water pipe shall not be installed below sewer pipe in the same trench or at any crossing, or below sewer pipe in parallel trenches less than 3 m apart.

When a water pipe crosses above a sewer pipe, a vertical separation of at least 300 mm between the top of the sewer and the bottom of the water pipe shall be maintained.

Pipe sleeves.--The Contractor shall provide sleeves, inserts and openings necessary for the installation of pipe, fittings and valves. Damage to surrounding surfaces shall be patched to match existing.

PVC pipe sleeves shall be provided where each pipe passes through concrete floors, footings, walls or ceilings. Inside diameter of sleeves shall be at least 20 mm larger than outside diameter of pipe. Sleeves shall be installed to provide at least 10 mm space all around pipe the full depth of concrete. Space between pipes and pipe sleeves shall be caulked watertight.

Pipe penetrations in fire rated assemblies.--Where pipes pass through fire rated wall, floor or ceiling assemblies, the penetration shall be protected in accordance with the requirements specified under "Through-Penetration Firestopping" in Division 7, "Thermal and Moisture Protection," of these special provisions.

Cutting pipe.--All pipe shall be cut straight and true and the ends shall be reamed to the full inside diameter of the pipe after cutting.

Damaged pipe.--Pipe that is cracked, bent or otherwise damaged shall be removed from the work.

Pipe joints and connections.--Joints in threaded steel pipe shall be made with teflon tape or a pipe joint compound that is nonhardening and noncorrosive, placed on the pipe and not in the fittings.

The use of thread cement or caulking on threaded joints will not be permitted. Threaded joints shall be made tight. Long screw or other packed joints will not be permitted. Any leaky joints shall be remade with new material.

Exposed polished or enameled connections to fixtures or equipment shall be made with special care, showing no tool marks or threads.

Cleaning and closing pipe.--The interior of all pipe shall be cleaned before installation. All openings shall be capped or plugged as soon as the pipe is installed to prevent the entrance of any materials. The caps or plugs shall remain in place until their removal is necessary for completion of the installation.

Securing pipe.--Pipe in the buildings shall be held in place by iron hangers, supports, pipe rests, anchors, sway braces, guides or other special hangers. Material for hangers and supports shall be compatible with the piping or neoprene isolators shall be used. Allowances shall be made for expansion and contraction. Steel pipe shall have hangers or supports every 3 m. Copper pipe 25 mm or smaller shall have hangers or supports every 2 m and sizes larger than 25 mm shall have hangers or supports every 3 m. Plastic pipe shall have hangers or supports every 1 m. Cast iron soil pipe with neoprene gaskets shall be supported at each joint. Vertical pipes shall be supported with clamps or straps. Horizontal and vertical piping shall be securely supported and braced to prevent swaying, sagging or flexing of joints.

Hangers and supports.--Hangers and supports shall be selected to withstand all conditions of loading to which the piping and associated equipment may be subjected and within the manufacturer's load ratings. Hangers and supports shall be spaced and distributed so as to avoid load concentrations and to minimize the loading effect on the building structure.

Hangers and supports shall be sized to fit the outside diameter of pipe or pipe insulation. Hangers shall be removable from around pipe and shall have provisions for vertical adjustment after erection. Turnbuckles may be used.

Materials for holding pipe in place shall be compatible with piping material.

Hanger rods shall be provided with locknuts at all threaded connections. Hanger rods shall be sized as follows:

Pipe Size	Minimum Hanger Rod Diameter
15 mm to 50 mm	10 mm
65 mm to 87 mm	13 mm

Wrapping and coating steel pipe.--Steel pipe buried in the ground shall be wrapped or shall be plastic coated as specified herein:

1. Wrapped steel pipe shall be thoroughly cleaned and primed as recommended by the tape manufacturer.
2. Tapes shall be tightly applied with 1/2 uniform lap, free from wrinkles and voids with approved wrapping machines and experienced operators to provide not less than 1.00 mm thickness.
3. Plastic coating on steel pipe shall be factory applied. Coating imperfections and damage shall be repaired to the satisfaction of the Engineer.
4. Field joints, fittings and valves for wrapped and plastic coated steel pipe shall be covered to provide continuous protection by puttying and double wrapping with 0.50 mm thick tape. Wrapping at joints shall extend a minimum of 150 mm over the adjacent pipe covering. Width of tape for wrapping fittings shall not exceed 50 mm. Adequate tension shall be applied so tape will conform closely to contours of fittings. Putty tape insulation compounds approved by the Engineer shall be used to fill voids and provide a smooth even surface for the application of the tape wrap.

Wrapped or coated pipe, fittings, and filed joints shall be approved by the Engineer after assembly. Piping shall be placed on temporary blocks to allow for inspection. Deficiencies shall be repaired to the satisfaction of the Engineer before backfilling or closing in.

Thrust blocks.--Thrust blocks shall be formed by pouring concrete between pipe and trench wall. Thrust blocks shall be sized and so placed as to take all thrusts created by maximum internal water pressure.

Plastic pipe underground shall be provided with thrust blocks and clamps at changes in direction of piping, connections or branches from mains 50 mm and larger, and all capped connections.

Union.--Unions shall be installed where shown and at each threaded or soldered connection to equipment and tanks. Unions shall be located so piping can be easily disconnected for removal of equipment or tanks. Unions shall be omitted at compression stops.

Dielectric waterway.--Dielectric waterway shall be provided between metal pipes of different material, and between brass or bronze valves and steel piping.

Insulating union and insulating connection.--Insulating union and insulating connection shall be provided where shown and at the following locations:

1. In metallic water, gas and air service connections into each. Insulating connections shall be installed on the exterior of the building, above ground and after shut-off valve.
2. In water, gas and air service connections in ground at point where new metallic pipes connect to existing metallic pipes. Install valve box above insulating connection.
3. At points of connections of copper or steel water pipes to steel domestic water heaters and tanks.

Bonding at insulating connections.--Interior water piping and other interior piping that may be electrically energized and are connected with insulating connections shall be bonded in accordance with the National Electrical Code. Bonding shall all be coordinated with electrical work.

Compression stop.--Each fixture, including hose faucets, shall be equipped with a compression stop installed on water supply pipes to permit repairs without shutting off water mains. Ball valves may be installed where shown on the plans or otherwise permitted by the Engineer.

INSTALLATION OF VALVES.--

Exterior valves.--Exterior valves located underground shall be installed in a valve box marked "Water." Extensions shall be provided as required.

INSTALLATION OF FAUCETS.--

Hose faucet .--Faucets shall be installed with outlets 0.5 m above finished grade.

INSTALLATION OF CLEANOUTS.--

Cleanouts.--A concrete pad 0.5 m long and 100 mm thick shall be placed across the full width of trench under cleanout Wye or 1/8 bend. Cast iron soil pipe (C1 or C2) and fittings shall be used from Wye to surface. Required clearance around cleanouts shall be maintained.

Cleanout risers outside of a building installed in a surface other than concrete shall terminate in a cleanout to grade. Cleanout to grade shall terminate in a valve box with cover marked "CO-SS". Top of box shall be set flush with finished grade. Cleanout plug shall be 100 mm below grade and shall be located in the box to provide sufficient room for rodding.

Cleanout risers installed in tile and concrete floors, including building aprons and sidewalks, shall terminate in a cleanout through floor.

INSTALLATION OF MISCELLANEOUS ITEMS.--

Water hammer arrestor.--Water hammer arrestor shall be installed so that they are vertical and accessible for replacement. Water hammer arrestor shall be installed with access door when in walls or there is no access to ceiling crawl spaces. Access door location shall be where shown on the plans or as approved by the Engineer.

Gas appliance connection.--Gas valve and flexible connector shall be provided for gas piping at each appliance. Appropriately rated gas cocks may be used in 15 mm gas pipe. Cock or valve shall be within one meter of the appliance.

Gas regulator.--Gas regulator shall be installed complete with dirt leg, capped test tee, union, insulating union, gas valve and fittings.

Backflow preventer.--Backflow preventer assembly shall include a wye strainer, backflow preventer, fittings and pipe. Assembly components shall be the same size as the pipe in which they are installed unless otherwise shown on the plans.

Backflow preventer shall be installed a minimum of 610 mm above ground and shall be the same size as the pipe in which it is installed unless otherwise shown on the plans.

Flushing completed systems.--All completed systems shall be flushed and blown out.

Chlorination.--The Contractor shall flush and chlorinate all domestic water piping and fixtures.

Calcium hypochlorite granules or tablets, if used, shall not be applied in the dry form, but shall first be dissolved into a solution before application.

The Contractor shall take adequate precautions in handling chlorine so as not to endanger workmen or damage materials. All pipes and fittings shall be completely filled with water containing a minimum of 50 ppm available chlorine. Each outlet in the system shall be opened and water run to waste until a strong chlorine test is obtained. The line shall then be closed and the chlorine solution allowed to remain in the system for a minimum of 24 hours so that the line shall contain no less than 25 ppm chlorine throughout. After the retention period, the system shall be drained, flushed and refilled with fresh water.

FIELD QUALITY CONTROL.--

Testing.--The Contractor shall test piping at completion of roughing in, before backfilling, and at other times as directed by the Engineer.

The system shall be tested as a single unit, or in sections as approved by the Engineer. The Contractor shall furnish necessary materials, test pumps, instruments and labor and notify the Engineer at least 3 working days in advance of testing. After testing, the Contractor shall repair all leaks and retest to determine that leaks have been stopped. Surplus water shall be disposed of after testing as directed by the Engineer.

The Contractor shall take precautions to prevent joints from drawing while pipes and appurtenances are being tested. The Contractor shall repair damage to pipes and appurtenances or to other structures resulting from or caused by tests.

Cathodic protection tests.--The State will conduct tests at locations where cathodic protection is required to determine compliance with the specified requirements.

General tests.--All piping shall be tested after assembly and prior to backfill, pipe wrapping, connecting fixtures, wrapping joints and covering the pipe. Systems shall show no loss in pressure or visible leaks.

The Contractor shall test systems according to the following schedule for a period of not less than 4 hours:

Test Schedule		
Piping System	Test Pressure	Test Media
Sanitary sewer and vent	3 m head	Water
Water	860 kPa	Water
Gas (except P6)	690 kPa	Air
Air	860 kPa	Air
Lubrication piping	860 kPa	Air and Product

During testing of water systems, valves shall be closed and pipeline filled with water. Provisions shall be made for release of air.

Sanitary sewers shall be cleared of obstructions before testing for leakage. The pipe shall be proved clear of obstructions by pulling an appropriate size inflatable plug through the pipe. The plug shall be moved slowly through the pipe with a tag line. The Contractor shall remove or repair any obstructions or irregularities.

Sanitary sewer pipes beyond 1.5 m perpendicular to the building shall be tested for leakage for a period of not less than 4 hours by filling with water to an elevation of 1.2 m above average invert of sewer or to top of manholes where less than 1.2 m deep. The system shall show no visible leaks. The sewer may be tested in sections with testing water progressively passed down the sewer as feasible. Water shall be released at a rate that will not create water hammer or surge in plugged sections of sewer.

Testing backflow preventers.--Backflow preventers installed by the Contractor shall be tested at the completion of the supply system installation for proper operation by a certified Backflow Preventer Tester.

The tester shall hold a valid certificate as a Backflow Preventer Tester from the county in which the device to be tested is located or, if the county does not have a certification program for Backflow Preventer Testers, the tester shall have a certificate from one of the following:

1. The American Water Works Association.
2. A county which has a certification program for Backflow Preventer Testers. The certification under which the tester has been certified shall be acceptable to the water purveyor and the local agency having jurisdiction.

Testing for proper operation shall conform to the procedures of the county in which the testing is being performed, or, if such procedures are not available in the county, such tests shall conform to the provisions in the latest edition of the Guidance Manual For Cross Connection Control Program, which is available from the California Department of Health Services, Division of Drinking Water and Environmental Management, 601 N 7th Street, P.O. Box 942732, Sacramento, CA 94234.

The Contractor shall notify the Engineer at least 5 days prior to testing backflow preventers. Such tests shall be satisfactorily completed after installation of the backflow preventer assemblies and before operation of the systems.

One copy of all test results for each backflow preventer shall be furnished to the Engineer.

Full compensation for providing the certified Backflow Preventer Tester and for testing the backflow preventers shall be considered as included in the lump sum price paid for building work and no additional compensation will be allowed therefor.

15.03 MECHANICAL INSULATION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing mechanical insulation in accordance with the details shown on the plans and these special provisions.

Piping insulation shall be installed on all domestic hot and cold water piping, above grade.

P-trap, hot water supply pipes and angle valves for lavatories and sinks, except in janitor closets or similar enclosed spaces, shall be insulated.

QUALITY ASSURANCE.--

Codes and standards.--Mechanical insulation shall conform to California State Energy Commission regulations and, where applicable, shall meet American Society of Testing and Materials (ASTM) standards.

All materials shall bear the label of the Underwriters Laboratory (UL) or other approved testing laboratory indicating that the materials proposed for use conform to the required fire hazard ratings.

Pipe safety insulation shall conform to Section 1504(b) of Title 24, Part 5, California Plumbing Code.

PART 2.- PRODUCTS

MATERIAL.--

General.--All pipe insulation and wrapping material, including adhesives and jackets, located within buildings shall be certified to have a composite flame spread rating of not more than 25 and smoke development rating of not more than 450 when tested in accordance with ASTM Designation: E 84.

Domestic water piping insulation.--

Piping insulation shall be glass fiber molded pipe insulation with factory applied jacket suitable for service temperatures up to 175°C. Covering jacket shall have pressure sealing lap adhesive joints. Pipe insulation shall have a minimum thermal resistance of $R-0.5 \text{ K}\cdot\text{m}^2/\text{W}$. Insulation and jackets shall be Owens-Corning, Fiberglass 25 with ASJ/SSL All Service Jacket; Manville, Micro-Lok 650ML with AP-T All Purpose Jacket; or equal.

Piping insulation cement.--

Insulation cement shall be Fenco, All Purpose Cement; Manville, JM375; or equal.

PVC jacket.--

PCV jacket shall be rated for a service temperature of 80°C. PVC jacket shall include covers specifically designed to cover pipe fittings.

Alternative pipe insulation.--

Alternative pipe insulation shall be closed cell, elastomeric material in a flexible tubular form. Insulation shall have a service temperature range between -40°C and 93°C, a minimum vapor transmission rating of 0.29 Perm-m, and a minimum thermal resistance of $R-0.5 \text{ K}\cdot\text{m}^2/\text{W}$.

Pipe safety insulation.--

Pipe safety insulation for P-traps, hot water supply pipes and angle valves shall be molded closed cell vinyl or closed cell foam with exterior vinyl surface. Pipe safety insulation shall be configured to protect against contact. Pipe safety insulation shall be Truebro Inc., Handi Lav-guard; Plumberex Specialty Products, Handy Shield; or equal.

Adhesive.--

Adhesive shall be non-flammable type: Benjamin Foster Company, No. 85-20 Spark Safe; Goodloe E. Moore Company, Tuff Bond No. 6; Permacel, No. PA-310; 3M, No. 38 Insulation Adhesive; Swift's, No. 7228 brush type or No. 7336 spray type; Chicago Mastic, 17-461; or equal.

PART 3.- EXECUTION

INSTALLATION.--

General.--Insulation materials shall be neatly installed with smooth and even surfaces, jackets drawn tight and smoothly cemented down.

Insulation material shall not be installed until all pipes or surfaces to be covered are tested for leaks, cleaned and dried, and foreign materials, such as rust, have been removed.

Piping insulation.--Piping insulation shall be in accordance with the following, except that unions, unless integral with valves, and flexible connections shall not be insulated.

- a. Where insulation butts against flanges or is discontinued, insulation shall be tapered to pipe to allow for covering jacket to completely seal off end of insulation.

Insulation shall be extended on the valve bodies up to the valve bonnet.

Extend insulation continuous through pipe hangers and pipe sleeves. At hangers where pipe is supported, provide an insulated protection shield.

Insulating cement shall be applied to fittings, valves, and strainers and troweled smooth to thickness of adjacent covering. Strainer cleanout plugs shall remain accessible. Covers fabricated from molded pipe covering may be used in lieu of cement, provided covers are neat and well secured.

- b. Jacket flap shall be sealed down with factory applied self-sealing lap. Seams shall be lapped not less than 40 mm. Jacket shall be secured with aluminum bands installed at 300 mm centers.

Alternative pipe insulation, where used, shall be installed on hot water piping before connections are made or the insulation may be slit lengthwise, applied to pipe and sealed with adhesive.

Pipe safety insulation.--Pipe safety insulation shall be installed in accordance with the manufacturer's recommendations.

15.04 PLUMBING FIXTURES

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing plumbing fixtures in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

General.--Plumbing fixtures shall be white in color and shall meet the following requirements:

Water closet (disabled accessible, 6 liters per flush, floor mounted with tank).--

Disabled accessible water closet shall be 6 liters per flush maximum, vitreous china, siphonable jet, 410 mm to 440 mm high elongated bowl, close coupled tank, floor mounted, with solid plastic open front elongated seat with check hinges. Water closet shall meet or exceed Americans with Disabilities Accessibility Act Guidelines (ADAAG) and ANSI Standards: A117.1 and A112.19.2. Closet and accessories shall be of the following types or equal:

	American Standard	Crane	Universal Rundle
Closet	"Cadet 17 EL1.6/PA" 2168.100 or 4086.800	"Hymont" 3-154E or 3-152 with3-655	"Atlas 1.5" UR 4078-341 or UR 4078-342
Seat	Church 5321.070	Olsonite 95	Benke 527

Lavatory (wall-mounted).--

Lavatory shall be vitreous china, with back, integral perforated grid drain, drilled for 102 mm centers, size 508 mm x 457 mm, with single extra long lever mixing faucet and chair carrier with concealed arms. Lavatory shall

be equipped with temperature controls to limit the hot water supply to 43°C. Lavatory and accessories shall be of the following types or equal:

	Eljer	Crane	Kohler
Lavatory	"Lucerne" 0355.012	"Norwich" 1-194-V	"Greenwich" K-2032
Drain	--	C-1065-G or Moen 52659	K-7715
Supplies	Brass Craft FR1711C	C-1151 or Moen 52664	K-7605
Faucet	2385.130	Moen 8400	K-15592-5
Trap	32 mm chromium plated brass exposed bent tube adjustable 1.37 mm (17-gage) minimum thickness.		
Carrier	Concealed wall mounted carrier with leveling screws and locking devices; Zurn, J.R. Smith, Josam, Wade, Jonespec, or equal.		

Service sink.--

Service sink shall be acid resisting enameled cast iron, plain undrilled back, stainless steel strainer, stainless steel or chrome plated sheet brass rim guard on three sides, size approximately 560 mm x 460 mm, with 75 mm trap with cleanout and floor mounting flange. Sink and accessories shall be of the following types or equal:

	American Standard	Eljer	Kohler
Service sink	"Lakewell" 7692.023	242-0120	"Bannon" K-6718
Strainer	8301.061	-----	-----
Trap	7798.176	804-1060 w/strainer	K-6673 w/strainer
Faucet	Bucket hook, vacuum breaker, integral stops, top brace, long spout with hose threads.		
	8344.111	749-1200	K8907

Water heater (gas).--

Water heater shall be minimum capacity as shown on plans, designed for minimum 860 kPa, glass lined, and equipped with gas pressure regulator, magnesium anodes, cold water drop tube, high temperature energy shut-off device, valved drain, high density R-1.4 K•m²/W minimum foam insulation and finished with a steel jacket with baked enamel finish. Water heater shall meet the requirements of the California Energy Commission.

Water heater shall be equipped with an ASME labeled, tank mounted, pressure and temperature relief valve sized for maximum input.

Electric water cooler (disabled accessible, wall mounted).--

Electric water cooler shall be wall mounted, wheelchair accessible, and shall produce a minimum of 28 liters of 10°C water per hour based upon an inlet water temperature of 27°C and an ambient room temperature of 32°C. Cooler shall have self closing, front and side mounted pushbar actuators, shielded bubbler, automatic stream regulator, loose key stop, adjustable thermostat and cast brass P-trap.

Compressor shall be hermetically sealed, positive start with fan cooled condenser and shall be mounted above the cooler top. Cooler shall be provided with 3-wire grounded plug and cord.

Electric water cooler shall be Haws, HWCA8D; Sunroc, HCWC-8S; Elkay, EHFS-8; or equal.

Emergency eyewash and shower.--

Emergency eyewash and shower shall be separate drench shower and eye bath, 32 mm minimum, galvanized steel pipe stand with 229 mm floor mounting flange and equipped with 216 mm x 279 mm pictorial and worded emergency identification sign.

Shower head shall have a 254 mm diameter ABS plastic head with a stay-open ball valve operated by a rigid pullrod with triangular handle.

Eyewash shall have a 254 mm diameter stainless steel bowl, anti-surge heads and circular chrome plated spray ring to bathe the entire face, dust cover assembly, and a stay-open ball valve operated by a flag handle. Eyewash unit shall be mounted on the shower pipe stand.

Emergency eyewash and shower shall be Haws, 8346; Speakman, SE-607; Western, 9231; or equal.

PART 3.- EXECUTION

INSTALLATION.--

General.--All finish for exposed metal on any fixture, including wall flanges, bolts, nuts and washer, shall be polished chrome plated.

Fixtures shall be sealed to wall or floor with silicone caulk bead.

All exposed metal surfaces on fixture supports shall be enameled to harmonize with fixtures.

Wall mounted fixtures shall be installed on concealed chair carriers designed to support weight of fixture from the floor, made for the specific fixture to be supported and for the particular installation conditions.

All fixtures, including showers, shall be provided with accessible metal stop valves.

Hot water supply, trap and tailpiece on lavatories shall be wrapped with insulating material.

Flush handles for fixtures designated on the plans as disabled accessible shall be installed so that the valve handle is on the widest side of the toilet space.

FIXTURE MOUNTING HEIGHTS.--

General.--Unless otherwise noted, fixtures shall be mounted at the heights shown on the plans.

Service sink.--Service sink double faucet shall be mounted on wall above sink back with spout outlet face 400 mm above service sink rim.

Water heater.--Water heater shall be installed with seismic restraints, inlet ball valve and insulating connections, and 20 mm pressure and temperature relief drain pipe.

Emergency eyewash and shower.--Emergency eyewash and shower shall be installed with a rigid bracket located 1.2 m above the floor. Bracket shall be minimum 1.52 mm (16-gage) steel and shall be braced to the wall.

FIELD QUALITY CONTROL.--

Testing.--The Contractor shall test piping in accordance with the requirements specified elsewhere in these special provisions.

All installed fixtures shall be tested for proper operation after all plumbing work has been completed.

15.05 WHEELCHAIR ACCESSIBLE SHOWER UNIT

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing a wheelchair accessible shower unit and fittings in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, installation instructions and color palette shall be submitted for approval. The color will be selected from the manufacturer's standard product line by the Engineer after approval of the contract.

QUALITY ASSURANCE.--

Codes and standards.--Shower units shall conform to the requirements of the California State Accessibility Standards contained in the California Building Standards Code, Title 24.

PART 2.- PRODUCTS

Shower stall.--

Shower stall shall be single unit, single piece construction with clear interior dimensions of 1524 mm wide, 1067 mm deep, with an entrance width of 915 mm, and no obstruction at the threshold. Shower stall shall be fabricated from gel-coated fiberglass or acrylic with a Class I Flame Spread. Shower unit shall be reinforced to accommodate the grab bars and seat.

Shower unit shall have a threshold or recessed drop, a maximum of 13 mm in height, sloped at an angle not exceeding 45 degrees from the horizontal. The floor shall be slip-resistant, sloping a maximum of 4 percent to a drain located near the rear wall.

Shower unit shall be provided with the following fittings and accessories: stainless steel corner grab bar and folding teakwood or woodgrain phenolic wheelchair transfer seat, each capable of resisting 1112 N of lateral, vertical and tensile load, stainless steel soap dish, chromium plated or stainless steel curtain rod, chromium plated steel hand-held shower head with ball joint, chromium plated 1524 mm long flexible shower spray hose, chromium plated fixed shower head, chromium plated metal outlet drain with removable strainer, chromium plated single lever control thermostatic mixing valve with control cartridge with no metal to metal wearing surface, a lever operated shower head selector, and vinyl shower curtain with corrosion resistant hooks.

Shower stall units shall be Crane; Florestone; Maron and Associates; or equal.

PART 3.- EXECUTION

INSTALLATION.--

General.--Shower shall be installed with the manufacturer's instructions. All joints shall be sealed and caulked watertight.

15.06 HEATING, VENTILATING AND AIR CONDITIONING EQUIPMENT AND SYSTEMS

PART 1.- GENERAL

Scope.--This work shall consist of furnishing, installing and testing heating, ventilating and air conditioning (HVAC) equipment and systems in accordance with the details shown on the plans and these special provisions.

The performance rating and electric service of the HVAC equipment shall be as shown on the plans.

Temperature controls.--Thermostats, relays, time switches, and other sensor type control devices required for this work shall be furnished and installed by the supplier of the heating, ventilating and air conditioning equipment. All temperature control wiring shall be furnished and installed in accordance with the requirements specified in Division 16, "Electrical," of these special provisions.

Codes and standards.--Equipment and systems shall conform to California State Energy Commission Regulations and, where applicable, shall be American Refrigeration Institute (ARI), American Gas Association (AGA), Sheet Metal and Air Conditioning Contractors National Association, Inc. (SMACNA), and Air Movement and Control Association (AMCA) approved for performance ratings and application shown on the plans.

Any appliance for which there is a California standard established in the Appliance Efficiency Standards may be installed only if the manufacturer has certified to the Commission, as specified in those regulations, that the appliance complies with the applicable standards for that appliance. Space conditioning equipment may be installed only if the manufacturer has certified that the equipment meets or exceeds all applicable efficiency requirements listed in the Energy Efficiency Standards.

PART 2.- PRODUCTS

HEATING AND COOLING UNITS.--

Unit heater.--

Unit heater shall be gas-fired, propeller fan type, AGA approved for LPG and shall be equipped with aluminized steel heat exchanger, built in backdraft diverter, fan switch marked "SUMMER"-"WINTER," adjustable discharge louvers, gas pressure regulator, intermittent ignition device, gas main and pilot shutoff valves, automatic gas valve, high limit shutoff, 24-volt transformer, and fan motor local disconnect. All components shall be factory assembled. Unit heater shall be Reznor; Modine; Hastings; or equal.

Unit heater fan motor shall have integral thermal overload protection.

High intensity infrared radiant heater.--

High intensity infrared radiant heater shall be AGA approved for LPG and shall be equipped with intermittent ignition device, electric flame safety, and junction box secured to the unit. All components shall be factory assembled. Radiant heater shall be provided with an aluminum rectangular reflector and mounting brackets. High intensity infrared radiant heater shall be Solaronics; Lambert; or equal.

Automatic controls shall be provided to shut off the electric ignition if the pilot fails to light.

Electric wall heater.--

Electric wall heater shall be forced air, recessed type, and shall be equipped with a grille and integral thermostat.

Heat pump (wall mounted).--

Heat pump shall be wall mounted, through-the-wall type with backup electrical resistance heating, rotary type compressor, and shall include slide-out chassis design, thermostat, adjustable discharge grilles, multi-speed fan, and integral thermal overload protection.

FANS AND VENTILATORS.--

Exhaust fan (ceiling mounted).--

Exhaust fan shall be ceiling mounted, AMCA certified and shall be equipped with grille, backdraft damper and metal housing. Exhaust fan motor shall have integral thermal overload protection. Ceiling exhaust fan shall be Breidert, ILG, Penn, or equal.

Exhaust fan (wall mounted).--

Exhaust fan shall be wall mounted, AMCA certified and shall be equipped with grille, metal housing, backdraft damper, centrifugal fan wheel and bird screen. Fan motor and fan assembly shall be isolated from base with rubber vibration isolators. Fan shall be completely weatherproof and shall have a disconnect means under the hood and fan motor shall have integral thermal overload protection. Wall exhaust fan shall be Jenn-Air; Carnes; EWDA; Penn; or equal.

The Contractor shall submit to the Engineer for approval the proposed hanging arrangement of exhaust fan and wall framing.

Declassification fan (wall mounted).--

Declassification fan shall be wall mounted, centrifugal type, AMCA certified, direct drive, aluminum blades, metal housing, venturi orifice, and safety grills. Declassification fan shall be constructed in accordance with the requirements of the latest of AMCA Publication 99, "Standards Handbook."

Fan motor and fan assembly shall be isolated from base with rubber vibration isolators. Fan motor shall be 3-phase, continuous duty and explosion proof with integral thermal overload protection.

Wall declassification fan shall be supplied with wall mount collar, motor side guard, backdraft damper and weatherhood. Weatherhood shall be galvanized steel with bird screen. All parts shall be supplied by the fan manufacturer.

The Contractor shall submit to the Engineer for approval the proposed supporting arrangement with wall framing of declassification fan.

Combination heat lamp/light/fan.--

Combination heat lamp/light/fan shall be ceiling mounted, recessed type unit with metal housing, grille and backdraft damper. Ducting size shall be as required by the manufacturer. Combination heat lamp/light/fan shall be Broan, No. 164; Nutone, No. 9427; or equal.

HVAC CONTROLS.--

Unit heater thermostat.--

Unit heater thermostat shall be low voltage type, single set point range internally adjustable from 4°C to 27°C, and provided with a blank cover.

Radiant heater thermostat.--

Radiant heater thermostat shall be low voltage type, single set point range internally adjustable from 4°C to 27°C, and provided with a blank cover.

Time switch.--

Time switch shall be double pole six-hour range, spring-wound, "OFF" type time switch without a "HOLD" feature. Time switch contacts shall be rated 20 amps at 120 volts. Time switch shall be Intermatic, Type F60M; Tork, A500 Series; or equal.

AUXILIARY HVAC COMPONENTS.--

Unless specified herein, all components shall be sized and have the characteristics as shown on the plans.

Rigid ductwork.--

Rigid ductwork shall be galvanized steel sheet metal conforming to the latest edition of the SMACNA "Low Velocity Duct Construction Standards." Galvanized steel shall be cleaned by washing with mineral spirit solvent sufficient to remove any oil, grease or other materials foreign to the galvanized coating.

Flexible ductwork.--

Flexible ductwork shall be UL 181, Class 1 air duct rated and shall meet the requirements of NFPA 90-A. Duct shall have steel helix wire, flexible insulation, minimum thermal resistance of R-0.7 (m²*K/W), and flame resistant vapor barrier. Inner and outer surfaces shall be non-metallic. Outer surface shall be Copolymer or Mylar, factory applied.

Vents and flues (for heaters).--

Vents and flues for heaters shall be approved Type B.

Refrigerant and condensate drain piping.--

Refrigerant and condensate drain piping shall be rigid, Type L copper tubing with brazed solder fittings. The suction line shall be insulated, with vapor barrier and shall be weatherproofed for exterior installation. Factory sealed tubing shall not be used.

PART 3.- EXECUTION

INSTALLATION.--

Heaters.--Unit heaters, radiant heaters and wall heaters shall be installed in such a manner as to insure adequate furnace clearance and separation of combustion air and circulating air. Appliances shall be connected to a rigidly mounted gas pipe supply system by an AGA approved flex connector and gas valve.

High intensity infrared radiant heaters shall be installed as per manufacturer's recommendation.

Ventilators.--Exhaust ducts connected to exhaust fans shall be routed as shown on the plans and shall terminate in a weatherproof cap. Duct sizes shall be as shown on the plans or as recommended by the manufacturer, whichever is larger.

Wall mounted exhaust fan shall be supported in accordance with the fan manufacturer's recommendations. Framing for wall attachment shall be included in the submittal for the pre-engineered steel building.

Condensate drains.--Heat pump shall be provided with condensate drain trap and piping. Outdoor piping shall extend as shown on the plans. Air gap shall be installed where required by code. Interior condensate drain piping shall be insulated with foam insulation.

Mounting heights.--Thermostats and time switches shall be installed as shown on the plans.

Temperature controls.--Temperature control for each unit and radiant heater shall be provided by 2 low voltage thermostats and a time switch. One thermostat shall be set at 7°C. for low-limit temperature control and the second thermostat shall be set at 21°C. The first thermostat shall energize the heater whenever the temperature is below the setpoint. The second thermostat shall be wired in series with the time switch and shall de-energize the heater above the setpoint.

Each thermostat shall be insulated from the outside walls, and shall be provided with an aluminum radiation shield above the thermostat.

The time switch shall be installed beside the thermostat or where shown on the plans.

Vents and flues.--Vents and flues shall be securely fastened to the building construction, shall be provided with a thimble at the wall penetrations and shall terminate with a weather cap fabricated of the same material.

Ducts and vents.--Where ducts pass through walls, galvanized sheet metal or steel angle collars shall be installed around the ducts.

FIELD QUALITY CONTROL.--

Pre-test requirements.--Before starting or operating systems, equipment shall be cleaned and checked for proper installation, lubrication and servicing.

The final air quantities shall be achieved by the fan RPM.

Final adjustments and balancing of the systems shall be performed in such a manner that the systems will operate as specified and as shown on the plans.

The Contractor shall replace or revise any equipment, systems or work found deficient during tests.

Project completion tests.--The Engineer shall be notified at least 3 working days in advance of starting project completion tests.

Upon completion of mechanical work and pre-test requirements, or at such time prior to completion as determined by the Engineer, the Contractor shall operate and test installed mechanical systems for at least 3 consecutive 8-hour days to demonstrate satisfactory overall operation.

15.07 LIQUEFIED PETROLEUM GAS (LPG) SYSTEM

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing a liquefied petroleum gas (LPG) distribution system in accordance with the details shown on the plans and these special provisions.

The LPG distribution system shall include relocation of an LPG storage tank, supply and installation of pipe, fittings, valves and such other system components necessary for the proper installation and operation of the LPG system.

Permits.--The Contractor shall obtain the required permits to operate pressure vessels in accordance with the requirements of the State Division of Industrial Safety (DIS), shall pay the costs for such permits and shall perform all required tests. Such permits shall be posted under glass at the site of the work.

QUALITY ASSURANCE.--

Codes and standards.--All work performed and materials installed shall conform to the California Building Standards Code, Title 24, Part 4 and Part 5; the California Code of Regulations, Title 8, Chapter 4, Subchapter 1, Article 5; and National Fire Protection Association (NFPA) Standard No. 58-2001.

PART 2.- PRODUCTS

Tank.--

The LPG tank and its accessories shall be relocated from the existing position to the new position as shown in the plans without damaging. If any damage occurs the contractor has to replace the damage component.

Tank valves, fittings, regulators and accessories.--

Tank valves, fittings, regulators and accessories shall be UL listed and labeled. Valves, fittings, regulators and accessories shall be as required by the California Codes listed above and shall be Rego, Fisher, Rockwell, or equal.

Pipe and fittings (at the tank and underground).--

Pipe and fittings shall be as specified under "Pipe, Fittings and Valves" in Division 15, "Mechanical," of these special provisions. Piping below grade shall be factory coated.

Warning signs.--

Warning signs shall be sheet steel, not less than 1.2 mm thick (18-gage) with a baked enamel coating and shall have red letters on a white background.

PART 3.- EXECUTION

INSTALLATION.--

General.--The LPG tank and system components shall be installed in accordance with NFPA Standard No. 58-2001, the manufacturer's instructions and the approved installation drawings.

Foundation.--The tank shall be installed on a concrete foundation. The tank installation shall include seismic restraint and provisions for expansion and contraction. Neoprene or asphalt impregnated felt anti-corrosion pads shall be installed between the saddle and the concrete foundation.

The concrete foundation shall be constructed in accordance with the requirements specified for minor work under "Cast-In-Place Concrete" in Division 3, Concrete and Reinforcement," of these special provisions.

All openings shall be capped until ready for field connections. Piping shall be supported adequately, with allowance for swing joint movement.

Piping installation.--Piping shall be buried 900 mm minimum depth and shall be provided with cathodic protection. Insulating unions shall be installed at least 150 mm above grade between the coated pipe and the above ground pipe lines.

Joints for underground piping shall be cleaned, primed and wrapped in accordance with the requirements specified under "Pipes, Fittings and Valves" in Division 15, "Mechanical," of these special provisions. The cleaning, priming and wrapping of pipe joints shall be completed after testing the piping system.

Cathodic protection shall be installed in accordance with the details shown on the plans and the requirements specified under "Cathodic Protection" in Division 16, "Mechanical," of these special provisions.

Coated pipe inspection.--The coating on all coated pipe shall be inspected for flaws prior to any testing, and shall be reinspected after testing and before the cleaning, priming and wrapping of the joints.

Finish painting.--After installation of the tank, all areas where the shop applied primer has been damaged or has deteriorated shall be thoroughly cleaned and spot painted with primer. Spot painted areas shall be approved by the Engineer prior to the application of the finish coats.

Two applications of the finish coating shall be applied to shop primed steel surfaces exposed to view after the erection of the tank has been completed. The finish coating shall be white gloss, exterior, alkyd enamel.

The word "FLAMMABLE" shall be painted on each side of the tank. Sign lettering shall be standard-type not less than 100 mm in height. The lettering color shall be red and shall be in sharp contrast to the color of the tank.

Warning sign installation and applicationFour warning signs with the words "NO SMOKING, OPEN FLAMES OR OTHER SOURCE OF IGNITION PERMITTED WITHIN 15.2 METERS (50 FEET)" shall be placed at the locations shown on the plans. Sign lettering shall be standard-type not less than 38 mm in height. The lettering color shall be in sharp contrast to the color of the sign.

FIELD QUALITY CONTROL.--

Testing.--After construction, installation and pipe testing, the LPG system shall be pressure tested with air or nitrogen. The system shall be tested for a minimum time period of 30 minutes at 1380 kPa. If any leaks are detected during the test, the system shall be repaired and retested until no leaks are detected.

After the pressure tests have been completed, the LPG system shall be purged 5 times with methanol (methyl alcohol), using one-liter per 1000 liters water capacity, to remove moisture from the system.

After testing and purging the system, the tank shall be filled to 25 percent of the water capacity of the tank, measured in liters, with State-furnished LPG as provided under "State-Furnished Materials" in Division I, "General Requirements," of these special provisions.

An operational test shall be performed on the LPG system upon completion of the pressure tests, the purging of the system and the delivery of the State furnished LPG fuel. The operational test shall consist of operating all LPG equipment for a period of three 24-hour days.

15.08 CATHODIC PROTECTION

GENERAL.--This work shall consist of providing cathodic protection for LPG pipes in accordance with the details shown on the plans and the requirements in these special provisions.

SUBMITTALS.--Descriptive data for anodes, test stations, test boxes, and fusion welded connections shall be submitted for approval.

PRODUCTS.--

Anodes.--

Anodes shall be magnesium, prepackaged in cloth bags containing hydrated gypsum and bentonite clay; Dow, Galvo Mag; Kaiser, Electromag; or equal.

Anode test station.--

Anode test station shall be conduit mounted non-metallic terminal board with integral compression-fit base and screw on cover. The terminal board shall have nickel plated brass factory installed hardware. The test station shall be fabricated of white polycarbonate.

Anode test box.--

Anode test box shall be precast concrete box with terminal board as described herein and cast iron locking traffic cover marked "ANODE"; Christy, B3; Brooks, 3TL; or equal.

Conductors.--

Conductors shall be solid No. 12 AWG copper, Type TW or THW, insulation colored black for anode and red for all others.

Fusion weld material.--

Fusion weld material shall be a mixture of copper oxide and aluminum.

EXECUTION.--

INSTALLATION.--Excavation and backfill shall be in accordance with the requirements specified under "Earthwork for Building Work" in Division 2, "Sitework," of these special provisions.

Impervious wrapping around the cloth bag packaged anode shall be removed immediately before installing the anode.

Anodes shall be installed at the locations shown on the plans. The packaged anode shall be wetted thoroughly before backfilling. Backfill material placed to 300 mm above the anode shall be native soil, free from aggregate larger than 13 mm in size.

Conductors shall be connected to pipes by fusion welding. Connection to the lift post shall be located to remain visible. All other connections shall be insulated watertight after inspection by the Engineer.

Fusion weld connection to steel surface shall be made of molten copper produced by exothermic reaction following ignition of a mixture of copper oxide and aluminum flowing into weld cavity of a properly fitting graphite mold.

Each pipe conductor shall connect only one pipe to a terminal on the terminal board in the anode test box except where otherwise shown on the plans.

Pipe conductors shall have 300 mm slack at pipe connections and 600 mm slack at the anode test box.

Conductors shall be direct buried and located safe from damage due to construction operations.

All metals connected to cathodic protection, except plastic-coated pipes, shall be tape-wrapped as specified under "Pipe, Fittings and Valves" in Division 15, "Mechanical," of these special provisions. Cathodically protected metals shall be isolated from all other metals.

TESTING.--

CATHODIC PROTECTION TESTING.--Cathodic protection systems shall be tested by a corrosion technician certified by the National Association of Corrosion Engineers (NACE). Tests shall include the following:

1. Isolation of protected metal from electrical conduit, piping for water and sewage, steel the building, or other metals.

If the same potential is measured from a stationary copper-copper sulphate half cell to any foreign structure as to the protected structure, the protected structure shall be deemed to be metallicaally connected to the foreign structure and the installation shall be deemed unacceptable.

2. Anode current.
3. Polarized potential.

An instant-off potential of less then 850 millivolts shall be deemed to indicate an unacceptable installation. The instant-off potential shall be the voltage between the protected structure and a copper-copper sulphate half cell measured after the immediate shift that occurs when anode current is interrupted, but before any further current decay.

4. Anode potential.

The anode open-circuit potential shall be at least 95 percent of the value listed in the manufacturer's published data for the type of anode furnished.

The tests shall be performed after all reinforcing steel, conduits, pipes and other foreign structures that might be inadvertently connected to the protected structures have been installed and backfilled or encased.

The corrosion technician shall submit a written report certifying the cathodic protection. The report shall indicate each measurement made and its recorded value.

DIVISION 16. ELECTRICAL

16.01 ELECTRICAL WORK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of performing electrical work in accordance with the details shown on the plans and these special provisions.

Electrical work shall include furnishing all labor, materials, equipment and services required to construct and install the complete electrical system shown on the plans and the work of installing electrical connections for the thermostats, motors, and controls specified elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of conduits and other facilities and location of equipment is to be governed by structural conditions and other obstructions, and shall be coordinated with the work of other trades. Equipment requiring maintenance and inspection shall be located where it is readily accessible for the performance of such maintenance and inspection.

Related work.--Earthwork, foundations, sheet metal, painting, mechanical and such other work incidental to and necessary for the proper installation and operation of the electrical work shall be done in accordance with the requirements specified for similar work elsewhere in these special provisions.

CLOSEOUT SUBMITTALS.--

Operation and maintenance manuals.--Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be in a bound manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material will be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

QUALITY ASSURANCE.--

Codes and standards.--All work performed and materials installed shall be in accordance with the National Electrical Code; the California Building Standards Code, Title 24, Part 3, "California Electrical Code," and the California Code of Regulations, Title 8, Chapter 4, "Electrical Safety Orders," and all state ordinances.

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

TESTING.--

After the electrical system installation work has been completed, the electrical system shall be tested in the presence of the Engineer to demonstrate that the electrical system functions properly. The Contractor shall make necessary repairs, replacements, adjustments and retests at his expense.

16.02 BASIC MATERIALS AND METHODS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing conduits, conductors, fittings, and wiring devices in accordance with the details shown on the plans and these special provisions.

Conduits, conductors, fittings, and wiring devices shall include those accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the electrical system.

Related work.--Roof penetrations shall be flashed and sealed watertight conforming to the requirements specified under "Sheet Metal Flashing" in Division 7, "Thermal and Moisture Protection," of these special provisions.

Where conduits pass through fire rated wall, floor or ceiling assemblies, the penetrations shall be protected in accordance with the requirements specified in Division 7, "Thermal and Moisture Protection," of these special provisions.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval.. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for recessed junction and pull boxes, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS

CONDUITS AND FITTINGS.--

Rigid steel conduit and fittings.--

Rigid steel conduit shall be threaded, full weight rigid steel, hot-dip galvanized inside and outside with steel or malleable iron fittings. Fittings shall be threaded unless otherwise specified or shown on the plans.

Split or three-piece couplings shall be electroplated, malleable cast iron couplings.

Insulated grounding bushings shall be threaded malleable cast iron body with plastic insulated throat and steel, lay-in ground lug with compression screw.

Insulated metallic bushings shall be threaded malleable cast iron body with plastic insulated throat.

Electrical metallic tubing (EMT) and fittings.--

Electrical metallic tubing shall be formed of cold rolled strip steel, electrical resistance welded continuously along the longitudinal seam with zinc coating outside and enamel or lacquer coating inside.

Couplings shall be electroplated, rain and concrete tight, gland compression type, steel body couplings with malleable iron nuts.

Connectors shall be electroplated, rain and concrete tight, gland compression type, steel body connectors with male hub, malleable iron nut and insulated plastic throat.

Flexible metallic conduit and fittings.--

Flexible metallic conduit shall be fabricated in continuous lengths from galvanized steel strip, spirally wound and formed to provide an interlocking design.

Fittings shall be electroplated screw-in type with malleable cast iron body and threaded male hub with insulated throat.

Liquid tight flexible metallic conduit and fittings.--

Liquid tight flexible metallic conduit shall be fabricated in continuous length from galvanized sheet steel, spirally wound and formed to provide an interlocking design with an extruded polyvinyl chloride cover.

Fittings shall be electroplated, malleable cast iron body, with cap nut, grounding ferrule, and connector body with insulated throat.

Rigid non-metallic conduit and fittings.--

Rigid non-metallic conduit shall be Schedule 40, high impact, nonconducting, self-extinguishing polyvinyl chloride (PVC) rigid non-metallic conduit for direct underground burial.

Couplings shall be PVC, socket type or thread on one end and socket type on the other end as required for the particular application.

Terminal adapters for adapting PVC conduit to boxes, threaded fittings, or metallic conduit system shall be PVC adapters with threads on one end and socket type on the other end.

CABLES AND CONDUCTORS.--

Cables.--

Cables shall be as required by the manufacturer of the equipment or as indicated on the plans.

Conductors.--

Conductors shall be stranded copper wire.

Conductor insulation types unless otherwise shown or specified, shall be as follows:

1. Conductors across hinges of control panel enclosures shall be Type MTW.
2. Conductors shall be type XHHW-2 in wet, underground, and outdoor locations.
3. Conductors shall be type THHN in dry locations.

Wire connections and devices.--

Wire connections and devices shall be pressure or compression type, except that connectors for No. 10 AWG and smaller conductors in dry locations may be preinsulated spring-pressure type.

ELECTRICAL BOXES.--

Outlet, device and junction boxes.--

Unless otherwise shown or specified, boxes shall be galvanized steel boxes with knock-outs and shall be the size and configuration best suited to the application indicated on the plans. Minimum size of outlet, receptacle, switch or junction boxes shall be 100 mm square by 40 mm deep, except that switch boxes for the installation of single switches and outlet boxes for flush-mounted light fixtures shall be 50 mm by 75 mm by 40 mm deep.

Multiple switches shall be installed in standard gang boxes, unless otherwise specified or shown on the plans.

Cast metal boxes shall be cast iron boxes with threaded hubs and shall be of the size and configuration best suited to the application shown on the plans.

Flush-mounted boxes shall have stainless steel covers, one mm thick. Cover screws shall be metal with finish to match cover finish.

Unless otherwise shown or specified, surface-mounted boxes shall have galvanized steel covers with metal screws.

Weatherproof junction boxes shall have cast metal covers with gaskets.

Weatherproof switch and receptacle boxes shall have gasketed covers with gasketed hinged flaps to cover switches and receptacles.

Sectional device plates will not be permitted.

Underground pull boxes.--

Pull boxes shall be high density reinforced concrete box with ultraviolet inhibitor polyethylene etched face anchored in concrete and fiberglass cover with hold down bolts. The polyethylene and fiberglass material shall be fire resistant and show no appreciable change in physical properties with exposure to the weather. No. 5 pull box shall be Brooks Products No. 5; Christy Concrete Products, N30; or equal.

RECEPTACLES AND SWITCHES.--**Ground fault circuit interrupter receptacles, (GFCI).--**

Ground fault circuit interrupter receptacles shall be NEMA Type 5-20R, feed-through type, ivory color, 3-wire, 20-ampere, 125-volt AC, grounding type, specification grade, duplex receptacle with ground fault interruption. Receptacle shall detect and trip at current leakage of 5 milliamperes and shall have front mounted test and reset buttons.

Duplex receptacles.--

Duplex receptacles shall be NEMA Type 5-20R, 3-wire, 20-ampere, 125-volt AC, safety grounding, ivory color, specification grade receptacle suitable for wiring with stranded conductors.

Reel light receptacles.--

Reel light receptacles shall be 3-wire, 15-ampere, 125-volt AC, twist-lock, grounding type, single, specification grade receptacle suitable for wiring with stranded conductors.

Multi-outlet assemblies.--

Multi-outlet assemblies shall be 3-wire, 15-ampere, 125-volt AC, 1600 mm long strip, grounding type receptacles spaced 150 mm on center. The assembly shall be provided with the necessary entrance end fitting and blank end fitting.

Welding receptacles.--

Welding receptacles shall be surface-mounted, 600-volt, 60-ampere, 4-wire, 3-pole, circuit breaking, weather resistant, raintight receptacle with female interior assembly. The receptacle shall be complete with back box, angle adapter and spring door. The receptacle shall be grounded through extra pole and shell, and shall have crimp or solder type connections. A mating plug for the receptacle shall be provided.

Vehicle lift receptacle.--

Vehicle lift receptacle shall be surface-mounted, 600-volt, 60-ampere, 4-wire, 3-pole, circuit breaking, weather resistant, raintight receptacle with female interior assembly. The receptacle shall be complete with back box, angle adapter and spring door. The receptacle shall be grounded through extra pole and shell, and shall have crimp or solder type connections. A mating plug for the receptacle shall be provided.

Snap switches.--

Snap switches shall be 20-ampere, 120/277-volt AC, quiet type, specification grade, ivory color switch with silver cadmium alloy contacts. Switch shall be suitable for wiring with stranded conductors.

Motion sensor wall switches.--

Motion sensor wall switches shall be wall-mounted, 3-wire, 800-watt incandescent or fluorescent, off-auto-on, passive infrared sensor switch with adjustable photocell override and time delay and shall operate on 120/277 volts. The sensor switch shall cover a minimum of 84 square meters of floor area, be suitable for installation in a single gang box, and shall have a field of view of not less than 170 degrees. The time delay setting shall be adjustable from 30 seconds to 20 minutes, initially set at 5 minutes.

MISCELLANEOUS MATERIALS.--

Warning Tape.--

Warning tape shall be 100 mm wide and contain the printed warning "CAUTION ELECTRICAL CONDUIT" in bold 19 mm black letters at 760 mm intervals on bright orange or yellow background. The printed warning shall be non-erasable when submerged under water and resistant to insects, acids, alkali, and other corrosive elements in the soil. The tape shall have a tensile strength of not less than 70 kg per 100 mm wide strip and shall have a minimum elongation of 700 percent before breaking.

Pull ropes.--

Pull ropes shall be nylon or polypropylene with a minimum tensile strength of 225 kg.

Watertight conduit plugs.--

Watertight conduit plugs shall be a hollow or solid stem expansion plugs complete with inner and outer white polypropylene compression plates and red thermoplastic rubber seal. Seal material shall be non-stick type rubber resistant to oils, salt, and alkaline substances normally available at the construction sites.

Anchorage devices.--

Anchorage devices shall be corrosion resistant, toggle bolts, wood screws, bolts, machine screws, studs, expansion shields, and expansion anchors and inserts.

Electrical supporting devices.--

Electrical supporting devices shall be one hole conduit clamps with clamp backs, hot-dipped galvanized, malleable cast iron.

Construction channel shall be 41 mm x 41 mm, 2.66 mm (12-gage) galvanized steel channel with 13 mm diameter bolt holes, 40 mm on center in the base of the channel.

Telephone outlet boxes.--

Telephone outlet boxes shall be 102 mm square boxes and plates with modular type telephone outlet. Boxes on stud walls shall have plaster ring.

Plates for flush mounting outlets in finished room shall be Type 430 stainless steel, one mm thick with satin finish.

PART 3.- EXECUTION

INSTALLATION.--

Conduit, general.--Rigid steel conduit shall be used unless otherwise shown on the plans or specified in these special provisions.

Electrical metallic tubing may be used in furred spaces and for exposed work indoors above the switch height.

Unless otherwise specified or shown on the plans, flexible metal conduit shall be used to connect suspended lighting fixtures, motors, HVAC equipment, and other equipment subject to vibration in dry locations.

Unless otherwise specified or shown on the plans, liquid-tight flexible metal conduit shall be used to connect motors, HVAC equipment, and other equipment subject to vibration in wet locations.

Rigid non-metallic conduit shall be used at the locations shown on the plans for direct underground burial outside the building foundation. All risers and elbows shall be rigid steel.

Conduit installation.--Conduit trade sizes are shown on the plans. No deviation from the conduit size shown on the plans will be permitted without written permission from the Engineer.

Conduit shall be concealed unless otherwise shown on the plans.

Conduits shall be tightly covered and well protected during construction using metallic bushings and bushing "pennies" to seal open ends.

Rigid non-metallic conduit bends of 30 degrees or greater shall be factory-made long radius sweeps. Bends less than 30 degrees shall be made using an approved heat box.

A pull rope shall be installed in all empty conduits. At least one meter of pull rope shall be doubled back into the conduit at each termination.

Locations of conduit runs shall be planned in advance of the installation and coordinated with the ductwork, plumbing, ceiling and wall construction in the same areas and shall not unnecessarily cross other conduits or pipe, nor prevent removal of ceiling tiles or panels, nor block access to mechanical or electrical equipment.

Where practical, conduits shall be installed in groups in parallel, vertical or horizontal runs and at elevations that avoid unnecessary offsets.

Exposed conduit shall be installed parallel and at right angles to the building lines.

Conduits shall not be placed closer than 300 mm from a parallel hot water or steam pipe or 75 mm from such lines crossing perpendicular to the runs.

All raceway systems shall be secured to the building structures using specified fasteners, clamps and hangers.

Single conduit runs shall be supported by using one hole pipe clamps. Where run horizontally on walls in damp or wet locations, conduit shall be installed with "clamp backs" to space conduit off the surface.

Multiple conduit runs shall be supported with construction channel secured to the building structure. Conduits shall be fastened to construction channel with channel compatible pipe clamps.

Raceways of different types shall be joined using approved couplings or transition fittings.

Expansion couplings shall be installed where conduit crosses a building separation or expansion joint.

All floor and wall penetrations shall be sealed water-tight.

Existing underground conduit to be incorporated into a new system shall be cleaned with a mandrel or cylindrical wire brush and blown out with compressed air.

Conduit terminations.--Rigid steel conduits shall be securely fastened to cabinets, boxes and gutters using 2 locknuts and specified insulating metallic bushing. Electrical metallic tubing shall be securely fastened to cabinets, boxes and gutters using specified connectors. Conduit terminations at exposed weatherproof enclosures and cast outlet boxes shall be made watertight using specified hubs.

Grounding bushings with bonding jumpers shall be installed on all type of conduits terminating at concentric knockouts and on all conduits containing service conductors, grounding electrode conductor, and conductors feeding separate buildings.

Rigid non-metallic conduits shall be terminated inside the underground pull boxes with an approved conduit bushings or fittings. All conduits shall enter the pull box at an angle of 45 degrees or more.

All future conduits terminated in underground pull boxes or exposed indoor and outdoor shall be provided with watertight conduit plugs.

Warning Tape.--Warning tape shall be placed over each conduit in a trench. Each warning tape shall be centered over the conduit and shall be placed over the 150 mm layer of sand covering the conduit as described elsewhere in these special provisions.

Conductor and cable installation.--Conductors shall not be installed in conduit until all work of any nature that may cause injury is completed. Care shall be taken in pulling conductors that insulation is not damaged. An approved non-petroleum base and insulating type pulling compound shall be used as needed.

All cables shall be installed and tested in accordance with manufacturer's recommendations.

Splices and joints shall be insulated with insulation equivalent to that of the conductor.

Provide 155 mm of slack at each outlet and device connection. If the outlet or device is not at the end of a run of wire, connection shall be made with correctly colored pigtails tapped to the runs with splices as specified herein.

Branch circuit conductors in panelboards and load centers shall be neatly trained along a path from the breaker terminals to their exit point. The conductors shall have ample length to transverse the path without strain, but shall not be so long as to require coiling, doubling back, or cramming. The path shall transverse the panelboard gutter spaces without entering a gutter containing service conductors and, unless otherwise shown on the plans, without entering the gutter space of any panelboard feeder.

All pressure type connectors and lugs shall be retightened after the initial set.

Splices in underground pull boxes and similar locations shall be made watertight.

Junction boxes in furred or accessible ceiling spaces shall be identified with felt-tip pen denoting the circuits contained in the box.

Conductor identification.--The neutral and equipment grounding conductors shall be identified as follows:

Neutral conductor shall have a white or natural gray insulation except that conductors No. 4 and larger may be identified by distinctive white marker such as paint or white tape at each termination.

Equipment grounding conductor shall be bare or insulated. If insulated, equipment grounding conductors shall have green or green with one or more yellow stripes insulation over its entire length except that conductors No. 4 and larger may be permanently identified by distinctive green markers such as paint or green tape over its entire exposed insulation.

Ungrounded feeder and branch circuit conductors shall be color coded by continuously colored insulation, except conductors No. 6 AWG or larger may be color coded by colored tape at each connection and where accessible. Ungrounded conductor color coding shall be as follows:

SYSTEM	COLOR CODE
120/240 V-Three phase	Black, orange, blue

Once an insulated circuit conductor, including grounded and ungrounded conductors, is identified with a specific color code, that color code shall be used for the entire length of the circuit.

Where more than one branch circuit enters or leaves a conduit, panel, gutter, or junction box, each conductor shall be identified by its panelboard and circuit number. All control conductors including control conductors of manufacturer supplied and field wired control devices shall be identified at each termination with the wire numbers shown on the plans, approved shop drawings, and as directed by the Engineer where deemed necessary. Identification shall be made with one of the following:

1. Adhesive backed paper or cloth wrap-around markers with clear, heat shrinkable tubing sealed over either type of marker.
2. Self-laminating wrap around type, printable, transparent, permanent heat bonding type thermoplastic film markers.
3. Pre-printed, white, heat-shrinkable tubing.

Each terminal block shall have a molded marking strip attached with screws. The identifying numbers of the terminating conductors, as shown on the plans or on the submittal drawings, shall be engraved in the marking strip.

Outlet, device and junction box installation.--Where exposed threaded steel conduits are connected to an outlet, device, or junction box below switch height, the box shall be a cast metal box. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall be sheet steel boxes. Weatherproof outlet, device and junction boxes shall have cast metal covers with gaskets. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall have standard galvanized covers.

All boxes shall finish flush with building walls, ceiling and floors except where exposed work is called for.

Raised device covers (plaster rings) shall be installed on all boxes concealed in concrete, masonry or stud walls.

No unused openings shall be left in any box. Knockout seals shall be installed as required to close openings.

Outlet, device, and junction boxes shall be installed at the locations and elevations shown on the plans or specified herein. Adjustments to locations may be made as required by structural conditions and to suit coordination requirements of other trades.

Boxes in stud walls and partitions shall not be mounted back to back. Through-wall boxes shall not be used.

Boxes installed in metal stud walls shall be equipped with brackets designed for attaching directly to the studs or shall be mounted on heavy gauge galvanized steel, snap-in box supports.

Fixture outlet boxes installed in suspended ceilings of gypsum board or lath and plaster construction shall be mounted on 1.52 mm (16-gage) metal channel bars attached to main ceiling runners.

Fixture outlet boxes for pendant-mounted fixtures installed in suspended ceilings supporting acoustical tiles or panels shall be supported directly from the structures above.

Underground pull box installation.--Electrical pull box covers or lids shall be marked "ELECTRICAL." Telephone service pull box covers or lids shall have plain, unmarked covers.

The bottom of pull boxes shall be bedded in 155 mm of clean, crushed rock or gravel and shall be grouted with 40 mm thick grout prior to installation of conductors. Grout shall be sloped to a 25 mm PVC pipe drain hole. Conduit shall be sealed in place with grout.

Top of pull boxes shall be flush with surrounding grade or top of curb. In unpaved areas where pull box is not immediately adjacent to and protected by a concrete foundation, pole or other protective construction, the top of pull box shall be set at plus 30 mm above surrounding grade. Pull boxes shown on the plans in the vicinity of curbs shall be placed adjacent to the back of curb. Pull boxes shown on the plans adjacent to lighting standards shall be placed on the side of foundation facing away from traffic.

Anchorage.--Hangers, brackets, conduit straps, supports, and electrical equipment shall be rigidly and securely fastened to surfaces by means of toggle bolts on hollow masonry; expansion shields and machine screws, or expansion anchors and studs or standard preset inserts on concrete or solid masonry; machine screws or bolts on metal surfaces; and wood or lag screws on wood construction.

Anchorage devices shall be installed in accordance with the anchorage manufacturer's recommendations.

Mounting heights.--Electrical system components shall be mounted at the following mounting heights, unless otherwise shown on the plans. The mounting height dimensions shall be measured above the finished floor to the bottom of the device or component.

Thermostats	1.1 m maximum, office areas 1.25 m maximum, hallways
Wall switches	1.0 m maximum
Convenience outlets	510 mm minimum, office areas 1.25 m minimum, all other areas
Electric water cooler outlet	As recommended by the water cooler manufacturer.
Telephone and radio outlets	510 mm minimum

16.03 ELECTRICAL EQUIPMENT

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing panelboards, starters, disconnect switches, transformers, and related accessories in accordance with the details shown on the plans and these special provisions.

Related work.--Anchorage devices shall be as specified under "Basic Materials and Methods" elsewhere in this Division 16.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval.. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS

PANELBOARDS.--

Panelboard W.--

Panelboard W shall be indoor type, surface-mounted, factory assembled, 3-phase, 4-wire, 120/240-volt, AC panelboard at least 540 mm wide with 200-ampere main breaker, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panel shall be Square D Company, NQOD; Westinghouse, Type-R-Line; General Electric, NLAB; or equal.

STARTERS.--

Air compressor starter.--

Air compressor starter shall be combination 3-pole, 240-volt, NEMA Size 1, NEMA rated, line voltage starter and motor circuit protector in a NEMA-1 enclosure. Air compressor starter shall have two, 2-ampere, dual element, 250-volt fuses with 2-pole barrier type fuse base; 240-volt coil, double-break silver contacts and 3 manual reset, non-adjustable thermal overloads, set to trip between 115 and 125 percent of full load motor current, as quoted on the nameplate by the motor manufacturer. Reset button shall be externally operable.

Declassification fan controller.--

Declassification fan motor starter shall be combination 3-pole, 240-volt, NEMA Size 0, NEMA rated, line voltage starter and motor circuit protector in a NEMA-1 enclosure. Declassification fan motor starters shall have start-stop push button, 120-volt coil, double-break silver contacts and 3 manual reset, non-adjustable thermal overloads, set to trip between 115 and 125 percent of full load motor current, as quoted on the nameplate by the motor manufacturer. Start-stop and reset button shall be externally operable.

Exhaust evacuation fan motor starter.--

Exhaust evacuation fan motor starter shall be 2-pole, 240-volt, manual motor starter with toggle type operator in a NEMA-1 enclosure complete with thermal overloads, set to trip between 115 and 125 percent of full load motor current, as quoted on the nameplate by the motor manufacturer.

SWITCHES.--

Declassification fan disconnect switch.--

Declassification fan disconnect switch shall be 3-pole, 240-volt, AC, 30-ampere, non-fusible, general duty safety switch in a NEMA-3R enclosure with provision for padlocking in the "OFF" position.

Door operator disconnect switch.--

Door operator disconnect switch shall be 3-pole, 240-volt, AC, 30-ampere, non-fusible, general duty safety switch in a NEMA-1 enclosure with provision for padlocking in the "OFF" position.

MISCELLANEOUS MATERIALS.--

Nameplates.--

Nameplates shall be laminated phenolic plastic with white core and black front and back. Nameplate inscription shall be in capitals letters etched through the outer layer of the nameplate material.

Warning plates.--

Warning plates shall be laminated phenolic plastic with white core and red front and back. Warning plates inscription shall be in capitals letters etched through the outer layer of the nameplate material.

Declassification fan warning sign.--

Declassification fan warning sign shall be sheet steel, not less than 1.2 mm thick (18-gage) with a baked enamel coating and shall have red letters, 50 mm in height, on a white background.

Plywood backing board.--

Plywood backing board for mounting electrical or telephone equipment shall be 19 mm, APA plywood panels, C-D PLUGGED and touch-sanded, Exposure 1.

PART 3.- EXECUTION

INSTALLATION.--

Plywood backing board.--Plywood backing board shall be securely fastened to walls or other vertical framing.

Surface to be coated shall be cleaned of all dirt, excess materials, of filler by hand cleaning.

Plywood backing board exposed surfaces shall receive the following paint system: one prime coat, alkyd, interior wood primer and 2 finish coats, acrylic, interior enamel, semi-gloss. Color shall match surrounding surfaces, or shall be as directed by the Engineer.

Coatings shall be applied in accordance with the manufacturer's instructions. Each coat shall be applied to a uniform finish, free of skips, brush marks, laps or other imperfections.

Existing service metering equipment.--Provide new circuit breakers, where required to match existing type and interrupting capacity, unless otherwise shown on the plans. Provide mounting hardware, bus straps, and related materials for proper circuit breaker installation. Provide new identification nameplate with designation as shown for each circuit breaker. Remove existing nameplates where applicable.

Panelboard installation.--Set cabinets plumb and symmetrical with building lines. Train interior wiring as specified under "Conductor and Cable Installation" in "Basic Materials and Methods" of these special provisions. Touch-up paint any marks, blemishes, or other finish damage suffered during installation. Replace cabinets, doors or trim exhibiting dents, bends, warps or poor fit which may impede ready access, security or integrity.

Mounting height shall be 1.67 meters to the highest circuit breaker handle, measured above the finished floor.

Where "Future" or "Space" is indicated on the plans, branch connectors, mounting brackets, and other hardware shall be furnished and installed for future breaker.

A typewritten directory under transparent protective cover shall be provided and set in metal frame inside each cabinet door. Directory panel designation for each circuit breaker shall include complete information concerning equipment controlled, including room number or area designated on the plans.

Equipment identification.--Equipment shall be identified with nameplates fastened with self-tapping, cadmium-plated screws or nickel-plated bolts.

Nameplate inscription shall be 6 mm high letters and shall be provided to each control station on the plans and as follows:

Inscriptions for panel boards shall include panel designation, voltage, and phase of supply and shall read like the following example: PANEL A, 120/240 VOLTS, 3 PHASE, 4 wire

Inscription of disconnect switches and pushbuttons shall be the respective device it is controlling and shall read like the following: OVERHEAD DOOR, DECLASSIFICATION FAN.

Warning plates.--Warning plates shall be attached to designated equipment with self-tapping cadmium-plated screws or nickel-plated bolts.

Declassification Fan warning sign.--Warning sign with inscription "ENERGIZE DECLASSIFICATION FANS BEFORE REPAIR GASOLINE POWERED VEHICLES" shall be fastened to the wall next to each pushbutton (for declassification fan) with at least six anchorage device.

16.04 LIGHTING

GENERAL.--This work shall consist of furnishing, installing and connecting all lighting equipment in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive information, photometric curves, catalog cuts, and installation instructions shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

PRODUCTS.--

Lighting fixture lamps.--

Lighting fixture lamps shall be type and size as shown on the plans. Lamps shall be General Electric, Phillips, Sylvania, or equal. Fluorescent lamps, unless otherwise noted, shall be 4100K tri-phosphor with a CRI of 70 or greater.

Ballasts.--

All fixtures shall be equipped with high power factor ballasts suitable for the line voltage and for the type, size and number of lamps required by the fixture. Fluorescent ballasts shall be UL Listed, Class P and ETL Certified ballasts with sound rating A. Fluorescent ballasts shall be high-frequency electronic ballasts with power factor greater than 0.95, nominal ballast factor of 0.88 unless specified otherwise, total harmonic distortion less than 20 percent, crest factor less than or equal to 1.7, complying with ANSI C 62.41 Category A for surge protection, and FCC Part 18 for interference.

Lighting fixtures.--

Lighting fixtures shall be as shown on the plans and as specified herein. Outdoor luminaires shall be listed and labeled "Fixture Suitable For Wet Locations."

F1.--

Ceiling-mounted fluorescent fixture with two 32-watt T8 lamps, electronic ballast and one-piece, clear acrylic, wrap-around diffuser. The fixture shall be Day Brite, Catalog No. SWN232; Lithonia, Catalog No. LB 2 32 120; or equal.

F2.--

Wall mounted fluorescent fixture with one 32-watt T8 lamps, electronic ballast and prismatic acrylic diffuser. The fixture shall be Columbia, Catalog WB 132 CP; or equal.

MH1.--

Stem mounted 400 watt, 120-volt, metal halide, enclosed optical, wide distribution with integral ballast. The luminaire shall be Lithonia, TXR series; Day-Brite LC series; or equal.

H1.--

Outdoor, wall mounted, 70-watt, 120-volt high pressure sodium luminaire with integral ballast. The luminaire shall be Holophane Wall Pack Series, Lithonia TWP Series; or equal.

Photoelectric unit, PEC.--

Photoelectric unit shall be cadmium sulfide photoelectric control with capacity of 1800-watt incandescent or 1800-watt inductive or fluorescent load, mounting adapter, and EEI-NEMA twist lock receptacle; Fisher-Pierce, Ripley, or equal.

Lighting control station, LCS.--

Lighting control station shall consist of a lighting contactor, selector switch and pilot light in a surface mounted NEMA-12 enclosure with a hinged door.

Lighting contactor, LC.--

Lighting contactor shall be electrically held, 3-pole combination lighting contactor with 120-volt AC coil and 20-ampere, double-break, silver alloy contacts; Square D Company, I.T.E., Westinghouse, or equal.

Selector switch, SS.--

Selector switch shall be rotary action, double-pole, 3-position, 10-ampere, 120-volt switch. Switch contacts shall have an inductive pilot duty rating of 60 amperes (make), 6 amperes (break) and 10 amperes (continuous) at 120 volts and 35 percent power factor. Selector switch shall have legend plate marked MANUAL-OFF-AUTO.

Pilot light, PL.--

Pilot light shall be panel mounted, heavy duty, oil tight indicating light with 120-volt, AC, LED lamp with red domed cap.

Terminal block, TB.--

Terminal block shall be 30-ampere, 600-volt, molded plastic with two or more mounting holes and two or more terminals in each cast block. The molded plastic shall have a high resistance to heat, moisture, mechanical shock, and electrical potential and shall have a smooth even finish. Each block shall have a molded marking strip attached with screws. Terminal blocks shall have tubular, high pressure clamp connectors.

EXECUTION.--

LIGHTING FIXTURES.--Lighting fixtures shall be mounted securely in accordance with the manufacturer's recommendations. Mounting methods shall be suitable for the particular type of ceiling or support at each location.

The Contractor shall provide all supports, hangers, spacers, channels, fasteners and other hardware necessary to support the fixtures.

Fixtures shall be set at the mounting heights shown on the plans, except heights shown shall be adjusted to meet conditions.