

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.
Help save water!*

April 29, 2015

10-SCI,Mer-152-R35.0/R35.2, R0.0/R2.4

10-0W1404

Project ID 1012000042

ACHSNHPG-P152(085)E

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN SANTA CLARA AND MERCED COUNTIES ABOUT 16.0 MILES WEST OF LOS BANOS FROM 0.1 MILE EAST OF FIFIELD ROAD TO 0.1 MILE WEST OF VISTA POINT.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, May 14, 2015, instead of the original date of Tuesday, May 5, 2015.

This addendum is being issued to set a new bid opening date as shown herein and revise the project plans, the *Notice to Bidders and Special Provisions*, and the *Bid* book.

Project plan sheets 2, 3, 25, 43, 51 and 54 are replaced and attached for substitution for the like-numbered sheets.

In the *Notice to Bidders and Special Provisions*, and the *Bid* book the District-County-Route-Post Mile on the covers and in the Notice to Bidders are replaced as follows:

"04, 10-SCI, Mer-152-R35.0/R35.2, R0.0/R2.4."

In the *Special Provisions*, Section 2 BIDDING, 2-1.06B Supplemental Project Information, is replaced as attached.

In the *Special Provisions*, Section 15-2.02B(3)(a), is replaced as attached.

In the *Bid* book, in the "Bid Item List," Item 31 is replaced.

Addendum No. 2
Page 2
April 29, 2015

10-SCI,Mer-152-R35.0/R35.2, R0.0/R2.4
10-0W1404
Project ID 1012000042
ACHSNHPG-P152(085)E

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file, and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/10/10-0W1404

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



SHARRI BENDER EHLERT
District Director
District 6 Central Region

fox

Attachments

Add to section 2-1.06B:

The Department makes the following supplemental project information available:

Supplemental Project Information

Means	Description
Included in the <i>Information Handout</i>	<ol style="list-style-type: none">1. U.S. Fish and Wildlife Service - Biological Opinion2. Manufacturer's Drawings for Alternative Flared Terminal System3. Manufacturer's Drawings for Temporary Alternative Crash Cushion4. Manufacturer's Drawings for Alternative Crash Cushion5. Water Source Availability
Available as specified in the <i>Standard Specifications</i>	<ol style="list-style-type: none">1. Cross Sections2. Cross Sections with Grid3. KCM file of Alignments4. KCM file of Profiles

15-2.02B(3)(a) General

Schedule cold planing activities to ensure that cold planing, placement of HMA, and reopening the area to traffic is completed during the same work shift.

If you do not complete HMA placement before opening the area to traffic, you must:

1. Construct a temporary HMA taper to the level of the existing pavement
2. Place HMA during the next work shift
3. Submit a corrective action plan that shows you will complete cold planing and placement of HMA in the same work shift. Do not restart cold planing activities until the Engineer approves the corrective action plan.

**BID ITEM LIST
10-0W1404**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	141120	TREATED WOOD WASTE	LB	620		
22	150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	EA	17,700		
23	150722	REMOVE PAVEMENT MARKER	EA	600		
24	150742	REMOVE ROADSIDE SIGN	EA	3		
25	150809	REMOVE CULVERT (LF)	LF	28		
26	150820	REMOVE INLET	EA	4		
27	152320	RESET ROADSIDE SIGN	EA	4		
28	152430	ADJUST INLET	EA	1		
29	152443	ADJUST PIPE INLET TO GRADE	EA	2		
30	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	5,850		
31	180106	DUST PALLIATIVE	LS	LUMP SUM		
32	190101	ROADWAY EXCAVATION	CY	7,170		
33	210300	HYDROMULCH	SQFT	244,000		
34	210600	COMPOST	SQFT	244,000		
35	260203	CLASS 2 AGGREGATE BASE (CY)	CY	3,290		
36	374002	ASPHALTIC EMULSION (FOG SEAL COAT)	TON	6		
37	390132	HOT MIX ASPHALT (TYPE A)	TON	10,600		
38	394053	SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS)	STA	270		
39	394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	7,900		
40	397005	TACK COAT	TON	12		