

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.  
Help save water!*

May 8, 2015

11-SD-11, 125, 905-Var

11-288814

Project ID 1113000167

ACCBI-X073(111)N

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN SAN DIEGO COUNTY IN AND NEAR SAN DIEGO AT ROUTE 11/125/905 SEPARATION.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, May 21, 2015.

This addendum is being issued to revise the project plans, the *Notice to Bidders and Special Provisions* and the *Bid* book.

Project plan sheets 27, 28, 29, 30, 31, 32, 33, 163 and 165 are replaced and attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 86-5.01A(1) is added as follows:

**"Add to section 86-5.01A(1):**

Loop detector lead-in cable must be Type B.

For Type E detector loops, sides of the slot must be vertical and the minimum radius of the slot entering and leaving the circular part of the loop must be 1-1/2 inches. Slot width must be a maximum of 5/8 inch. Loop wire for circular loops must be Type 2. Slots of circular loops must be filled with elastomeric sealant or hot-melt rubberized asphalt sealant.

The depth of the loop sealant above the top of the uppermost loop wire in the sawed slots must be 2 inches, minimum."

In the *Bid* book, in the "Bid Item List," Items 51, 70, 72, 75, 82 and 147 are replaced.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Addendum No. 1  
Page 2  
May 8, 2015

11-SD-11, 125, 905-Var  
11-288814  
Project ID 1113000167  
ACCBI-X073(111)N

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

**[http://www.dot.ca.gov/hq/esc/oe/electronic\\_bidding/electronic\\_bidding.html](http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html)**


Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file, and attachments are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/11/11-288814](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/11/11-288814)**

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



LAURIE BERMAN  
District Director

Attachments

**BID ITEM LIST**

**11-288814**

| Item No.  | Item Code | Item Description   | Unit of Measure | Estimated Quantity | Unit Price | Item Total |
|-----------|-----------|--|-----------------|--------------------|------------|------------|
| 41        | 153121    | REMOVE CONCRETE (CY)                                     | CY              | 92                 |            |            |
| 42        | 028787    | REMOVE ROCK SLOPE PROTECTION                             | CY              | 37                 |            |            |
| 43        | 160102    | CLEARING AND GRUBBING (LS)                               | LS              | LUMP SUM           | LUMP SUM   |            |
| 44        | 170101    | DEVELOP WATER SUPPLY                                     | LS              | LUMP SUM           | LUMP SUM   |            |
| 45        | 180106    | DUST PALLIATIVE  | LS              | LUMP SUM           | LUMP SUM   |            |
| 46        | 190101    | ROADWAY EXCAVATION                                       | CY              | 177,000            |            |            |
| 47<br>(F) | 192003    | STRUCTURE EXCAVATION (BRIDGE)                            | CY              | 1,482              |            |            |
| 48        | 028788    | GRAVEL BEDDING   | CY              | 560                |            |            |
| 49<br>(F) | 193003    | STRUCTURE BACKFILL (BRIDGE)                              | CY              | 1,186              |            |            |
| 50        | 194001    | DITCH EXCAVATION   | CY              | 130                |            |            |
| 51        | 198010    | IMPORTED BORROW (CY)                                     | CY              | 177,000            |            |            |
| 52        | 200002    | ROADSIDE CLEARING  | LS              | LUMP SUM           | LUMP SUM   |            |
| 53        | 204045    | SOD  | SQYD            | 4,670              |            |            |
| 54        | 204099    | PLANT ESTABLISHMENT WORK                                 | LS              | LUMP SUM           | LUMP SUM   |            |
| 55        | 028789    | 2" ELECTRICAL CONDUIT FOR CONTROL AND NEUTRAL CONDUCTORS | LF              | 310                |            |            |
| 56        | 028790    | 3" ELECTRICAL CONDUIT FOR CONTROL AND NEUTRAL CONDUCTORS | LF              | 290                |            |            |
| 57        | 028791    | TRUCK WATERING   | LS              | LUMP SUM           | LUMP SUM   |            |
| 58<br>(F) | 208029    | 4" SUPPLY LINE (BRIDGE)                                  | LF              | 263                |            |            |
| 59<br>(F) | 208607    | 3" PLASTIC PIPE (CLASS 315) (SUPPLY LINE)                | LF              | 16                 |            |            |
| 60<br>(F) | 208608    | 4" PLASTIC PIPE (CLASS 315) (SUPPLY LINE)                | LF              | 411                |            |            |

**BID ITEM LIST**  
**11-288814**

| Item No. | Item Code | Item Description                                      | Unit of Measure | Estimated Quantity | Unit Price | Item Total |
|----------|-----------|---|-----------------|--------------------|------------|------------|
| 61       | 208738    | 8" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT  | LF              | 16                 |            |            |
| 62       | 208740    | 12" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT | LF              | 290                |            |            |
| 63       | 210010    | MOVE-IN/MOVE-OUT (EROSION CONTROL)                    | EA              | 1                  |            |            |
| 64       | 028792    | CHECK DAM   | LF              | 1,170              |            |            |
| 65       | 210250    | EROSION CONTROL (BONDED FIBER MATRIX) (SQFT)          | SQFT            | 904,000            |            |            |
| 66       | 210360    | COMPOST SOCK  | LF              | 6,250              |            |            |
| 67       | 210600    | COMPOST   | SQFT            | 946,000            |            |            |
| 68       | 210630    | INCORPORATE MATERIALS                                 | SQFT            | 946,000            |            |            |
| 69       | 220101    | FINISHING ROADWAY                                     | LS              | LUMP SUM           | LUMP SUM   |            |
| 70       | 250401    | CLASS 4 AGGREGATE SUBBASE                             | CY              | 10,200             |            |            |
| 71       | 250501    | CLASS 5 AGGREGATE SUBBASE                             | CY              | 21,000             |            |            |
| 72       | 260203    | CLASS 2 AGGREGATE BASE (CY)                           | CY              | 7,360              |            |            |
| 73       | 374002    | ASPHALTIC EMULSION (FOG SEAL COAT)                    | TON             | 1.9                |            |            |
| 74       | 377501    | SLURRY SEAL   | TON             | 180                |            |            |
| 75       | 390132    | HOT MIX ASPHALT (TYPE A)                              | TON             | 5,970              |            |            |
| 76       | 390136    | MINOR HOT MIX ASPHALT                                 | TON             | 160                |            |            |
| 77       | 394075    | PLACE HOT MIX ASPHALT DIKE (TYPE D)                   | LF              | 68                 |            |            |
| 78       | 394076    | PLACE HOT MIX ASPHALT DIKE (TYPE E)                   | LF              | 3,000              |            |            |
| 79       | 394077    | PLACE HOT MIX ASPHALT DIKE (TYPE F)                   | LF              | 2,400              |            |            |
| 80       | 394090    | PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)            | SQYD            | 230                |            |            |

**BID ITEM LIST**  
**11-288814**

| Item No. | Item Code | Item Description   | Unit of Measure | Estimated Quantity | Unit Price | Item Total |
|----------|-----------|--|-----------------|--------------------|------------|------------|
| 81       | 397005    | TACK COAT  | TON             | 2.9                |            |            |
| 82       | 401050    | JOINTED PLAIN CONCRETE PAVEMENT                          | CY              | 5,450              |            |            |
| 83       | 414201    | JOINT SEAL (SILICONE)                                    | LF              | 22,600             |            |            |
| 84       | 414241    | ISOLATION JOINT SEAL (SILICONE)                          | LF              | 530                |            |            |
| 85       | 420201    | GRIND EXISTING CONCRETE PAVEMENT                         | SQYD            | 230                |            |            |
| 86       | 028793    | 48" STEEL CASING (0.625" THICK)                          | LF              | 61                 |            |            |
| 87       | 044867    | FURNISH PILE(CLASS 200)(ALTERNATIVE W MODIFIED)          | LF              | 1,900              |            |            |
| 88       | 044868    | DRIVE PILE(CLASS 200)(ALTERNATIVE W MODIFIED)            | EA              | 70                 |            |            |
| 89       | 498052    | 60" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | LF              | 66                 |            |            |
| 90       | 500001    | PRESTRESSING CAST-IN-PLACE CONCRETE                      | LS              | LUMP SUM           | LUMP SUM   |            |
| 91 (F)   | 510051    | STRUCTURAL CONCRETE, BRIDGE FOOTING                      | CY              | 276                |            |            |
| 92 (F)   | 510053    | STRUCTURAL CONCRETE, BRIDGE                              | CY              | 1,291              |            |            |
| 93 (F)   | 510086    | STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)              | CY              | 119                |            |            |
| 94 (F)   | 028794    | STRUCTURAL CONCRETE (JUNCTION STRUCTURE)                 | CY              | 67                 |            |            |
| 95 (F)   | 510092    | STRUCTURAL CONCRETE, HEADWALL                            | CY              | 45                 |            |            |
| 96 (F)   | 510502    | MINOR CONCRETE (MINOR STRUCTURE)                         | CY              | 119                |            |            |
| 97 (F)   | 044869    | FRACTURED RIB TEXTURE (MODIFIED)                         | SQFT            | 366                |            |            |
| 98       | 519091    | JOINT SEAL (MR 1 1/2")                                   | LF              | 120                |            |            |
| 99 (F)   | 520101    | BAR REINFORCING STEEL                                    | LB              | 6,376              |            |            |
| 100 (F)  | 520102    | BAR REINFORCING STEEL (BRIDGE)                           | LB              | 348,859            |            |            |

**BID ITEM LIST**

**11-288814**

| Item No. | Item Code | Item Description   | Unit of Measure | Estimated Quantity | Unit Price | Item Total |
|----------|-----------|--|-----------------|--------------------|------------|------------|
| 141      | 800361    | CHAIN LINK FENCE (TYPE CL-6, VINYL-CLAD)                                       | LF              | 1,180              |            |            |
| 142      | 028804    | 6' CHAIN LINK GATE (TYPE CL-6, VINYL CLAD)                                     | EA              | 4                  |            |            |
| 143      | 028805    | CONCRETE BARRIER MARKER  | EA              | 6                  |            |            |
| 144      | 820107    | DELINEATOR (CLASS 1)   | EA              | 130                |            |            |
| 145      | 820118    | GUARD RAILING DELINEATOR   | EA              | 64                 |            |            |
| 146      | 832005    | MIDWEST GUARDRAIL SYSTEM   | LF              | 2,550              |            |            |
| 147 (F)  | 839521    | CABLE RAILING  | LF              | 171                |            |            |
| 148      | 839543    | TRANSITION RAILING (TYPE WB-31)  | EA              | 5                  |            |            |
| 149      | 839581    | END ANCHOR ASSEMBLY (TYPE SFT)   | EA              | 4                  |            |            |
| 150      | 839585    | ALTERNATIVE FLARED TERMINAL SYSTEM   | EA              | 2                  |            |            |
| 151 (F)  | 839725    | CONCRETE BARRIER (TYPE 736)  | LF              | 506                |            |            |
| 152      | 840515    | THERMOPLASTIC PAVEMENT MARKING   | SQFT            | 1,460              |            |            |
| 153      | 840516    | THERMOPLASTIC PAVEMENT MARKING (ENHANCED WET NIGHT VISIBILITY)                 | SQFT            | 180                |            |            |
| 154      | 840655    | PAINT TRAFFIC STRIPE (1-COAT)  | LF              | 15,800             |            |            |
| 155      | 840656    | PAINT TRAFFIC STRIPE (2-COAT)  | LF              | 14,500             |            |            |
| 156      | 846001    | 4" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY)                | LF              | 28,500             |            |            |
| 157      | 846002    | 4" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY) (BROKEN 6-1)   | LF              | 480                |            |            |
| 158      | 846004    | 4" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY) (BROKEN 17-7)  | LF              | 610                |            |            |
| 159      | 846005    | 4" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY) (BROKEN 36-12) | LF              | 13,200             |            |            |
| 160      | 846009    | 8" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY)                | LF              | 5,410              |            |            |