




10-Ama-88-KP 88.0/97.8(PM 54.7/60.8)  
06240-0K130K  
HA22 Program  
201.120  
Pavement Rehabilitation  
August 2005


## PROJECT SCOPE SUMMARY REPORT (Pavement Rehabilitation)



### ON ROUTE 88


In Amador County from 0.1 mile west of  
Foster Meadow Road to 1.1 miles east of Shot Rock Vista Point

*I have reviewed the right of way information contained in this Project Scope Summary report and the R/W Data Sheet attached hereto, and find the data to be complete, current, and accurate:*

  
SPIROS KARAMBAKAS

Acting Central Region Chief - Right of Way

APPROVAL RECOMMENDED BY:

  
JOY PINNE  
Project Manager

APPROVED BY:

  
KOME AJISE  
District 10 Director

11/29/05  
Date

PROJECT SCOPE & TECHNICAL DATA ARE VALID THROUGH: \_\_\_\_\_  
(Two years from Director approval data for PSSRs, and three years for PSRs)  
COST & WORK PLAN MUST BE UPDATED PRIOR TO USE FOR PROGRAMMING

10-Ama-88-KP 88.0/97.8(PM 54.7/60.8)  
06240-0K130K  
HA22 Program  
201.120  
Pavement Rehabilitation  
August 2005

This Project Scope Summary Report has been prepared under the direction of the following registered civil engineer. The registered Civil Engineer attests to the technical information contained herein and the engineering data upon which recommendations, conclusions, and decisions are based.

*Randall Won*

RANDALL WON, P.E.  
Registered Civil Engineer

*8/31/05*

Date





10-Ama-88-KP 88.0/97.8(PM 54.7/60.8)  
06240-0K130K  
HA22 Program  
201.120  
Pavement Rehabilitation  
August 2005

## PROJECT SCOPE SUMMARY REPORT (PSSR)

### 1. **PROJECT LIMITS:** 10-Ama-88- KP 88.0/97.8 (PM54.7/60.8)

This project is located in Amador county about 40 miles east of Jackson from 0.1 mile west of Foster Meadow Road to 1.1 miles east of Shot Rock Vista Point (*See Attachment A*).

### 2. **BRIEF PROJECT DESCRIPTION**

The proposed project (*See Attachment B & C*) will rehabilitate the existing pavement between KP 88.0/97.8 (PM 54.7/60.8). The proposed construction includes digging out and repairing all localized failures, and placing an asphalt concrete (AC) overlay with shoulder backing. The construction will also include the removal of AC dike, the placement of metal beam guardrail, and the upgrade of drainage facilities.

There are two locations where the existing alignment will be realigned for curve corrections. The first location is between KP 93.9 (PM R58.3) and KP 94.1 (PM 58.5), and the second location is between KP 96.0 (PM 59.7) and KP 96.9 (PM 60.2). The realignments are proposed to have standard two 3.6 m lanes and 2.4 m shoulders.

The total estimated construction cost is \$13,429,000 and with additional Right of Way to be acquired at a cost of \$286,000 (*see Attachment D*). The project is proposed to be a long lead project programmed in the 2006 State Highway Operation and Protection Program (SHOPP) with funding from the 201.120 (HA-22) Program.

### 3. **ENVIRONMENTAL STATUS:**

This project is anticipated to require an Initial Study/Negative Declaration for the California Environmental Quality Act (CEQA) compliance and a Finding of No Significant Impact for National Environmental Policy Act (NEPA). Cultural resources would be the critical path for completion of the CEQA/NEPA environmental document. The project area would need a phase II survey for archaeological sites in the project area. Assuming a start date of 1/1/07 for environmental studies, environmental approval is anticipated by 10/1/10. For Preliminary Environmental Analysis Report, (see Attachment E).

#### 4. TRAFFIC DATA

The 2005 Average Daily Traffic (ADT) for this segment of Route 88 is shown in the table below:

ADT (2005) = 2,600	ADT (2019) = 3,800
DHV (2005) = 439	Trucks = 6%
T.I. (2019) = 8.0 (TW)	Safety Review: <u>05/02/05</u>
V = 90 km/h	

A three-year traffic accident study for this portion of Route 88 was conducted from December 31, 2001 to December 31, 2004. A summary of the study follows:

LOCATION (KP to KP)	TOTAL NO. OF ACC.	ACTUAL RATE *(MVM)			AVERAGE RATE *(MVM)		
		F	F+I	TOTAL	F	F+I	TOTAL
SR 88 (KP 88.0/97.8)	17	0.00	0.39	<b>0.94</b>	0.27	0.55	<b>1.19</b>

\*MVM – Million Vehicles per Mile

#### Accident History & Traffic Analysis:

A review of the accident history within the project limits for the three-year period from Dec 31, 2001 to Dec 31, 2004, shows that there were a total of 17 accidents with 0 fatal accidents, 7 injury accidents. The traffic analysis reflects that the actual accident rate is less than the statewide average accident rate within the project limits.

Location(s) of Accident Concentrations: None, there is no common pattern between the accidents

Corrective Strategy: None, this project addresses pavement rehabilitation and curve corrections with some upgrade in safety features (e.g. metal beam guard rail).

#### 5. ROADWAY GEOMETRIC INFORMATION

Facility (SR 88)	Minimum Curve Radius	Through Traffic Lanes			Paved Shoulder Width		Median Width
		No. of Lanes	Lane Width	Type (AC or PCC)	Left	Right	
KP88.0 / 97.8	188	2	3.6	AC	1.2	1.2	-----
*KP 93.9 / 94.1	260	2	3.6	AC	2.4	2.4	-----
*KP 96.0 / 96.9	260	2	3.6	AC	2.4	2.4	-----
Min. 3R Stds.	260	-----	3.6	-----	1.2	1.2	-----

\* Proposed

**6. STRUCTURES INFORMATION**

None

**7. CONDITION OF EXISTING PAVEMENT**

2004 Pavement Condition Inventory Survey Data (*see Attachment F*).

Condition of Existing Facility (Repeat info for each homogeneous segment):

PMS Category (1-29) 8 Priority Classification (.1-.4) 0.2

Ride Score 27 Project Priority Score 48

\*PCC Pavement:

\* AC Pavement:

\* From latest PMS-2004 Pavement Condition Inventory Survey Data

3rd Stage Cracking% N/A Alligator B Cracking% 79%

Faulting N/A Patching% None

Joint Spalls N/A Rutting Yes

Pumping N/A Bleeding Yes

Corner Breaks% N/A Raveling No

Locations(s) of subsurface or ponded surface-water problem None

**8. DEFLECTION STUDY DATA**

A Deflection Study Report has been requested, but was not received in time to be included in this report. The District Materials Lab has recommended that a deflection study be completed within 18 months before the PS&E date. Therefore, the following method was used as the basis of the scope and cost for the pavement design for this project. The pavement rehabilitation strategy is given in the Materials Report (*see Attachment G*).

When the actual deflection study report is received, the Project Development Team and District will need to assess if the results of the report are compatible with the project as scoped. Assumptions made in this report without the availability of a deflection study report could have significant impacts on the cost, scope and schedule of the project.

Rubberized AC is not recommended because of the distance between the AC plant and the project makes it difficult to meet the temperature requirements of the mix.

**9. COST ESTIMATE BREAKDOWN**

<u>Structural Section Work</u>	<u>Lane-KM</u>	<u>Quant.</u>	<u>Unit</u>	<u>Price</u>	<u>*Cost</u>
AC Overlay of AC Pavement	9.2	26000	tonne	\$ 100.00	\$ 2,600,000
New Pavement	1.1				\$ 1,022,000
Digouts					\$ 350,000
Roadway Excavation		52000	m3	\$ 30.00	\$ 1,560,000
Embankment		10000	m3	---	
Shoulder Backing (Imported Borrow)		7100	tonne	\$ 100.00	\$ 710,000
Remove Dike		5000	m	\$ 2.00	\$ 10,000
Clearing And Grubbing		1	LS	\$ 60,000	\$ 60,000
Total Lane-Kilometers of Rehabilitation	10.3				
				<b>COSTS SUBTOTAL</b>	<b>\$ 6,312,000</b>
				Does the Project Include?	
				YES NO	
<u>Drainage Rehabilitation</u>	X				\$ 500,000
List appropriate work type : ( culvert )					
<u>Safety</u>					
Rumble Strip		X			
Superelevation Correction	X				
Vertical Alignment		X			
Horizontal Alignment	X				
Metal Beam Guardrails (New)	X				\$ 5,000
Construction Area Signs	X				\$ 22,000
Traffic Management Plan	X				\$ 46,000
<u>Utility Relocation</u>	X				\$ 37,500
<u>Railroad Agreements</u>		X			
<u>Misc.</u>					
Environmental Mitigation	X				\$ 1,000,000
Pavement Delineation/Signs	X				\$ 119,000
Erosion Control	X				\$ 194,000
Water Pollution Control	X				\$ 316,000
Implementation of SWPPP		X			
<u>Traffic Control</u>					\$ 74,000
<u>Other</u>					
Resident Engineer Office	X				\$ 40,000
*Minor Items	X				\$ 631,000
*Supplemental Work & State Furn.	X				\$ 947,000
*Roadway Mobilization	X				\$ 947,000
				<b>COSTS SUBTOTAL</b>	<b>\$ 4,878,500</b>
				<b>SUM OF SUBTOTALS</b>	<b>\$ 11,190,500</b>
				<b>20% Contingency</b>	<b>\$ 2,238,100</b>
				<b>TOTAL PROJECT COST</b>	<b>\$ 13,429,000</b>

**10. OTHER AGENCIES INVOLVED** (Permits/Approvals from Fish & Game, Corps of Engineers, Costal Commission, etc.)

Permits from the U.S. Corp of Engineers, Regional Water Quality Control Board, U.S. Forest Service will be needed.

**11. OTHER CONSIDERATIONS**

Hazardous waste

Initial Site Assessment (ISA) should be performed with regard to parcel ownership and land use history, specific database searches for hazardous waste and right-of-way parcel acquisition, regulatory consultation (as appropriate), and site visits. (see Attachment E).

Materials and/or disposal site

A site for AC disposal is needed. Potential disposal sites are being investigated.

Utility Involvement

Utility relocation (Volcano Telephone) will be required for this project.

Railroad

There is no railroad in the vicinity.

Other planning

Our Transportation System Development Program (TSDP) identifies no planned project for this segment.

Salvaging and recycling

Salvaging and recycling of hardware and other non-renewable resources is not anticipated.

Bicycle traffic

There is no effect on bicycle traffic.

Recycling of AC

This option is not viable due to the quantities involved.

Environmental Issues

Cultural resources would be the critical path for the completion of the CEQA/NEPA environmental document. The project area will need a phase II survey for archeological sites in the project area. (see Attachment E)

Storm Water

As required by the Department's NPDES permit, this project will submit a Notification of Construction to the Central Valley Regional Water Quality Control Board and a Storm Water Pollution Prevention Plan will be implemented during construction. A Storm Water Data Report has been completed (see Attachment I, for the signature page)

What are the consequences of not doing this entire project?

The consequences for not doing this project will result in roadway deterioration and decrease operations and safety.

## 12. PROJECT REVIEWS

**Has the Project been Field Reviewed by:**

District? Yes Date 05/02/05

Headquarters (HQ) OPPD ? No Date         

**Project Reviewed by:**

District Safety Mark Orr Date 05/02/05

District Maintenance Alvin Mangindin Date 06/01/05

District Materials Dave Whaling Date 06/17/05

HQ Maintenance Program Rob Marsh Date 06/01/05

Type of federal Involvement: **Exempt**

## 13. PROPOSED FUNDING

This project is proposed for programming as a long lead project in the 2006 SHOPP with funding from the 201.120 Roadway Rehabilitation Program (HA22).

The Project Development Team has discussed which WBS activities can be worked on out of sequence or in parallel with other activities. This project has considered and is implementing Change Control.

Change control was considered for this project and was deemed appropriate. It is very likely that much of the work done in advance would be used in final design.

**Capital Outlay Support Estimate**

The escalated Construction, Right of Way, and support costs are summarized in the table below, followed by the proposed project schedule.

Project Cost	Fiscal Year						Total
	06/07	07/08	08/09	09/10	10/11	11/12	
Component							
R/W Capital					\$403		\$403
Constr Capital						\$16,034	\$16,034
PA&ED	\$1,102						\$1,102
PS&E					\$1,412		\$1,412
R/W Support				\$251			\$251
Constr Support						\$1,065	\$1,065
<b>Total</b>	<b>\$1,102</b>	<b>\$0</b>	<b>\$0</b>	<b>\$251</b>	<b>\$1,815</b>	<b>\$17,099</b>	<b>\$20,267</b>

All costs x\$1000. Support Categories are the same as those identified by SB45.

Construction Capital escalated at 3.0%. Right of Way Capital estimate is escalated at 3.0%.

Support cost escalated at 2.0%.

Support Cost Ratio : 24% [ All Support Costs (\*) divided by the escalated Construction Capital (\*\*)]

**Tentative Project Schedule**

PID Approval	8/31/2005
PA&ED	10/1/2010
Right of Way Cert	4/1/212
Ready to List	4/1/2012
Approve Contract	7/15/2012
Job Complete	11/1/2013

**14. RISK STATEMENTS**

In late May, 2005, priorities for the SHOPP program were changed to broaden the types of projects potentially available for programming in the 2006 SHOPP cycle. This change, plus the addition of potential funding in certain programs, resulted in the need to quickly update or initiate candidate projects. Due to the fact that only approximately two months have been available to *update/develop* this project, various risks have been taken by the Project Development Team and the District in presenting this project for programming. This project is being proposed for programming as a long lead project.

**Task Force Field Review**

The original task force field review occurred on 06/01/05. Due to the limited time to prepare this document, a new task force field review was not held. However, Alvin Mangindin, the District HA22 Program Advisor, and Rob Marsh, Headquarters HA 22 Program Advisor, have reviewed the site and concur on the scope of work as contained in this document.

Deflection Study

A Deflection Study Report has been requested, but was not received in time to be included in this report. The District Materials Lab has recommended that a deflection study be completed within 18 months before the PS&E date. When the actual deflection study report is received, the Project Development Team and District will need to assess if the results of the report are compatible with the project as scoped.

Constructability Review

Due to the limited time available to complete this document, and the lack of complexity of the project, the Project Development Team has determined that a constructability review will not be held at this time. However, it is recommended that a review be held at 30% to ascertain if any issues have arisen.

**15. PROJECT PERSONNEL**

Yoon Hahn	Project Engineer	(209) 948-3896
Randall Won	Project Engineer	(209) 948-3896
Paul Elliott	Design Manager	(209) 948-7079
Joy Pinne	Project Manager	(209) 948-7976
David Hyatt	Senior Environmental Planner	(559) 243-8312
Duper Tong	Chief, Traffic Safety	(209) 948-7859
Vu Nguyen	Chief, Traffic Operations	(209) 948-7875
Laurie Jurgens	Chief, Traffic Management	(209) 948-7963
Alvin Mangindin	Chief, Maintenance	(209) 948-7300

**16. LIST OF ATTACHMENTS**

Attachment A	Vicinity Map (Title Sheet)
Attachment B	Layouts
Attachment C	Typical Cross Sections
Attachment D	Right of Way
Attachment E	Preliminary Environmental Assessment Report (PEAR)
Attachment F	Pavement Condition Survey
Attachment G	Material Report
Attachment H	Traffic Management Plan Checklist
Attachment I	Storm Water Data Report
Attachment J	Risk Management Plan
Attachment K	Distribution List


INDEX OF SHEETS

# STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION PROJECT PLANS FOR CONSTRUCTION ON STATE HIGHWAY


## IN AMADOR COUNTY ABOUT 40 MILES EAST OF JACKSON FROM 0.2 KM WEST OF FOSTER MEADOW ROAD TO 1.8KM EAST OF SHOT ROCK VISTA POINT

To be supplemented by Standard Plans dated July, 1999

DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET TOTAL SHEETS
10	Amo	88	88.0/97.8	



The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.  
Calltrans now has a web site. To get to the web site, go to <http://www.calltrans.com>




**BEGIN WORK AND CONSTRUCTION**  
STA 100+00 KP 88.0  
PM 54.6

**END WORK AND CONSTRUCTION**  
STA 198+00 KP 97.8  
PM 60.6

NO SCALE

The Contractor shall possess the Class (or classes) of license as specified in the "Notice to Contractors".



Project Engineer: \_\_\_\_\_ Date: \_\_\_\_\_  
Registered Civil Engineer

Plans Approval Date

Contract No. CU 06240 EA OK130K

NOTE: FOR COMPLETE R/W DATA, SEE R/W RECORD MAPS AT DISTRICT OFFICE.



DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET NO	TOTAL SHEETS
10	Amo	88	88.0/99.8		

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

Caltrans now has a web site! To get to the web site, go to <http://www.dot.ca.gov>





DATE REVISIED BY

CALCULATED/DESIGNED BY  
CHECKED BY

PROJECT ENGINEER  
**RANDALL WON**


IDM



ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SHOWN

**LAYOUT**

SCALE: 1:1500 **L-1**



USERNAME -> USER  
DGN FILE -> #REQLEST

CU 06240

EA OK130K

**ATTACHMENT B**  
Layout

DATE PLOTTED -> DATE  
TIME PLOTTED -> TIME

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
**Caltrans**  
 PROJECT ENGINEER  
**RANDALL WON**  
 DESIGN

DATE REVISOR BY DATE REVISOR BY  
 CALCULATED/DESIGNED BY CHECKED BY

NOTE: FOR COMPLETE R/W DATA, SEE R/W RECORD MAPS AT DISTRICT OFFICE.




DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET No	TOTAL SHEETS
10	Amo	88	88.0/99.8		

REGISTERED CIVIL ENGINEER DATE \_\_\_\_\_  
 PLANS APPROVAL DATE \_\_\_\_\_

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.


Caltrans now has a web site! To get to the web site, go to: <http://www.dts.ca.gov>



ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SHOWN

**LAYOUT**  
 SCALE: 1:1500 **L-2**

FOR REDUCED PLANS ORIGINAL SCALE IS IN MILLIMETERS



USERNAME -> RUSER  
 DGN FILE -> RREQUEST

CU 06240

EA 0K130K

DATE PLOTTED -> DATE  
 LINE PLOTTED -> STYLE

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
**Caltrans**

PROJECT ENGINEER  
**RANDALL WON**

DESIGN

CALCULATED/DESIGNED BY  
 CHECKED BY

DATE REVISED BY  
 DATE REVISED BY

NOTE: FOR COMPLETE R/W DATA, SEE R/W RECORD MAPS AT DISTRICT OFFICE.




DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET No	TOTAL SHEETS
10	Alameda	88	88.0/99.8		

REGISTERED CIVIL ENGINEER DATE \_\_\_\_\_

PLANS APPROVAL DATE \_\_\_\_\_

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

Caltrans now has a web site! To get to the web site, go to: <http://www.dts.ca.gov>



ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SHOWN

**LAYOUT**  
 SCALE: 1:1500 **L-3**

FOR REDUCED PLANS ORIGINAL SCALE IS IN MILLIMETERS

USERNAME -> USER  
 DGN FILE -> REQDEST

CU 06240 EA 0K130K

DATE PLOTTED -> DATE  
 TIME PLOTTED -> TIME

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
**Caltrans**  
 PROJECT ENGINEER  
**RANDALL WON**  
 DESIGN

DATE REVISIONS BY  
 DATE REVISIONS BY  
 CALCULATED/DESIGNED BY  
 CHECKED BY

NOTE: FOR COMPLETE R/W DATA, SEE R/W RECORD MAPS AT DISTRICT OFFICE.




DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET No	TOTAL SHEETS
10	Amo	88	88.0/99.8		

REGISTERED CIVIL ENGINEER DATE \_\_\_\_\_

PLANS APPROVAL DATE \_\_\_\_\_

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

Caltrans now has a web site! To get to the web site, go to: <http://www.dtd.ca.gov>



ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SHOWN

**LAYOUT**  
 SCALE: 1:1500 **L-4**

FOR REDUCED PLANS ORIGINAL SCALE IS IN MILLIMETERS

USERNAME -> USER  
 DGN FILE -> #REQUEST

CU 06240

EA 0K130K

DATE PLOTTED -> DATE  
 TIME PLOTTED -> TIME



DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET No	TOTAL SHEETS
10	Alameda	88	88/97.8		

REGISTERED CIVIL ENGINEER DATE \_\_\_\_\_



PLANS APPROVAL DATE \_\_\_\_\_

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

Caltrans now has a web site! To get to the web site, go to: <http://www.fdot.ca.gov>




- NOTES:
1. Dimensions of the structural sections are subject to tolerances specified in the Standard Specifications.
  2. Superelevation as shown or as directed by the engineer.
  3. For location and type of AC dike, see layout plans and summary of quantities.




**ROUTE 88**  
 STA 100+00 TO 151+36  
 STA 155+60 TO 172+96  
 STA 182+68 TO 198+00


**Super Elevation Correction**



**Realignment**  
 STA 151+36 TO 155+60  
 STA 172+96 TO 182+68



**TURNOUTS**  
 E.B STA 111+17  
 STA 130+58  
 STA 142+97  
 STA 167+59  
 W.B STA 171+62




**PUBLIC ROADS AND DRIVEWAYS (Overlay)**

**TYPICAL CROSS SECTIONS**  
 NO SCALE X-1

ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SHOWN

FOR REDUCED PLANS ORIGINAL SCALE IS IN MILLIMETERS



USERNAME => THAKH  
 DGN FILE => 0k1300b1.dgn

CU

EA

DATE PLOTTED => 18-AUG-2003  
 TIME PLOTTED => 10:23

PROJECT ENGINEER  
 CHECKED BY  
 CALCULATED/DESIGNED BY  
 DATE REVISSED  
 REVISSED BY  
 DATE REVISSED

**ATTACHMENT C**  
 Typ. X-sect.

**Memorandum**

To: Paul Elliott  
Stockton Design

Date: 9/28/05

File: EA OK130K ALT N/Ac2  
CO AMA RTE 88

Attn: Randall Won  
Stockton Design

From: Department of Transportation  
Division of Right of Way Central Region

DESCRIPTION:  
Peddler Hill Rehabilitation.

Subject: RIGHT OF WAY DATA SHEET

We have completed an estimate of the right of way costs for the above-referenced project based on the Right of Way Data Sheet Request Form dated 8/23/05


The following assumptions and limiting conditions were identified:

**Appraisal**

\$ 33,000 for environmental mitigation. (\$30,000 for biology mitigation and \$3,000 for permits.)

**Utility**

Right of Way Lead Time will require a minimum of 18 months after we receive certified Appraisal Maps, the necessary environmental clearance has been obtained, and freeway agreements have been approved.

  
\_\_\_\_\_  
SAHROOM ALL  
Senior Right of Way Agent  
(209) 948-3675

REQUEST DATE 8/23/05  
 REVISED DATE 5/20/05

EA 0K130K ALT N/Ac2

CO/RTE/KP-KP AMA/88/87.868-97.524 & /0/-0.000

<b>RIGHT OF WAY COST ESTIMATE</b>	<b>CURRENT YR 2005</b>	<b>CONTINGENCY RATE</b>	<b>RIGHT OF WAY ESCALATION RATE</b>	<b>ESCALATED YEAR 2012</b>
ACQUISITION	\$200,250	25.00%	5.00%	\$281,772
MITIGATION	\$41,250.00	25.00%	5.00%	\$58,043
STATE SHARE OF UTILITIES	\$37,500	25.00%	5.00%	\$52,766
RAP	\$0	25.00%	5.00%	\$0
CLEARANCE/DEMO	\$0	25.00%	5.00%	\$0
TITLE AND ESCROW	\$6,875	25.00%	5.00%	\$9,674
PROPERTY MANAGEMENT				
SUPPORT HOURS				
<b>TOTAL CURRENT VALUE *</b>	<b>\$285,875</b>			<b>\$402,255</b>

ESTIMATED CONSTRUCTION CONTRACT WORK

R/W LEAD TIME/MONTH

<b>PARCEL DATA</b>			
# OF PCL TYPE X	0	# OF DUAL APPR X	0
# OF PCL TYPE A	0	# OF DUAL APPR A	0
# OF PCL TYPE B	4	# OF DUAL APPR B	0
# OF PCL TYPE C	0	# OF DUAL APPR C	0
# OF PCL TYPE D	0	# OF DUAL APPR D	0
<b>TOTALS</b>	<b>4</b>	<b>TOTALS</b>	<b>0</b>
# OF EXCESS PARCEL		<input type="text" value="0"/>	

<b>UTILITIES</b>	
U4-1	1
U4-2	0
U4-3	0
U4-4	0
U5-7	0
U5-8	0
U5-9	1

<b>RR INVOLVEMENT</b>	
ARE RAILROAD FACILITIES OR RIGHTS OF WAY	NO
CONST/MAINT AGREEMENT	NO
SERVICE CONTRACT	NO
RIGHT OF ENTRY	NO
CLAUSES	NO

<b>MISC R/W WORK</b>	
# OF RAP DISPLACEMENT	0
# OF CLEARANCE/DEMO	0
# OF CONST PERMITS	0
# OF CONDEMNATION	0

\* IF R/W COST ESTIMATE FIELDS ARE BLANK, TOTAL CURRENT VALUE = \$0

ARE RAILROAD FACILITIES OR RIGHTS OF WAY AFFECTE  NO

RAILROAD LEADTIME REQUIRED

PARCEL AREA UNIT: ACRE

TOTAL R/W TAKE	13.4
TOTAL EXCESS AREA	0

TOTAL R/W FEE	\$160,200
TOTAL EXCESS COST	\$0

GENERAL DESCRIPTION OF R/W AND EXCESS LANDS REQUIRED (ZONING, USE, MAJOR IMPROVEMENTS, CRITICAL OR SENSITIVE PARCELS, ETC.):

The required right of way will come from an area that is forest land that includes marketable timber.

GENERAL DESCRIPTION OF UTILITY INVOLVEMENT

More accurate utility information will be provided when utility verifications are received from the affected utility owners. Accurate determination of State costs cannot be determined at this time. Potholing \$20,000

IS THERE A SIGNIFICANT EFFECT ON ASSESSED VALUATION?  No

WERE ANY PREVIOUSLY UNIDENTIFIED SITES WITH HAZARDOUS WASTE OR MATERIAL FOUN  No

ARE RAP DISPLACEMENTS REQUIRE  No

# OF SINGLE FAMILY  0 # OF MULTI FAMILY  0 # OF BUSINESS/NONPROFIT  0 # OF FARMS  0

SUFFICIENT REPLACEMENT HOUSING WILL BE AVAILABLE WITHOUT LAST RESORT HOUSING  N/A

ARE MATERIAL BORROW OR DISPOSAL SITES REQUIRED  No

ARE THERE POTENTIAL RELINQUISHMENTS OR ABANDONMENTS?  No


ARE THERE ANY EXISTING OR POTENTIAL AIRSPACE SITES  No

ARE ENVIRONMENTAL MITIGATION PARCELS REQUIRED  Yes

DATA FOR EVALUATION PROVIDED BY

ESTIMATOR	TIAIRA MOERING	Tiaira Moering	8/23/05
RAILROAD LIAISON AGENT		Maria Toles	4/18/05
UTILITY RELOCATION COORDINATOR		Angela Jackson	5/16/05

I have personally reviewed this Right of Way Sheet and all supporting information. I find this Data Sheet complete and current, subject to the limiting conditions set forth

  
SAHROOM ALI  
Senior Right of Way Agent

Date ENTERED PMC 9/28/05  
BY Gina Pippenger  
cc: Joy Pinne



**Preliminary Environmental Analysis Report**

**Project Information**

District 10 County AMA Route 88 Kilopost 88.0/97.8 Post Mile 54.5/60.8 EA 10-0K130K

Project Name: Peddler Hill Rehab.

Funding: 2006 SHOPP

Project Manager Joy Pinne Phone # (209) 948-7976

Design Manager Paul Elliott Phone # (209) 948-7079

Environmental Manager David Hyatt Phone # (559) 243-8312

Environmental Planner Generalist Christine Kelley Phone # (559) 243-8167

**Project Description:** The proposed project would rehabilitate Route 88 from .2 km west of Foster Meadow Rd. to .2 km west of Shot Rock Vista Rd by pavement overlay, curve corrections to standard, superelevation correction, installing guardrail, and upgrading drainage.

**Anticipated Environmental Approval**

**CEQA**

- Categorical Exemption
- Negative Declaration / focused ND
- Environmental Impact Report

**NEPA**

- Categorical Exclusion/Programmatic Categorical Exclusion
- Finding of No Significant Impact
- Environmental Impact Statement

**PSR Summary Statement**

The proposed project is anticipated to require an Initial Study/Negative Declaration for California Environmental Quality Act (CEQA) compliance and a Finding of No Significant Impact for National Environmental Policy Act (NEPA) compliance. Cultural resources would be the critical path for completion of this CEQA/NEPA environmental document. The project area would need a phase II survey for archaeological sites in the project area. Assuming a start date of 1/1/07 for environmental studies, environmental approval is anticipated by 10/1/10 (45 months -- see attached Gantt chart).

**Capital Cost Estimate Requirements**

Construction Capital

Paleontology mitigation	\$ 50,000
Cultural Resources mitigation	\$ 550,000
Tree replacement, erosion control and storm water issues	\$ 400,000

Right of Way Capital

Biology mitigation	\$ 30,000
Permits	\$ 3,000

REVISED 8/30/05

**Disclaimer**


This report is not an environmental document. Preliminary analysis, determinations, and estimates of mitigation costs are based on the project description provided in this report. The estimates and conclusions provided are approximate and are based on cursory analysis of probable effects. This report is to provide a preliminary level of environmental analysis to supplement the Project Study Report. Changes in project scope, alternatives, or environmental laws will require a re-evaluation of this report.

**Reviewed by:**



Date: 8/30/05

David Hyatt  
Environmental Branch Chief



Date: 8/30/05

Joy Pinn  
Project Manager

Environmental Technical Reports or Studies Required

	Study	Document	N/A
Community Impact Study	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Farmland	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Section 4(f) Evaluation	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Visual Resources	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Water Quality	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Floodplain Evaluation	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Noise Study	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Air Quality Study	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Paleontology	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Wild and Scenic River Consistency	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Cumulative Impacts	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Dust Control Plan	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
<b>Cultural</b>			
ASR	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HRER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HPSR	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Section 106 / SHPO	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Native American Coordination	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Finding of Effect	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Data Recovery Plan	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<b>Hazardous Waste</b>			
ISA (Additional)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
PSI	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
<b>Biological</b>			
Endangered Species (Federal)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Endangered Species (State)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Species of Concern (CNPS, USFS, BLM, S, F)	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Biological Assessment (USFWS, NMFS, State)	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Biological Opinion	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Wetlands	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Invasive Species	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Natural Environment Study	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
NEPA 404 Coordination	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
<b>Permits</b>			
401 Permit Coordination	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
404 Permit Coordination	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Nationwide <input checked="" type="checkbox"/> Individual <input type="checkbox"/>			
1601 Permit Coordination	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
City/County Coastal Permit Coordination	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
State Coastal Permit Coordination	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
NPDES Coordination	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
US Coast Guard (Section 10)	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Section 2081	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Discussion of Technical Review

Socio-economic and Community Effects. N/A

Farmlands. N/A

4(f) Impacts. N/A

Visual Effects. A Visual Impact Assessment will be needed for this project. It appears replacement planting will be needed, and erosion and storm water issues will need to be addressed.

**Mitigation for tree replacement, erosion control, and storm water issues is estimated at \$400,000.**

Water Quality. The project would not include significant earthwork, and short-term but less than significant surface water quality impacts are expected from the implementation of the project. No groundwater impacts are expected from the project.

Any potential impact (erosion, accidental spills of hazardous material and disruption of natural drainage patterns) must be addressed, eliminated or minimized to the maximum extent practicable during the design and construction by incorporating the appropriate permanent and temporary Best Management Practices (BMP's) into the project.

Before project initiation, the Caltrans' stormwater unit should be consulted to identify the appropriate management practices for all stormwater concerns.

If the project disturbs more than an acre of soil, the following is required:

1. A Notification of Construction (NOC) is to be submitted to the appropriate Regional Water Quality Control Board at least 30 days prior to the start of construction.
2. A Stormwater Pollution Prevention Plan (SWPPP) is to be prepared and implemented during construction to the satisfaction of the Resident Engineer.
3. A Notice of Construction Completion (NOCC) would be submitted to the Regional Board upon completion of construction and site stabilization. A project will be considered complete when the criteria for final stabilization in the Construction General Permit are met.

If the project disturbs less than one acre of soil, a Water Pollution Control Program needs to be prepared by the contractor in accordance with Caltrans Standard Specification Section 7-1.01G – Water Pollution.

Potential impacts on water quality during construction should be addressed in the design and construction phases. Potential impacts include erosion, accidental spills of hazardous materials, and disruption of natural drainage patterns. In the design phase, plans need to insure that there would be no direct discharge into any water bodies. In the construction phase, the contractor has the responsibility to take whatever measures are necessary to eliminate potential impacts (as stated in Caltrans Standard Specifications Section 7-1.01G). If adequate measures and precautions were taken, then there would not be any adverse effects to water quality in the project area.

By incorporating proper and accepted engineering practices and BMP's, the proposed project would not produce significant impacts to water quality during construction or operation. No further investigation concerning water quality is needed to proceed with the project.

REVISED 8/30/05

Air. According to the Transportation Conformity Rule (40 CFR Section 93.126), this project is exempt from the requirement that a conformity determination be made. No further investigation is needed to proceed with this project.

Noise. Aerial photographs do not indicate any noise sensitive land uses. The alignment alterations are not substantially different and therefore according to the definition of Type 1 projects, this project does not qualify for consideration.

Paleontology. The project area is underlain in part by the Tertiary Mehrten Formation. This Formation contains numerous vertebrate fossil localities and is ranked as high sensitivity. Additional study is required to identify geologic strata that will be disturbed by the project-related activities and to assess the potential to encounter significant paleontology resources.

**Paleontology mitigation is currently estimated at \$50,000. (Construction Capital)**

Cultural Resources. No information on the project area was available from Caltrans files and a records search was not completed because a request to open the 0-Phase of this project was denied. A review of a project completed adjacent to the proposed project (Silver Lake Rehab.) identified 20 potentially sensitive areas within that project area. The region is known to be highly sensitive for historical and prehistoric archaeological resources.

The Mormon-Carson Emigrant trains runs through the project area. This resource is considered potentially eligible for the National Register of Historic Places and is a California State Historic Landmark. Recorded and unrecorded archaeological sites within the project area will need to be evaluated. A Phase II Study will likely be needed. Thirty-four months would be required to complete cultural resources compliance. This is the critical path for completion of the environmental document (see attached Gantt chart).

**Mitigation for Phase III data recovery is estimated at \$550,000 (Construction Capital).**

Native American Coordination. The Native American Heritage Commission has provided a list of eleven individuals/organizations with potential interest in the project. Consultation with the tribes would be required throughout project development but particularly during archaeological site investigations and during construction.

Hazardous Waste/Materials. A digital aerial and database review of the proposed project limits identified specific areas of concern including a leaking underground storage tank at Bear River Lake Resort, aerial deposited lead, and leaded lane line paint striping. Also, Amador County has been identified as having ultramafic rock. Ultramafic rock is formed originally as igneous rocks and through time and extreme pressure can be transformed to metamorphic rock, which contains naturally occurring asbestos.

An Initial Site Assessment (ISA) should be performed with regard to parcel ownership and land-use history, specific database searches for hazardous waste and right-of-way parcel acquisition, regulatory consultation (as appropriate), and site visits. Should an ISA reveal a medium to high risk for the presence of excess hazardous waste, leaking underground storage tanks, naturally occurring asbestos and/or lead contamination, then a Preliminary Site Investigation (PSI) would be warranted.

Biological Resources. The following threatened and endangered species have the potential to occur within or adjacent to the project area: Mountain yellow-legged frog, California Spotted Owl, Northern Goshawk, Bald Eagle, and Pacific Fisher. No critical habitat is designated within the project area, but, California Spotted owl are located in the project area. Coordination with the U.S. Forest Service and preparation of a Biological Evaluation will be required. Surveys will be

**REVISED 8/30/05**

needed for California Spotted owl, Goshawk, and Pleasant Valley Mariposa Lily, and tree counts will be needed.

If waters of the U.S. are identified in the project area, 401 and 404 permits may be required. Mitigation may be required if waters of the U.S. are identified in the project area or for possible relocation of Pleasant Valley Mariposa Lily, if found.

**Biology mitigation is currently estimated at \$30,000. (Right of Way Capital)  
The total permit cost is approximately \$3,000 (Right of Way Capital)**

**List of Preparers**

Hazardous Waste Scoping by Bill Horge	Date 5/9/05
Biological Scoping by Primavera Parker	Date 4/21/05
Archaeology Scoping by Brian Gassner	Date 5/27/05
Architectural History Scoping by Jon Brady	Date 5/17/05
Paleontology Scoping by Peter Hansen	Date 5/12/05
Water Quality Scoping by Rajeev Dwivedi	Date 5/10/05
Air Quality Scoping by Abdul Chafi	Date 5/10/05
Noise Analysis by Christopher Bassar	Date 4/27/05
Visual Scoping by Elbert Cox	Date 5/31/05
Preliminary Environmental Analysis Report by Christine Kelley	Date 5/31/05



## Central Region Environmental Division Mitigation Cost Compliance Estimate Form

PEAR    
  Draft ED    
  Final ED    
  PS&E

Dist.-Co.-Rte.-PM: 10-AMA-88-54.5/60.6

EA: 10-0K130K

Project Name: Peddler Hill

Alternative #:

Project Description: The proposed project would rehabilitate Route 88 from .2 km west of Foster Meadow Rd. to .2 km west of Shot Rock Vista Rd by pavement overlay, curve corrections to standard, superelevation correction, installing guardrail, and upgrading drainage.

Environmental Manager: David Hyatt

Phone Number: (559) 243-8312

Project Manager: Joy Pinne

Phone Number: (209) 948-7976

Design Manager: Paul Elliot

Date: 5/31/05

Numbers are in thousands

	Right of Way Capital (Prior to Construction) (050)	Construction Capital (During and Post Construction) (042)
Archaeological		550,000
Biological	30,000	
Historical		
Paleontology		50,000
Hazardous Waste Remediation		
Landscape		400,000
Noise		
Total Permit Cost*	3,000	
DFG Document Review Fee		
Other		
<b>Total</b>	<b>33,000</b>	<b>1,000,000</b>

\* Includes 1601, 401 and 404 permit fees

- This form is completed as part of the PEAR for all candidate projects, at completion of the Draft Environmental Document, and at the completion of the Final Environmental Document
- This form is to be completed for all SHOPP & STIP projects (even those w/o Mitigation)
- This form is to be completed for all Minor A & B projects with mitigation requirements
- Costs are to include all costs to complete the commitment including: capital outlay (non-staffing support costs); cost of right-of-way or easements; long-term monitoring and reporting, and; any follow-up maintenance
- Attach detailed descriptions of line items included in estimates

Attach completed ROW data sheets when forwarded to ROW.

PA & ED Date	RTL Date	Months Between	Months Required

### Right of Way Data Sheet Input Information

3.	Environmental mitigation parcels:	REQUIRED <input type="checkbox"/>	NOT REQUIRED <input checked="" type="checkbox"/>
	_____ Acres     \$ _____ Additional funding     \$ <u>3,000</u> Permit Fees		
	(Mitigation required)		

\*\* This information is to be obtained from the Environmental Branch prior to submittal to the Right of Way Field Office Chief

# Caltrans Maintenance Program 2004 Pavement Condition Survey Inventory Caltrans Drive Order

District  
 County AM  
 Route 0  
 Begin PM 53.5

District 10, AMA, Rte 088, PM 54.7 - 60.8

District 10 County AMA Route 088

Begin PM - End PM	Length	LaneMi. (Est.)	Type	AADT (,000)			MSL	Faulting	Patching		Ride, IRI	Priority	Skid	Defect
				Slab Cracking					Area %	Poor Cond.?				
Lane	Surface Type	Alligator Cracking A % B % C (Y/N)?	Rutting, Bleeding	1st %	3rd %	Corner %								
53.549	-	54.681	1.132	2.264	2LNU	2	2							
L1	F-DG	1 4								8 99	31			
R1	F-DG	0 13								6 92	10			COARSE RAVEL MOD ABC
R 54.681	- R 54.849	0.168	0.336	2LNU	2	2				10 107	31			COARSE RAVEL MOD ABC
L1	F-DG	1 4								11 110	10			
R1	F-DG	0 13												
R 54.849	- R 55.849	1.000	2.000	2LNU	2	2				5 85	8			HIGH ABC
L1	F-DG	19 36								5 86	8			HIGH ABC
R1	F-DG	24 33												
R 55.849	- R 56.849	1.000	2.000	2LNU	2	2				5 80	8			HIGH ABC
L1	F-DG	0 38								5 77	31			ALL. A & B
R1	F-DG	19 8												
R 56.849	- R 57.849	1.000	2.000	2LNU	2	2				5 83	8			HIGH ABC
L1	F-DG	0 50								5 85	8			HIGH ABC
R1	F-DG	24 33												
R 57.849	- R 58.649	0.800	1.600	2LNU	2	2				5 88	8			HIGH ABC
L1	F-DG	25 50								5 88	8			HIGH ABC
R1	F-DG	0 64												
R 58.649	- R 59.649	1.000	2.000	2LNU	2	2				13 118	8			HIGH ABC
L1	F-DG	0 57								14 123	8			HIGH ABC
R1	F-DG	0 53												
R 59.649	- R 59.861	0.212	0.424	2LNU	2	2				27 174	8			HIGH ABC
L1	F-DG	0 79								20 145	8			HIGH ABC
R1	F-DG	0 58												
R 59.861	- R 60.369	0.508	2.032	MLU	2	2				16 129	31			ALL. A & B
L1	F-CS	22 8								N/A	8			HIGH ABC
L2	F-CS	0 53												
R1	F-CS	21 13								12 113	10			MOD ABC
R2	F-CS	0 61								N/A	8			HIGH ABC

\*Surface type of 'EB' is Enhanced Binder.

ATTACHMENT F  
 Pavement Cond. Survey

**Memorandum**

**To:** RANDALL WON  
Design Engineer, Branch I

**Date:** June 7, 2005

**Attn:**

**File:** 10-Ama-88-54.7/60.8  
Peddler Hill Rehab.  
10-0K130K

**From:** **DEPARTMENT OF TRANSPORTATION**  
District 10 – Materials Branch

**Subject:** Structural Section

The following structural sections, based on a 10 year TI of 10.0, are recommended for placement over basement soils with a minimum R-value of 50

MAINLINE ROUTE 88                      TI = 10.0

AC	150mm	or	245mm
AB	200mm		-----

SHOULDER ROUTE 88                      TI = 6.5

AC	90mm	or	150mm
AB	105mm		-----

Slopes can be as follows: Cut slopes can be 1 to 1 or flatter, and fill slopes can be 1 (vertical) to 1.5 (horizontal).

Based on Deflection Study data and recommendations from the near vicinity of this project, and a field review, the following may be used for cost estimating purposes.

Alternative 1. - Conduct a field review and locate specific areas of severe failure identified by rutting greater than 15mm and/or loose or spalling pavement. Dig out and repair these localized areas and seal all cracks wider than 5mm. Finally, place a Dense Graded AC (DGAC) overlay of 105mm (0.35').

Alternative 2. - Dig out and repair localized failures and seal all cracks as described above. Then place an asphalt-rubber hot mix – gap graded (RAC-GG) overlay of 60mm (0.20').

If you have any questions or comments, please contact me at 7951.

Dave Whaling, P.E.  
District Materials engineer

**ATTACHMENT G**  
**Material Report**

## D-10 TRANSPORTATION MANAGEMENT PLAN CHECKLIST

District / EA: 10 / 0K1301  
 Date Prepared: April 11, 2005  
 Prepared By: Jose A. Alicea II  
 Requested By: Randall Won

Co.Rte.-PM.(KP) AMA-88-PM 54.7/60.8 (KP 88.0/97.8)  
 Location: In Amador County from 0.3 mile east of Peddler Hill Road to 2 miles west of tragedy springs road (KP 88.0/97.8)

Stage of Project (X box)  PID  PSR  PR  PS&E

Description: Rehab roadway by structural pavement repair and resurfacing, superelevation & curve correction to standard.

Date Signed	Date Signed	Date Signed	Date Signed

REQUIRED	RECOMMENDED	NOT APPLICABLE	BEEES Item No.	COMMENTS	ITEM COST	REQUIRED IN SPEC.
----------	-------------	----------------	----------------	----------	-----------	-------------------

**1.0 Public Information Strategies**

- 1.1 Brochures and Mailers
- 1.2 Media Releases (& minority media sources)
- 1.3 Paid Advertising
- 1.4 Public Information Center
- 1.5 Public Meetings/Speakers Bureau
- 1.6 Project Telephone Hotline
- 1.7 Internet, E-Mail
- 1.8 Local cable TV and News
- 1.9 Notification to Impacted groups  
(i.e. bicycle users, pedestrians with disabilities, others)
- 1.10 Project Web Page
- 1.11 Caltrans Public Information Office
- 1.12 Consultant Public Information Office
- 1.13 Other items

<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		As needed for adjacent establishments.		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	066063			
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>				
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Designer to verify ped and bicyclist traffic.		
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	066063		\$6K	<input checked="" type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				

**2.0 Traveler Information Strategies**

- 2.1 Changeable Message Signs(permanent)
- 2.2 Changeable Message Signs (portable)
- 2.3 Special Construction Signs
- 2.4 Traveler Information Systems(CHIN/Internet)
- 2.5 Highway Advisory Radio "HAR"(fixed or mobile)
- 2.6 Radar Speed Sign
- 2.7 Traffic Management Team
- 2.8 Revised Transit Schedules/ Maps
- 2.9 Bicycle community information
- 2.10 Other item

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	128650	1 sign in ea dir. (1 pair * 3 months * \$3.5k= \$11k)	\$11K	<input checked="" type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	120690			
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	861985			
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	860520			
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	066064			
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Designer to verify bicycle traffic and events.		
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				

**3.0 Incident Management**

- 3.1 COZEEP
- 3.2 Freeway Service Patrol(tow truck service patrol)
- 3.3 Traffic Surveillance Stations(loops or CCTV)
- 3.4 Transportation Management Center
- 3.5 Traffic Control Inspector(Caltrans)
- 3.6 Traffic Management Team
- 3.7 On-site Traffic Advisor (contractor)
- 3.8 Other Items

<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	066062	See Comments below.		
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	066065			
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	066876			
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				

**4.0 Construction Strategies**


- 4.1 Delay damage clause
- 4.2 Night work
- 4.3 Weekend Work
- 4.4 Extended Weekend Closures
- 4.5 Planned Lane Closures
- 4.6 Planned Ramp/Connector Closures
- 4.7 Total Facility Closure
- 4.8 Project Phasing
- 4.9 Truck Traffic Restrictions
- 4.10 Reduced Lane Widths

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Per Lane Closure Charts		<input checked="" type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>				



**APPENDIX E**

**Long Form - Storm Water Data Report**



Dist-County-Route: 10-Ama-88  
Kilometer Post (Post Mile) Limits :  
R88.0/R97.8(R54.7/R60.8)  
Project Type: Pavement Rehabilitation  
EA: 10-0K130K  
RU: 06-240  
Program Identification: 201.120  
Phases:  PID  PA/ED  PS&E

**Regional Water Quality Control Board(s):** Central Valley Regional Water Quality Control Board

Is the project required to consider incorporating Treatment BMPs? Yes  No

If yes, can Treatment BMPs be incorporated into the project? Yes  No

If No, a Technical Data Report must be submitted to the RWQCB at least 30 days prior to Advertisement. List submittal date: \_\_\_\_\_

Total Disturbed Soil Area: 9.7 ha

Estimated: Construction Start Date: 2009

Construction Completion Date: 2010

Notification of Construction (NOC) Date to be submitted: 2008

Notification of ADL reuse (if Yes, provide date) Yes  Date \_\_\_\_\_ No

Separate Dewatering Permit (if Yes, permit number) Yes  Permit # \_\_\_\_\_ No

*This Report has been prepared under the direction of the following Licensed Person. The Licensed Person attests to the technical information contained herein and the data upon which recommendations, conclusions, and decisions are based. Professional Engineer or Landscape Architect stamp required at PS&E.*

Randall Won 8/16/05  
**RANDALL WON**, Registered Project Engineer/Landscape Architect Date

*I have reviewed the storm water quality design issues and find this report to be complete, current, and accurate:*

Joy Pinne 8/24/05  
**JOY PINNE**, Project Manager Date

Allan E. Shafer 8/30/05  
**ALLAN SHAFER**, Designated Maintenance Representative Date

Elbert Cox 9/6/05  
**ELBERT COX**, Designated Landscape Architect Representative Date

Kerry Molz 8/29/05  
**KERRY MOLZ**, District/Regional SW Coordinator or Designee Date

# APPENDIX E

## Evaluation Documentation Form

DATE: 6/30/05

See Figure 4-1, Project Evaluation Process for Consideration of Permanent Treatment BMPs

EA: 0K130K

NO.	CRITERIA	YES 3	NO 3	SUPPLEMENTAL INFORMATION FOR EXEMPTION
1.	Begin Project Evaluation regarding requirement for consideration of Treatment BMPs	X		Go to 2
2.	Is this an emergency or Safety project?		X	If <b>Yes</b> , go to 12. (Safety Projects must be funded from the 010 SHOPP Program). If <b>No</b> , continue to 3.
3.	Have TMDLs been established for surface waters within the project limits?		X	If <b>Yes</b> , contact the District/Regional NPDES coordinator to discuss the Department's participation in the TMDL (if Applicable), go to 11 or 4 (as determined by the NPDES Coordinator). ____ (Dist./Reg. SW Coordinator initials) If <b>No</b> , continue to 4.
4.	Is the project within an urban MS4?		X	If <b>Yes</b> , continue to 5. <i>(write the MS4 Area here)</i> If <b>No</b> , go to 12.
5.	Is the project directly or indirectly discharging to surface waters?			If <b>Yes</b> , continue to 6. If <b>No</b> , go to 12.
6.	Is it a new facility or major reconstruction?			If <b>Yes</b> , continue to 8. If <b>No</b> , go to 7.
7.	Will there be a change in line/grade or hydraulic capacity?			If <b>Yes</b> , continue to 8. If <b>No</b> , go to 10.
8.	Is the Disturbed Soil Area (DSA) created by the project <u>greater than or equal to 1.2 hectares?</u>			If <b>Yes</b> , continue to 11. If <b>No</b> , go to 9. ____ (Total DSA quantity)
9.	Is the project part of a Common Plan of Development?			If <b>Yes</b> , continue to 11. If <b>No</b> , go to 10.
10.	Are there any Pollution Control Requirements within the project limits? <i>(Contact your Dist./Reg. SW Coordinator)</i>			If <b>Yes</b> , continue to 11. If <b>No</b> , go to 12.
11.	Consider approved Treatment BMPs for the project.			See Sections 2.4 and either Section 5.5 or 6.5 for BMP Evaluation and Selection Process. Complete Checklist T-1 in this Appendix E.
12.	Project is not required to consider Treatment BMPs. <i>JMV</i> (Dist./Reg. SW Coord. Initials) <i>KW</i> (Project Engineer Initials) <u>06/16/05</u> (Date)	X		Document for Project Files by completing this form, and attaching it to the SWDR.
13.	End of checklist	X		



PROJECT RISK MANAGEMENT PLAN

Dist - E.A 10-0K130  
 Project Name Peddler Hill  
 Co-Rte-PM AMA-88- 54.7/ 80.8  
 Date 5/25/2005  
 Project Mngr Joy Plinne Telephone Number 209-948-7976

PROJECT RISK MANAGEMENT PLAN																																																		
Priority	Identification					Qualitative Analysis				OPTIONAL Analysis			Quantitative		Risk Response Plan		Monitoring and Control																																	
	Status (1)	ID # (2)	Date Identified Project Phase (3)	Functional Assignment (4)	Threat/Opportunity Event (5)	Risk Trigger (7)	Type (8)	Probability (9)	Impact (10)	Risk Matrix (11)	Probability (%) (12)	Impact (\$ or days) (13)	Effect (days) (14) = (12)x(13)	Strategy (15)	Response Actions including advantages and disadvantages (16)	Responsibility (Risk Manager) (17)	Status Interval or Milestone Check (20)	Last date changes made to risk and Comments (18)																																
		1	2/24/2005		weather		Schedule	Low	Low	<table border="1"> <tr><td>VH</td><td></td><td></td><td></td><td></td></tr> <tr><td>H</td><td></td><td></td><td></td><td></td></tr> <tr><td>M</td><td></td><td></td><td></td><td></td></tr> <tr><td>L</td><td></td><td></td><td></td><td></td></tr> <tr><td>VL</td><td></td><td></td><td></td><td></td></tr> <tr><td></td><td>VL</td><td>L</td><td>M</td><td>H</td><td>VH</td></tr> </table>	VH					H					M					L					VL						VL	L	M	H	VH	30%				Acceptance	Wait for acceptable weather to begin work.			
VH																																																		
H																																																		
M																																																		
L																																																		
VL																																																		
	VL	L	M	H	VH																																													
		2	2/24/2005	Environmental/ Right of Way	Forest Service		Schedule	High	High	<table border="1"> <tr><td>VH</td><td></td><td></td><td></td><td></td></tr> <tr><td>H</td><td></td><td></td><td></td><td></td></tr> <tr><td>M</td><td></td><td></td><td></td><td></td></tr> <tr><td>L</td><td></td><td></td><td></td><td></td></tr> <tr><td>VL</td><td></td><td></td><td></td><td></td></tr> <tr><td></td><td>VL</td><td>L</td><td>M</td><td>H</td><td>VH</td></tr> </table>	VH					H					M					L					VL						VL	L	M	H	VH	70%			Mitigation	Right of Way and Environmental to begin early discussions with the Forest Service.	Sharon Parsons / David Hyatt			
VH																																																		
H																																																		
M																																																		
L																																																		
VL																																																		
	VL	L	M	H	VH																																													
		3	2/24/2005		Utilities		Schedule	Moderate	High	<table border="1"> <tr><td>VH</td><td></td><td></td><td></td><td></td></tr> <tr><td>H</td><td></td><td></td><td></td><td></td></tr> <tr><td>M</td><td></td><td></td><td></td><td></td></tr> <tr><td>L</td><td></td><td></td><td></td><td></td></tr> <tr><td>VL</td><td></td><td></td><td></td><td></td></tr> <tr><td></td><td>VL</td><td>L</td><td>M</td><td>H</td><td>VH</td></tr> </table>	VH					H					M					L					VL						VL	L	M	H	VH	50%			Mitigation	Early coordination with Utility Companies	John Amazon			
VH																																																		
H																																																		
M																																																		
L																																																		
VL																																																		
	VL	L	M	H	VH																																													
		4	2/24/2005		Local Native American Committee		Schedule	Moderate	Moderate	<table border="1"> <tr><td>VH</td><td></td><td></td><td></td><td></td></tr> <tr><td>H</td><td></td><td></td><td></td><td></td></tr> <tr><td>M</td><td></td><td></td><td></td><td></td></tr> <tr><td>L</td><td></td><td></td><td></td><td></td></tr> <tr><td>VL</td><td></td><td></td><td></td><td></td></tr> <tr><td></td><td>VL</td><td>L</td><td>M</td><td>H</td><td>VH</td></tr> </table>	VH					H					M					L					VL						VL	L	M	H	VH	50%			Avoidance	Work with local Native American Committee. Refer to project 0J600 for information regarding Native American contacts.	David Hyatt			
VH																																																		
H																																																		
M																																																		
L																																																		
VL																																																		
	VL	L	M	H	VH																																													
										<table border="1"> <tr><td>VH</td><td></td><td></td><td></td><td></td></tr> <tr><td>H</td><td></td><td></td><td></td><td></td></tr> <tr><td>M</td><td></td><td></td><td></td><td></td></tr> <tr><td>L</td><td></td><td></td><td></td><td></td></tr> <tr><td>VL</td><td></td><td></td><td></td><td></td></tr> <tr><td></td><td>VL</td><td>L</td><td>M</td><td>H</td><td>VH</td></tr> </table>	VH					H					M					L					VL						VL	L	M	H	VH									
VH																																																		
H																																																		
M																																																		
L																																																		
VL																																																		
	VL	L	M	H	VH																																													
										<table border="1"> <tr><td>VH</td><td></td><td></td><td></td><td></td></tr> <tr><td>H</td><td></td><td></td><td></td><td></td></tr> <tr><td>M</td><td></td><td></td><td></td><td></td></tr> <tr><td>L</td><td></td><td></td><td></td><td></td></tr> <tr><td>VL</td><td></td><td></td><td></td><td></td></tr> <tr><td></td><td>VL</td><td>L</td><td>M</td><td>H</td><td>VH</td></tr> </table>	VH					H					M					L					VL						VL	L	M	H	VH									
VH																																																		
H																																																		
M																																																		
L																																																		
VL																																																		
	VL	L	M	H	VH																																													
										<table border="1"> <tr><td>VH</td><td></td><td></td><td></td><td></td></tr> <tr><td>H</td><td></td><td></td><td></td><td></td></tr> <tr><td>M</td><td></td><td></td><td></td><td></td></tr> <tr><td>L</td><td></td><td></td><td></td><td></td></tr> <tr><td>VL</td><td></td><td></td><td></td><td></td></tr> <tr><td></td><td>VL</td><td>L</td><td>M</td><td>H</td><td>VH</td></tr> </table>	VH					H					M					L					VL						VL	L	M	H	VH									
VH																																																		
H																																																		
M																																																		
L																																																		
VL																																																		
	VL	L	M	H	VH																																													

ATTACHMENT J  
 Risk Management Plan

